Wireless World

APRIL 1952 · TWO SHILLINGS



RADIO, TELEVISION AND ELECTRONICS

NEW MOULDED-ON COUPLER

to B.B.C. Standard for T/V Outside Broadcasts


Screwed lock-ring provides forced engagement and withdrawal.
Contacts secured by Polythene injection moulding in gun-metal shell.
Group screening designed to suit individual requirements.
Tough rubber muff controls bending at this point.

BICC has produced a new 32 contact Polypole Coupler and associated cable to meet the increasingly complex needs of modern television cameras.

This new coupler and cable providing 4 co-axial and 24 other circuits has been designed to the B.B.C. new standard requirements for Outside Broadcast Services.

Experience has proved that the combination of solid conductors and moulded-on couplers give the unit greater mechanical strength and freedom from conductor end-breakage.

BICC Television Camera Cables and Couplers are used with the majority of the B.B.C. Outside Broadcast Television Units.

B.I. Callenders

POLYPOLE CABLE COUPLER

BRITISH INSULATED CALLENDER'S CABLES LIMITED
NORFOLK HOUSE, NORFOLK STREET, LONDON, W.C.2

WHEN YOU THINK OF A VALVE TESTER..



What do you expect ?

The answer is, of course, not to think of an emission tester when you can have so much more. Here is a precision measuring instrument that will not only give a quick good/bad verdict on any receiving valve, small transmitting valves, etc., but will also provide the electronic engineer and designer with accurate facts about any valve under working conditions.

12 GOOD REASONS for the success of The AVO Valve CHARACTERISTIC Meter

Price **£50**

Complete with quick-reference Data manual containing data covering more than 3,000 British, American and Continental valves, plus approximately 1,200 Service equivalents

Plus **FREE INFORMATION SERVICE**

The completion and return of the registration card within the Manual will bring you from time to time additional data set out in such a manner that it can be inserted in the Manual in correct alphabetical and numerical sequence.

1. Whilst its features make it invaluable for the **skilled** radio and television engineer, it can be used as a reliable good/bad indicator by any **unskilled** operator of normal intelligence.
2. It is more than an emission tester . . . it enables the slope of a multi-electrode valve to be checked at any point between 0 and −100 V. on the control grid.
3. A special form of polarised relay is incorporated to give protection against inadvertent overloads or valve failure.
4. With the exception of a small diode, there are no internal electronic components to deteriorate or break down and cause misleading readings. Thus no expensive periodical replacements are required.
5. The comprehensive Data Book supplied free with the instrument facilitates the rapid checking of over 3,000 different types of valve. The instrument can be used, however, with complete accuracy by employing any other data available, thus bringing obsolete and experimental valves within its scope.
6. It enables Ia/Va, Ia/Vg, Ia/Vs, etc., characteristics to be plotted.
7. It detects grid current **and** indicates its direction and magnitude.
8. It measures inter-electrode insulation in rotation with valves cold or hot, also cathode/heater insulation with the valve hot, and indicates any breakdown below 10 megohms.
9. Rectifiers and Signal Diodes can be subjected to maximum operating load.
10. It subjects the valve under test to working voltages.
11. It will carry out tests on small thyratrons, tuning indicators, etc.
12. It is fitted with bases for **all valves in current use** and adaptors will be available to keep the instrument fully up to date as new bases come into use.

Write for fully descriptive pamphlet, or for complete catalogue of all "Avo" Instruments.

THE AUTOMATIC COIL WINDER & ELECTRICAL EQUIPMENT CO. LTD.
WINDER HOUSE • DOUGLAS STREET • LONDON S.W.1 *Telephone* VICtoria 3404—9

VC.4

A GOODWILL MESSAGE FROM NEW YORK

British Industries Corporation

PRESIDENT: LEONARD CARDUNER

send their friends in Britain their best wishes for success at the 1952 R.E.C.M.F. Exhibition

BRITISH INDUSTRIES CORPORATION ARE PRIVILEGED TO REPRESENT IN THE U.S.A. THE FOLLOWING BRITISH COMPANIES

Automatic Coil Winder & Electrical Equipment Co. Ltd.
MEASURING INSTRUMENTS, COIL WINDING MACHINES

A. F. Bulgin & Co. Ltd.
ELECTRONIC COMPONENTS

Garrard Engineering & Manufacturing Co. Ltd.
AUTOMATIC RECORD CHANGERS, RECORD PLAYERS

General Electric Co. Ltd.
VALVES, GERMANIUM DIODES

H. J. Leak & Co. Ltd.
AMPLIFIERS

Multicore Solders Ltd.
MULTICORED SOLDERS, FLUXES

Reproducers & Amplifiers Ltd.
PRODUCTION TYPE LOUDSPEAKERS

Trix Electrical Co. Ltd.
PORTABLE AMPLIFIED GRAMOPHONES

Vitavox Ltd.
MULTI-CELL HORN LOUDSPEAKERS

Wharfedale Wireless Works
SPECIALISED LOUDSPEAKERS, TECHNICAL BOOKS

Wright & Weaire Ltd.
TAPE DECKS

BRITISH INDUSTRIES CORPORATION, 164, DUANE STREET, NEW YORK 13

A Range of Thyratrons for Static and Mobile Applications

The Mullard range of thyratrons now includes types suitable for use in both static and mobile applications.

For static power and motor control applications a group of mercury-vapour valves is available, with anode current ratings ranging from 0.5 to 6.4 amperes.

For switching, servo mechanisms and motor control applications in aircraft, ships and mobile industrial equipments, there is a series of xenon-filled thyratrons available, with anode current ratings ranging from 0.1 to 6.4 amperes. On account of the small variations-with-temperatures of xenon, these tubes are specially suitable for use in equipments operating over a large ambient temperature range.

For special applications where extremely rapid rates of current rise are required, as, for example, in the modulation of radar transmitting systems, there is also a hydrogen-filled thyratron, the ME1503. This valve, characterised by its very low ionisation and de-ionisation time, is the first of a group of hydrogen thyratrons now being developed.

Brief technical details of the Mullard range of thyratrons are given below. More comprehensive information will be gladly supplied on request.

TYPE	DESCRIPTION	BASE	V_a (pk) max. (KV)	PIV max. (KV)	I_a (pk) max. (A)	I_a (av) max. (A)
MERCURY-VAPOUR						
MT17	Triode	4-pin UX	2.5	5.0	2.0	0.5
MT57	Triode	4-pin UX	1.0	1.0	15	2.5
MT105	Tetrode	B4D	2.5	2.5	40	6.4
XENON-FILLED						
2D21	Tetrode	B7G	0.65	1.3	0.5	0.1
MT5544*	Triode	B4D	1.5	1.5	40	3.2
MT5545*	Triode	B4D	1.5	1.5	80	6.4
HYDROGEN-FILLED						
ME1503	Triode	B4D	8.0	8.0	60	0.015

* *Supplies temporarily restricted to Government Contractors only.*

Mullard

MULLARD LTD., COMMUNICATIONS & INDUSTRIAL VALVE DEPT., CENTURY HOUSE, SHAFTESBURY AVENUE, W.C.2
MVT 113

The Cone takes shape



Testing at every stage. *Infinite care is taken at Goodmans to ensure and maintain the uniformly high quality of speaker cones. "Felts" are tested visually for texture as they come from the drying oven before being weighed on a delicate balance.*

Second of a series telling the story of Goodmans Loudspeakers.

It is in the processing tank that the cone first assumes a recognisable shape. Here the pulp, whose manufacture we described in the first of this series, is held in suspension in water: a suspension whose concentration is strictly controlled to ensure absolute uniformity of weight and texture of the finished cones.

The suspension is drawn through a cone-shaped gauze filter by vacuum action, and there emerges a damp, fibrous but recognisably cone-shaped "felt." The young lady in the foreground is seen removing a "felt" as the vacuum filter head rises from the processing tank.

From the processing tank the "felts" pass through an oven where advanced techniques of infra-red drying are applied before passing to the press room for the final shaping, finishing, and testing which will be described in the next of this series. Distinct from the "Open Felting" method described above is the "Transfer" process, by which diaphragms possessing special characteristics are made to customers' specified acoustic requirements.

(above) Producing a cone by the "Transfer" process.

WE SHALL BE AT THE
NORTHERN
RADIO SHOW
CITY HALL MANCHESTER
Apr 23-May 3

GOODMANS

GOODMANS INDUSTRIES LTD. Axiom Works, Wembley, Middx. WEM. 1200

Goodmans Industries Ltd

have pleasure in introducing
the latest in the now famous series of
AXIOM High Fidelity Loudspeakers—

The

AXIOM 150 Mark II

12-inch 15w. P.M. Loudspeaker

This high fidelity reproducer gives extremely smooth response in the middle and upper registers ensuring minimum "scratch" from recordings. On all inputs this shows to advantage no matter what the origin.

The very low bass resonance ensures faithful reproduction down to the lowest audible frequency.

This new AXIOM is a marked advance on past models and is suitable for use with all high quality amplifiers.

A special corner reflex cabinet has been designed with speaker aperture at optimum listening height.

SPECIFICATION

Frequency Coverage ...	30/15,000 c.p.s.
Overall Diameter ...	12 5/16" (31.3 cms)
Overall Depth	6 15/16" (17.6 cms)
Fundamental Resonance	35 c.p.s
Voice Coil Diameter	1¾" (4.4 cms)
Voice Coil Impedance ...	15 ohms at 400 c.p.s
Max. Power Capacity ...	15 watts peak A.C.
Flux Density	14,000 gauss

You are invited to write for details of the Axiom 150 Mk. II and the specially designed corner reflex cabinet.

GOODMANS

The Axiom 150 Mk. II will be on show at Stand 35 at the R.E.C.M.F. Exhibition, April 7-9, and will be demonstrated in a specially designed soundproof room at Stand 47 at the Northern Radio Show, April 23-May 3.

GOODMANS INDUSTRIES LIMITED, Axiom Works, Wembley, Middx. WEMbley 1200



How are YOU fixed?

17 Spire Speed Nuts are used in the assembly of the new Bendix Automatic Washer. Production and assembly costs have thus been reduced considerably because Spire Speed Nuts make assembly easier and faster. Saving has not been achieved at the expense of performance, however. Very far from it. These self-locking fasteners are functionally better than the old methods they replace. And—a very great advantage—each fastener saves 50/75% by materials used.

SNJ

9 SNJ Spire Speed Nuts used to assemble front panel to sides and for securing back panel to top and sides.

8 SNU Spire Speed Nuts used in assembly of Washer base.

SNU

Spire **SPEED NUTS** *fastest things in fastenings*

Enquiries to:
SIMMONDS AEROCESSORIES LTD., Byron House, 7-8-9 St. James's Street, London, S.W.1.
Head Office & Works: Treforest, Glamorgan. Also Birmingham, Stockholm & Melbourne.
CRC265

PREMIER RADIO Company

(REGD.) RADIO

B. H. MORRIS & CO. (RADIO) LTD.
Please quote Dept. W.W.

ESTAB. 40 YRS. TELEVISION

The NEW
PREMIER MAGNETIC TAPE RECORDING KIT

£29 · 8 · 0
(Carriage and Packing 15/-)

Including ALL parts, Valves, Cabinet, Loudspeaker, etc., but excluding Microphone.

To those unable to build this TAPE RECORDER we can offer it completely wired and tested at £34.8.0 plus £1.1.0 Ins., Pack. and Carr.

The kit incorporates the ***NEW MODEL*** **LANE TAPE TABLE** already assembled and ready for use, a **6 VALVE SPECIALLY DESIGNED AMPLIFIER KIT** including **Bias** and **Erase Oscillator for use with the above unit,** and a **WELL MADE WALNUT FINISHED TABLE CABINET** to house the complete unit. Outside dimensions when closed: Height 13¼in., Length 17in., Depth 13¼in.

INSTRUCTIONAL BOOKLET 2'6
This is credited if a complete Kit of the Tape Recorder is ordered.

SPECIAL FEATURES of the Amplifier include separate Bass and Treble lift controls, high and low gain Input Sockets, Record Playback indicator, etc. May be fed from Microphone, pick-up or directly from the Speaker terminals of your radio. Chassis size 14"×9"×2½".

The **PREMIER MAGNETIC TAPE RECORDING KIT** When completed compares favourably with all existing makes.

The **AMPLIFIER KIT COMPLETE**



SPECIFICATION of the ***NEW*** **LANE TAPE TABLE :—** Made to high standards and incorporating features ensuring low level of "Wow" and "Flutter" throughout the full length of tape.

FAST REWIND Provision for fast rewind and forward run in less than 1 min. in either direction. **THREE MOTORS** obviating friction drive.

HIGH FIDELITY RECORD PLAYBACK (1 hour approx. playing). The Table is fitted with high fidelity record play-back head of new design wound to high impedance and a separate **A.C. Erase Head.** The Heads are half track size allowing approx. 1 hr. playing from standard 1,200ft. Reel of Tape.

TAPE SPEED 7½in. sec. **For use on A.C. 200/250, 50 cycles mains only.**

The ***NEW*** **LANE TAPE TABLE**



As is usual in all PREMIER KITS every single item down to the last nut and bolt is supplied. The chassis is punched and lay-out diagrams and theoretical circuits are included.

EACH UNIT MAY BE PURCHASED SEPARATELY

PREMIER AMPLIFIER KIT INCLUDING 8in. SPEAKER	PREMIER TABLE CABINET	*NEW* LANE TAPE TABLE
£7 · 19 · 6	£4 · 18 · 6	£16 · 10 · 0
2/6 packing and carriage	5/- packing and carriage	7/6 packing and carriage

This Recording Outfit has been designed for use with M.C.-1-111 SCOTCH BOY Magnetic Tape. With this high quality tape a frequency range of 50 c.p.s. to 9,000 c.p.s. at tape speed of 7½in./sec. can be readily achieved.
1,200ft. reels 35/-.

WORKING MODELS CAN BE SEEN AT THE ADDRESS BELOW

LUSTRAPHONE High Fidelity Microphones are especially recommended for use with the Premier Magnetic Tape Recording Kit

The slightly rising frequency response together with freedom from distortion makes these microphones especially suitable for transmission of speech, whilst the general frequency characteristic which is entirely free from pronounced peaks, allows the instrument to be most satisfactorily used for recording purposes. All exposed surfaces are either chromium plated or stove enamelled, contributing to the generally attractive appearance of these microphones.

BOTH MODELS CAN BE SUPPLIED FROM STOCK

HAND MICROPHONE
£6 . 6 . 0

STAND MICROPHONE
£5 . 12 . 6

Table Stand £2 . 7 . 6

THIS IS OUR ONLY ADDRESS

207 · EDGWARE ROAD · LONDON · W·2

TERMS OF BUSINESS:
Cash with order or C.O.D. over £1. Please add 1/- for Post Orders under 10/-. 1/6 under 40/- unless otherwise stated

Telephones: ANBassador 4033 PADdington 3271/2

OPEN UNTIL 6PM ON SATURDAYS

PREMIER RADIO Company

REGD. B. H. MORRIS & CO. (RADIO) LTD. EST. 40 YRS.

Please quote Dept. W.W.

RADIO **TELEVISION**

BRAND NEW R1155 RECEIVERS

In original cases, complete with 10 valves. Frequency range 18.5 Mcs.-13 Kcs in 3 wave bands. £12 10 -. 7/6 packing and carriage.

POWER SUPPLY UNIT for above incorporating output stage. Supplies an output of 250 volts at 80 Ma. which is ample for the R1155 with the output stage. Jones plugs for connecting the Power Pack to the Receiver are included. The 6V6 output stage complete with Output Transformer is built into the unit. Price £4.19.6. Plus 5/- packing and carriage.

CAR BATTERIES—BRAND NEW

6 v. 11 plate WALKER Hght. 9½in., Lgth 7¾in., Dpth. 8¾in. Price **65/-**.

6 v. 15 plate READING Hght. 12½in., Lgth 9¼in., Dpth. 7¾in. Price **95/-**.

6 v. 15 plate DELCO-REMY Hght. 12½in., Lgth. 9¼in., Dpth. 7¾in. Price **97.6**.

6 v. 23 plate DELCO-REMY Hght. 8¼in., Lgth. 13¾in., Dpth. 7¾in. Price **110/-**.

12 v. 9 plate WALKER Hght. 8¼in., Lgth. 13¾in., Dpth. 8¾in. Price **110/-**.

ALL PRICES PLUS 7/6 CARR. & PACKING.

PREMIER BABY ALARM KIT



NEW DESIGN

A tremendously improved and re-designed version of the famous Premier Baby Alarm Kit, consisting of a Kit of Parts in Plastic Cabinet to construct a device to enable Baby's cries, or even breathing, to be heard in any selected room in the house. Consists of a 2-valve Amplifier (A.C. mains operated 200/250 volts), with a Midget Telephone used as a Microphone. A 3½in. Loud-speaker is now incorporated in the Kit which, together with other improvements in the design, have resulted in tremendously improved sensitivity and quality of reproduction. May be left permanently connected. Extra Microphones in different rooms may be used without impairing the efficiency of the unit. The lead from Microphone to the unit may be up to 50ft. in length. Complete with valves, Circuit and Instructions. Price **69.6**.

Can be supplied wired and tested ready to plug in at **79.6** plus 2/6 carriage.



SPECIAL OFFER

PREMIER De Luxe BABY ALARM

This is a completely wired and tested amplifier, housed in a grey resine-covered cabinet. Entirely self-contained for use on A.C. or D.C. mains supply of 200/250 volts, already assembled and ready to plug in.

Reduced price **£5 8 -**, plus 1/6 p. & c.

MAINS NOISE ELIMINATOR KIT

Two specially designed chokes with three smoothing condensers with circuit diagram. Cuts out all mains noise. Can be assembled inside existing receiver. **6/-** complete.

BUILD A PROFESSIONAL LOOKING RADIO AT LESS THAN HALF TO-DAY'S PRICE

We can supply all the parts to help you

Bakelite Cabinet (Brown or Ivory)	17 6
Packing and insurance	2 6
Punched chassis, 3-valve plus rectifier T.R.F.	3 9
Engraved Glass Dials, 180-550 and 800-2,200 m.	1 6
With station names, new wavebands	
T.R.F. Coils, 180-550, 800-2,200 metres, pair	6 6
Drum (3¾in. diam.)	1 6
Driving head	1 6
Double pointer	4d.
spring	3d.
Nylon cord (yard)	6d.
Dial Front Plate	2 6

SEND **1 6** FOR EASY TO FOLLOW POINT-TO-POINT DIAGRAMS AND CIRCUIT DIAGRAM which shows how YOU can build the Receiver illustrated above.

THE COMPLETE KIT

to construct a 3 valve plus rectifier TRF Receiver for use on 200/250 v. A.C. mains can be supplied at **£6 9 6** plus 7/6 packing and carriage.

Each Kit is complete in every detail, nothing has to be made or improvised. Easy to follow, point-to-point diagrams are supplied, making construction very simple. The Dial is illuminated and the Receiver housed in a Bakelite Cabinet size 12in. × 8in. × 6in. presents an attractive appearance. The valve line-up is: 717A—H.F. Pentode. VR116—Detector. ATP4—Output, and Metal Rectifier.

Wavebband coverage is for the medium and long bands. Choice of Walnut or Ivory coloured Cabinet.

P.M. MOVING COIL LOUDSPEAKERS (3. ohms Voice Coil)

2½in. W.B.	17 3	8in. Rola	17 6
3½in. Goodmans	15 -	8in. Elac	17 6
3½in. W.B.	19 6	8in. Plessey	14 6
3½in. Plessey	15 -	10in. P.M.C.	27 6
4½in. Rola	27 -	10in. Plessey	29 6
5½in. Rola	27 -	10in. W.B.	44 6
5in. Goodmans	13 6	10in. Wharfedale	62 6
5in. Plessey	12 8	12in. Celestion	£4 5 -
5½in. Elac	14 6	6½in. Rola, Mains energised with trans.(1140 ohms field)	15 -
6½in. Elac	16 6		
6½in. Truvox	12 6		
6½in. Rola	15 -		
6½in. Rola with trans.	16 6		

(15. ohms Voice Coil)

10in. Wharfedale	£3 2 6	12in. Goodmans Audiom 60	£8 12 6
12in. Vitavox K12/10	£8 10 -	12in. Goodmans Audiom 70	£11 - -
12in. Goodmans Axiom 150	£10 5 6	15in. Wharfedale W12C/8	£9 15 -

BURGOYNE SOLDER GUNS, 75/-.

TUNING CONDENSERS

4-Gang .0005 mfd. Ceramic insulation, ¼in. spindle, 5/-; 3-Gang .005 mfd., ¼in. spindle, 7/6.

METAL RECTIFIERS FULL WAVE

6 v. 1 amp. **4/-**; 12 v. 1 amp. **5/-**.

E.H.T. Pencil Type:

Output 450 v. 1 m.a. **4/7** each. 1,000 v. 1 m.a. **6/-** each

BATTERY CHARGER KITS

All incorporate metal rectifiers. Transformers are suitable for 200/250 v. A.C., 50 cycle MAINS.

Cat. No.		
3002	Charges 6 volt accumulator at 1 amp. Resistance supplied to charge 2 v. accumulator	£1 2 6
3003	Charges 12 volt accumulator at 1 amp.	£1 7 6

ACCUMULATORS

By world-famous maker, 2 volt 10 amp. 4/11

IMPORTANT ANNOUNCEMENT: All prices quoted in our advertisements are those ruling at the time of submitting advertisement copy, and are subject to alteration without notice.

HEADPHONES

Balanced Armature Low Resistance
Type 1, 5/11 pair. Type 2, 7/11 pair.
High Resistance
12/6 pair.
Moving Reed
Type 3, 8/11 pair.
Lightweight High Resistance
14/6 pair.

CRYSTAL MICROPHONE

An entirely insulated crystal microphone which can be safely used on A.C./D.C. amplifiers. High impedance. No background noise, really natural tone. The ideal Mike for tape, wire and disc recording and sound projectors. Price **22/6**.

CARBON HAND MICROPHONE

Super quality, with switch in handle. Type 3A, **4/11**

GARRARD ELECTRIC GRAM' MOTOR

Induction motor, 160-250 volts, 50 cycles A.C. only. The GARRARD Induction Motor is totally enclosed. Entirely free from radio frequency disturbance, magnetic hum and electrostatic. Variable speed. With 12in. Turntable. Price **£5.17.6**. Plus packing and carriage 5/-.

Govt. Surplus—Ex-W.D. AERIALS

BRAND NEW

12ft.—5 4ft. screw-in sections of copper-plated steel, highly flexible with non-stick screw fits, tapering ⅞in. to ¼in. *Brand new* in container, **6/6**. Packing and carriage 1/6. Insulated Base, **2/6**. Also plug-in type **3/9**.

These aerials make ideal fishing rods

EX-U.S.A. U.H.F. AERIAL

with untuned detector stage, consisting of V.R.92 valve, etc. Brand new, in carton **5/-**.

FRACTIONAL H.P. MOTOR

A 50 v. 3 phase A.C. motor, 1/40th h.h.p. by famous maker. Supplied complete with resistor, condenser and circuit diagram to convert the motor to ¼ h.p. for use on 240 v. single phase A.C. mains. Brand new **25/-**, plus 2/6 carriage and packing.

GERMANIUM CRYSTAL DIODES

Wire ends, midget size. The ideal Crystal Detector. G.E.C. or R.T.H., **4/6**.

ADJUSTABLE BENCH LAMP

Complete with flex, lampholder and reflector. **25/-**. Post and insurance 2/-.

PREMIER SOIL HEATING EQUIPMENT

Designed specially to aid Growers. Heat is generated with equal intensity in all parts of the circuit by the passing of an electric current. All that is necessary to prepare the equipment for use, is to connect the two heavy leads supplied to the conductor, and the Mains Lead to the nearest switch socket, then switch on.

SPECIFICATION: The unit is housed in a strongly made box, fitted with carrying handles and measures 22in. × 8in. × 12¼in., weight approx. 90lbs., input voltage 200/250 v. A.C., output voltage approx. 6 to 7 volts, output current approx. 220 amps., length of Mains Lead 15ft., length of heavy cable 66ft. complete with two Clamps.

These Units were originally marketed at £30, we have a small quantity left to clear at **£9.9** - plus £1/1/- carriage charge.

SPECIAL OFFER of

ADMIRALTY REFLEX-RE-ENTRANT P.A. LOUDSPEAKERS

V coil 7 ohms. Matching transformers 4.5-1 and 6-1 ratios with volume control at max. Very sensitive and directional. Twin Units, **75/-**. Plus 5/- carriage and packing.

THIS IS OUR ONLY ADDRESS

207 · EDGWARE ROAD · LONDON · W·2

TERMS OF BUSINESS: Cash with order or C.O.D. over £1. Please add 1/- for Post. Orders under 10/-, 1/6 under 40/- unless otherwise stated

Telephones: AMBassador 4033 PADdington 3271/2

OPEN UNTIL 6PM ON SATURDAYS

IMPORTANT ANNOUNCEMENT WE CANNOT ACCEPT RESPONSIBILITY FOR, NOR CAN WE GUARANTEE ANY—

PREMIER RADIO Company

(REGD.) ESTAB. 40 YRS.

R. H. MORRIS & CO. (RADIO) LTD.

Please quote Dept. W.W

RADIO

TRANSMITTER RECEIVER TYPE TR9H



Consists of Transmitter type T1396 and Receiver R1139 in one case. This is a 9-valve Battery operated Unit covering 4.3 Mc/s. to 6.6 Mc/s. Crystal controlled, complete with valves. **50/-**, plus 7/6 packing and postage.

PX25 AMPLIFIERS



A superb push-pull 15-watt model with all the latest refinements, extended tone control range, 3in. moving coil panel meter for current and distortion checks, oil filled condensers, fuses in circuits, two smoothing chokes and although in a steel case the front panel extends to fit on a 19in. standard rack. The high gain circuit of latest design will give full volume from the smallest input. 500 ohm output. Less valves. **£3 5/-**, plus £1/1/- carriage, packing and insurance.

1124 RECEIVER UNIT



Range 30 to 40 mc/s. Contains six new Valves, 3-SP2, 1-SP2, 1-1LD2 (frequency changer) 1-4D1, 24 ceramic trimmers, 6 ceramic valve holders, 6 valve screening cans, 30 resistors, 3 pot-meters, mica and tubular condensers, ceramic coil formers 5-way 4-bank switch with long spindle I.F. transformers, etc. Brand new in makers carton at **22/6** plus 2/6 postage and packing.

7-VALVE SUPERHET CHASSIS



All control mountings cut out, fitted with completely assembled full vision drive scale, long, medium and short waveband and band spread. Heavy flywheel tuning. **19/6**, plus 2/6 pkg and carr.

4-WATT 'GRAM AMPLIFIER

This is a converted ex-Govt. unit, incorporating a 6V6 OUTPUT STAGE giving excellent reproduction on Gram. Complete in a metal case finished in grey enamel. Outside dimensions (approx.) 9in. long, 6¼in. high, 8in. deep. Price **£6 10/-**. Plus 5/- packing and carriage.

RADIO CABINET (WALNUT FINISH)

Outside dimensions: 12¼in. high, 10¼in. deep, 20in. wide.



Price **£2/2/6**, plus 7/6 carr./pkg.

GRAMOPHONE UNITS

"Golden Wing" Playing Desk, consists of the famous Collaro RC500 Autochanger Unit, single speed 78 r.p.m. Mag. Head, mounted on attractive metal plinth **£16 10 0**

Ditto, (Unmounted, with Mag. Head) **£11 16 9**

Ditto (Unmounted, with Crystal Head) **£12 2 11**

Collaro 3 speed "Golden Wing" Playing Desk, consists of the famous Collaro RC511 3 speed Autochanger Unit mounted on attractive metal plinth, with dual purpose Head suitable for long playing and standard recordings **£18 14 1**

Ditto, (Unmounted, with Dual Purpose Head) **£15 11 9**

Ditto, (Unmounted, with two separate plug-in Heads, one long playing, one standard) **£18 14 1**

Collaro single speed rim drive Unit with plug-in Mag. Head, 78 r.p.m. **£6 10 6**

BSR Model GC4 3 speed Gram unit, incorporates the latest type of Crystal turnover Head for long playing and standard recordings **£9 19 11**

Garrard Gramophone Motor. Variable speed induction Motor. Complete with 12in. turntable (this Unit does not include Pick-up) **£5 19 6**

Connoisseur 2 speed Gram. Unit LESS Pick-up **£22 18 8**

Pick-up with 2 Heads for above **£10 0 8**

Conrad Rim Drive Gramophone Unit LESS Pick-up Arm 78 r.p.m. **£3 3 10**

Ditto, 33 r.p.m. **£4 7 5**

Decca 3 speed Rim Drive Gram Unit LESS Pick-up **£7 3 4**

Decca Single Speed Rim Drive LESS Pick-up, 78 r.p.m. **£3 14 4**

Ditto, 33 r.p.m. **£3 14 4**

Decca Pick-up with 2 Heads, one long playing, and onestandard **£7 0 0**

Plessey Autochanger 3 speed Mag. Head, plays mixed records **£23 13 0**

Please add 5/- extra for packing and carriage charges on Gramophone Units.

ALL THE ABOVE ARE FOR USE ON A.C. MAINS ONLY

PREMIER SUPERHET COILS

16-50, 180-550, 800-2,000 metres, set with circuit. **10/6**.

SUPER QUALITY TELEVISION MAGNIFYING LENS

To suit 5in., 6in. or 7in. Tubes. Increase picture size considerably. **25/-** each.

CORRECT ASPECT WHITE RUBBER MASK

For 12in. Round or Flat faced Tube **16 11**

PREMIER TELEVISOR CABINET FOR 12in. TUBE TELEVISOR

A handsome walnut finished cabinet. Primarily designed for our own Kits. They are quite suitable for most of the kits published in the various Radio periodicals. For this reason the holes for control knobs have not been drilled. A baffleboard suitable for a 10in. Loudspeaker is provided. Outside dimensions 33¼in. high, 20½in. deep 16in. wide **£9 9/-**, plus 7/6 packing and carriage.

TELEVISION

RADIO CABINET (WALNUT FINISH)

Outside dimensions: 16½in. high, 9in. deep, 17in. wide



A beautifully made cabinet. **£3 10/-** plus 7/6 carr. pkg.

5-VALVE SUPERHET RADIO CHASSIS



Drilled and cut out for all necessary control mountings and Mains Transformer, fitted with 5 Amphenol Octal Valveholders, Aerial Earth and Gramophone Sockets 800 pf Tuning Gang Condenser, full vision drive Tuning Assembly consisting of unbreakable perspex 3-coloured scale for long, medium and short wavebands. Calibrated in metres, kilocycles and station names, price **39/6**

AS A SPECIAL OFFER—CABINET ILLUSTRATED ABOVE AND CHASSIS, TOGETHER £5. 5. 0. Plus 7/6 Carr. Pkg. & Insurance.

RADIO CABINET (WALNUT FINISH)

Outside dimensions: 17in. high, 11in. deep, 16in. wide



Price **£2/2/6**, plus 7/6 carr. / pkg.

THIS IS OUR ONLY ADDRESS

207 · EDGWARE ROAD · LONDON · W·2

TERMS OF BUSINESS: Cash with order or C.O.D. over £1. Please add 1/- for Post Orders under 10/-. 1/6 under 40/- unless otherwise stated.

Telephones: AMBassador 4033 PADdington 3271/2

OPEN UNTIL 6PM ON SATURDAYS

—KIT OR COMPONENT SOLD AS A PREMIER PRODUCT BY FIRMS OTHER THAN OURSELVES

Osmor 'Q' RANGE Coils...

ACTUAL SIZE

are super selective!

Great Noose! OSMOR "Q" RANGE COILS make rings around all imitations—they're picked out by experts for their super-selectivity and sensitivity. What other coils can give you these 5 BIG STAR features?

★ Only 1in. high ★ Variable iron dust cores ★ Low loss Polystyrene formers
★ Packed in damp-proof containers ★ Fitted tags for easy connection

You can't go wrong with OSMOR "Q" COILS—the water-tight guarantee is your positive assurance of satisfaction.

COILPACKS. A full range is available for Superhet and T.R.F. Mains or Battery. Size only 1⅞in. high × 3⅛in. wide × 2¼ins. Ideal for the reliable construction of new sets, also for conversion of the 21 RECEIVER, TR. 1196, TYPE 18, WARTIME UTILITY and other Types.
Aligned and tested with full circuits, etc. Fully descriptive leaflets available.

WARNING! Avoid inferior imitations. Genuine OSMOR Coilpacks are sold only under the name OSMOR.

MATCHED COMPONENTS. Various types of OSMOR Dials, Chassis, I.F.'s, Speakers, Transformers, etc., etc., to match our coils and coilpacks are all listed.

Send 5d. (stamps) for FREE CIRCUITS and full lists of coils, coilpacks and radio components.

OSMOR RADIO PRODUCTS LTD. (Dept. W.29), BRIDGE VIEW WORKS, BOROUGH HILL, CROYDON, SURREY. Tel.: Croydon 5148 9

FOR RADIO OSMOR RELIABILITY

FOR HIGH-FREQUENCY INSULATION
—specify 'FREQUELEX'



The illustration shows a Four Gang Radio Variable Condenser using our "FREQUELEX" Ceramic Rod for the Centre Rotating Spindle. This Rod is 7¼" long × .437" diameter, centreless ground to within plus or minus .0005". Maximum camber allowance of .002".
This is only one of many applications where Rods made to close limits are required.
We specialise in the manufacture of Ceramic Rods and Tubes of various sections in several classes of materials over wide dimensional ranges.

The Principal Materials Are:—

1. **Porcelain for General Insulation**
2. **Frequelex for High-Frequency Insulation**
3. **Permalex and Templex for Capacitors**

The degree of accuracy depends on the size of the Rod or Tube, but the standard degree of accuracy is outlined in the Inter Service Component Manufacturers' Council — Panel R Specification embodied in our Catalogue of Radio Frequency Ceramics, copy of which will be sent on request.
Large Rods up to 44" long and 1¼" square are used as supports for Tuning Coils, etc.
We shall be pleased to have your enquiries for all sizes of Tubes and Rods. Prompt deliveries can be given for most sizes.

Condenser manufactured by Messrs. Wingrove & Rogers Ltd.

Bullers LOW LOSS CERAMICS

BULLERS LIMITED, 6 Laurence Pountney Hill, E.C.4 Phone: MANsion House 9971 (3 lines) Grams: 'Bullers, Cannon, London'

BL1B

● LET OTHERS SPEAK ABOUT *Stentorian* SPEAKERS

These unsolicited letters are typical of those received from Stentorian users — they are evidence of the benefits of specialisation.

A speaker for every need



from 2½" to 12" cone dia.

The reasons for the outstanding quality of reproduction given by W.B. chassis are because the actual designers of the first great W.B. moving coil speaker over 25 years ago are still personally engaged in improving Stentorians, and because all operative parts — "Alcomax" magnet, graduated multi-fibre cone, speech coil assembly, transformer, are designed and made in the one organisation, under the same knowledgeable supervision.

● The famous Stentorian Concentric Duplex has been acclaimed as the ultimate in fine reproduction. This distinguished speaker is available as 10" and 12" chassis and also in handsome cabinets.

"I am very glad to say that this speaker is giving me great satisfaction. Its frequency response, transient response and power handling capacity are truly remarkable, particularly for such a moderately priced speaker. It surpasses most other speakers I have heard, even considerably more costly ones."

●

"It will doubtless be of interest to you to learn that this particular W/B 10" loudspeaker was purchased during 1928 and continues to give excellent service."

●

"It surprises me how you get a single cone unit, like the S.1012, to cover such a wide frequency range. Every note and syllable comes out with such natural realism. For instance, the 'ting' of the triangle and clash of the cymbals are very clearly heard—but not at the expense of the bass, for that is there too in correct proportion, resulting in a very good balance of tone."

●

"Thanks once again for a really fine speaker (in fact the finest speaker) in my humble opinion."

●

"You may be sure that I would do my utmost to insist that your 10" Unit be used exclusively. I doubt if there is a better one of its type in the World, or even as good, and we have tried a few. This is not idle flattery, but a fact which can be demonstrated at any time.

●

"I must congratulate you on producing the finest speaker unit I have had the privilege to own. Your claims regarding the performance of the 10" Concentric Duplex speaker are not in any way exaggerated. I find it ideally suited for domestic use."

●

Stentorian **LOUDSPEAKER CHASSIS**

W B

Full details and prices of Stentorian Speakers available on request.

WHITELEY ELECTRICAL RADIO CO. LTD · MANSFIELD · NOTTS

This MARKS THE SPOT...
FOR AERIAL NEWS AND VIEWS

The £.S.D. of T.V. Aerial Erection

THE ever-rising cost of wages and transport make it increasingly difficult for dealers to keep their installation prices at a reasonable level while providing a sound installation. Any economies made by skimping the job soon come home to roost, as the labour cost of servicing a television aerial may well be as much as the original installation. The real solution is to use an aerial which can rapidly be assembled and installed, and is also thoroughly reliable.

Of all directional aerials the most simple and the quickest to install is undoubtedly the "Antex", as all installation engineers who have used it would immediately agree. The absence of a spacer arm reduces the weight and increases the mobility, and the use of a single moulded weatherproofed junction unit provides positive alignment of the four aerial rods. The essentially practical mechanical design incorporates screw-in aerial rods of tough aluminium alloy, which can be assembled on the roof if required. As is the case with all Antiference arials, the reliability of the "Antex" is without question and if efficiently erected will provide years of service without further attention.

There is a model suitable for every location. Full details in leaflet No. E.30.W sent on request.

Other Antiference Aerials

Single Dipole, Dipole and Reflector, Three Element arrays, etc.; also Radio aerials including "Exstat" Anti-static Aerials, "Silmount" for the flat dweller, and the "Autoserial" for the car.

ANTIFERENCE *Aerials*

ANTIFERENCE LIMITED 67 BRYANSTON ST LONDON W.1

MAINS TRANSFORMERS

FULLY INTERLEAVED
SCREENED AND IMPREGNATED. ALL GUARANTEED.
ALL PRIMARIES ARE 200/250 v. Half Shrouded.

HSM63. (Midget). Output 250-0-250 v. 60 m/a., 6.3 v. at 3 amps., 5 v. at 2 amps. 18/-
HS63. Output 250-0-520 v. 60 m/a., 6.3 v. at 3 amps., 5 v. at 2 amps. 18 6
HS40. Windings as above. 4 v. at 4 amps., 4 v. at 2 amps. 18 6
Output
HS2. 250-0-250 v. 80 m/a. 21/-
HS3. 350-0-350 v. 80 m/a. **GS30.** 300-0-300 v. 80 m/a. 21/-
HS2X. 250-0-250 v. 100 m/a. **HS75.** 275-0-275 v. 100 m/a. 23/-
HS30X. 300-0-300 v. 100 m/a. **HS3X.** 350-0-350 v. 100 m/a. 23/-

Fully Shrouded

FSM63. (Midget). Output 250-0-250 v. 60 m/a., 6.3 v. at 3 amps., 5 v. at 2 amps. 18 6
Output
FS2. 250-0-250 v. 80 m/a. 23/-
FS30. 300-0-300 v. 80 m/a. **FS3.** 350-0-350 v. 80 m/a. 23/-
FS2X. 250-0-250 v. 100 m/a. **FS75.** 275-0-275 v. 100 m/a. 25 9
FS30X. 300-0-300 v. 100 m/a. **FS3X.** 350-0-350 v. 100 m/a. 25 9
All the above have 6.3-4-0 v. at 4 amps., 5-4-0 v. at 2 amps.
FS43. Output 425-0-425 v. 200 m/a., 6.3 v. 4 amps., C.T. 6.3 v. 4 amps., C.T. 5 v. 3 amps. Fully shrouded 51/-
FS50. Output 450-0-450 v. 250 m/a., 6.3 v. 2 amps., C.T., 6.3. v. 4 amps., C.T. 5 v. 3 amps. Fully shrouded 75/-
F30X. Output, 300-0-300 v. 80 m/a., 6.3 v. 7 amps., 5 v. 2 amps. Framed. Flying leads 31 9
F35X. Output, 350-0-350 v. 250 m/a., 6.3 v. 6 amps., 4 v. 8 amps., 4 v. 3 amps., 0-2-6.3 v. 2 amps. Fully shrouded 71 6
FS160X. Output, 350-0-350 v. 160 m/a., 6.3 v. 6 amps., 6.3 v. 3 amps., 5 v. 3 amps. Fully shrouded 47 6
FS43X. Output, 425-0-425 v. 250 m/a., 6.3 v. 6 amps., 6.3 v. 6 amps., 5 v. 3 amps. Fully shrouded 69/-
HS6. Output, 250-0-250 v. 100 m/a., 6.3 v. 6 amps., C.T. 5 v. 3 amps. For receiver R1355. Half shrouded 29 3
HS150. Output, 350-0-350 v. 150 m/a., 6.3 v. 3 amps., C.T. 5 v. 3 amps. Half shrouded 30 9
F36. Output, 250-0-250 v. 100 m/a., 6.3 v. 6 amps., C.T. 5 v. 3 amps. Fully shrouded 32 6
FS120. Output, 350-0-350 v. 120 m/a., 6.3 v. 2 amps., C.T. 6.3 v. 2 amps., C.T. 5 v. 3 amps. Fully shrouded 33/-
FS256. Output, 250-0-250 v. 80 m/a., 6.3 v. at 6 amps., 5 v. at 3 amps. Fully shrouded 30 9
PR11. Output 230 v. at 30 m/a., 6.3 v. at 1.5/2 amps. 23/-
FS150. 350-0-350 v. 150 m/a., 6.3 v. 4 amps., 5 v. 3 amps. 34 9
FS150X. Output, 350-0-350 v. at 150 m/a., 6.3 v. at 2 amps., C.T. 6.3 v. at 2 amps., C.T. 5 v. at 3 amps. Fully shrouded 34 9
The above have inputs of 200/250 v.

FILAMENT TRANSFORMERS

F4. Output, 4 v. 2 amps., **F6.** Output, 6.3 v. 2 amps. 9/-
F12X. Output, 12 v. at 1 amp., 9/-. **F6X.** Output, 6.3 v. 0.3 amps. 6/-
F12. Output. 12.6 v. tapped 6.3 v. at 3 amps. 18 6
F24. Output, 24 v. tapped 12 v. at 3 amps. 26/-
F12 and F24 framed with Flying Leads.
FU6. Output, 0-2-4-5-6.3 v. at 2 amps. 11/-
F29. Output, 0-2-4-5-6.3 v. at 4 amps. 20 9
FU6 and F29 clamped with Flying Leads.
F3. Output 6.3 v. at 10 amps. or 5 v. at 10 amps. or 12.6 v. at 5 amps. or 10 v. at 5 amps. 37 9
F6.4. Output, four at 6.3 v. tapped at 5 v. at 5 amps. per winding giving by suitable series and parallel connections 24 v. at 5 amps., 20 v. at 5 amps., 18 v. at 5 amps., 15 v. at 5 amps., 12.6 v. at 10 amps., 10 v. at 10 amps., 6.3 v. at 20 amps., 5 v. at 20 amps. 57/-
F5 and F6.4 framed with Flying Leads.
FU12. Output 0-4-6.3 v. 3 amps. **FU24.** Output 0-12-24 v. 1 amp. 19 6
The above have inputs of 200/250 v.

OUTPUT TRANSFORMERS

MOP1. Ratios, 26, 46, 56, 66, 90, 120-1 50 m/a. max. current. C.T. for Q.P.P. Class B, etc. Secondary 2/4 ohms. Top panel and clamped, each 6/-
OP1. Midget Power Pentode, ratios 30, 60, 90-1, 40 m/a. Secondary 2/3 ohms, each 4/-
OP2. Midget Pentode, ratios 45-1, Secondary 2/3 ohms, 40 m/a., per doz. 39 6
OP10. 10/15 watts output. 20 ratios on Full and Half primary 19 9
OP30. 30 watts output, 20 ratios on Full and Half primary 28 6
Williamson's O.P. Transformer to Author's specification £8 13 6
Chokes for Williamson's Ampl.fier. 30H. at 20 m/a. 18 6
10H. at 150 m/a. 35 6
Choke C4. 60 m/a., approx. 8H, 350 ohms 5/-
Choke C5. 40 m/a., approx. 5 H., 350 ohms 4/-
Choke C6. 50 m/a., 50 H., 1,500 ohms 22/-
C8. 360 Micro henries clamped, **5/3. C7.** 90 m/a. 180 ohms, clamped 6/3
Belling-Lee Co-Axial Plugs. Type 642/P., each 1/3
Belling-Lee Co-Axial Sockets. Type 604/S, each 1/3
Quotations, etc.—stamped addressed envelope please.
C.W.O. (add 1/3 in £ for carriage), all orders over £2 carriage paid.
Trade and also Export enquiries invited.

H. ASHWORTH (Dept. WW)
676, Gt. Horton Road, Bradford, Yorks.

PAINTON

By Appointment to the Professional Engineer...



ATTENUATORS · FADERS · SWITCHES · WIREWOUND POTENTIOMETERS · PLUGS
AND SOCKETS · WIREWOUND RESISTORS · HIGH STABILITY CARBON RESISTORS
KNOBS DIALS AND POINTERS · TERMINALS

PAINTON

Northampton England





INSTRUMENT CASES FROM STOCK

90 per cent of our standard range of cases, including enclosed racks, is available from stock for delivery within 48 hours. Imhof standard enclosed rack units in 4ft. and 6ft. sizes 19in. deep and taking 19in. panels, and standard instrument cases in twenty-two different types and sizes are designed to meet the main needs of electronic instrument housing. They are available in any quantity from one upwards and give you the advantages of low price based on quantity production with no design worries or tool charges and NO PRODUCTION DELAYS. Please write for our 1952 catalogue and latest price list of full standard range.

IMHOF'S

ALFRED IMHOF LIMITED, 112-116 NEW OXFORD STREET, LONDON, W.C.1. MUSEUM 7878

COPPER INSTRUMENT WIRE (ex-stock)

SWG	Inch	ENAMELLED 2 ozs.	ENAMELLED 4 ozs.	TINNED 2 ozs.	TINNED 4 ozs.	COTTON COVERED 2 ozs.	COTTON COVERED 4 ozs.	SILK COVERED 2 ozs.	SILK COVERED 4 ozs.
16	.064	1/3	1/10	1/3	1/10	1/3	1/10	1/3	1/10
17	.056	1/3	1/11	1/3	1/11	1/3	1/11	1/3	1/11
18	.048	1/3	2/–	1/3	2/–	1/3	2/–	1/3	2/–
19	.040	1/3	2/1	—	—	1/4	2/1	1/5	2/3
20	.036	1/4	2/2	1/4	2/2	1/4	2/2	1/6	2/6
21	.032	1/4	2/3	—	—	1/4	2/3	1/7	2/8
22	.028	1/5	2/4	1/5	2/4	1/5	2/4	1/8	2/10
23	.024	1/6	2/5	1/6	2/5	1/6	2/5	1/9	3/–
24	.022	1/6	2/6	1/6	2/6	1/6	2/6	1/9	3/–
25	.020	1/7	2/7	1/7	2/7	1/7	2/7	1/10	3/2
26	.018	1/7	2/8	1/7	2/8	1/8	2/9	1/11	3/4
27	.0164	1/8	2/9	—	—	1/9	2/11	2/–	3/6
28	.0148	1/8	2/10	1/8	2/10	1/9	3/–	2/1	3/8
29	.0136	1/9	2/11	1/9	2/11	1/10	3/2	2/2	3/10
30	.0124	1/9	3/–	1/10	3/3	1/11	3/4	2/3	4/–
31	.0116	1/10	3/1	1/11	3/4	2/–	3/5	2/4	4/2
32	.0108	1/10	3/2	2/–	3/6	2/–	3/6	2/6	4/6
33	.010	1/11	3/3	2/1	3/8	2/2	3/9	2/9	5/–
34	.0092	1/11	3/4	2/2	3/10	2/3	4/–	2/10	5/2
35	.0084	2/–	3/5	2/3	4/–	2/5	4/3	3/–	5/6
36	.0076	2/–	3/6	2/5	4/3	2/6	4/6	3/2	5/10
37	.0068	2/1	3/8	2/6	4/6	—	—	3/4	6/2
38	.006	2/2	3/10	2/8	4/9	3/3	6/–	3/6	6/6
39	.0052	2/3	4/–	2/9	5/–	—	—	3/9	7/–
40	.0048	2/4	4/2	2/11	5/4	4/6	8/–	4/–	7/6
41	.0044	1/6 per oz.		1/9 per oz.				2/3 per oz.	
42	.004	1/9 " "		2/– " "				2/6 " "	
43	.0036	2/3 " "						3/– " "	
44	.0032	3/– " "						4/– " "	
45	.0028	4/– " "						5/6 " "	
46	.0024	5/– " "						7/6 " "	

47 & 48 swg Enam. and 47 swg E.S.S.C. wires in stock. State needs.

ALL ABOVE POSTAGE EXTRA.

POST ORDERS ONLY PLEASE Send stamp for comprehensive lists.

RESISTANCE WIRES

Prices per ounce

SWG	Enam.	D.R.C.
16	1/6	1/6
17	1/6	1/6
18	1/6	1/6
19	1/6	1/6
20	1/6	1/6
21	1/6	1/6
22	1/6	1/8
23	1/6	1/10
24	1/8	2/–
25	1/10	2/2
26	2/–	2/4
27	2/–	2/4
28	2/–	2/6
29	2/2	2/6
30	2/2	2/6
31	2/3	2/8
32	2/3	2/9
33	2/4	3/–
34	2/6	3/–
35	2/8	3/3
36	2/9	3/6
37	3/–	3/9
38	3/3	4/3
40	—	4/9

44 & 46 swg stocked.

LITZ WIRES also available.

Large stocks of B.A. SCREWS, NUTS, WASHERS, SOLDERING TAGS & EYELETS; Paxolin type TUBING; Laminated Bakelite and Ebonite PANELS; TUFNOL and EBONITE TUBES and ROD; ERIE and DUBILIER RESISTORS; GERMANIUM and SILICON DIODES.

Trade supplied.

POST RADIO SUPPLIES
33 BOURNE GARDENS, LONDON, E.4



For Mutual and Self Inductance measurement...

..... in the range 0.001μH to 30mH, the 'CINTEL' Mutual and Self Inductance Bridge will be found unequalled for accuracy and simplicity of use. Also measuring resistance in the range 100μΩ to 3000Ω, this bridge is an essential piece of laboratory equipment, full details of which are available on request.

CINEMA-TELEVISION LIMITED

A Company within the J. Arthur Rank Organisation

WORSLEY BRIDGE ROAD · LONDON · SE 26

Telephone: HITher Green 4600

SALES AND SERVICING AGENTS

F. C. Robinson & Partners Ltd., 287 Deansgate, Manchester, 3
H. Hawnt & Co., Ltd., 59 Moor St., Birmingham, 4
Atkins, Robertson & Whiteford Ltd., 100 Torrisdale Street, Glasgow, S.2

CINTEL

REGISTERED TRADE MARK

Recognised as the Most Reliable Valveholders

Now in full production NOVAL and B7G Valveholders of all types in NYLON LOADED BAKELITE



We make all types of Valveholders

Wholesale Enquiries:—CYRIL FRENCH LTD., HIGH STREET, HAMPTON WICK, MIDDLESEX · KIN. 2240
Manufacturers' Enquiries:—THE McMURDO INSTRUMENT CO. LTD., VICTORIA WORKS, ASHTEAD, SURREY ASHTEAD 3401

the new

ADC speaker

A BRITISH INVENTION

PERFECT & NATURAL REPRODUCTION

Manufactured by:—

AUDIO-ACOUSTIC DIFFUSEURS LTD.

BROOK HOUSE, PARK LANE, LONDON, W.1

Factory: Torrent Street, Arundel.



THE A.D.C. SPEAKER DESIGN
Model C

The most revolutionary design in Loudspeakers since the advent of the Moving Coil.

1. Magnet assembly gives 15,000 gauss. 2, 4. Voice coil, both windings operate in undistorted field. 3, 7, 8. The suspension system offers constant frictional resistance to motion. 5. The suspension is such that the terminating periphery of the actual Cone is not a free edge. 6. The Cone and supporting member do not constitute a change of medium at their junctions.

From above follows

A. NO MECHANICAL RESTORING FORCE.
B. THE SYSTEM IS FREE FROM FUNDAMENTAL RESONANT FREQUENCY.
C. THE MOTIONAL DECAY TIME OF THE CONE ASSEMBLY HAS SQUARE WAVE FORM.
D. TRANSIENTS ARE THUS FREE FROM FUNDAMENTAL RESONANT FREQUENCY MODULATION.

Technical Details

Resonant Frequency—Nil. Smooth sinusoidal base wave form. No phase-change or voltage generated in voice coil. **Decay Time**—Open voice coil circuit critical non oscillatory. **Cone Damping**—Resistance at all frequencies. **Cone Movement**—Linear at all frequencies. **Air Loading**—Both sides radiating 20 grams. **Motion Modulation**—Electrical, non-mechanical. **Frequency Response**—30 to 16,000 cycles. **Transient Response**—Transients are free of basic resistance and reverse modulation throughout the frequency scale. **High Frequency**—Low ambient noise level, wide angle 70° of axis at 10,000 cycles. **Reproduction**—The tone is without colouration and hardness, therefore the colour-tone of any musical instrument is not altered by the addition of colour-tone from the speaker.

Write for illustrated Brochure.

The World's first Reproducer in Audio Sound.

ADVANCE COMPONENTS LTD., BACK ROAD, SHERNHALL STREET, LONDON, E.17 Telephone : LARkswood 4366/7/8

THE ADVANCE TYPE H1

The Advance type H1 Audio Signal Generator completely covers the unusually wide range of 15 c/s to 50,000 c/s. It is characterised by its extremely low distortion and level output over the entire range ; provides both sine and square wave output. A robust, reliable and accurate instrument for the discriminating service engineer

● *Accuracy ± 1%, ± 1 c/s.* ● *Distortion less than 1% at 1,000 c/s.* ● *Output from 200 microvolts to 20 volts with accuracy of ± 2 db.* ● *Weight 14 lb.* ● *Size 13½" × 10½" × 8"*

Full technical details available in Folder S.16.W

Advance audio generator

ADVANCE COMPONENTS LTD., BACK ROAD, SHERNHALL STREET, LONDON, E.17 Telephone : LARkswood 4366/7/8



Photograph by courtesy of Raymond Electric Ltd.

FOR HIGH SPEED PRECISION SOLDERING USE

DU BOIS

TRI-SOL

Activated

RESIN CORED SOLDER

'Tri-Sol' offers a consistently high standard of flux for high speed precision soldering. Specially designed for radio, television and electrical assemblies. The core reduces the thickness of the solder wall ensuring the correct proportion of flux. Prov. pat. 6654/50.

THE DU BOIS CO. LTD., BRITANNIA ST., KING'S CROSS, LONDON, W.C.1. *TERminus 6624*

"Cyldon" Precision Variable CAPACITORS

Miniature Trimmers to High Voltage Transmitter Capacitors



For precision, stability, and long life, "Cyldon" superiority is recognised by all designers and users of electronic equipment.

5-Gang Capacitor

Designed to the requirements of Mobile Communications equipment for operation from −35° to +55°C. at a max. R.H. of 90 per cent. Metal parts cadmium plated, followed by chromic acid passivation dip. Exceptions are the tinned terminals, stainless steel worm and ball race, and the anti-backlash gearing. A 36:1 reduction drive, fitted with a stop limiting rotation to 180°, enables smooth fine capacity setting. The effective max. cap. per section is 29pF matching to the oscillator section within ±0.2pF. The air-spaced trimmers each provide an effective change of capacity of not less than 6pF. Rotor connections are via five insulated silver contact wipers, permitting contact to each rotor section.

This capacitor is subjected to a breakdown test of 500v. D.C. between any rotor and stator section.

● *Full details of the complete "Cyldon" range, and list of Overseas Agents available from the Manufacturers*

SYDNEY. S. BIRD & SONS. LTD

Contractors to Ministry of Supply, Post Office, and other H.M. Government Depts.

CAMBRIDGE ARTERIAL ROAD · ENFIELD · MIDDX. *Enfield 2071*

HANNEY OF BATH

Offers the following brand new goods from stock :—

WILLIAMSON AMPLIFIER. PARTRIDGE output transformers (1.7 ohm sec) 127/-; WODEN potted components as follows: 200 mA. mains trans., 95/-; 10H 150 mA. choke 37/6; 50H 20 mA. choke 28/-; pre-amp mains trans. (Fig. 19) 45/-; T.C.C. 8 mfd. 600 volt electrolytic condensers 15/-; .25 mfd. TCC metalpaks 2/10; .05 metalmites 1/1. Reliance 100 ohm 5 watt pots 5/6; Elstone mains trans. to specification 57/6; 130 mA. 10H. choke £1; 30H 20 mA. choke 10/-; RESISTOR POT kits available for Main Amplifier 33/9; (Fig. 13) 9/6; (Fig. 15) 24/-; (Fig. 19) 37/-; (Fig. 20) 6/8. CONDENSER kits (Fig. 13) 15/-; (Fig. 19) 47/-; (Fig. 19) 54/6; (Fig. 20) (less C66 and C72) 12/9. All are complete with Dubilier electrolytics, 19 1% silver micas for Fig. 19 15/-, 7 5% 7/-; 5 bank 6 position switches 9/6; S.P.D.T. genuine OAK switches 4/4; D.P.D.T. 4/6. Matched pair KT66 valves 50/2. EF37A's 25/1; 35KU rectifiers 21/6 (indirectly heated, 5 v. 3 a.—500 v. 250 ma).

VIEWMASTER. Complete kit of parts carriage paid £29/10/-, or in complete stages as follows: Stage 1 61/-; Stage 2 42/9; Stage 3 £5/1/8; Stage 4 9/10; Stage 5 £9/18/9; Stage 6 £6/18/6; Stage 7 53/-. W.B. components, all chassis, heater trans., choke and speaker packed into one carton £6/8/6 or separately as follows: WB100 (sound and vision chassis) 18/6; WB101 6/-; WB102 18/6; WB103 37/6; WB104 15/6; WB105 32/6; WB105A 52/6; TCC condensers £7/7/-; Morganite resistors 35/3; Type Q pots 5/- each Westinghouse rectifiers 5EHT100 29/5; 14A86 20/4; 14D36 11/7; WX3 and WX6 3/6 each. Colvern pots, set of 6 22/8, or CLR901 3/- each and 8K-CLR 4099/73 6/4. Boigin kit 13/6. WB Pre-amp chassis 17/7; coils £3 pair. Line Trans. 27/9. Frame trans. 22/6; Width control 10/-; Boost choke 5/9; Tube supports 18/9; Focus rings WB100/1 for Mazda 29/6; Plessey 7200S for Mullard 22/6; Set of 12 valves to exact specification £12/10/4 inc. tax. Any item sold separately from 1 resistor or condenser upwards.

CATHODE RAY TUBES. 9in. Mullard MW9-14C, MW9-16, 12 and 18, Mazda CRM 92 £13/13/7; 12in. Mullard MW31-14C, MW31-16, 17 and 18 Mazda CRM 121A and 121B £18/4/10; Mazda CRM 123 £20/10/4; Brimar C12B £19/7/4. We pay carriage on all tubes and guarantee safe delivery per passenger train. Long and Hambly new aspect ratio cream masks 12in. 22/6 pair, 11/-.

ACOS GP20 pick-ups, standard or LP £3/11/5; heads only £2/3/4. Acos crystal microphones MIC 22-2 and MIC 22-1 £6/6/- either model.

COLLARO AUTOMATIC RECORD CHANGERS. Model RC 500 magnetic PU head £11/15/6; Crystal PU £12/2/6; Model RC 511. THREE SPEED with 2 Hi-Fi crystal PU heads £18/14/1.

DECCA gram-motors, less pick-up, 2 speed 74/4, 3 speed £7/3/4.

All goods are still available as per our Feb. and March adverts. C.W.O. or C.O.D. please add 9d. P. & Pkg. on all orders under £1, over this amount post free. 2/- is added to all C.O.D. orders under 50/-

L. F. HANNEY

77 LOWER BRISTOL ROAD, BATH

Telephone 3811

Sole Distributors for **BURGOYNE** MAGNETIC RECORDING HEADS **39'6** each Record/ Playback or Erase

RADIO & TELEVISION · ELECTRICAL APPLIANCES · ELECTRIC TOOLS · KITS

RADIO CENTRE

TEST EQUIPMENT · HI-FI REPRODUCTION · TAPE RECORDERS · AMPLIFIERS

Sole Distributors for **BURGOYNE** MAGNETIC RECORDING TAPE TABLES OSCILLATOR COILS, Etc.

The "BURGOYNE" TAPE TABLE

TAPE RECORDER KITS

KIT A. Comprising Burgoyne Tape Table, Lane Oscillator Unit and MO8 A4 R/P Amplifier Kit for **£25.19.6** Cash or **£6/13/6** deposit and 12 monthly payments of 2/-.

KIT B. Comprising Burgoyne De Luxe Tape Table, Lane Oscillator Unit and MO8 A4 Record/Playback Amplifier Kit for **£34.10.-** Cash or **£11.10.-** deposit and 12 monthly payments of 43/-.

★ **Precision built.** ★ **3 motors with ample reserve of power.** ★ **Fast re-wind facilities.** ★ **Tape speed : 7½in. per second.** ★ **Heavy precision balanced flywheel.** ★ **High fidelity heads—perfect alignment.** ★ **Half track width high impedance heads.** ★ **Negligible "wow" and "flutter."** ★ **Take up spool supplied.** ★ **Circuit diagram included.** ★ **For use on A.C. mains.**

£16/10 CASH or £6/10 Deposit and 12 monthly payments of 20/-
Plus 10/- carr. & packing

TANSA RECORD/PLAYBACK, PLAYBACK AND ERASE HEADS, still available from stock **59/6** each. These are current production series 100. *Fully Guaranteed.*

***Introducing the* BURGOYNE OSCILLATOR COIL**
with circuit diagrams **8/6** (Post & Packing 6d)

The LANE OSCILLATOR UNIT
70/- or 10/- deposit
& 12 monthly payments of 8/4

The BURGOYNE DE LUXE TAPE TABLE at £25 will soon be available
£9 deposit and 12 monthly payments of 30/-
(10/- post and packing extra)

M.O.S. RECORD/PLAYBACK AMPLIFIER KIT, TYPE A4

For use with high impedance record/playback heads, such as the Burgoyne series.
In the Record position, the amplifier has provision for microphone and gramophone inputs, and a mixer circuit allows fading and balancing between them. A provision is also made for monitoring the material being recorded on headphones.
In the Playback position the circuit is re-arranged to form a stable high gain amplifier. The playback pre-amplifier stage uses an EF37A giving extremely high signal to noise ratio, complete freedom from microphony, and negligible hum. Pre-set equaliser circuits are included and further tonal adjustment is given by variable tone control.
The microphone circuit is terminated in an impedance satisfactory for crystal microphones, the Acos MIC 22-2 at **£6.6/-** being particularly recommended. There is sufficient output to modulate all types of tapes.

KIT COMPLETE with instruction manual **£6 . 19 . 6**
Instruction Manual Only **3/9.**
Or **£2** Deposit and 12 monthly payments of **11/8.**

"HANDY UTILITY" TOOLS

Low priced electric tools for every engineers kit.

Tough Drilling Drills from ¼" to ½" in Steel (or hardwood 1")

¼" PORTABLE ELECTRIC DRILL
Type HU20 Cash **£11 . 7 . 6** or
67/6 Deposit & 12 monthly paym'ts of 14/8

Vertical bench stand for above HU2201 **£5.10.-**. OR Complete ¼in. Drill with Bench stand : CASH **£16.17.6** or **£5.17.6** Deposit and 12 monthly payments of **21/8.**
We specialise in easy H.P. terms on the full range of Black and Decker "Handy-Utility" tools.

	Cash	Deposit	12 Mthly Pay-ments
¼in. Drill HU1	£6.10.-	£1.10.-	11/8
Vertical bench stand for above HU2300	£2.19.6	—	—
Horizontal stand for above HU2302	17/6	—	—
Buffing and Polishing kit for above	19/6	—	—
¼in. Drill Kit complete HU1004	£11.15.-	£3.15.-	18/8
3in. Sander Polisher HU50	£9.17.6	£2.17.6	15/-
*Electric Saw HU60	£15.15.-	£5.-.-	21/6

*The Superbly Built Heavy Duty "LECTRO SAW" is illustrated. * For use on Wood or cast iron etc. *Special heavy duty motor. *Helical gears for durability. *Perfect balance. *Telescoping blade guard closes as the saw is lifted. *Nett weight 9½ lb. *for AC/DC mains.



For the man whose business does not justify the use of costly industrial models and who requires years of faithful, trouble-free service.

acos HIGH FIDELITY MICROPHONES FOR PUBLIC ADDRESS, RECORDINGS, AMATEUR RADIO

TYPE MIC 16-2 (as shown)
Incorporates the Acos Floating Crystal Sound Cell giving a response substantially flat from 30-10,000 cps. Unaffected by vibration, shock and low-frequency wind noises.
Price **£12.12/-** or **£4.12/-** Deposit and 12 monthly payments of **16/8.**

TYPE MIC 22-2 (as shown)
Incorporates the Acos "Filtersel" insert giving extreme sensitivity and high fidelity. Response substantially flat from 40-6,000 cps. Vibration—and shock proof. Not affected by low-frequency wind noises.
Price **£6.6/-** or **36/-** deposit and 12 monthly payments of **10/10.**

AVO Precision Electrical Testing Instruments

A dependably accurate instrument for testing and fault location is indispensable to the engineer who builds or services his own equipment.

	Cash	H.P. Deposit	12 Monthly Payments of
Model 7 and 40 Avometers	£19 10 0	£6 0 0	25/6
Universal Minor	£10 10 0	£3 10 0	15/-
Signal Generator, Mains or Battery	£30 0 0	£10 0 0	37/6
Universal Bridge	£26 0 0	£9 0 0	32/6
Electronic Testmeter	£40 0 0	£12 0 0	52/6
Valve Characteristic Meter	£50 0 0	£16 0 0	65/-
D.C. Avominor	£5 5 0	£1 15 0	9/2
Model 8 Avometer	£23 10 0	£7 15 0	30/-

The full range of AVO test gear as previously advertised is still available, but we would remind you that supplies are now getting very difficult owing to the shortage of raw materials and the re-armament programme. Buy now on our easy Hire Purchase terms while we have stocks!

PULLIN MULTI-RANGE TEST SET Series 100

The universal testing set for Service Engineers. Sensitivity 1,000 ohms per volt. Strong metal case with carrying handle —complete with leads having detachable bull-dog clips and test prods. Size 9½in. by 5½in. by 4in.

RANGES.
AC/DC Volts : 10, 25, 100, 250, 500, 1,000.
D.C. Milliamps : 2.5, 10, 25, 100, 500.
AC/DC Microamps : 100 Microamps 10 volt range.
Resistance ranges : 0/1 Meg. (15,500 ohms mid scale). 0/10,000 ohms (155 ohms mid-scale.)

£11.11s. CASH or **40/-** Deposit and 12 monthly payments of 20/-



All other test equipment by Evershed, Advance, Cossor, EMI, Amplion, Hunts, BPL, etc. in stock and available on our unrivalled hire purchase service.

M·O·S

MORE M.O.S. H.P. OFFERS on the following pages

MAIL ORDER SUPPLY, *The* RADIO CENTRE
Dept. WW, 33, TOTTENHAM COURT ROAD, LONDON, W.1.

MUSeum 6667

Sole Distributors of the BURGOYNE SOLDER GUN **79/6** Spare bits 10 for 7/6

M·O·S

BSR DE LUXE MOTOR UNIT MU1S

Specification.

SPEED	78 R.P.M.
MAINS INPUT	200/250 volts, 50 cycles, A.C. Other voltages and frequencies to order.
MAINS CONSUMPTION	Approx. 10 watts
TURNTABLE	8in. diameter
NET WEIGHT	2 lb.

This unit can be used with any normal type of pick-up. Its constancy of speed and ample torque make it suitable for lightweight or the heavier types. **£3 CASH.**

The COLLARO Series of GRAMOPHONE UNITS

		CASH	DEPOSIT	12 monthly Payments
AUTOMATIC RECORD CHANGERS (less pick-up heads:	Model RC521 500 or 511, auto-mixing changer for 78 r.p.m.	£9.16.1	£3.6.1	14.2
	Model 3RC 521 or 511, 3-speed version of above	£12.8.9	£4.3.9	17.1
	Model 3RC522, mixing version of above (12in., 10in. or 12in. inter-mixed)	£14.19.0	£5	£1
RADIOGRAM UNITS (less pick-up heads:	Model AC514, 78 r.p.m., rim drive	£4.10.11	£1.10.6	8.4
	Model AC3 514, 3-speed version of above	£8.3.0	£2.15.0	12.4
	Model US16, for A.C. or D.C. mains, centre drive units for 78 r.p.m.	£12.4.4	£4.1.5	17.-
PLUG-IN PICK-UP HEADS FOR ABOVE UNITS TO YOUR CHOICE:	Magnetic 78 r.p.m.	£1.19.4	—	—
	High fidelity high impedance	£2.6.-	—	—
	High fidelity, low impedance	£1.19.4	—	—
	High fidelity, Xtal GP27, 78 r.p.m. (green)	£3.2.2	—	—
	High fidelity, Xtal GP27, 33⅓ r.p.m. (red)	£3.2.2	—	—
	High fidelity, Xtal GP27 dual-purpose	£3.2.2	—	—
	* Matching transformer for this head, 7.-			
AUTOMATIC RECORD CHANGERS, COMPLETE WITH PICK-UP HEADS	RC521/511 with GP27 Head, 78 or 33⅓ r.p.m.	£12.18.3	£4.14.3	17.-
	RC521/511, with ordinary head	£11.16.9	£4	16.4
	3RC521, with GP27 high-fidelity head dual-purpose	£15.10.6	£5.3.6	£1.0.7
	3RC521, with two high-fidelity heads, 78 r.p.m. and 33⅓/45 r.p.m.	£18.12.8	£6.4.8	£1.4
RADIOGRAM UNITS COMPLETE WITH PICK-UP HEADS	AC514, with Magnetic head	£6.10.5	£2.3.6	10.6
	AC3 514, with high fidelity low impedance head and matching transformer	£10.9.6	£3.10.0	15.-

BSR TYPE MU14 3-SPEED MOTOR UNIT
78, 45 and 33 r.p.m.



CASH **£6.8.6** or **£2.3.0** DEPOSIT and 12 monthly payments of 10/6.

● 10in. diameter heavy pressed steel turn-table fitted on a precision ground taper steel spindle. ● Self-lubricating bearings employed throughout, ensuring a long life of quiet running. ● Speed change from 78 to 45 or 33⅓ r.p.m. simple and instantaneously effected. ● No belts employed whatsoever. ● Incorporates the well-known BSR 4-pole motor. ● Instantaneous speed variation (wow), vibration, and rumble at an absolute minimum. ● Uniform turn-table speeds under widely varying loads. ● No stray field radiation noticeable with any type of pick-up. ● Ideal for use with any type of crystal or magnetic pick-up.

Motors are despatched connected either 100/125 or 200/250 volts, 50 c/s., but change from one voltage range to another is accomplished easily.

All other BSR Gramophone Motors in stock as advertised by the manufacturers and ourselves.

BSR SHADED POLE MOTOR Type TP1

A two-pole induction motor that has been designed to give the maximum efficiency with the minimum physical dimensions.

The motor is ideal for gramophone motors, tape motor displays, wire and tape recorders, timing mechanism and many other applications.

SPECIFICATION

Voltage 200/250. Frequency 50 cycles. Starting Torque, 1.0-1.5 in-lb oz. Pull Load Torque, 1.2-2.0 inch oz. Mains consumption 10-13 watts. Speed (light), 3,000 r.p.m. Shaft Diameter 0.1250in. Weight 10¼. Dimensions 2¼in. × 2⅛in. × 1⅞in. External shaft Length, 1 in.

22/- *Post and Pkg. 1/6*

BSR INDUCTION MOTORS for recording

TYPE FF 1/2
4 pole, 1,400 r.p.m., weight 1¼lb., length 3¼in. o.c., minimum stray magnetic field, each £1 18 0

TYPE SR 2
A medium power motor suitable for take-up spool drive where fast forward facilities are not required. each £1 5 0

TYPE SR 1
A motor of the same power as the renowned FF1/2, suitable for reel spool operation, giving fast rewind. Suitable also for take-up spool when fast forward facilities are required. Due to its higher stray magnetic field this motor is not recommended for capstan drive, each £1 12 0

All the above motors are suitable for A.C. mains.

DECCA PLAYERS

	Cash	Deposit	12 Monthly Payments of
Model 33A playing desk, 33⅓ r.p.m.	£9.9.0	£3.3.0	13.10
Model 33B, as above but in portable carrying case	£12.1.6	£4.0.6	16.9
Model 37A 3-spd. playing desk	£12.1.6	£4.0.6	16.9
Model 347C or M 3-speed in portable case	£19.19.0	£6.13.0	£1.5.6
Model 348C, 3-speed in handsome polished walnut cabinet	£22.1.0	£7.7.0	£1.8.0
Deccalian 1-speed	£33.3.0	£11.13.4	£2.2.3

PICK-UPS

BSR

PU1 High fidelity light weight crystal pick-up for use on 78 r.p.m. recordings.

PU2 High fidelity light weight crystal pick-up for use on Microgroove recordings.

PU3 Light weight crystal pick-up with specially designed stylus for playing both 78 r.p.m. and Microgroove recordings.

All £3.18.7 each or £1.1s. deposit and 12 monthly payments of 8/-.

DECCA

Turnover XTAL 3-speed, **£3.19.4**; **£1.9.4** deposit, 12 monthly payments of 7.6.
XM6. Pick-up with interchangeable heads for 33⅓ and 78 r.p.m. recordings. £7 cash or £2 deposit and 12 monthly payments of 11.8.

ACOS

GP20. Lightweight Pick-up **£3.11.5** complete:

GP19. L.P. Heads, **£2.3.4** complete: **£1.14.9** deposit, 12 monthly payments of 10.-
GOLDRING, Type 137A, **£2.6.7**.
GOLDRING 3-way type 150, **£3.11.8**.
CONNOISSEUR Super light weight with 2 heads, **£10.0.8**: **£2.0.8** deposit, 12 monthly payments of 16.8.
MARCONI T14 with transformer, **£2.9.0**.
CHANCERY 78 r.p.m. or L.P. head, **£2.13.0**.

Connoisseur Super Lightweight Pick-up

COLLARO RECORDING MOTOR

1,400 R.P.M. 4-POLE 4oz/03 TORQUE

with Cooling Fan

42/- *each, or* **84/-** *a matched pair*

H.P. on pair 28/- deposit and 12 monthly payments of 8/-

WHARFEDALE OUTPUT TRANSFORMERS

Wharfedale transformers have been in steady demand since their introduction 18 years ago, and have built up a high reputation for reliability.

O.P.3, 3 ratios	7.6	De Luxe, 6 ratios	27.6
P. Type, 4 ratios	8.6	W.12, 3 ratios	25.-
G.P.8, 8 ratios	12.6	W.12, ratios to order	29.-
Universal, 6 ratios	17.-	W.15, ratios to order	67.6

"ADCOLA" SOLDERING INSTRUMENTS

Designed for Wireless Assembly and Maintenance. SUPPLIED FOR ALL VOLT RANGES FROM 6/7 v. to 230/60 v. The three Adcola Models cover the requirements of the **Television, Telecommunication and Radar Engineers** and assure thorough jointing.
⅛in. dia. Bit Standard Model ..... **22/6** ¼in. dia. Bit Standard Model 25/-
⅜in. dia. Detachable Bit, **30**/-

"EKCO" SOLDERING PENCILS

For 6 volt or 12 volt operation
For fine work

21/-

Spares available from stock

HIRE PURCHASE

All H.P. facilities granted are financed solely by M.O.S. Finance Co.

TRADE & EXPORT ORDERS INVITED

M·O·S

TERMS OF BUSINESS

Cash with Order or C.O.D (if goods suitable for post).

Please add sufficient to cover carr. & packing

Lists available detailing terms on all Proprietary Equipment.

Come and inspect the vast stocks in our spacious showrooms.

An Announcement

We have been appointed Leading Agents and Distributors for the London Area for

HARTLEY-TURNER HIGH FIDELITY EQUIPMENT

We offer unrivalled hire purchase facilities, full technical service, demonstrations, etc., on

HARTLEY-TURNER 215 SPEAKER

The Harley Turner 215 Speaker is now recognised by musical connoisseurs as giving the closest approach to realism in reproduction that has yet been achieved. Its outstanding characteristics—extreme width of frequency response, complete freedom from cross-modulation and entire absence of bass resonance—place it in a unique position.

Specification

Peak power-handling capacity	20 watts
Maximum diaphragm displacement	¼in.
Flux density in gap	11,500lines sq.cm.
Permanent magnet	Alcomax II
Diameter of baffle hole	9in.
Voice-coil impedance	4 ohms
Maximum diameter	10in.
Maximum depth	6in.
Net weight	6¼lb.
Weight packed	10lb.
Four-hole mounting.	



£14 : 10 cash

or £4 : 10 deposit and 12 monthly payments of £1.

HARTLEY-TURNER TONE CONTROL PRE-AMPLIFIER

Considerable time in research and experiment was spent to find the most elegant method of providing complete correction for all recording characteristics as well as compensation for deficiencies in broadcast transmissions, and final release of the design was delayed until the amplifier was used with the recently introduced microgroove recordings. We can now guarantee almost perfect compensation for microgroove recording characteristics.

This design provides a wide range of bass and treble control without the need to readjust the main volume control when bass or treble are altered. The use of continuously variable controls is most necessary when dealing with unknown characteristics, for compensation of these can only be done by ear. As the characteristics of the human ear vary with intensity, the compensation required is a function of the loudness of reproduction. With a badly designed tone-control amplifier, where the voltage output varies with bass and treble settings, the critical listener will find himself indulging in an orgy of knob twiddling which cannot be rationalised. This Hartley-Turner unit not only avoids introducing distortion into the reproduction, but precisely and easily overcomes the defects of the signal fed into it. The unit is supplied completely assembled and tested.

£7 : 10 cash or £2 : 10 deposit and 12 monthly payments of 11/8.

All other Hartley-Turner equipment available on easy terms

For EFFICIENCY plus RELIABILITY

you must have a

BURGOYNE AERIAL CO-AXIAL CONNECTOR

This is the ONE and ONLY unit available which enables a really efficient and reliable weatherproof connection to be made between a dipole and its feeder.

As is typical of all BURGOYNE products, much thought was given to the design of this first-class connector.

Each connector in carton with full assembly instructions. **24/6** **As supplied to Marine and Colonial Govt. Depts.**

DISTRIBUTED EXCLUSIVELY BY M.O.S.



The M.O.S. "EASY-to-BUILD" series of KITS

All available from stock

Illustration shows the A1 Amplifier assembled.

Type	Description	Price	Deposit	12 monthly payments of	Instruction Book	Price fully assembled and wired
A1	3-valve AC Amplifier, 4W	£4/12/6	£1	9/4	3/6	£5/12/6
A2	2-valve AC/DC ,, 3W	£3/5/-	15/-	7/6	3/-	£4/2/6
A3(A)	7-valve AC ,, 8W	£9/19/6	£3	15/-	4/6	£12/10/-
A3(B)	7-valve AC ,, 12W	£11/5/-	£3/10/-	16/8	4/6	£13/15/-
RF1	MW TRF Feeder Unit ...	£2/12/6	17/6	4/3	2/-	£3/10/-
A4	Record Playback Amplifier	£6/19/6	£2	11/8	3/9	£8/5/-

THE "SIMPHONIC" TAPE RECORDER

£60 Cash or £20 Deposit & 18 monthly payments of 52/-

THE "CLIFTON" TAPE RECORDER

£55 : 10 Cash or £18 : 10 Deposit & 18 monthly payments of 48/-

BOTH AVAILABLE FROM STOCK.

PLESSEY MULTI-SPEED AUTO-CHANGERS

£23 : 13 Cash

or £8 Deposit and 12 monthly payments of 29/6.

The Record Changer that does everything!

LATEST RELEASE!

Cossor Portable Oscillograph Model 1039 **£28** or Deposit £9.6.8. and 12 monthly payments of 32/-.

HELLERMANN BINDING SYSTEM

Now available to the small user in kit form.

HELLERMANN TOOL KIT Type TK2

Contains a complete range of components as follows :—

1 Type TL Tool, 1 Bottle Hellerine Lubricant, an assortment of genuine Hellermann Rubber Sleeves in red and black, Hellermann Cable markers printed "Earth" **17/6 each** (Post and Packing 1/-)

M·O·S

MUSeum 6667

MAIL ORDER SUPPLY, *The RADIO CENTRE*

Dept. WW, 33, TOTTENHAM COURT ROAD, LONDON, W.1.

IMMEDIATE DELIVERY
From
OUR LARGE STOCKS

CINCH COMPONENTS
Stockists of all CINCH COMPONENTS

RESISTORS
VITREOUS, WIRE WOUND and HIGH STABILITY, close tolerances ¼, ½, 1 and 2 watt. All values up to 2 meg. also 8, 13 and 30 meg.
CARBON—½ watt to 5 watt. Standard Car Suppressors 15,000 ohms.

CAPACITORS
Block Paper, Silvered Mica, Mica, Tubular and Ceramic.

SWITCHES
TOGGLE, YAXLEY, OAK, ETC.

VARNISHED COTTON SLEEVING
Various colours ½ mm.—20 mm.

INDICATOR LAMP HOLDERS
Red, Green and Clear.

LAMINATIONS
RADIOMETAL 31, 39 and 40. Also many other types.

VOLUME CONTROLS
MORGANITE "H" type, "M" type and WIRE WOUND. Most popular values in stock.

PLUGS AND SOCKETS
CINCH, PYE, JONES, BELLING & LEE, BULGIN, ETC.

TRIMMERS
Variable CERAMIC TRIMMERS. Capacities from 5 to 100 pf. Spindle and pre-set types.

WIRES
ENAMELLED, SILK COVERED, REGENERATED CELLULOSE and PUSH-BACK.

VALVE HOLDERS
Paxolin, Moulded and Ceramic. Large selection including all latest types.

NUTS, BOLTS, WASHERS, P.K. SCREWS, RIVETS, EYELETS, SOLDER TAGS, GROMMETS, GLASS CARTRIDGE FUSES, ETC

Many other lines including ex-government components in stock. All enquiries dealt with individually, but regret no lists are issued.

TRADE COUNTER OPEN
9.30 TO 5.30 MONDAY TO FRIDAY

WHOLESALE, MANUFACTURERS' AND EXPORT ENQUIRIES ONLY

RADIO TRADERS LTD.
23, WARDOUR ST.,
(Coventry St. end)
LONDON, W.1.
Phone: GERrard 3977/8 *Grams: "Radiotrade"*

ICS

HOME STUDY
backs radio experience with sound technical knowledge

MANY men who wished to link their radio experience with a sound technological background have received successful instruction by means of an ICS Course. Its value has been proved not only to amateurs but to men who already have a professional interest in radio and television engineering, including those taking qualifying examinations. It is invaluable, also, to students who wish to prepare themselves for a job in this field. Courses of instruction covering radio and, if necessary, television, include the following: **Complete Radio Engineering . Radio Service Engineers . Radio Service and Sales . Advanced Short-Wave Radio . Elementary Electronics, Radar and Radio . Television Technology.**

And the following Radio Examinations
British Institution of Radio Engineers . P.M.G. Certificates for Wireless Operators . City and Guilds Telecommunications . Wireless Operators and Wireless Mechanics, R.A.F.

Students intending to sit for the above Examinations should enrol NOW for preparatory Courses.

Using a specially prepared study programme, students study at their own pace, in their spare time and, with time for revision, sit with full confidence of success. *(I.C.S. Students are coached until successful.)*

Moderate fees include ALL books required.

GENEROUS DISCOUNT TO H.M. FORCES.

Write today for our FREE **"RADIO"** booklet which fully describes the above ICS Courses and the facilities for the complete study of Radio and/or Television technology. The ICS Advisory Department will also give free and impartial advice on the need for and the means of instruction.

International
CORRESPONDENCE SCHOOLS
Dept. 223A, International Buildings, Kingsway, London, W.C.2

Masteradio
'VIBRATORPACK'

Masteradio Vibratorpacks convert low voltage DC to H.T. with minimum loss of power.

Please write for full details;
MASTERADIO LTD.
FITZROY PLACE - - LONDON, N.W.1

Fit..

the same make and type the setmaker uses

When a valve or cathode ray tube replacement is needed you can't do better than fit the same make and type the Setmaker uses. This is particularly important in television, when many of the special circuits used require for their proper operation the exact type of valve round which they were designed. That is why so many Setmakers use Ediswan Mazda valves and tubes and that is why you should replace with Ediswan Mazda. They're the right valves for the job.

EDISWAN
MAZDA

Valves and Television Tubes

The Edison Swan Electric Company, Ltd. 155 Charing Cross Road, W.C.2.
Member of the A.E.I. Group of Companies.

RV64

VITAVOX

LOUDSPEAKERS AND MICROPHONES

. . . for solving sound problems

The VITAVOX range of microphones, loudspeakers and reproducers is sufficiently wide in its scope to meet all practical requirements in the field of sound reproduction. Thus the solution to your sound problem is primarily the selection of the right Vitavox model to meet your specific needs and the manufacturers will be pleased to assist you by sending full details of Vitavox products on request.

Specify **VITAVOX**

VITAVOX LIMITED, WESTMORELAND ROAD, LONDON, N.W.9

Telephone: COLindale 8671-3

BRIERLEY DIAMOND MICROARMATURE PICK-UP

This new pick-up has many noteworthy characteristics, some of which are listed below :—

1. The mass of the moving parts is less, we believe, than in any other pick-up of any type—other than our own Ribbon, which is, of course, unique.
2. The output voltage—about 1·25th v.—is high enough to cause no trouble.
3. It is sufficiently robust to be used by any reasonably intelligent and careful family.
4. The use of a diamond point has, *inter alia*, the enormous advantages that a very large number of records may be played with negligible point wear. This results in a sustained "new" performance together with the elimination of that mental irritation at the gradual and perceptible "falling off" unavoidable with less wear-resistant points.
5. Organised production on a reasonable scale should give us a satisfactory "spares" and repair service and has enabled us to produce this pick-up at a price which many may at first have believed to be either a mistake or a printer's error.



Photograph of A. Standard Needle, B. Miniature Needle and C. Brierley Microarmature.

Pick-ups, types JB.P.A.1D (78) and JB.P.A.1MD (LP), £6.0.0. Purchase Tax, £2.12.-.

Mumetal Coupling Transformer, type JB.T.A. £1.5.-.

Full details sent on request.

J. H. BRIERLEY (Gramophones and Recordings) LTD.
KIRKBY TRADING ESTATE LIVERPOOL

URGENTLY REQUIRED

THE FOLLOWING EQUIPMENT IN ANY CONDITION :—

FREQUENCY METERS Type BC.221, BC.221AK, TS.174/U, TS.175, TS.69/AP. Also LR2 (Naval Version) by General Radio Co., and other types.

AMERICAN TEST SETS Type TS.13/AP, TS.12/AP, TS.34/AP, TS.47/AP, TS.10, TS.16/APN, TS.33, TS.35, TS.36, TS.45, TS.59, TS.110, TS.118 and others.

RECEIVERS Type APR1, APR4 and APR5 also Tuning Units types TN16/APR4, TN17/APR4, TN18/APR4 and others.

QUARTZ CRYSTALS 1 M.C. Model 135R by R.C.A. (or alternatives) also 1 M.C. Crystals octal based.

ALSO :—IMPEDANCE OR UNIVERSAL BRIDGES, OSCILLOSCOPES, "Q" METERS, VARIACS, OUTPUT METERS, ETC.

Please write, call or phone, giving price, condition, etc.

ELM ELECTRIC CO.,
175, UXBRIDGE RD., HANWELL, W.7
EALing 0779

THE *New* WINDSOR

TEST METERS

MODEL 77A 20,000 o.p.v.

MODEL 71A 1,000 o.p.v.

Two entirely new instruments incorporating the 'ates' improvements in manufacturing technique. Refinements include shockproof moulded cases, clear and easy to read scales and many other features.

MODEL 77A AND 71A

OVERLOAD PROTECTION Meter movement has instantaneous overload protection, effective on all ranges.

BUZZER A Buzzer is fitted internally for quick continuity testing.

METER Precision engineered moving coil, fitted with 5" scale and knife edge pointer.

SWITCHING One switch selects both circuit and range. Heavily silver plated beryllium copper switch contacts ensure low loss and trouble free operation. Large 2" milled knob for easy handling.

MODEL 71A

SENSITIVITY 1,000 ohms per volt A.C. 1,000 ohms per volt D.C.

RANGES

VOLTS D.C. 0-3-15-75-300-750-3000

VOLTS A.C. 0-15-75-300-750-3000

MILLIAMPS D.C. 0-15-150-1500

MILLIAMPS A.C. 0-15-150-1500

AMPERES D.C. 0-15

RESISTANCE 1 ohm to 200 K. ohms in two ranges with self contained battery.

OUTPUT As for A.C. volt ranges except 3,000 V., via a condenser.

LIST PRICE: £12.10.0

MODEL 77A

SENSITIVITY 20,000 ohms per volt D.C. 5,000 ohms per volt A.C.

RANGES

VOLTS D.C. 0-7.5-30-75-300-750-3000

VOLTS A.C. 0-7.5-30-75-300-750

MILLIAMPS D.C. 0-.15-1.5-15-150-1,500

AMPERES D.C. 0-15

RESISTANCE 10 ohms-5 megohms in two ranges with self contained battery.

OUTPUT As for A.C. volt ranges except 3,000 V., via a condenser.

LIST PRICE: £15.0.0

Please write for illustrated leaflet featuring our new range of radio and television test gear.

TAYLOR ELECTRICAL INSTRUMENTS LTD.

419 - 424 MONTROSE AVENUE, SLOUGH BUCKS. Telephone: SLOUGH 21381

FIELDEN PROXIMITY METER

In most applications it is unnecessary to establish physical contact with the specimen.

An indispensable tool for laboratory and workshop investigation of physical, chemical and mechanical phenomena which may be resolved into changes of electrical capacitance. At maximum sensitivity, full scale deflection can be obtained for a 0.2% change in terminal capacity.

For example, dimensional displacements, vibrations, strains, surface irregularities, dielectric properties of solids and liquids, certain moisture content and coating thickness problems.

Fielden INSTRUMENTATION



There is a FIELDEN INSTRUMENT for most physical measurements.

Full details by return post from

FIELDEN (ELECTRONICS) LIMITED, "H" Block, Paston Road, Wythenshawe, Manchester

Also at LONDON, PENNSYLVANIA and MELBOURNE.

FOR GREATEST EFFICIENCY AT THE HIGHER FREQUENCIES

SILVERED JAY CERAMIC

PRECISION CAPACITORS

FOR TELEVISION, F.M., AND ALL U.H.F. APPLICATIONS

Constructors', service replacement, and all kit types.

High precision and laboratory types.

INQUIRIES INVITED

JAY DEVELOPMENTS,
HEATH LANE, WEST BROMWICH.
Tel.: STO 2194.

Extension Loudspeakers

Major £3 15-



THESE

Richard Allan

"BAFFLETTES" are fitted with larger loudspeakers than any similarly priced extension speakers! Ask for demonstration at your Dealers.

Obtainable from all Good Radio Dealers or write for details of these and other Models and Record Players to :—

Richard Allan Radio Ltd., Dept. W.D. Hallaite House Batley, Yorkshire

Service to the ELECTRONICS INDUSTRY



OAK SWITCHES are supreme in the radio and electronic fields. OAK—the superior wafer-type switch — incorporates self-cleaning double-contact clips and floating rotors ensuring self-alignment.

CUTLER-HAMMER SWITCHES are famous in the electronic and electrical industries throughout the world for reliability and efficiency. They are available in a wide range of ratings and with several types of operating mechanisms such as lever, slider, trigger, or plunger actions.





POTENTIOMETERS are ruggedly built for long and reliable service under the most exacting conditions. There is a full range of composition types, with or without switches, and wire-wound types for television applications.

ROTARY SOLENOIDS are compact, robust, and efficient electro-mechanical devices with a powerful snap-action rotary movement. As circuit selectors—with Oak switch sections — they have numerous applications in the electronic and telecommunication fields.



A full range of our products is displayed on Stand No. 64 at the R.E.C.M.F. Exhibition

N.S.F. LIMITED · KEIGHLEY · YORKS

Phone: Keighley 4221 5 *Grams:* ENESEF, Keighley · LONDON OFFICE: 9 Stratford Place, W.1. *Phone:* Mayfair 4234

Sole licensees of Oak Manufacturing Co., Chicago and G. H. Leland Inc., Dayton, U.S.A.

Licensees of Igranic Electric Co. Ltd. for the products of Cutler-Hammer Inc. Milwaukee, U.S.A.

Authoritative Modern Technical Books

ADVANCED THEORY OF WAVEGUIDES

By A. Lewin. Sets out the various methods that have been found successful in testing the types of problems arising in work on the subject. The topics collected for discussion are representative of the field in which the micro-wave engineer is at present engaged; and although many of the examples are concerned with the rectangular waveguide, the reader will be able to apply the general principle to most of the cases encountered in practice.

30s. net. *By post 30s. 7d.*

MICROPHONES: A B.B.C. Training Manual

By the Staff of the Engineering Training Department, B.B.C. This book, originally written as a text book for B.B.C. Engineers, has now been made available for general publication. Subjects treated in detail include: requirements for microphones in a broadcasting studio; laws relating to sound waves and their behaviour and the design and characteristics of various types of microphones.

15s. net. *By post 15s. 5d.*

TELEVISION RECEIVING EQUIPMENT (3rd. Ed.)

By W. T. Cocking, M.I.E.E. A full and lucid description of each stage of the normal television receiver. Details of special circuits are also given and there are additional chapters on faults and their remedies, servicing of modern sets and the problem of obtaining selectivity. Mathematical data of value to the designer appears in appendices.

18s. net. *By post 18s. 8d.*

ASSOCIATED ILIFFE TECHNICAL BOOKS

Obtainable from all booksellers or direct from the Publishers

ILIFFE & SONS LTD., DORSET HOUSE, STAMFORD STREET, LONDON, S.E.1

CONSTANT VOLTAGE POWER SUPPLY UNITS

MODEL 101-C

***Output*:** 250/400v. 0.250mA max.
***Stability*:** Better than 0.1%.
***Output Impedance*:** Less than 1 ohm.
***Output Ripple*:** Less than 2mV. R.M.S.
***Mains Supply*:** 200/250v. 40-60c/s.
Regulation down to zero load.

DETAILS ON REQUEST.

ALL-POWER TRANSFORMERS LTD.

CHERTSEY ROAD, BYFLEET, SURREY.

Tel: Byfleet 3224/5.

A ***workshop*** in your ***pocket!***

THE TELEVISION AND RADIO SERVICE ENGINEER'S **MASTER** TRIMMER KIT

Contains:

- 1 End Trimmer.
- 1 Side Trimmer.
- 1 Yaxley Switch Contact Adjustor.
- Low Capacity Trimmer.
- 1 Screwdriver.
- 1 Set of Feeler Gauges.
- 1 Set of six Box Spanners from 1 to 8 B.A.
- 1 Set of four Spanners from 0 to 8 B.A.

in durable black crackle finish metal case.

Export enquiries invited

SEND YOUR ORDER TO:

J. & S. NEWMAN LTD.

100 HAMPSTEAD RD., N.W.1

Tel.: EUSton 5176/7

There's a place for YOU

. . . in the

part-time

R·A·F

The Royal Air Force urgently needs a trained reserve it can count on in an emergency. And it is men and women like *you* who must form that reserve — people who are ready to give up a small part of their spare time to training: either to continuing to fly or to doing equally important jobs on the ground. Your close association with the Royal Air Force will bring you new experience and fresh companionship. Moreover, by volunteering now, you will be showing the world that you at least are ready to face up to whatever the future holds. Post the coupon below for full details.

TO: ROYAL AIR FORCE W.D.69B), VICTORY HOUSE, LONDON W.C.2

Please send particulars of part-time service with the R.A.F. (*Applicants from British Isles only.*)

NAME .....

ADDRESS .....

.....

(*If ex-R.A.F. or W.A.A.F. please give rank, trade and number*)

★ *If you are between 14 and 17 — and keen — join the Air Training Corps* ★

The BPL SUPER RANGER

★ Leather carrying handle.

★ Easy to read 2-colour dial.

★ 1,000 ohms per volt for D.C. and A.C.

★ 5" scale meter with mirror scale. Movement fitted with spring loaded sapphires.

★ Captive head terminal connectors for all ranges.

★ 5,000 volts range for A.C. and D.C.

★ Rotary switch selects ranges clearly marked.

★ Built-in 3 range current transformer.

PRECISION BUILT

The B.P.L. Super Ranger is a precision built instrument equipped with a fine 5in. movement mounted in spring loaded sapphires. In order to fully exploit the high accuracy a mirror scale is incorporated. The range selector is of sturdy construction consisting of solid silver contacts mounted on a ceramic base. By means of this switch all ranges are selected except the A.C. current ranges and the 5,000 volts range. Both the Electrician and the Radio Engineer will appreciate the provision of A.C. current ranges which, in conjunction with the other ranges will cover all ranges to be expected.

LIST PRICE

£19-19-0 including test leads.
Subject to Trade Discount.

Also supplied:
B.P.L. Universal Test Sets and D.C. Test Sets.

LONDON STOCKIST:
M.R. SUPPLIES LTD.,
68, New Oxford Street, W.C.1

BRITISH PHYSICAL LABORATORIES

HOUSEBOAT WORKS · RADLETT · HERTS · Telephone: RADlett 5674-5-6

The "RD BABY DE-LUXE" Amplifier

Accepted as the most outstanding low priced amplifier available in this Country, the "Baby" provides the answer for the man of modest means who requires High Fidelity Reproduction.

Within its power limitations, which are entirely adequate for normal domestic use, its performance matches the majority of high priced amplifiers on the market.

In keeping with all "RD" products the "Baby" is individually built by craftsmen, and represents the best in British Workmanship.
Price, complete with pre-amplifier and engraved control panel, **£17/10/-.**

A detailed specification will gladly be forwarded on request, and a demonstration may be had at any time. Also obtainable in London from: Webb's Radio, The Gramophone Exchange, Tele-Radio, City Sale and Exchange and Holley's Radio Stores.

Trade and Export enquiries invited.

ROGERS DEVELOPMENTS Co.

"Rodevco House," 116 Blackheath Road,
GREENWICH, S.E.10.
Telephone TIDeway 1723

DIRECT T.V. REPLACEMENTS

A. ROSE
134-136 LEWISHAM WAY, NEW CROSS, S.E.14
TIDEWAY 3696

REPLACEMENTS AVAILABLE FOR BAIRD - DECCA EKCO - G.E.C. - FERGUSON - H.M.V. - INVICTA - K.B. - FYE - ULTRA. S.A.E. FOR LIST.

G.E.C.	Germanium Crystal Diode	T/V	6/6
EKCO	E.H.T. Transformer	TSC30	87/-
	E.H.T. Osc. Coil	TS46	19/6
FERGUSON	Deflector Coils	968T	32/-
	20,000Ω Slider	T/V	4/3
H.M.V.	Line Osc. Transformer	1811	12/6
	Line Osc. Transformer	1807	12/6
	Thermisters		4/9
	Frame Osc. Transformer	1807	15/6
	Line Output Transformer	1807 & 1811	41/6
K.B.	Line Output Transformer	EV30 & FV30	91/6
FYE	Metrosils	FV1	2/9
	Thermisters	FV1	3/3
	Deflector Coils	FV1	29/-
	Deflector Coils	B18T	24/3
	Line Osc. Transformer	B18T	11/3
BAIRD	E.H.T. Transformer	Townsman	46/6

T.V. Engineers Lab Resistor Kit 180 ½ watt 15 standard values in free cabinet £6 0 0

Books for T.V. Engineers

Osram Valve Manual	5 9
40 circuits using Germanium Crystals	3 2
Television Receiving Equipment, W. T. Cocking.....	18 9
T.V. Servicing Manual including 7 service sheets.....	4 9

ALL PRICES INCLUDING PKG. & POSTAGE, CASH WITH ORDER



WHAT'S BEHIND IT ALL?

Extensive research laboratories, special design and development departments, wide manufacturing resources—all at your service, but not on your overheads! When you use any Hunt Capacitor, whether a normal type or as advanced as the Hunt's exclusive Metallised Paper series, you are benefiting from everything that Hunt's have achieved in many years of wholehearted specialisation in capacitor design and manufacture. To specify Hunt's as standard, to choose Hunt's for replacements, to decide on Hunt's for special purposes —all are the wise actions of people who demand nothing but complete reliability.

ESTABLISHED 1901

HUNTS CAPACITORS

THE TRADE MARK OF RELIABILITY

A. H. HUNT (Capacitors) LTD., Wandsworth, London, S.W.18 · Tel: BAT. 3131

HOLME MOSS AND SUTTON COLDFIELD

ALL SPECIFIED VIEWMASTER COMPONENTS IN STOCK

BERRY'S (SHORT WAVE) LTD.

25 HIGH HOLBORN, LONDON, W.C.1
TEL.: HOLBORN 6231

"Q-MAX" MODEL CV-1 VARIABLE FREQUENCY OSCILLATOR

A series tuned Colpitts (Clapp) V.F.O. for use as a Crystal substitute. Output at 3.5; 5.25 and 7 Mc/s. Calibrated on all amateur bands. Price 14 gns.

WILLIAMSON AMPLIFIER
All components available, including precision resistors and condensers, Partridge, Woden and Vortexion Output and mains transformers, Chokes, etc.

SPEAKERS
WHARFEDALE — We carry all types of Wharfedale Speakers, Microgroove Equalisers, Cross-over units, etc., in stock.
BARKER 14BA, 15 Gns. ; 15QA. 18 Gns.
GOODMANS 12in. Axiom 150 £10 5 6
W.B. Stentorian 8in. £1 12 6
W.B. Duplex 10in. £6 15 0
Do., with trans. £7 15 0

AMPLIFIERS
LEAK "Point One" £38 7 0
Do., Pre-amp. £9 9 0
ACOUSTICAL "QUAD" £35 0 0
Do., Tuner Unit £26 0 0

ARMSTRONG CHASSIS
Complete range of these excellent receivers.

GRAMOPHONE MOTORS
Chancery Long Playing attacht. £3 12 6
Collaro Motor and pick-up £6 10 10
Connoisseur, 2-speed £22 10 8
Decca 2-speed Record Player £12 1 6
Decca 3-speed Motor and Table £6 8 6
Plessey 3-speed Record Changer £23 13 0
Collaro Record Changer £12 3 0

MONTROSE METERS—Just out :
Pocket size, A.C. and D.C., 6 v., 30 v., 150 v., 300 v., 30 mA., 300 mA., 3 a., and circuit test, 50/-.

MAGNETIC RECORDING MADE EASY
Our Units MRU1 and 2 effectively convert existing amplifiers **without internal modifications** to enable recording and playback to be done. Unit MRU3 is a complete recording amplifier. Complete instructions and circuits, 5/-, post free. (Recording price list 3d. post free)

LINCOLN Oscillator Coils, 45 kc/s 12 6
LINCOLN Spool Adaptors 5 9

PHIDELITY HEADS, High or Low Impedance, from £3 4 6

TAPE :
G.E.C., 30/- ; SCOTCH BOY £1 15 0
E.M.I. H.60A or 65A £1 15 0
Spare spools 4 6

RECORDING MOTORS :
Collaro £2 2 0
B.S.R. £1 10 0

MICROPHONES :
Rothermel D104 Xtal £5 5 0
Reslo Ribbon £7 10 0
Acos Mic-22 Xtal £6 6 0
Trix Movg. Coil £8 0 0
Grampian Movg. Coil £5 19 6
Lustraphone Low Imped. £5 0 0
Floor Stands £3 13 6
Table stands £1 17 6

PICK-UPS :
Acos GP20 £3 11 8
Do., GP19 Head £2 3 4
Decca X.M.S. 2 heads £7 0 0
Connoisseur with 1 head £6 9 0
Do., extra heads £3 11 8
Wilkins & Wright £7 10 7
Leak Ruby Stylus £12 0 0

EXPORTING SIMPLIFIED

Exporting procedure can be a headache to the manufacturer wishing to sell to overseas markets. That is where we come in. Shipping and forwarding has become a highly developed side of our business during the last four years. We can relieve manufacturers of all the paperwork and formalities necessary for the efficient forwarding of electrical and electronic goods to foreign buyers. We can pack them, too, if required. Not only that, but our wide connection overseas may enable us to bring you export orders. Let us discuss the help we could be to you.

N. MIERS & CO. LTD.

115 Gower Street, London, W.C.1
Phone : EUSton 7313 Grams : Mierseco, Westcent

ALL the A.C. power you require from your D.C. supply



with a Valradio

D·C·/A·C· CONVERTER

Models for Electric Gramophone from **£8 16 0** *plus 10%*

Models for
- Radio-grams and Autochange Radio-grams (inc. 3-speed motors)
- Radios
- Televisions, etc., *from* **£11 16 6** *plus 10%*

Input, 6, 12, 24, 32, 50, 110 or 200/250V. D.C.
Output 230V. 50 or 60 c/s.

Valradio *Descriptive literature W.W. 14 from the manufacturers:* NEW CHAPEL ROAD, HIGH ST., FELTHAM, MIDDX. Tel.: FELtham 4242
Service Dept.: 57 Fortess Road, London, N.W.5. Tel.: GULliver 5165
Overseas Enquiries to nearest E.M.I. Organisation Depot.

3 industrial valves from a large range



The Electronics Department of Ferranti Ltd. manufacture an extensive range of indirectly heated single and double tetrode electrometer valves with control grid insulation ranging from 30 x 10^{-14} ohms to better than 3 x 10^{-14} ohms.

Illustrated here (centre and right) are two examples of Electrometer valves and (left) a Crater lamp, which gives a light output proportionate to the anode current. Ferranti specialize in the manufacture of Industrial valves to suit a wide diversity of needs.

Let us send you more details.

Ferranti Ltd.

ELECTRONICS DEPARTMENT MOSTON MANCHESTER 10

F FERRANTI

C

FREE! for YOU

The opportunity of a personal demonstration of the Simphonic Tape Recorder! . . . . .

As a result of increasing requests from "Wireless World" readers for a personal demonstration of the Simon Simphonic Tape Recorder, we today institute a scheme to give YOU the opportunity of seeing and hearing for yourself the outstanding merits of this equipment FREE—wherever you are in Great Britain.

There is no obligation on your part. Simply fill in the coupon alongside and post to us TODAY. We will do the rest. Act NOW as requests must be taken in order of receipt.

To:—SIMON SOUND SERVICE (Dept. W.I), 48-50 George Street, London, W.1.

Please arrange for me to have a personal demonstration of the Simphonic Tape Recorder as advertised.

Name .....

Address .....

★ Offer applies to Great Britain only.

AMMETERS • VOLTMETERS • TEST SETS • AMPLIFIERS • BRIDGES • COMPARATORS • SIGNAL GENERATORS • VALVE VOLTMETERS • COIL ANALYSERS •

BPL

Again at the

PHYSICAL SOCIETY EXHIBITION

Huxley Building, S. Kensington
April 3rd—8th.

showing our latest

ELECTRICAL LABORATORY & PRODUCTION TESTING EQUIPMENT

at

STAND No 106

BRITISH PHYSICAL LABORATORIES
HOUSEBOAT WORKS · RADLETT · HERTS
Telephone RADLETT 5674-5-6

GRAM MOTORS · PICK-UPS

for MICROGROOVE & STANDARD RECORDS

"X-ray" view of MU-10

B.S.R. MU-10 motors for 33 & 78 r.p.m. Speed change by reversing drive pulley. 10in. turntable. 100-250v. **£3.15s.**

MU-14

MU-14 de luxe model with ROTACAM instant speed change for 33 45 & 78 r.p.m. **£6. 8. 6d.**

GU-4A Three-speed RADIOGRAM UNIT

Now available for the home market, this new combined unit uses the popular MU-14 motor on a unit plate with pickup and AUTO-STOP.

The pickup is of the Acos dual purpose type fitted with a sapphire needle.

Beautifully finished in mottle enamel. **£10.**

Full list including Auto changers on request!

ACOS GP-20 pickups, standard £3.11.5
GP-19 LP microgroove head only £2.3.4

MARCONI Type 14, with matching transformer .. £2.8.4

GOLDRING Type 130 standard lightweight .. £1.15.10
Type 137 De-luxe lightweight £1.19.5
ditto with AUTO-STOP £2.6.7
Type 150 with adjustable counterweight for 33 45 or 78 r.p.m. records. Complete with two sapphires. £3.11.8

DECCA Twin head 'turnover' £3.19.4

CONNOISSEUR Standard £4.11.8
Super de luxe, with two heads £10.0.0

All post free in U.K!

GU-4A

Frith RADIOCRAFT Ltd
PHONE 58927
CHURCH GATE LEICESTER

There are* QUADS *for schools

and* QUADS *for printers



even* QUADS *like this

★ *Alternative spelling for 'QUODs'*



***but only one* QUAD**

like this –

The Design of electronic equipment is an exact science, and it must be guided by a specification.

Whilst international agreement was reached on such a specification for the optimum reproduction from pre-war records, no such provision has been made to encompass the recent great advances in recording. This is, no doubt, due to the wide variations in the inherent quality of records to be found in the average library.

The control technique of the Q.U.A.D. amplifier represents the only real attempt in recent years to obtain the best possible performance from each and every recording.

. . . £35

Send a postcard for our illustrated booklets

ACOUSTICAL MANUFACTURING CO LTD

HUNTINGDON · HUNTS · TEL. 361

Post Terms C.W.O. or C.O.D.
No C.O.D. under £1

RADIO SUPPLY CO

15 WELLINGTON ST. LEEDS 1

Postage 1/3 charged on orders under £3. Open to callers 9 a.m. to 5.30 p.m. Saturdays un'il 1 p.m.

R.S.C. MAINS TRANSFORMERS

Fully Guaranteed, Interleaved, and Impregnated. Primaries 200-230-250 v. 50 c/s. Screened.

TOP SHROUDED DROP THROUGH
260-0-260 v. 70 ma., 6.3 v. 3 a., 5 v. 2 a. 14 11
260-0-260 v. 80 ma., 6.3 v. 2 a., 5 v. 2 a. 14 11
350-0-350 v. 80 ma., 6.3 v. 2 a., 5 v. 2 a. 17 6
350-0-350 v. 90 ma., 6.3 v. 3 a., 5 v. 2 a. 21 9
250-0-250 v. 100 ma., 6.3 v. 4 a., 5 v. 3 a. 23 11
300-0-300 v. 100 ma., 6.3 v.-4 v. 4 a., C.T. 0-4-5 v. 3 a. 23 11
350-0-350 v. 100 ma., 6.3 v.-4 v. 4 a. C.T. 0-4-5 v. 3 a. 23 11
350-0-350 v. 120 ma., 6.3 v. 4 a., 5 v. 3 a. 28 11
350-0-350 v. 150 ma., 6.3 v. 4 a., 5 v. 3 a. 29 11

CLAMPED UPRIGHT MOUNTING
250-0-250 v. 100 ma., 6.3 v. 6 a., 5 v. 3 a., for R1355 conversion 26 9
350-0-350 v. 100 ma., 6.3 v. 3 a., 5 v. 3 a. 23 10
350-0-350 v. 150 ma., 6.3 v. 4 a., 5 v. 3 a. 29 9

FULLY SHROUDED, UPRIGHT
250-0-250 v. 60 ma., 6.3 v. 2 a., 5 v. 2 a. Midget type 2½-3-3in. 17 9
250-0-250 v. 100 ma., 6.3 v.-4 v. 4 a., 0-4-5v. 3 a. 25 9
300-0-300 v. 100 ma. 0-4-6.3 v. 4 a., 0-4-5 v. 3 a. 25 9
350-0-350 v. 70 ma., 6.3 v. 2 a., 5 v. 2 a. 18 9
350-0-350 v. 100 ma., 6.3 v.-4 v. 4 a., 0-4-5 v. 3 a. 25 9
350-0-350 v. 150 ma., 6.3 v. 4 a., 5 v. 3 a. 32 9
350-0-350 v. 250 ma., 6.3 v. 6 a., 4 v. 8 a., 0-2-6 v. 2 a., 4 v. 3 a., for Electronic Eng. Televisor 67 6
425-0-425 v. 200 ma., 6.3 v.-4 v. 4 a. C.T. 6.3 v.-4 v. 4 a., C.T., 0-4-5 v. 3 a., suitable Williamson Amplifier 51 -
325-0-325 v. 20 am., 6.3 v. 0-5 a., 6.3 v. 1.5 a. for Williamson Preamplifier 17 6

FILAMENT TRANSFORMERS
All with 00-250 v. 50 c.s., primaries: 6.3 v. 2 a., 7 6; 0-4-6.3 v. 2 a., 7 9; 12 v. 1 a., 7 11; 6.3 v. 3 a., 10 11; 6.3 v. 6 a., 17 9; 0-2-4-5-6.3 v. 4 a., 16 9; 12 v. 3 a., or 24 v. 1.5 a. 17 9

CHARGER TRANSFORMERS
All with 200-230-250 v. 50 c.s. Primaries:
0-9-15 v. 1.5 a., 13 9; 0-0-15 v. 3 a., 16 9;
0-9-15 v. 6 a., 22 9; 0-4-9-15-24 v. 3 a., 22 9;
0-9-15-30 v. 3 a. 23 9

SMOOTHING CHOKES
250 ma., 8-10 h., weight 12 lb. 17 6
200 ma. 5 h. 100 ohms 7 6
100 ma. 10 h. 100 ohms 7 6
80 ma. 10 h. 350 ohms 5 6
60 ma. 10 h. 350 ohms 5 3

AUTO TRANSFORMERS
100 watts 100-200-230-250 v. 19 9

ELIMINATOR TRANSFORMERS
Primaries 200-250 v. 50 c.s. 120 v. 40 ma. 7 11
120-0-120 v. 30 ma., 4 v. 1 a. 12 9

OUTPUT TRANSFORMERS
Midget Battery, Pentode 66: 1 for 354, etc. 3 6
Small Pentode, 5,000 ohms to 3 ohms 3 9
Standard Pentode 5,000 ohms to 3 ohms 4 9
Multi ratio 40 ma., 30: 1, 45: 1, 60: 1, 90: 1 Class B Push-Pull 5 6
Push-pull B watts 6V6 to 3 ohms 8 9
Push-pull 10-12 watts 6V6 to 3 or 15 ohms 15 11
Push-pull 10-12 watts to match 6L6, PX4, 6V6, etc., to 3-5-8 or 15 ohms speaker 16 11
Push-pull 15-18 watts to match 6L6, etc., to 3 or 15 ohms speaker 21 9

P.M. SPEAKERS. All 2-3 ohms: 5in. 11 9; 6in. 14 11; 8in. 14 11.

M.E. SPEAKERS: 8in. 3 ohms, field 600 ohms, 12 9. 10in. 3 ohm (field 1,000 ohms), 21 9.

VOLUME CONTROLS, with long spindles. All values less switch, 2 9; with S.P. switch, 3 11.

WIRE WOUND POTS, 20 ohms, 750 ohms, 5K, 20K, 50K, 2 9.

ELECTROLYTICS. Tubular, 8 mfd. 350 v., 1 9; 8 mfd. 450 v., 2 3; 16 mfd. 350 v., 2 3; can 16 mfd. 450 v. 2 11; 24 mfd. 350 v., 2 11; 8-8 mfd. 450 v., 8-16 mfd. 450 v., 4 6; 16-16 mfd. 450 v., 5 3; 32 mfd. 350 v., 4 3; 32 mfd. 450 v., 5 3; 40 mfd. 450 v., 4 9; 32-32 mfd. 350 v., 6 6; 32-32 mfd. 450 v., 6 9; 12-12 mfd. 350 v., 3 3; 250 mfd. 12 v., 11d.

SPECIAL OFFERS
Fil. trans. (small), 220/240 v. input, 6.3 v. 1.5 a. output 5 9
Auto Trans. 0-200-230-320 v. 70 ma., with separate L.T. 6.3 v. 3 a. 7 6
Standard Output Trans. 5,000 to 5 ohms 3 9
25 mfd. 25 v. cans with clip 10d
Accumulators, dry charged, 2 v. 10 a. H. 4 9
.0005 mfd. 2-gang variables (ex. E.M.I.) 5 9
1500 mfd. 6v. can eleco. 3/9 ea.

RECEIVER CHASSIS, 16 s.w.g. Undrilled Aluminium 10-5½-2in., 3 9; 11-6-2½in., 4 3; 12-8-2½in., 5 3; 16-8-2½in., 8 6; 20-8-2½in., 8 11;

AMPLIFIER CHASSIS, 16 s.w.g. Undrilled Aluminium, 12-8-2½in., 7 11; 16-8-2½in., 10 11; 20-8-2½in., 13 9.

MISC. ITEMS. Philips chokes 90 ma. 8 h. 100 ohms 4 6; TRF coils L. and M. with circuit 6 6; 4-pole 4-way Yaxleys L/S, 1 11. Ex-Gov. Chokes (Trop), 50 ma. 50 h. 1,000 ohms, 4/6. VR91 Ex. New Equipment, 6 6.

SELENIUM RECTIFIERS. Ex-new equipment. 230 v. 50 ma. H.W., 4 9; 250-500 v. 60 ma. H.W., 6 9; 680 v. 30 ma., 6 9.

FULL RANGE OF STANDARD COMPONENTS AVAILABLE AT KEEN PRICES. ALL GOODS GUARANTEED AND NEW, UNLESS OTHERWISE STATED. QUANTITY QUOTATIONS GIVEN FOR STANDARD TYPES OR SPECIAL MAINS TRANS. S.A.E. PLEASE WITH ALL ENQUIRIES. FULL STOCK LIST 4d. SPECIAL LIST FOR TRADE, 4d.

The new HYDE

foot operated

WIRE STRIPPER

These two machines will, between them strip with speed and accuracy practically all types of Insulated Wires and Cables from Small Wires and Flexes up to Cables of ¾" diameter. HYDE Stripping Machines are cutting the costs and speeding the production of many world famous manufacturers.

SEND SAMPLES OF WIRES AND CABLES USED, FOR FULL REPORT

. . . and the

BENCH MODEL

Telephone: Wythenshawe 2850

J. B. HYDE & CO. LTD., Wythenshawe, Manchester

Recently released by the B.B.C.—the finest moving-iron cutterhead yet available. . . . .

B.B.C. TYPE

Negative Feedback

RECORDING CUTTERHEADS



- Temperature effect reduced by Silicone damping.
- Frequency response 2 db 50 c.s 15 Kc.s.
- Vertical and horizontal patterns.
- Standard or modified types for velocities up to 21 cm sec. r.m.s.

Send for our new, illustrated 34-page book, giving details and circuit diagrams of amplifiers suitable for use with these cutterheads. Useful recording data and tables 5/- *post free.*

GRAMPIAN REPRODUCERS LTD

9, HANWORTH TRADING ESTATE, FELTHAM, MIDDX.

Phone: Feltham 2657 *'Grams: Reamp, Feltham*

The ECONOMY of PURPOSEFUL DISK SELECTION

THE great development in the art of direct recording has resulted in the use of disks for a steadily increasing variety of purposes. Some applications call for a disk possessing a quality not demanded by other applications. For example, in the recording of disks as "masters" for processing gramophone records the disk must not only be beyond reproach in performance but also in appearance. On the other hand, there are many occasions, such as auditions, rehearsals, etc., when this high standard is not required, and when the extra cost of the finest disks is not justified.

In order to fulfil every possible recording requirement in the most economical way we have arranged that any user can select disks of a quality most suited to the particular recording needs. To this end we have adopted a new and exacting system of classification by which our disk production is divided into four selected groups. Each group has been carefully chosen to cover effectively the class of recording for which we consider the disk most suitable.

THE NEW CLASSIFICATION

●

WHITE LABEL ("Master")

For processing where a perfect blank is required. Since only one side of a disk can be processed, an easily removable label is affixed to the reverse side.

GREEN LABEL

A disk of excellent quality, recommended for use by Broadcasting Stations, Film Studios and Commercial Recording Studios, where both sides of the disk are required for direct playback.

YELLOW LABEL

A disk of excellent quality, recommended for use by Broadcasting Stations, Film Studios and Commercial Recording Studios, where one side of the disk is required for direct playback. The second side may, or may not, be slightly inferior in appearance but is capable of being fully recorded for rehearsal or audition.

BLUE LABEL

A high quality double-sided disk which may have one or both sides only slightly inferior to those of the Green and Yellow Label disks. Recommended for use in speech training, speech therapy and for rehearsals

THE MASTER SOUND SYSTEM

Since the same high quality M.S.S. lacquer is used for coating the disks in all four groups, the user is assured of the finest possible performance within the price class.

It is opportune to mention here that very large numbers have been selected every year from M.S.S. standard disks for processing by some of the most critical users throughout the world.

M.S.S. disks will in future be available with the labels as shown which indicate their recommended uses.

Fullest technical details available on request.

M.S.S. RECORDING CO. LTD. · POYLE CLOSE · COLNBROOK · BUCKS · Telephone : Colnbrook 284.

They are the most Reliable



WESTINGHOUSE

WESTALITE METAL RECTIFIERS

WESTINGHOUSE BRAKE & SIGNAL CO., LTD., 82, York Way, King's Cross, London, N.1.

made to measure . . .

The man who knows exactly the state of his insulation at any time—is wise.

But one who uses a "Record" Insulation Test Set is wisest. It is made to measure—ACCURATELY, by those who were pioneers in this field and who have kept ahead.

RECORD MAKERS OF MANY OTHER FINE INSTRUMENTS

THE RECORD ELECTRICAL CO LTD

BROADHEATH · ALTRINCHAM · CHESHIRE

Phone: Altrincham 3221 (3 lines) Cables and Grams: "Circscale" Altrincham
London Office: 28 Victoria Street, London, S.W.1. Phone: Abbey 5148 & 2783
Grams: "Circscale" Sowest, London. Cables: "Circscale" London

MODERN ELECTRICS LTD.,

164, Charing Cross Road,
London, W.C.2 'phone TEMple Bar 7587

Immediate delivery from stock

Export enquiries welcomed. *Prompt attention to post orders.*

TAPE RECORDERS

SOUNDMIRROR	
Table Model	£69 10 0
Portable Model	£79 10 0
SIMPHONIC	
1A (now booking early delivery)	£76 0 0
SCOPHONY-BAIRD	
Mk. I	£58 5 6
Mk. II (new model)	£68 5 0
"Magnetic Recording" by S. J. Begun. Post free	£1 4 0

RECORDING TAPE

Soundmirror	£1 5 0
E.M.I. (Hi-Co)	£1 15 0
(Med-Co)	£1 15 0
Type 57 ..... 3250ft.	£6 0 0
600ft. Sin. spool	£1 1 0
Durex (Scotch Boy)	£1 15 0
Philitape	£2 0 0
Empty spools	4 0 & 6 6

PICK-UPS AND MOTORS

ACOS G.P.20	£3 11 5
L.P. and Std. Heads	£3 3 4
DECCA Pick-up, Std.	£3 15 4
XL. Pick-up, T.O. Head for L.P. and Std.	£3 19 2
Mag. XMS. with L.P. and Std. Hds.	£7 0 0
DECCA MOTORS	
33⅓ and 78 spds.	£3 14 4
33⅓, 45 and 78	£7 3 4
PLESSEY 3-speed Auto-changer unit	£23 13 0

TEST GEAR

AVO	
Model 7	£19 10 0
Model 8	£23 10 0
D.C. Minor	£5 5 0
Uniminor	£10 10 0
Univ. Bridge	£16 0 0
Wide Band Signal Generator	£30 0 0
Valve Tester	£50 0 0
Electronic Testmeter	£40 0 0
PIFCO Radiometer	£1 7 6

TAYLOR
ALL THE NEW TAYLOR TEST-GEAR IN STOCK AND AVAILABLE ON H.P. TERMS.
Send S.A.E. for catalogue and terms.

new

METALLISED CERAMICS FOR HERMETIC SEALS

Steatite & Porcelain Products present an outstanding advance in the technique of metallising ceramics; they can now offer ceramic bushes for hermetically sealed components free from all shortcomings common to earlier types of metallising



There are five important advantages of the new process:

1. The new metallising is robust and highly resistant to solution in any soft solder alloys.
2. Any method of soldering may be used, without precautions of controlled temperature and soldering time; no special skill in soldering is necessary for consistent results.
3. The new metallised ceramics may be repeatedly mounted and demounted: they may be removed from faulty or broken-down components and used again.
4. High melting-point soft-solders (such as silver-lead) may be used in assembly of these new metallised ceramics. Thus, all risk is eliminated of failure of the hermetic sealing during component assembly into equipment.
5. No gas or oil leakage can occur—the bond between the new metallising and the ceramic is stronger than the ceramic itself.

SEND FOR FULL DETAILS

The new metallising is applied to all the hermetic seals of the standard range (shown in catalogue No. 25, available on request). Special types, including multi-seals, can readily be produced to customer's requirements. Please write to us for further details. We shall be glad to answer any queries on the new metallised ceramics.

STEATITE & PORCELAIN PRODUCTS LTD

STOURPORT-ON-SEVERN WORCESTERSHIRE TEL: STOURPORT 111 GRAMS: STEATAIN STOURPORT

SPP9

STRICTLY EXPORT ONLY



HALTRON

Leading Exporters of all types of Radio Receiving and Transmitting Tubes. Current Production and Ex-Government Surplus Special Purpose Tubes. Over 400 types in large quantities, available Ex-Stock. Suppliers to Foreign Governments, Airlines, etc.

HALL ELECTRIC LTD

89, CHARLOTTE ST., LONDON, W.1. Phones: MUSEUM 9681 (5 lines) Cables: HALLECTRIC, LONDON

SHORTAGE OF RADIO & T/V ENGINEERS

The demand of Industry for our trained students is still greater than we can supply —and is likely to remain so for many years.

We offer:

FULL TIME DAY COURSE

1 year course in Principles and Practice of Radio and Television.

Next Course commences 15th April

Write for FREE BROCHURES giving details of the above, of our 3-year course, and of others.

E.M.I. INSTITUTES—the only college which is part of a great industry.

E.M.I. INSTITUTES

(DEPT. 16A), 10, PEMBRIDGE SQUARE, LONDON, W.2. TEL.: BAYSWATER 5131/2

Associated with "H.M.V." MARCONIPHONE COLUMBIA E.T.C.

I.A.1

BAKERS 'Selhurst' RADIO

PIONEERS OF MOVING COIL SPEAKERS SINCE 1925

NEW "HIGH FLUX" 1952 MODELS

HIGH FIDELITY SPEAKERS

- The World Famous 12" Triple Cone.
- 12" Single Cone Model.
- 18" "Duplex".

Write for illustrated list and technical details of SPEAKERS, TUNERS, AMPLIFIERS & RECORD PLAYERS

BAKERS 'SELHURST' RADIO

Quitable House, Dingwall Road, Croydon

Telephone: CROydon 2271/2



MARCONI instruments

Marconi Instruments are in the picture — in radio communications, in industry and in the operating theatre. The world of radio uses Marconi measuring and test equipment at every stage of manufacture, maintenance transmission and reception.

Industry looks to Marconi for measuring instruments of high accuracy with which to monitor processes and maintain standards: while, speeding the progress of modern medicine, Marconi electro-medical and X-ray apparatus is at work in hospitals and clinics.

MARCONI INSTRUMENTS LIMITED
ST. ALBANS · HERTS · Telephone: St. Albans 6161/7

Midland Office: 19 The Parade, Leamington Spa.
Northern Office: 30 Albion Street, Hull.
Export Office: Marconi House, Strand, London, W.C.2.

"THE NEW HIGH-FIDELITY EQUIPMENT YOU HAVE BEEN WAITING FOR"

GARRARD DUAL-SPEED (33⅓ and 78) GRAM UNITS incorporating superior type A.C. motor mounted on unit-plate with speed switch and lightweight pickup arm. Complete with two latest type, 3-pin plug-in DECCA hi-fi magnetic pickup heads for Standard and L.P. Limited number only. Price **£12**, carr. and pack. 3/6.

COLLARO AUTOCHANGERS, model RC511, new single speed model with interchangeable plug-in pick-up head, plays nine records, reject mechanism, beautifully finished unit plate. A.C. operation. Price with magnetic head **£11 16 9**, or with Acos GP27 crystal head, **£13 2 6**, carr. 5/-.

COLLARO 3-SPEED AUTOCHANGERS, model 3RC511, as above but for 33⅓, 45 and 78 r.p.m. Price with one dual purpose Acos GP27 head, **£15 10 6**, or with two separate GP27 heads for Std. and L.P. **£18 15 -**, carr. and pack. 5/-.

COLLARO 3-SPEED GRAM. UNIT, model AC3/514, with pick-up and autostop. Price with dual-purpose GP27 plug-in head **£11 8 9**; with two sep. GP27's, **£14 8 9**, carriage and pack. 3/6.

DECCA GRAM MOTORS, adjustable for 78 or 33⅓ r.p.m., **£3 17 6**. Ditto with switch giving instantly 33⅓, 45 and 78, **£6 8 6**. Post 1/6.

CHANCERY LIGHTWEIGHT PICKUPS accurately counterpoised, fitted with hi-fi crystal push-in cartridges and permanent sapphires (GP20 standard). With std. or L.P. head, price **53/-** or with both heads **84/6**, post 1/6.

RECORD PLAYER CASES, well made, measure 15½in. x 13½in. x 7in., beautifully covered in brown rexine, fitted hinged lid, clasps and sprung carrying handle. Price complete with uncut motorboard, **57/6**. Post 2/6.

RECORD PLAYERS. No. 1 comprises above Decca 3-speed motor with above Chancery Pickup with 2 heads in above Record Player cases. Price **15 gns. No. 2** comprises Collaro AC3/514 with two GP27 heads in same case. Price **17 gns. No. 3** incorporates the above Garrard dual-speed motor with two Decca heads. Price **15 gns. No. 4** comprises B.S.R. model GU4 3-speed gram. unit with lightweight turnover Acos crystal pickup in same case. Price **13 gns.** (Unit only **£10**). All these units supplied in microgram case (below) **7/6** cheaper.

MICROGRAM CABINETS, ex ENSA, very robust, measure 17½in. wide a 15½in back to front x 8½in. high overall with uncut motorboard and speaker grill at front, reinforced corners, two locked clasps and carrying handle, finished blue rexine. Price **52/6**. Post paid.

SYMPHONY No. 1 (AMPLIFIER) by N.R.S. The most versatile domestic Audio Amplifier on the market to-day. Independent control of Bass, Middle and Top, separate Scratch Cut, negative feedback. For A.C. 200-250 v. Input for magnetic, crystal and hi-fi pick-ups and Tuner. 5-watts output. Price 3 ohm model, **9½ gns.**; 15 ohm model, **£10 7 6**, carriage 5/-.

SYMPHONY No. 2 MARK II. New model with 10 watts push-pull triode output, breathtaking realism, hum level negligible—90 db down. Woden mains transformer, choke and output transformer for 3, 7.5 and 15 ohms. Input for ordinary and hi-fidelity pick-ups. Tone control system same as No. 1. A truly magnificent instrument for only **15 gns.**, carriage 5/-.

ABOVE, but fitted with remote control panel on flying cable, **17 gns.**

DECCA AND CONNOISSEUR PICKUP ENTHUSIASTS should note that we do two special models of our "Symphony" Amplifiers with extra pre-stage to exactly match these famous pickups. Prices: No. 1 (either ohmage) **£12**; No. 2 Mark II **17 gns.** Carr. 5/-.

No. 2 PUBLIC ADDRESS AMPLIFIER. For A.C. Same Chassis and power parts as No. 2. Symphony but simple one knob tone control. 15 watts push-pull output. 2 inputs with separate vol. controls for fading mike and gram. Comp. kit **10 gns.** Ready built, **£11 19 6**. **A.C. D.C PUBLIC ADDRESS AMPLIFIERS.** To fulfil the demand for high-quality on D.C. we have secured a number of the extremely fine Rees Mace Model U. 66 Amplifiers. The input selector switch gives Radio/Gram/Mike. Undistorted push-pull output is conservatively rated at 8 watts, matching 15 ohms. Mike trans. incorporated. Six Mazda valves, the whole housed in beautiful dove-grey metal case with chrome handles. Volume and tone controls, indicator light, fully fused. Brand new in makers cartons, fully guaranteed. List Price **24 gns.**—Our Special Offer **15 gns.**, carr. 5/-.

WODEN OUTPUT TRANSFORMERS, high-grade, input to match two 6V6's or two 6L6's, output tapped 3, 7.5 and 15 ohms, **25/6**, post paid.

BASS-REFLEX CABINET KITS give superb bass response and top (¾in. patent timber). Full instructions supplied. 8in. speaker model 2ft. 6in. high x 1ft. 3in. x 1ft. deep. Price **85/-**; 10in. speaker model, 30in. x 16in. x 13½in., **97/6**; 12in. speaker model, 30in. x 17½in. x 16in., **107/6**. Any of above ready built for 7/6 extra. Carr. in any case, 7/6.

FOR CALLERS ONLY. Above B/R Cabinets also now available, finished in high-class veneers to match customers' individual furnishing schemes. Examples on view.

DEMONSTRATIONS. We are open for demonstrations of all our advertised and other lines from 9 a.m. till 6 p.m. daily (incl Sats.). We respectfully suggest you call in and see us first—it will save you time and money. Expert technical advice without obligation.

NORTHERN RADIO SERVICES
16 Kings College Road, London, N.W.3
Phone: PRimrose 8314

FREE! to those who wish to Qualify in any of these subjects*



Applied Mechanics ★ Aviation Wireless ★ Draughtsmanship—Electrical or Mechanical ★ Electrical Engineering ★ Electrical Instruments ★ Electric Wiring and Lighting ★ General Cert. of Education ★ Mechanical Engineering M.I.Mech.E. ★ Mathematics ★ Physics ★ Radio Service Engineering—C and G Radio Servicing Cert. ★ Telecommunications C and G Telephony, Telegraphy, Radio, Lines Plant Practice, Line Transmission, Telecomm. Practice, Telecomm. Principles, Mathematics for Telecomms. ★ Television C and G Servicing Cert. ★ Telegraphy—P.M.G. Exams. ★ Works Management. All Commercial Subjects.

This book costs you nothing. But it offers you success in terms of your career.

TEAR OUT

★ BY POST, specialised Tutors in these and many other subjects give individual and understanding attention to Bennett College Students to whom books are free. Tuition is guaranteed until you qualify. State your subject. Send coupon for prospectus as it applies to you.

To the Governor, Dept. D.41
The BENNETT COLLEGE
Sheffield, England. Send me the free book on how I can qualify in.....(subject)
NAME.....
ADDRESS.....
.....AGE (if under 21).....
PLEASE WRITE IN BLOCK LETTERS

You can start on a BENNETT COURSE FOR ONLY 30/- and monthly instalments of 15/-



SIGNAL GENERATOR TYPE 10. 100 Kc/s-100 Mc/s

Price £7 . 10 . 0

The accuracy, reliability and comprehensive specification, are some of the reasons why the *TYPE 10* has achieved such outstanding success.

● *100 Kc/s to 100 Mc/s* ● *Modulated or unmodulated carrier* ● *Direct calibration* ● *Adjustable 400 c.p.s., AF signal* ● *Stable RF oscillator* *Large, easily read scale* ● *AC mains operation.*

New instruments now available include the *HOMELAB CHECKTEST* price 37/6d., and a range of accurately calibrated variable condensers, 100pf., 500pf., and 1000pf., price 42/- each.

Obtainable only direct from the manufacturers. Send for full technical details or call at address below

HOMELAB INSTRUMENTS LTD.,
68a, COBDEN ROAD, LONDON, E.11
Telephone: LEY 5651

ATE/TMC

OPEN WIRE AND CABLE
LINE TRANSMISSION EQUIPMENT

Compactness . . .

combined with accessibility are features of this carrier telephone equipment.

The modulators, demodulators, band-pass filters and demodulator amplifiers for three sub-groups of four channels, are mounted on one side of the 10′ 6″ bay, in addition to a meter panel and a link panel.

Right: Channel bay of a 12-channel system for use on cable



AUTOMATIC TELEPHONE & ELECTRIC CO. LTD.

Radio and Transmission Division: STROWGER HOUSE, ARUNDEL STREET, LONDON, W.C.2
Telephone: TEMple Bar 9262 *Cablegrams:* Strowgerex, London

Manufacturers:
AUTOMATIC TELEPHONE & ELECTRIC CO. LTD. - - - - - Liverpool and London
TELEPHONE MANUFACTURING CO. LTD. - - - - - - - St. Mary Cray, Kent

AT. 8431-B105

Three heads are better than one!

For Standard and Microgroove Recordings

Green Spot with .001" radius sapphire for microgroove recordings.

Red Spot with .0025" radius sapphire for modern standard recordings.

Yellow Spot with .003" radius sapphire for older standard recordings.

These pickup heads are fitted with an easily replaceable armature system complete with a semi-permanent sapphire. Armature mass 20 mg.

Extremely low mass at needle point (4/5 mg. only), allowing for reduction in downward pressure to 10/12 grams for standard recordings and 7/9 grams for microgroove recordings.

Prices: With one head £4 10 0 plus £1 19 0 Purchase Tax. Extra heads each £2 10 0 plus £1 1 8 Purchase Tax. Spare armature system with sapphire 14/8 including tax.

Licensed under Letters Patent No. 586900 and/or 615424.

a **Connoisseur** product

Tel.: HALIFAX 69169.

Manufactured by A. R. SUGDEN & CO. (ENGINEERS) LTD., Well Green Lane, Brighouse, Yorks.

10 Weeks!

20 WEEKS!!

40 WEEKS!!!

50 WEEKS!!!!

IF THESE DELIVERY DATES ARE DRIVING YOU CRAZY PERHAPS WE CAN HELP?

TELE-RADIO (1943) LTD.

177 EDGWARE ROAD, LONDON, W.2

Phone: PAD. 5606
PAD. 6116

Shop Hours:
Mon.-Sat. 9 a.m.—6 p.m
Thursday 9 a.m.—1 p.m

EXPORT AND WHOLESALE ONLY

VALVES RECEIVING VALVES TRANSMITTING

TUBES CATHODE RAY

- **Govt. Surplus & Regular Types**
- **Special purpose tubes**
- **No Dollar Expenditure**
- **Rapid Delivery from Ample Stocks**
- **One of the Largest in England**

Also large stocks of

- P.M. Speakers 2½"—12"
- Mains Transformers
- Resistors:- ¼, ½ and 1 Watt
- Condensers:- Mica, Electrolytic, Oil, etc.

SEND US YOUR REQUIREMENTS

V.E.S. WHOLESALE SERVICES LTD.,

11, GUNNERSBURY LANE, W. ACTON, W.3.

Telephone: ACOrn 5037 (3 lines).

Osram VALVES

Pointers for Designers

AND CONSTRUCTORS

X18—NEW 1·4 volt FREQUENCY CHANGER

The Osram X18 is a new all-glass 1.4V miniature pentagrid frequency changer suitable for operation up to 25 Mc/s and designed to supersede the Osram X17 (1R5) heptode. The improved conversion gain at higher frequencies will ensure a much more satisfactory performance in all-wave battery receivers. When used as a replacement for the X17, the X18 will give a 2:1 increase in conversion gain - for the same battery consumption.

A typical recommended circuit arrangement is given below; from which it will be seen that the pin connections differ from those of the X17.



Write for data on the X18 to: Osram Valve & Electronics Dept.

THE GENERAL ELECTRIC CO. LTD., MAGNET HOUSE, KINGSWAY, W.C.2

G.E.C.

QUARTZ CRYSTAL UNITS



for reliable Radio Communications

YOU CAN'T BUY BETTER!

A COMPREHENSIVE RANGE OF UNITS IS AVAILABLE COVERING ALL COMMUNICATION REQUIREMENTS. ASK FOR LEAFLET GC5012.

Be sure that the Quartz Crystal Units in your radio equipment are the best obtainable, for they are the most critical components.

SALFORD ELECTRICAL INSTRUMENTS LTD · SALFORD 3 · LANCS

A SUBSIDIARY OF THE GENERAL ELECTRIC CO LTD OF ENGLAND

-towards perfection-

LOWTHER:-

TUNERS

AMPLIFIERS

WHISTLE FILTERS

CORRECTORS

etc., etc.

Latest list now available, copy gladly sent upon request.

THE LOWTHER MANUFACTURING CO.

(The Laboratory Production Unit)

Lowther House, St. Mark's Road, Bromley, Kent. RAV. 5225.

TO HAMS & DEALERS

WE WANT TO BUY

AMERICAN SURPLUS EQUIPMENT OF EVERY KIND

FOR RADIO HAM SHACK— NEW YORK'S LEADING DEALERS

RECEIVERS • TRANSMITTERS

TEST SETS • SIG GENS

TELETYPE EQUIPMENT

EVERYTHING ELECTRONIC

We are interested in any quantity, from one upwards. 'Phone us immediately, transfer charge.

ALTHAM RADIO CO BRAZENNOSE ST MANCHESTER 2 *Tel.: DEAnsgate 5387*

GOVERNMENT SURPLUS

LONDON CENTRAL RADIO STORES

DELIVERY FROM STOCK

FLUXMETERS Model WY0023

Calibrated in three ranges, 500-1,000, 1,000-2,000, and 2,000-4,000 Gauss. Direct reading. Complete with polarity indicator and probe for minimum gap of 1¼in. Brand new in portable wood case with carrying handle. 12in. × 9in. × 5¼in. Less battery.

£4.5.0 Carr. and pkg., 5/-.

TELE F. DESK TELEPHONE complete with Amplifier

New condition. In two separate units. Suitable for office and many other purposes. Battery operated. Complete in transit case. Carr. and pkg. 3/6 **£5.17.6**

VIBRATORS

2-volt, Type R76C. 7-pin self-rectifying. Output 200 v. at 60 mA. Made by Electronic Laboratories Inc., **7/6.**

Mallory, Type 650, 6-volt 4-pin American base, **7/6.**

Mallory, Type G629C. 12-volt, 4-pin American base, **7/6.**

Owing to our large contract we are still able to supply

PHILCO 5-VALVE Reconditioned SETS

— UNIVERSAL MAINS —

These superhet receivers have all been thoroughly overhauled at our works. Ready for immediate use and GUARANTEED. We have sold over 3,000 of these sets all over the country. If in London call and see them for yourself.

184/- ALL-WAVE TABLE MODEL, incorporating two-speed tuning and provision for normal aerial or dipole. Medium or dark walnut cabinet, size 18¼ × 20 × 9¼in. Excellent performance.

115/- LARGE TABLE MODEL, in light walnut cabinet only, size 19 × 16 × 10¼in., large dial in metres and frequency. Exceptional high gain using high "Q" IF transformers and special aerial circuit. Normal or dipole aerials may be used.

110/- MEDIUM TABLE MODEL, known as the "Cathedral Model," receiving all British and European stations with great clarity and freedom from interference. Normal or dipole aerial input. Available in light or dark oak. Cabinet size, 19 × 14 × 10in.

Plus **10/6** per set carriage and packing

CATHODE RAY TUBES TYPE VCR97

6in. electrostatic, suitable for T/V. As new, unused and tested. Price **30/6** plus packing and carriage 7/6.

CHARGING BOARDS. Control Panels Only



24 v. 1,200 watts. Includes five 1½ in. moving coil ammeters (1, 0-40 a., 4, 0-15a.). One moving coil voltmeter 0-40 v. Five heavy duty sliding resistances, etc., complete in Metal case as shown with fold-back doors. Size 18 × 17 × 8½ in. Offered at less than half the component value. Price **£6.10.0**

Carriage extra.

MARCONI DE LUXE 8-VALVE MOTOR TUNING PRESS-BUTTON ALL-WAVE TABLE RADIO SUPERHET

For details see last issue. For callers only. Price **£23.10.0**

WALKIE-TALKIE (Transmitter and Receiver) CHASSIS, Type 38 Mk. II. Range 7-4-9 Mc/s. For details see last issue. Carriage and packing **2/6** **£4.10.0**

WANTED URGENTLY

GOOD USED or NEW EQUIPMENT

AR88s · D.B. 'SCOPES · METERS and all kinds of TEST GEAR · CONVERTERS, etc.

UNISELECTOR SWITCHES

Full Wipers

3-bank **19/6**
4-bank **35/-**
6-bank **35/-**
8-bank **47/6**

Half Wipers

4-bank, **27/6**; 6-bank, **27/6**; 8-bank, **42/6**

Have various applications, including automatic tuning circuit selection, etc. Operates on 25-50 v.

TELESONIC 4-VALVE BATTERY PORTABLE

(Fixed Range.) Type YA4915



Includes three XH and one XP Hivac midget valves. Can be adapted for Deaf Aid or Midget Receiver, but we do not supply information on this point. Batteries required, 3 v. L.T., 97 v. H.T. In metal case, size 8½ × 7 × 2in. Weight 4 lb., less batteries. Carr. and pkg., 2/6. **45/-**

(Illustration shows chassis partly removed from cabinet.)

SIMPSON MOVING COIL OHM-METER

Two-range 0-2,000 ohms, 0-200,000 ohms. Size 3in. × 5in. P.and.Pkg. 2/6 **42/6**

D.C. Motors, 24 v. approx. 3in. square. Carr. pd. **16/6.**

A.C. Unshrouded Motors 220 v., 3in. square, spindle ⅜in. × ⅜in. long. Useful for electric signs, fans, etc. **15/6**, post free.

New Blower Motors, 24 v. **22/6**, post and pkg. 1/6.

Self-energising Headphones, less headbands. **6/6** pr., post and pkg. 1/-.

Milliammeters. Centre zero 0-30, 3in. dia. **10/-**, post and pkg. 1/-.

Voltmeters. Centre zero 0-3 and 0-30, with testing point attached, 3in. dia. **22/6**, p. & p. 1/-.

Tannoy Hand Microphones, with switch. **8/6**, p. & p. 1/-

Midget Volume Controls, 30 ohm, wirewound. **2/6**, p. & p. 6d.

Volume Controls, 8,000 ohm wirewound. **2/3**, p. & p. 6d.

New Morse Keys. 3/6, p. & p. 9d.

Moving Coil Inserts, 30 ohm. Suitable for miniature speakers and microphones. 2in. dia., 1¼in. deep. **4/6.**

Rotary Converters, 12 v. D.C. output, 275-500 v. D.C. Size 7¼ × 4¼ × 5in. Weight approx. 10 lbs. **21/6**, carr. & pkg. 2/6.

Ex-G.P.O. Plug and Jack. 2/9, p. & p. 6d.

NEW INERT CELLS

No acid or charging required. Suitable for battery sets, electric bells, etc. 1.5 v. **2/10.** Post 9d.

Phosphor Bronze Stranded Aerial. Ex-Admiralty. 100ft. coils. **6/6**, p. & p. 1/-

Garrard Motor, 12in. Turntable and Magnetic Pick-up. 95/-, carr. and pkg. 7/6.

ELECTRO-MAGNETIC COUNTERS FRESH CONSIGNMENT JUST ARRIVED

Ex-G.P.O., every one perfect, electro-magnetic, 500 ohm coil, counting to 9,999, operated from 25 v.-50 v. D.C., many industrial and domestic applications. **ALL EQUAL TO NEW.** Post and pkg. 9d. **15/-**

NEW NIFE ACCUMULATORS. 2.5 v. 2½ amp./hours for 8 hours. Size 3 × 4¼ × 1¼in. (F'at) **6/6.** Post and packing 9d.

WALKIE-TALKIE (Transmitter-Receiver). Type 48 (Mk.1*). Brand new

Made by Emerson

Frequency coverage 6-9 Mc/s. Comprises transmitter/receiver with 10 valves and one 1-Mc/s crystal, in metal case with waterproof cover, sectional rod aerial in satchel. Spare valve case, complete with 10 spare valves, key assembly, hand microphone, two headsets, one hand generator (10 watts) with tripod as illustrated in April '51 issue, two battery boxes, all essential connecting cables. The complete equipment, together with comprehensive instruction manual (inland only). Carr. and pkg. 15/6 **£21.10**

N.B. All carriage charges relate to Inland Orders only. ● We do not issue lists or catalogues.

LONDON CENTRAL RADIO STORES, 23 LISLE ST. (GERrard 2969) LONDON, W.C.2

Closed Thursday 1 p.m. Open all day Saturday and weekdays 9 a.m. — 6 p.m.

with confidence, as only OKERIN Waxes are used.

Yours faithfully,
J. Power Factor
A.M.I.E.E.

P.S.
Waxes are small in bulk but
bulk large in importance —
they must be just right for the
job and reliable. Specify OKERIN.

Sales Department

ASTOR BOISSELIER & LAWRENCE LTD.

9. SAVOY STREET · STRAND · LONDON · W.C.2

Works and Laboratories · WEST DRAYTON · Middlesex

ARTHURS HAVE IT!

LARGE STOCKS OF NEW VALVES

TEST METERS IN STOCK

"AVO" "TAYLOR" TEST METERS AND SIGNAL GENERATORS

Leak Point One Amplifiers	... ...	£28 7 0
Leak Pre-Amplifiers	... ...	9 9 0
Leak Tuning Unit	... ...	36 17 4
Chapman Tuning Units	... ...	17 6
Crystal and Moving Coil Microphones. Decca Replacement Heads and Pickups.		
Goodman's Axiom 150 Speakers	...	£10 5 6
Partridge Output Transformers	for	
Williamson Amplifiers	... ...	6 12 0
Cossor Double Beam Oscilloscope	{1035 ...	85 0 0
	{1049 ...	120 0 0

LATEST VALVE MANUALS

MULLARD, OSRAM & BRIMAR No 4.5- each.

MAZDA 2- each.

Postage 6d. extra

TELEVISION SETS, WIRE AND TAPE RECORDERS ALWAYS IN STOCK.

Goods offered subject to price alterations and being unsold

Arthurs EST 1919

PROPS: ARTHUR GRAY, LTD. **first**

OUR ONLY ADDRESS: **Gray House,**

150-152 Charing Cross Road, London, W.C.2

TEMple Bar 5833-4 and 4765 WRITE FOR LISTS

TELEGRAMS—"TELEGRAY, WESTCENT, LONDON"

CABLES—"TELEGRAY, LONDON"

ALWAYS "SOUND" CHOICE

CELESTION

The Foremost Name in Sound Reproduction

Because no radio receiver can give better reproduction than its loudspeaker permits, Celestion has always been the first choice of discriminating buyers. There is a comprehensive range of models with characteristics to suit all requirements. Write today for details.

Wholesale enquiries to
TRUVOX LTD.
Exhibition Grounds,
Wembley, Middx
(Wembley 1012)

ROLA CELESTION LTD.

Phone Emberbrook 3402-6

WORKS · SUNBURY-ON-THAMES · MIDDLESEX



Routine Factory testing of Mumetal toroidal cores.

Measurement of Magnetic properties of Radiometal Stator Laminations by A.C. Potentiometer.

Technical Control

The key to the consistent excellence of TELCON Magnetic and Special-purpose Alloys.

Precision measurement of magnetic characteristics of toroidal Mumetal cores by the Ferrometer.



Projection Microscope in use in Metallographic laboratory.

Precision measurement of X-Ray difraction pattern.

Automatic testing of physical characteristics of Telcon wire specimens.

Close technical control of production is an all-important factor in the manufacture of Telcon Metals. Accurate tests and measurements are made at various stages in the course of production and the above illustrations show a few of the many routine examinations conducted in our well-equipped laboratories.

MAGNETIC ALLOYS—Mumetal, Radiometal, Rhometal, H.C.R., Permendur, R2799, 36/64, Dust.
RESISTANCE ALLOYS—Pyromic, Calomic, Telcuman, Telconstan, Telconal
SPECIAL ALLOYS—Thermostatic Bimetals 140, 400, 15, Telcoseal, Invar, Beryllium-Copper.

TELCON METALS

TELCON

THE TELEGRAPH CONSTRUCTION & MAINTENANCE CO LTD

HEAD OFFICE: 22 OLD BROAD STREET, LONDON, E.C.2. *TELEPHONE:* LONdon Wall 7104
ENQUIRIES TO: TELCON WORKS, GREENWICH, LONDON, S.E.10. *TELEPHONE:* GREenwich 3291

CAPACITANCE STABILITY MEANS

Our Silvered Mica Capacitors are mass produced to precision standards. Electrical characteristics which have previously been specified for laboratory standards are now a feature of a component which we produce by the million.

Reliability is the key word of our inspection methods which are based on statistical control in addition to the comprehensive application of modern electronic instruments. Quality control of this nature can only be performed by a specialist manufacturer who has carefully collected and analysed the production results of many millions of units over a period of years.

SRC

STABILITY RADIO COMPONENTS LTD

COMMERCE ESTATE WOODFORD AVENUE
LONDON E.18
TELEPHONE BUCKHURST 6501/2

ALEC Davis SUPPLIES Ltd.

Dept. W.W.
18 TOTTENHAM COURT ROAD, LONDON, W.1.
Tel.: MUSeum 2453/4539

Business Hours: Monday-Friday 9 — 5.30 Saturday 9 — 1

RELAYS



600 or 3,000 TYPE

D.C. COIL RESISTANCE

3,000 TYPES: 1.9Ω to 80,000Ω
600 TYPES: 0.4Ω to 9,200Ω

ALSO LARGE STOCKS OF DOUBLE & TRIPLEWOUND AND SLUGGED COILS.

CONTACTS

3,000 TYPES: up to 8 sets.
600 TYPES: up to 4 sets.

3,000 TYPES: Make (M), Break (B), in Twin-silver, Twin-platinum, Dome-silver (2 amp.), Tungsten (5 amp.), and Flat-silver (8 amp.). Change-Over (C), in all but Tungsten: Make-Before-Break (K), in Twin-silver and Twin-platinum.

600 TYPES: (M), (B) and (C), in Twin-silver and Twin-platinum.



SIEMENS H.S TYPE

SPECIAL
High resistance slugged coils (up to 10,000 OHMS with ½" slug) now available.

here's your

★ really comprehensive range of **Engraved Control Knobs!**

Adds the 'finishing touch' to your equipment!

These attractive Control Knobs are actually Inscribed In Gold. The range is the most comprehensive available anywhere and caters for the needs of every Radio—Television—Amplifier enthusiast. The following inscriptions are now in universal demand:—

TELEVISION. "Brilliance," "Contrast," "Focus," "Brightness," "Brilliance On Off."
RADIO. "Volume," "Tuning," "On Off," "Radio-Gram," "Tone," "Wavechange," "Vol. On Off" "S.M.L. Gram."
AMPLIFIER. "Treble," "Bass," plus any of the above engravings.

Each control knob is packed separately in a transparent envelope. Available in both Walnut and Ivory

1'6 each

Plain knobs to match inscribed types are available in Walnut and Ivory at **1/-** each

From your usual dealer or if in difficulty write to—

UNCLES, BLISS & CO. LTD.
139, Cherry Orchard Road, East Croydon, Surrey
Telephones: CROydon 3379/6390

Hear this NEW tape recorder with the NEW high performance

Twin-track technique—giving one hour's playing per spool—excellent response between 50 and 10,000 cps—robust construction—extreme simplicity of operation—here, from the pioneers of tape recording in Britain, is an instrument which sets a new standard of quality and value. Send for details and address of your local dealer, and try it for yourself!

Price in British Isles 65 gns.
(complete with microphone)



BAIRD

EXPORT ENQUIRIES INVITED

SCOPHONY-BAIRD LTD · LANCELOT RD · WEMBLEY · MIDDLESEX

Wharfedale CORNER ASSEMBLY

for life-like reproduction

Beautifully finished in veneer of your own choice to suit individual decoration schemes

The Wharfedale assembly is fitted with a W.15/CS unit plus small BAFFLE with Super 5 unit. CROSSOVER at 3000 c/s. Capacity 9 cu. ft. Bass resonance below 30 c/s. Treble response well maintained up to 16 kc/s.

PRICE COMPLETE £57.3.6

The assembly is made to fit in the corner of a room. Where necessary sand-filled back panels measuring 40" × 24" can be supplied to complete enclosure at **£12.0.0** per pair.

available in
WALNUT, OAK, MAHOGANY, BIRD'S EYE MAPLE
or in any special veneer to order



Made and guaranteed by
WHARFEDALE WIRELESS WORKS
BRADFORD ROAD, IDLE, BRADFORD, YORKS
Telephone: IDLE 461

VALVES!! TUBES!!

RECEIVING. TRANSMITTING. MAGNETRONS. KLYSTRONS.

CATHODE-RAY TUBES. PHOTOCELLS. ETC.

First Grade Quality - British and American Make - No Dollar Expenditure Involved

LARGE QUANTITIES & GREAT VARIETIES
IMMEDIATE DELIVERIES FROM STOCK

Write or 'Phone:-

S. Szymanski

(pronounced SHE-MAN-SKEE)

ELECTRONIC ENGINEER & STOCKIST

95, STRODES CRESCENT, STAINES, MIDDLESEX

Telephone: STAINES 3071 *Telegrams: "Shemanskee" Staines*

PROBABLY THE LARGEST ACTUAL STOCKIST IN ENGLAND

WHOLESALE & EXPORT ONLY

THE NEW
"ACE"
MODEL '8'
MAGNETIC TAPE RECORDER

INCORPORATES ALL THE LATEST DEVELOPMENTS

* 10 WATTS PUSH-PULL HIGH FIDELITY OUTPUT
** 2 TRACKS PER TAPE (2 Hrs. RECORDING).
*** 3 TAPE SPEEDS, 3¾", 7½" and 15" per second.
**** 3 INPUTS: CRYSTAL & M/C MICS. & GRAM.
***** 2 SEPARATE INPUT CONTROLS FOR "MIXING."
****** COMPLETELY AUTOMATIC ELECTRONIC ERASE.
******* DETACHABLE SPEAKER UNIT WITH LEAD.
******** FAST RE-WIND AND FORWARD WIND-ON.
********* CAN BE USED FOR PUBLIC ADDRESS, etc.

This unique instrument measuring only 15½" × 10" × 12½"—the smallest on the home market—is capable of very high quality reproduction and is definitely the most versatile instrument yet produced.

59 GNS. Suitable Microphones from 6 GNS.

DEMONSTRATIONS OR ILLUSTRATED BROCHURE FROM:
ASSOCIATED CINE EQUIPMENTS LTD.
353, BEXLEY ROAD, ERITH, KENT. Phone: Erith 2543

M. R. SUPPLIES Ltd.

Offer from stock the following brand new (or otherwise perfect) material. All prices nett. Immediate despatch.

INTERCOM. SYSTEMS (Magneta Time Co.). Master station provides for up to six sub-stations, with buzzer call and two-way speaking on loudspeakers. Operation 200/250 v. A.C. Owing to limited stock we can only offer sets of one Master and two subs., price the set, £12 17 6 (despatch 7/6). Impedance of subs. is standard 2-3 ohms and any P.M. m.coil speaker will provide extra subs. if required. These are reconditioned, maker-tested, perfect.

HIGH-DUTY RECTIFIER UNITS (S.T.C.). Input 200/250 v. (in 10 v. taps), 50 c. 1 ph. Output 100 volts D.C., 20 amps. continuous. In ventilated steel cabinet 3ft. 6in. long, 4ft. 6in. high, 1ft. 6in. wide, weight approx. 2 cwts., fitted fine and coarse adjustment and 0/100 voltmeter, fused A.C./D.C. These are new but slightly store-soiled, electrically and mechanically perfect. Price £36 nett, ex-London warehouse. We can quote for despatch.

FUSSEL-COOLED HIGH DUTY RECTIFIERS. S.T.C. selenium. Full-wave, 50 volts 10 amps., £5 10 0 (des. 3/6). Two in bridge: 108 v. 10 amps., £10 the pair (des. 5/- pair). Four in bridge: 220 v. 10 amps., £20 the four (des. 10/- the four). Other D.C. outputs can be provided—please enquire early. **L.T. RECTIFIERS.** Selenium f.w., 12 v. 1.5 amp., 12/6 (des. 9d.); 12 v. 3 amps., 20/- (des. 9d.); 12 v. 6 amps., 35/- (des. 1/3); 24 v. 3 amps., 32 6 (des. 1/-). All of these L.T. rectifiers are brand new—the high duty rectifiers are new, soiled, tested.

FRACTIONAL H.P. MOTORS. Brand new by B.T.H., 230/250 v. A.C./D.C. 1/90th h.p. continuously rated. Ball bearings—can be mounted in any position. Capable of speed control by variable resistance. Suitable for sewing machines, projectors, pumps, grindstones, stirrers and mixers, etc. Body 4¼in. long, 3¼in. dia. Shaft projection 1¼in. 47 6 (des. 1/6).

OHM-METERS. Fine new instruments by prominent U.S.A. maker. Two direct reading scales 0-2,000 and 0-200,000 ohms. In neat plastic case, 8 × 3 × 1¼in., takes ordinary U2 cell. Last few, at 52 6 (des. 1/-).

HOOVER SHADED POLE INDUCTION MOTORS. 8P202, 200/250 v. A.C. Body 2¼in. × 3¼in. with shaft projecting 1in. 950 r.p.m., very silent running, 26/- (des. 1/-). **MAINS GEARED MOTORS,** 220/240 v. A.C./D.C. 1/10th h.p. 8in. long, 4¼in. dia. Final speed 700 r.p.m. Double ended final shaft, series wound—speed can be governed. £4 17 6 (des. 2/6).

STRIP HEATERS, 220/240 v. 500 watts, 22¼in. long, 1¼in. wide, with two terminals at one end. Can be used for processing or space heating, 9 6 (des. 1/6). **LOW VOLTAGE HEATER PADS,** 24 volts 75 watts, copper sheathing, 6in. × 2¼in., with terminal block 3 6 (des. 6d.).

G.E.C. MINIATURE CRYSTAL CALIBRATORS. Operation 200/250 v. A.C. For frequency calibration in 100 Kc. steps from 100 Kc. to 40 Mc/s. Modulation at 400 c/s, ventilated to if desired. Containing vacuum mounted crystal, basic frequency 100 Kc. Accuracy 0.001 per cent at 20°C. Size: 6¾in. × 6¾in. × 3¾in. Special offer, brand new, £3 5/- (des. 2/-).

LONDEX A.C. RELAYS. Coil 220/240 v. A.C. 2-pole C.O. mercury switching, 15 amps. capacity, unmounted, model LQA. 75/- (des. 1/6).

ROOM THERMOSTATS (British Thermostat Co.). Range 40/80 deg. F., differential 4 deg. F., capacity 10 amps. A.C. (250 v.), with manual on-off, in neat metal housing 6in. × 2½in. × 2in., 45/- (des. 9d.).

STUART TURNTRIPTAL PUMPS. No. 12 Pedestal model, 600 g.p.h., require powering with approx. 1.9th h.p. Fitted 2in. pulley, ball bearings, lubricator etc., £4 (des. 1/6).

We are London stockists of, and give very prompt delivery of: Stuart Electric Pumps, Sangamo Synchronous Time Switches, Sangamo S. Motors, 1 r.p.m., 1 r.p.h., etc., S.P.I. Measuring Instruments. Of the latter we hold good stocks of their 50in mirror scale and 3½in. sensitive meters from 0-25 micro amps.—prices on application

M. R. SUPPLIES Ltd., 68 New Oxford Street, London, W.C.1
Telephone: Museum 2958

HANDY-UTILITY ¼" DRILL £6.19.6

It's a joy to possess, a pleasure to use, this compact, superbly powered ¼" Drill. Drills holes up to ¼" diameter in steel (double in hardwood) . . . drills cast iron, plastics, brick and tile . . . and with accessories . . . buffs, burnishes, grinds, etc. Can be quickly assembled with the Handy-Utility Bench Stand as a very useful drill press or with the Horizontal Stand it becomes a Bench power unit.

See them all at your dealer's—they are part of the famous 'Handy-Utility' range of electric tools.

ELECTRIC HANDY-UTILITY TOOLS

Other 'HANDY-UTILITY' tools include:
6" HEAVY DUTY 'LECTRO-SAW' £17.5.0
'HANDY-UTILITY' ½" DRILL £12.7.6
5" SANDER-POLISHER £9.17.6
and a wide range of useful accessories



PRODUCTS OF THE H.U. DIVISION OF BLACK & DECKER LTD.

OBTAINABLE FROM YOUR LOCAL TOOL SHOP, IRONMONGER, ELECTRICAL DEALER OR STORE

Smee's H.U.89

EDDYSTONE

FINE COMMUNICATION RECEIVERS



MODEL "680X"

- Fifteen Valves
- Two R F Stages
- Two I F Stages
- Separate Oscillator
- Variable Selectivity
- Crystal Filter
- "S" Meter
- Push-pull Output
- Polychromatic Finish

MODEL "750"

- Double Superheterodyne
- Eleven Valves
- High Sensitivity
- Variable Selectivity
- Free from Images
- Separate Gain Controls
- Large Dial with Linear Scales
- Mechanical Bandspread
- Robust Construction

For full information, please write direct to the Sole Manufacturers :—

STRATTON & Co. Ltd.
EDDYSTONE WORKS, BIRMINGHAM, 31



POWER AT AUDIO FREQUENCY FOR INDUSTRY & RESEARCH

THE SAVAGE MARK II KILOWATT AMPLIFIER

FACTS TO IMPRESS:

- The Savage Amplifier was used recently for echo-sounding to the bed of the deepest ocean.
- Used by aircraft manufacturers as a source of power for vibration tests.
- Used as variable frequency power source for machine tools.
- This Amplifier may have a direct application to your problems. Ask us for full details.
- Amplifiers used in Broadcast Relay networks throughout the country each feed several thousand loudspeakers.
- Invaluable for instrument calibration, transformer testing, transmitter modulation, etc.

FEATURES

NEGATIVE FEEDBACK OVER 3-STAGES
NO ELECTROLYTIC CONDENSERS ARE USED
ALL VALVES ACCESSIBLE FROM FRONT OF RACK
UNIQUE CONSTRUCTION ENSURES QUICK ACCESS TO ALL WIRING

SPECIFICATION

OUTPUT : 1,000 watts, A F
DISTORTION : 0.6% at 1,000 c s
NOISE LEVEL : —70 dB
OUTPUT REGULATION : 9.0% (0.8 dB)
SENSITIVITY : 0.09 V at 600 ohms



W. BRYAN SAVAGE LIMITED

WESTMORELAND ROAD, LONDON, N.W.9 · COLINDALE 7131 · 'GRAMS: DECIBEL, PHONE, LONDON

Widney-DORLEC
REGISTERED TRADE MARKS

See our display of Cabinets at the R.E.C.M.F. EXHIBITION Grosvenor House April 7, 8 & 9th STAND No. 80

- new TECHNICAL SALES OFFICE AND SHOWROOMS, 299 NEW KING'S ROAD, LONDON, S.W.6

MANUFACTURERS :
HALLAM SLEIGH & CHESTON LTD
WIDNEY WORKS · BIRMINGHAM · 4

A Widney PRODUCT
ESTABLISHED 1898

The Finest Needle for your Radiogram

THE GOLDRING ACOUSTIC FILTERED TYPE 56

- Eliminates Needle Changing
- Gives better reproduction
- Filters out surface noise
- Increases life of records

Goldring "Acoustic-filtered Needles" suit any Standard Pick-ups

Look for the Display Card at your Dealers

Goldring Needles cost 10/6, including P. Tax

The Radio Press acclaim this instruction book to build a Record Player of the highest quality. Price 2/- post free.

ERWIN SCHARF
GOLDRING PRODUCTS
49-51a De Beauvoir Road, London, N.1 Tel.: Clissold 3434/6

SIFAM ENGLAND

Precision INSTRUMENTS

This Bench type portable instrument is used in many laboratories where consistent accuracy is demanded. Single or multi ranges for D.C. or A.C., calibrated to customers' requirements. Sizes 3½", 4" or 6" instruments. Accuracy B.S. First Grade.



A First Grade B.S.I. moving coil, panel mounting instrument, supplied as D.C. Micro-Ammeter, Milli-ammeter, or Voltmeter. Also available as A.C. Voltmeter for frequencies up to 50,000 c/s A.C. Ammeter with internal transformer, or R.F. instrument with internal thermo-couple.

Type M35. 4½" square.

Portable

Pyrometer

A high-grade, 3½" scale, moving coil instrument, robust, accurate and speedy in response. Normally supplied with 2 scales, 0-200°C and 0-400°C, with a choice of 3 surface couples. Also supplied with ranges up to 1,600° for all standard thermo-couples.



Thermo-couples are supplied with 4 ft. compensating leads.

● *Write for Catalogue giving full details of the complete SIFAM range.*

SIFAM ELECTRICAL INSTRUMENT CO. LTD., Leigh Court, Torquay. *Telephone : Torquay 4547/8*

FIRST AGAIN! ★★★★★★★★★★★★★★★★★★★★★★★★

Here is Your Two-Valve Translator



You can magnetically record, using your gramophone motor as a drive and the amplifier within your radio as the tape amplifier. Conversion Kit (readily detachable) containing all necessary parts and instructions, £7, includes postage, etc.

★ 1948 We gave you wire recording utilising a gramophone motor
★ 1949 We gave you talking books for the blind
★ 1950 We gave you tape recording utilising a gramophone motor
★ 1952 We give you now for the FIRST TIME in MAGNETIC RECORDING

A Two-Valve Translator

By clever circuitry we have produced for you a 2-valve translator which supersedes costly amplifiers and saves you needless expense. This unique translator will magnetically record from any microphone or pick-up. This unique translator will playback from any make of recorder. It will (without electrical connection to telephones) record 2-way conversations. It will playback into business intercom systems. It will playback into cinema or wireless relay systems.

The translator has both audio and a radio frequency outlet so that any radio receiver tunable to say 900 metres can boost the output to greater volume if desired. This wonderful new TWO-VALVE TRANSLATOR CHASSIS costs only **£12 10**- ready for use on 230 A.C. Other voltages to order.



The Diamond Tape Recorder. Two speeds (Diction 2 hours, Music 1 hour). Twin tracks. Fast forward wind and fast rewind. Strongly built for hard work. Can be used with any conventional amplifier or the translator. **£25,** including choice of tape, Diamond, Scotch Boy, E.M.I., G.E.C.

Recording playback and erase heads for home assembly.
Bandeau Type 7.6 pair. Record/playback and erase. Kit contains all parts and instructions.
Cassette Type 30/-. Contains both record/playback and erase heads in one housing. The heads can be changed about according to tape direction (erase should preceed record head). Gaps are adjustable. Cores are stacked mumetal half width for 2-way tracking. Bobbins ready wound Hi or Lo impedance to choice.

Oscillator coils **6/6.** For generating 45Kc supersonic bias current and erase current. Primary and secondary windings for Hi or Lo impedance heads.

PARK RADIO OF MANOR PARK DISTRIBUTORS FOR JUDGE INDUSTRIES 783 ROMFORD ROAD, LONDON, E.12 Phone **ILF 2066** *for demonstrations by appointment only*

SELECTIVE TRANSMISSION MEASURING SET

B.C.C. introduce another outstanding success in their development of Measuring Instruments.

This instrument is a direct reading, selective, gain and loss measuring set to be used with an external signal generator.

Four terminal networks, active and passive, balanced or unbalanced, can be measured.

Facilities are provided for use as a high impedance Selective Detector Amplifier.

Frequency Coverage : 1—68 Kc/s in 4 ranges.
Range of Measurements : Gain 0-60 db. Loss 0-80 db.
Accuracy : ± 0.5 db.
Impedance range : 75, 150 and 600 ohms., balanced or unbalanced.
Det.-Amp Sensitivity : 10-12 μV.
Power Supplies : 100-150-200-250v. 50 c/s.

Based on Signals Research and Development Establishment design.

Manufactured for Ministry of Supply and G.P.O.



BRITISH COMMUNICATIONS CORPORATION LIMITED
31 GORDON AVENUE, STANMORE, MIDDX. GRIMSDYKE 2266
Cables : BEECEECEE, STANMORE

BRADMATIC

MAGNETIC TAPE RECORDING EQUIPMENT

Bradmaster Model 5 Tape Desk

- Built to professional standards.
- Two speeds—3¾ and 7½ inches per second.
- Easily adjusted for single or twin track recordings.
- Fast wind and rewind—full reel rewound in 1¼ minutes.
- Heavy alloy flywheel. Freedom from "wow" and "flutter."
- Double servo brakes on each hub.
- Push Button control.
- Three heavy duty motors.
- Three shielded Bradmatic heads.
- Size : 13½in. x 15½in. x 6½in. deep.

Price **£41** (fitted with 5 R.P. heads)
or with 6 R.P. heads **£42**

Hi-fidelity magnetic sound heads :				
type 5 R.P. (record/play head)	£3	5	0	each
type 5 E (erase head)	£3	5	0	"
Super fidelity magnetic sound head, type 6 R.P. (record/play head)	£3	15	0	"
Composite screening cans (constructed of steel and mumetal)		4	6	"
Oscillator coil type 1.B		9	0	"
Plate coil type 1.B		9	0	"
Tape on 7in. reels, 1,200ft. :				
Emitape type 65 Low Coercivity	£1	15	0	"
Emitape type H.60 High Coercivity	£1	15	0	"
G.E.C. Grade "A"	£1	10	0	"
Scotch Boy (Durex) MCI-111	£1	15	0	"

Amplifiers and Microphones supplied.

Trade Supplied. Send for Lists to the Sole Manufacturers.

BRADMATIC LIMITED
STATION RD. · ASTON · BIRMINGHAM 6
Phone: EAST 0574 Grams: Bradmatic, Birmingham

Have you "A.A."?*



This very small reproduction of a sub-assembly from one of our series of unique LIFE-SIZE, "EASY AS-A.B.C." CONSTRUCTION SHEETS illustrates how really simple radio assembly can be for the Home Constructor ! If you have average ability (**A.A.**) and could wire this simple unit then you could tackle any, or all, of our LARGE RANGE OF GUARANTEED OUTFITS knowing that with **OUR** sheets failure is impossible !

Our world-famous HOME CONSTRUCTOR'S HANDBOOK has ONCE AGAIN BEEN ENLARGED and the following are some of the sets, etc., YOU can construct. Each has a FULL PAGE circuit, with illustrations, descriptions, full parts lists† and details, and the Book also contains a host of extremely useful information, data, formulae, etc.

- 3 Valve 3 wave FEEDER UNIT
- 4 Valve 3 W. FEEDER (with hi-fi switching for locals)
- 5 Valve 3 wave AC SUPER-HET, also AC/DC SUPER.
- 6 Valve 3 wave A.C. SUPERHET
- 6 Valve 3 wave AC/DC SUPERHET
- SIGNAL TRACER
- QUALITY AMPLIFIERS
- SIGNAL GENERATOR, etc., etc.

† All Parts (which are obtainable from us by mail) are clearly marked and identified with our Construction Sheets.

The price ? **2/6 Only** which makes this Book DEFINITELY the best value-for-money obtainable anywhere to-day ! ! Many thousands of Constructors like yourself are using our GUARANTEED circuits, so SEND **NOW** FOR YOUR COPY. THIS SPECIAL 1952 ISSUE is obtainable by mail ONLY FROM :

RODING LABORATORIES
(Dept. WA)
694, LEA BRIDGE ROAD. - LONDON, E.10

SUPREME AT ANY DISTANCE!

Telecraft T.V. Aerials give the utmost in service and satisfaction and provide the most popular range on the market today. There is a *reliable* TELECRAFT Aerial for every district—for any distance.

to the extreme fringe

FA22

Guaranteed for 2 years, the famous FA22 Long Distance Aerial is unsurpassed. First class construction and high sensitivity. Built to stand up to all weather conditions. Seamless Steel Spreader, adjustable Steel Masthead Clamp to fit masts from 1¼in. to 3in. dia. Shock Absorber Reflector Mountings. The FA22 still leads for value, durability and reliability.

"Telestrip" room Aerial ...		15	0
Loft Aerial	£1	5	0
Single dipole, wall mounting	£2	2	0
Single dipole, chimney lashed	£3	0	0
Type TS 40, "H" wall mounting 7ft. mast.....	£4	15	0
Type TS 50, "H" chimney mounting 7ft. mast.....	£5	5	0
Type TS 55, "H" chimney mounting 10ft. mast.....	£6	5	0
Type TS 33, Triple array, 10ft. mast (for interference areas)	£8	5	0
Type TS 25, "H" mast mounting to fit 1¼in. to 3in. dia.....	£3	10	0
Type FA 22, long distance to fit 1¼in. to 3in. mast.....	£5	17	6

Matching transformer 6 6 extra.

There is a TELECRAFT AERIAL for every contingency—indoors or out.

BETTER THAN ANY—CHEAPER THAN MOST

Send for illustrated brochure and price lists

TELECRAFT LIMITED

THORNTON HEATH, SURREY

Tel.: THOrnton Heath 1191-2-3

Depots:—BIRMINGHAM, BRISTOL, MANCHESTER, WORTHING.

SCOTTISH ENQUIRIES: LOUIS GRACE, 28 Langside Place, Glasgow, S.1. Giffnock 2992

GOODSELL SOUND

A NEW

WILLIAMSON AMPLIFIER - - TYPE GW.12 to Goodsell's full quality specification:—

★ 12 watts output at 0.1% distortion.
★ Paper Condensers on H.T. supply line.
★ Double Power Supply.
★ Impregnated grid coupling condensers.

PRICE £29 - 0 - 0

• • • • •

SERIES S.P. 'PRE-SELECTIVE' TUNER UNITS with or without R.F. stage, panel illustrated.

★ VARIABLE SELECTIVITY ★ 3 STATION CONTROL

PRICE from £10 - 10 - 0 plus tax

• • • • • • • •

WIDE RANGE 4 STAGE CONTROL UNIT WITH OR WITHOUT PRE-AMPLIFIER FROM £7 - 10 - 0

• • • • • • • •

OTHER AMPLIFIERS FROM £15 - 15 - 0 UPWARDS

• • • • • • •

MILNES

enter the high fidelity L.S. field with their TRUPRODUCERS. New and sensational features include:-

★ Hexagonal speech coil used on a new claw principle.
★ Speech coil ¼ the normal weight.
★ No spider, as such, suspension and centring by six glass cords.
★ Flux density 17,000 lines per sq. cm.
★ Frequency response from 25 to 16,000 c.p.s.

PRICE 12" UNITS £15 - 15 - 0
10" UNITS £14 - 14 - 0

All Enquiries to:—

B.K. PARTNERS LTD., 229 REGENT ST., LONDON, W.1. Telephone REGENT 1267

DISTRIBUTORS FOR GOODSELL SOUND & MILNES TRUPRODUCER

WE ARE APPOINTING AGENTS THROUGHOUT GT. BRITAIN AND WELCOME TRADE ENQUIRIES

FERROXCUBE

FERROMAGNETIC FERRITE

FOR TELEVISION

THE improvement in television components, with their smaller size and greater efficiency, is largely due to Ferroxcube, the new Mullard magnetic core material.

The uses of Mullard Ferroxcube in the production of TV components fall into these three main groups:

LINE OUTPUT TRANSFORMER CORES

Since the advent of wide-angle television tubes, with the accompanying demand for increased E.H.T. supplies, the need for line output transformers of the highest possible efficiency has been greater than ever. Mullard Ferroxcube, with its low iron losses, completely fulfils this need — also facilitating the assembly of small, compact transformer units by means of solid, non-laminated U-shape cores.

DEFLECTION COIL YOKES

Mullard Ferroxcube cores in ring form are ideal for producing the magnetic circuit around deflection coils. Used in this way, Mullard Ferroxcube makes possible the construction of efficient deflector coils with a high Q factor. In order to simplify assembly problems, these ring cores are supplied either in the form of a complete circle, as two semi-circles, or as castellated yokes.

LINEARITY AND PICTURE WIDTH CONTROLS

Mullard Ferroxcube can very conveniently be extruded into rods and tubes. In this form it is ideal for use in linearity and picture width controls, providing a smooth control in a compact assembly.



OTHER APPLICATIONS

In addition to its uses in television receivers, Mullard Ferroxcube is also being widely employed in line communications, radar, and other specialised electronic equipments. The purposes for which it is already being most successfully applied in such equipments include filter networks, wide band transformers, magnetic amplifiers, and pulse transformers.

PLEASE WRITE FOR FULL DETAILS

Mullard **Mullard FERROXCUBE**

FERROMAGNETIC FERRITE

MULLARD LIMITED · CENTURY HOUSE · SHAFTESBURY AVENUE LONDON W.C.2.

(MF376)

R.C.A. TRANSMITTER ET4336. Unused and reconditioned. This magnificent transmitter is complete in one totally enclosed rack and includes aerial tuning panel.

TUBE LINE UP: 807 CO/Buffer. Two 813 P.A. Two 805 P.P. Class B modulator. Four 866A rectifiers. Controls — Manual or remote. Power output, 350 watts. Frequency coverage normal — Normal 2-20 Mc/s continuous. Frequency control. The transmitter has a detachable front panel for insertion of Wilcox Gay V.F.O. or Crystal Multiplier. 20-page manual and circuit diagram with each equipment. Every instrument is air tested and guaranteed perfect. Also available Wilcox Gay V.F.O., Crystal Multiplier, speech amplifier (British made) with 500 ohm output suitable for use with ET4336. Valves available for ET4336 in large quantities, 813, 805, 866, 807.

ET4336 SPARES: We carry very large stocks of essential maintenance spares and invite enquiries.

RECEIVERS AR88D and L.F. Available with A.I.D. certificate, **£75** each.

COMPLETE SETS CRYSTALS AND COILS for BC611 and BC711 handie talkies, SCR640, etc.

TELESCOPIC CAR AERIAL, 7ft. with 10ft. shielded, lead coax connector. **15/-** each.

EVERSHED AND VIGNOLL BRIDGE MEGGERS, 250 volt. **£21** each.

BC610 P.A. COILS, in complete sets. 7 Coils bulk quantities only supplied.

McELROY-ADAMS MFG. GROUP LTD.

(Late Communications U.K. Ltd. Electronic Communication Equipment)

46, GREYHOUND ROAD, LONDON, W.6

Cables: Hallicraft, London *Phone: Fulham 1138.9*

RADIO EXCHANGE CO.

HIGH RESISTANCE HEADPHONES. Ericsson's first grade, 4,000 ohms per pair, brand new, boxed. **17/6.**

LOW RESISTANCE 'PHONES, 5/11.

RECEIVER P40. Complete with valves, tuning 85-95 mc/s, these are ideal for Wrotham or "2" metre conversion. Housed in attractive robust grey cases these contain 4 EF54s (RF, mixer, Xtal multipliers), EC32 (Xtal oscillator), 2 EF39s (2.9 mc/s IFs), EB34 (det), 6J5 and 6V6 (audio). In original cartons, complete with circuit, **6F6.** Post 1/8. (Circuit only, 1/8).

TRANSMITTER 21. Sending CW, MCW or speech on 4.2—7.5 and 18—31 mc/s these are complete with valves, circuit, control box, key and front panel. Wire (not formers) from PA coils, and relays, have been stripped by the M.O.S. but may easily be replaced with the aid of our circuit and data. In excellent condition, **25/-.**

POWER UNIT S441B. With separate individually controlled HT and LT transformers, jewelled indicator lights, attractive appearance, modest size (14 in. x 7¼in. x 7in.) these delivering 300 v. at 200 mA, fully smoothed, 12 v. at 3A, AC and 5 v. DC, from 200 250 v. 50 cps. In ORIGINAL CARTONS. Only **65/-** (carr. 5/-).

VIBRATOR UNIT 21. 6 v. input, approx. 160 v. at 40 mA. smoothed DC output; designed for the Tx Rx 21. In new condition. ONLY **17/6.**

BRAND NEW ACCUMULATORS in transparent, unspillable, plastic cases. 7 A.H. 2 v., **6/6.**

POWER UNIT. With 5Z4 rectifier, choke, condensers, transformers, etc., our conversion will produce a fine little HT unit for mains input, providing approx. 450 v. at 50 mA. ONLY **15/-.** (P. and P. 2/6.)

NEW 1355 CONVERSION data for all 5 TV channels, **3/-.**

MIDGET AMPLIFIERS with two 12SH7s, one 12SJ7, these measure 5in. x 3¼in. x 3in. OUR PRICE **15/-.**

H.T. BATTERIES. 60 v., 2 for **9/6** post free.

HEMISPHERICAL CARBON MICROPHONES, with switch, new, boxed, **5/-.**

MALLORY 4 PIN VIBRATORS. 6 v. or 12 v. **5/-** (post 9d).

9 CAULDWELL STREET, BEDFORD

Phone 5568.

THE VERDIK ELECTRONIC CO.

OFFERS TO-DAY'S OUTSTANDING VALUE IN

The NEW LANE TAPE TABLE

As available from Premier Radio Co., Mail Order Supply, Garland Bros. Ltd., Alec Davis Supplies Ltd. and other good Radio Dealers.

Specification includes :—

- Three motors obviating friction drives.
- Heavy, balanced flywheel giving extremely low level of "wow" and flutter.
- Half track, high fidelity record playback and erase heads of NEW DESIGN.
- Fast forward and reverse rewind.
- Very simple mechanical action.
- For use on 200-250 v. A.C. 50 cycles only.

PRICE £16.10.0 *Carriage and Packing 10/-*

DISTRIBUTED THROUGHOUT THE WORLD BY



VERDIK SALES LTD. 17 SHAFTESBURY AVE. LONDON, W.1. Phone Gerrard 8266

Speed-up SOLDERING

Wolf

SOLDERGUNS

OFF-STRAIGHT EASY-GRIP HANDLE · PERFECT CONTROL · LOW CURRENT CONSUMPTION · A MODEL FOR EVERY PURPOSE · LOCALISED HEAT-MAINTAINS CORRECT HEAT · QUICKER HEAT-UP

It pays to Solder with

The Wolf Automatic Soldergun with its automatic trigger solder-feed action, is indispensable to all modern assembly.

SOLDERING IRONS



For all who, for special reasons, prefer the conventional straight type handle. Identical as regards elements and bits to Wolf Solderguns but with round hard wooden handle with heat deflecting skirt.

★ *Obtainable from all high class stockists and ironmongers*

Wolf *Electric* **SOLDERGUNS & SOLDERING IRONS**

WOLF ELECTRIC TOOLS LTD. PIONEER WORKS, HANGER LANE, LONDON, W.5. Tel.: PERivale 5631-4. Branches: BIRMINGHAM, MANCHESTER, LEEDS, BRISTOL, GLASGOW

VISIT STAND No. C483 B.I.F. (CASTLE BROMWICH) MAY 5—MAY 16

PULLIN MINIATURE MEASURING INSTRUMENTS



Series 20 Ammeters & Voltmeters, square or round flush type, 2" dial.

Series 25 Ammeters & Voltmeters, round flush or projecting type, 2½" dial.

AMMETERS
VOLTMETERS
OHMMETERS
WATTMETERS
FREQUENCY METERS

For switchboard or portable use, also multi-range test sets.

MIP

MEASURING INSTRUMENTS (PULLIN) LTD.
ELECTRON WORKS, WINCHESTER STREET, LONDON, W.3

S. G. Brown

"A" TYPE HEADPHONES

The first choice of RADIO OPERATORS throughout the world

These headphones feature a High Permeability Reed tuned to 1,000 c/s. and coupled to a conical aluminium diaphragm. Earpieces individually adjustable while in use for sensitivity and power-handling characteristic.

D.C. Resistance: 4,000 ohms.
Impedance: 16,000 ohms at 1,000 c/s.

The S. G. Brown range of headphones covers types for many specific requirements. Details of the full range are available in the illustrated Brochure "S."—sent on request.



G. Brown Ltd.
SHAKESPEARE ST., WATFORD, HERTS.
Telephone: Watford 7241

AVOID BOTTLENECKS!

We hold large and comprehensive stocks of components and units. Contact us; we may solve your production problem.

CONDENSERS. Silver Mica. Tubular. Mansbridge.
CRYSTALS. American FT241 & FT243 Etc.
HEADPHONES. DLR1, DLR5, 1BA5 Etc.
METERS. Thermo. Moving Coil. Moving Iron.
RESISTORS. High Stability. Carbon. Wire wound.
VOLUME CONTROLS. Morganite Types H, M, LH, BJ. Colvern 1-5 watts.
PLUGS & SOCKETS. Pye Patterns, Belling, etc.

Wholesale and Export Only.

ANDERS RADIO LTD.
167, HAMPSTEAD ROAD, LONDON, N.W.1.
EUS. 1639 EST. 1928

PRATTS RADIO
1070 Harrow Road, London, N.W.10
(Nr. SCRUBBS LANE)
Tel.: LADbroke 1734



MODEL AC10E £10.7.6

AMPLIFIERS. College general purpose units. **MODEL AC10E.** 4 valve 10 watts. Neg. feedback, **£10/7/6. MODEL AC15E,** 6 valve; 15 watt P/P output. Feedback over 3 stages, **£15/5/-. MODEL AC25E.** 25 watts P/P output. Feedback over 3 stages, **£18/18/-. MODEL U10E,** for DC/AC mains, 6 valve 10 watt P/P output. Feedback over 3 stages, **£12/19/6.** All are complete with cases and chrome handles. They have a separate microphone stage. Separate inputs for mike and gram., allowing individual mixing, etc. Outputs match 3, 8 or 15 ohms speakers. Max. input volts required for full stated output average Mike .005, Gram. .3 v. **MODEL AC6C,** 5 valve P/P 8-10 watt unit for records, radio, etc. Feedback over 3 stages. Output to 3, 8, 15 ohms. **£10/10/-. MODEL AC4C,** 3 valve record/radio amplifier, 4 watt to .3 ohms, **£5/15/-.** Ditto U4C for DC/AC mains, **£5/15/-.** Stamp for list. Full range of accessories available including: Rothermac Crystal Mikes, 105/-; Goodmans 12in. P.M. speaker, **£8/12/6;** Collaro A.C. Record Players, rim drives, magnetic model, **£6/9/-.** Crystal, **£6/15/-.** Jack plugs 2/- each extra.
All amplifiers are complete and ready for use.

Good Points of Superspeed ACTIVATED COLOURED ROSIN CORED SOLDER

- Coloured Core provides coloured rosin residue for ready identification.
- Choice of red, blue, green, purple or yellow core.
- Stellate Core cross-section for quick melting and fluxing.
- Activated Rosin Core for fast working and absence of corrosion.
- Identical—except for colour—with the famous Superspeed White Flash Cored Solder.
- Residue solidifies to a hard, semi-translucent film of high dielectric strength.

Let us send you full technical details of the new Coloured-core Solder.

We are established specialists in the production of solders and fluxes for every type of pre-tinning, dipping and soldering in electrical, radio and similar jointing and assembly work. If you are engaged in manufacture in this field it is almost certain that we can be of service to you. Make an appointment for a member of our Technical Sales staff to call on you.

H. J. ENTHOVEN & SONS LTD

ENTHOVEN HOUSE,
89 UPPER THAMES STREET, LONDON, E.C.4

Telephone : MANsion House 4533
Telegrams : Enthoven, Phone, London.

Works :
CROYDON, ROTHERHITHE & DERBYSHIRE

AT THE

R.E.C.M.F. EXHIBITION

STAND 76

Murex will be showing

ZIRCONIUM

ROD · SHEET · STRIP

TUNGSTEN

MOLYBDENUM

TANTALUM

and fabricated instrument and valve components in these metals

★

SINTERED PERMANENT MAGNETS

SINTERED COMPOSITE MAGNETS

★

MUREX LTD (Powder Metallurgy Division)
RAINHAM, ESSEX. *Telephone : Rainham, Essex 240.*
LONDON OFFICE : CENTRAL HOUSE, UPPER WOBURN PLACE, W.C.1. *Telephone : EUS 8265.*

13 MODULATION PATTERNS

with the

PHILIPS

Standard Television Signal Generator



The Philips GM.2657 Standard Television Signal Generator is used for the production of complete video signal and pattern, and modulated high frequency signal.

1 *Can be supplied for any fixed vision frequency between 45 Mc/s to 80 Mc/s.*
2 *Can be supplied for any number of lines between 400 and 700.*
3 *Built in sound modulation at 600 c/s.*
4 *Sound and vision frequencies arbitrary and both crystal controlled.*
5 *Choice of 13 modulation patterns.*
6 *Line and frame sync. obtainable separately if required.*
7 *External sound and vision modulation possible.*
8 *Built-in oscilloscope for checking video wave form.*

★ Owing to the unique nature of this equipment interested Engineers are invited to request an appointment to visit the Philips Application Showroom where facilities for full demonstration are available. ★

PHILIPS ELECTRICAL LTD.

CENTURY HOUSE, SHAFTESBURY AVENUE, LONDON, W.C.2.

The midland specialists in high fidelity reproduction ....

HAVE PLEASURE IN ANNOUNCING THE OPENING OF THEIR NEW FACTORY LABORATORIES AND DEMONSTRATION ROOMS AT

BICKFORD ROAD
WITTON
BIRMINGHAM 6
TELEPHONE EAST 0438

High Fidelity Amplifiers, Tone Control Units, Pre-Amplifiers and Radio Feeders, High Quality Record and Playback Amplifiers for Magnetic Tape.

•

Oscillator Units, Oscillator Coils, Bias Rejector Units, Mixer Stages, Magnetic Tape Erase and Record Play Heads, Crossover Units.

•

Matched Microphones, Gram Motors, Pick Ups, Headphones, Speakers and Speaker Systems.

ELECTRICAL & ELECTRONIC DEVELOPMENT LIMITED

Sound Craftsmanship beyond Compare

CO-AXIAL CHANGEOVER RELAY

Zo — 45Ω or 70Ω
Standing wave ratio — 1.08 @ 200 Mc/s.
Body size only 2½" × 1⅝" × 1⅝"
Write for List 245 WW

Type SCX

LONDEX Ltd.
ANERLEY WORKS
LONDON · S.E.20

Manufacturers of Relays

RAINBOW Radio & Television

CUSTOM BUILT MULTI-OUTLET T.V. PRE-AMPLIFIER



units now available to Aerial Manufacturers, Local Authorities and Contractors. Performance to specification, and with automatic switching if required. Please write for further Particulars.

RAINBOW RADIO MFG. Co. Ltd., Mincing Lane, Blackburn, Lancs.
Specialists in all types of T.V. Pre-Amplifiers, etc.

Diagram by courtesy of McGraw Hill Pub'g. Co. Inc.

V. H. F. BRIDGES

for balanced and unbalanced measurement at frequencies between 1 Mc/s and 250 Mc/s.

Wayne Kerr

THE WAYNE KERR LABORATORIES LIMITED, NEW MALDEN, SURREY. PHONE: MALDEN 2202

Magic New Entertainment for Every Home!

It is a fascinating pastime making your own personal recordings—and so simple that everyone can do it. The amazing Soundmirror Magnetic Tape Recorder will record with perfect fidelity music, from a song to a full orchestral score; speech and the fun and frolic of family parties, as well as important and family events such as weddings. Think of the pleasure these recorded items can give you when you play them back to entertain the family and your friends.

Models from **£69.10.0** *exclusive of microphone*

Write for further details or a demonstration by appointment to the manufacturers.

Soundmirror
MAGNETIC TAPE RECORDER

Now available in England — the book **"Magnetic Recording"** by **Dr. S. J. Begun.** A comprehensive treatise on the subject. Price 25s. postage 9d. extra.

THERMIONIC PRODUCTS LTD.

Sales and Service Centres: Manchester, Birmingham, Bristol, Leeds, Newcastle, Glasgow etc.

Head Office: Hythe, Southampton. *Phone:* Hythe 3265
London Showrooms: Morris House, Jermyn St., Haymarket, S.W.1. *Phone:* Whitehall 6422



A MASTERPIECE

The 'Monarch' auto changer

A masterpiece in design and technical excellence—a three-speed automatic record changer designed to play 12", 10" and the increasingly popular 7" records *intermixed in any order*. The "Monarch" combines ease and simplicity of operation with the high standard of reproduction and performance demanded by the most discriminating listener.

Note these 7 star features

- Automatically selects and plays 7", 10" and 12" records, intermixed, at 33⅓, 45 or 78 r.p.m. Capacity 10 records.
- Pick-up automatically returned to rest position and motor switched off after last record.
- New reversible dual stylus crystal pick-up has extended frequency range to 10,000 c.p.s. Self compensated for the L.P. lower frequencies with the Turnover frequency at the correct point.
- Remarkably compact design makes it an ideal unit for the radiogram/TV combination console.
- Simplicity of design guarantees long life and trouble-free operation.
- Beautiful styling and finish that will harmonize with any cabinet design.
- Operates on 100/125–200/250 volts, 50 cycles A.C. Models also available for 60 cycles A.C.



BIRMINGHAM SOUND REPRODUCERS LIMITED
Old Hill, Staffs. Tel: Cradley Heath 6212/3

Wireless World

RADIO, TELEVISION AND ELECTRONICS

42nd YEAR OF PUBLICATION

Managing Editor : HUGH S. POCOCK, M.I.E.E.
Editor : H. F. SMITH

APRIL 1952

In This Issue

EDITORIAL COMMENT 127

ORCHESTRAL STUDIO DESIGN. By *T. Somerville and H. R. Humphreys* 128

1400-Mc/s RADIOPHONE. By *J. B. Lovell Foot* 132

"SPORADIC E" CLOUDS. By *D. W. Heightman* 136

PHYSIOLOGICAL FEEDBACKS. By *T. E. Ivall* 137

F.M. IN GERMANY 141

LETTERS TO THE EDITOR 145

WORLD OF WIRELESS 147

PRE-HEAVISIDE PROPAGATION THEORIES. By *E. W. Marchant* 151

DUALS. By "*Cathode Ray*" 152

RADAR REFLECTORS 156

RADIO HEATING 157

RADIO MANUFACTURE IN INDIA. By *J. A. Howie* .. 159

SIMPLIFIED AERODROME APPROACH AID 162

HIGH-TENSION DELAY CIRCUIT. By *D. Clements* 163

MANUFACTURERS' PRODUCTS 165

RANDOM RADIATIONS. By "*Diallist*" 166

UNBIASED. By "*Free Grid*" 168

PUBLISHED MONTHLY (last Tuesday of preceding month) by ILIFFE & SONS LTD., Dorset House, Stamford Street, London, S.E.1. *Telephone*: Waterloo 3333 (60 lines). *Telegrams*: "Ethaworld, Sedist, London." *Annual Subscription*: Home and Overseas, £1 7s. 0d. U.S.A. $4.50. Canada $4.00. BRANCH OFFICES: *Birmingham*: King Edward House, New Street, 2. *Coventry*: 8-10, Corporation Street. *Glasgow*: 26B, Renfield Street, C.2. *Manchester*: 260, Deansgate, 3.

VALVES AND THEIR APPLICATIONS

Gun assemblies for Mullard LONG LIFE television tubes are subjected to the strictest inspection before being fitted in the tube.

Mullard

Long Life

Cathode Ray Tubes for Television

Mullard Cathode Ray Tubes for Television have earned their high reputation for performance and long life by reason of their advanced structural and electrical design, the close control exercised over the quality of the raw materials used, and the development of unique manufacturing techniques. Moreover, the great care taken during production, including rigorous inspection at every stage, and searching acceptance tests after manufacture, ensure a very high order of uniformity and reliability.

Advertisements in this series will contain, in addition to essential tube data, information concerning the construction of the tubes, and their application, which will be of assistance and interest to the equipment designer, to the service engineer, to the student, and even to the ultimate user.

Each of these little essays will be complete in itself and, as previously, the advertisements will be available in reprint form with additional information on the back page.

TUBE LIFE

It is scarcely too much to say that, in the majority of cases, the useful life of a tube is the life either of its luminescent screen or of its heater-cathode element.

With due care in manufacture and correct operating conditions, screen life is adversely affected only by those troubles grouped under the heading of "screen burn". The most serious form of screen burn—that due to the production of heavy *negative* ions in the region of the cathode—is prevented in Mullard tubes by a gun assembly of advanced design incorporating an efficient ion-trap and a small permanent magnet mounted on the tube neck.

Other forms of screen burn, and also risk of premature cathode deterioration, can be avoided by correct selection of operating conditions on the lines indicated by the tube data and limiting values specified in the Mullard publications.

MW 41-1

Metal-coned tube with 16-inch diameter screen.

HEATER Indirectly heated.

This tube is suitable for series or parallel operation.

V_h	6.3	V
I_h	0.3	A

TYPICAL OPERATING CONDITIONS

V_{a2}	12	KV
V_{a1}	300	V
V_g for cut-off	−39 to −86	V
Focusing ampere-turns (approx.)	900	

LIMITING VALUES (Design centre ratings)

V_{a2} max.	14	KV
V_{a2} min.	7	KV
V_{a1} max.	410	V
V_{a1} min.	200	V
$-V_g$ max.	150	V
$+v_{g(pk)}$ max.	2	V
V_{h-k} max. (heater positive)	125	V
V_{h-k} max. (heater negative)	200	V
$*v_{h-k(pk)}$ max. (heater negative)	410	V
R_{g-k} max.	0.5	M Ω
R_{h-k} max.	20	K Ω

* During a warming-up period not exceeding 45 secs.

WE SHALL BE AT THE
NORTHERN RADIO SHOW
CITY HALL · MANCHESTER
Apr 23 - May 3

STAND 26

Mullard

Reprints of this article together with additional data may be obtained free of charge from the address below.

MULLARD LTD., Technical Publications Department, Century House, Shaftesbury Avenue, W.C.2.

MVM 295

Wireless World

APRIL 1952 VOL. LVIII. No. 4

Harbour Radiophones

IT is a chastening thought that in one respect at least passengers in modern ocean liners are worse served than were their ancestors who voyaged in sailing ships. So long as they are on the high seas present-day travellers are remarkably well catered for by radio-telegraphy and often by radio-telephony as well, but, in the interval between arriving in a British harbour and actually landing, their only way of communicating with the shore is by hiring a waterman to take a message. And we gather that watermen are not so plentiful nowadays as in the days of sail! Normal radio communication is suspended on the ship's entering harbour limits, and there is apparently a real need for a last-minute telephone service. A short-range v.h.f. system for use in harbours and their approaches seems to be an amenity which may reasonably be expected to-day.

Provision of such a service is predominantly an economic and administrative problem. Multi-channel v.h.f. working of the kind likely to be necessary is practicable by the use of known and tried techniques, though the task would be somewhat complicated by the intermittent and highly concentrated nature of the load. Traffic would also be largely unpredictable; obviously, if a ship suffers an unexpected delay in docking, many passengers will want to make last-minute changes in their arrangements.

Up to a point the Thames Radio Service, introduced by the Post Office a year or two ago, paved the way for a radiophone system such as that under consideration, though it was intended rather more for small craft—tugs and the like—than for passenger ships. It was devised to put vessels navigating the waterways of the entire Port of London into connection, *via* v.h.f. radio, with the telephone system of the country. A service for liners in or approaching harbours would obviously involve more complex problems; the most difficult of these would fall on the G.P.O., which would be responsible for the shore terminal equipment.

As the port of Southampton handles by far the greatest number of passengers, it is the obvious choice for an initial experimental service.

It is not only in the shipping world that communications must keep abreast of public demand. Operators of aircraft are constantly reminding us that the ever-increasing speeds of flight call for commensurate increases in the speed of radio for both communications and navigational aids. Of course, we cannot do anything about the velocity of radio wave propagation, but, subject to that single limitation, we can, on the whole, flatter ourselves that this particular challenge has been met fairly satisfactorily. Such weaknesses as may at the moment exist are, more often than not, brought about by organizational rather than technical shortcomings.

Telegraph Tempo

Apart from the question of operational communications, the growth of passenger flying has brought about a need for quicker handling of ordinary inland and overseas telegrams.

Perhaps our own particular cross-section of experience is unfortunate, but we have gained the impression that there has of recent years been no increase in the speed of transit of telegrams; in fact, rather the reverse. Be that as it may, it seems to be a not entirely unknown experience for an air passenger to arrive at his destination ahead of a telegram announcing his departure.

Radio and wire telegraphy are now so closely integrated that for many purposes they must be treated as one, and in any case almost all radio-telegrams pass over the inland system to their destination. Radio is sometimes unjustly blamed for delays.

We suggest that in the telegraph world the well-known business axiom "the customer is always right" should be modified to "the customer is always in a hurry," and that this slogan should be inculcated into the minds of all concerned. Quite recently, on the occasion of the Queen's dramatic return flight from Africa, we saw what could be done in the way of rapid communication by wireless linked with wire. The communication achievements of the Ministry of Civil Aviation on that abnormal occasion might well be taken as setting a standard for more humdrum traffic.

Orchestral Studio Design

Recent Modifications to the B.B.C. Maida Vale Studio

By T. SOMERVILLE,* B.Sc., M.I.E.E., F.Inst.P., and H. R. HUMPHREYS,* A.R.I.B.A.

THE principal B.B.C. concert studio was built in 1935 at Maida Vale, when it became necessary to have a studio big enough to accommodate an orchestra of 100 and a large choir. The acoustic treatment was based on ideas current at that time and consisted mainly of building board on the walls and a floor carpeted except on the area occupied by the orchestra. Some additional absorption was obtained from an audience of about 150 seated in a balcony at the far end of the studio. The reverberation/time characteristic of this studio is shown in Fig. 1(a) and the shape is consistent with the boominess of the studio and its extreme deadness at high frequencies. At a later date an organ and orchestral platform were added, resulting in the reverberation/time characteristic shown in Fig. 1(b). The greater absorption at low frequencies reduced the boominess of the studio but there was little change at high frequencies. Although pleasing broadcasts could be obtained, the studio was never entirely satisfactory, and it was realized that improvements could be made. Consequently, after the war a treatment, using Cabot's quilt hanging loosely from the ceiling and on the rear wall, was introduced to improve the acoustics until a complete redesign could be undertaken. To increase the upper frequency response the walls were distempered and the wood block apron for the orchestra was extended, resulting in the curve of Fig. 1(c). The studio remained in this condition until the modernization which has been recently completed.

* *British Broadcasting Corporation.*



Fig. 1. Reverberation characteristics of Maida Vale No. 1 studio, (a) in original condition, (b) with organ and orchestral platform added, (c) with Cabot's quilt and extended wood block apron (1947).


PERFORATED COVER, FOR APPEARANCE AND PROTECTION
ROOFING FELT MEMBRANE (MASS AND ABSORPTION)
BOX APPLIED TO SOLID WALL
DEPTH OF AIR SPACE (COMPLIANCE)
ROCK WOOL BLANKET (ABSORPTION)

Fig. 2. Construction of membrane absorption units.

Since the end of the war the B.B.C. has been carrying out an intensive programme of research into the various problems of acoustics, and investigations have been carried out in broadcasting studios and concert halls on the Continent in addition to those in Britain. As a result of these investigations the conclusion has been reached that to obtain good "tone" and "definition" it is necessary to have efficient diffusion in a large concert hall or studio, so that the sound reaches the listener or the microphone by many diverse paths, instead of after only a few reflections. The opinion was also formed that the best tone was obtained in those halls in which a rectangular form of ornamentation, known in architectural circles as coffering, was employed. This opinion has been confirmed by experimental work.[1] It was further observed that good acoustic conditions for orchestra and audience seem to occur in those halls in which there is a choir or audience placed behind the orchestra.

In the light of these opinions it was therefore decided when re-treating the large concert studio to rebuild the orchestral platform to accommodate permanent absorbent choir seats behind the orchestra, and to use a rectangular form of ornamentation on the walls.

Membrane Absorbers

A rectangular form of ornamentation is convenient for another reason. One of the principal faults of this studio was its boominess, so that some form of bass absorption was necessary as part of the new treatment. The B.B.C. has been experimenting for some time with a type of absorber called a membrane absorber, which consists of a rectangular cavity sealed in front by a flexible membrane consisting of bituminous roofing material. A sketch of such a unit is shown in Fig. 2. It is essential that the membrane material should have high internal friction to provide resistance to motion and is responsible for most of the absorp-

[1] T. Somerville & F. L. Ward. "Investigation of Sound Diffusion in Rooms by Means of a Model." *Acustica*, Vol. 1, 1951, p. 40



Maida Vale Studio No. 1 before re-treatment. Below: After acoustic re-treatment, showing orchestra platforms and choir seating.

tion. The frequency of resonance, at which the greatest absorption occurs, is a function of the mass of the membrane, and the stiffness of the air which is inversely proportional to the depth of the box. The formula for these absorbers is

$$f_r = \frac{1}{2\pi}\sqrt{\frac{1}{MK_A}}$$

where f_r is the frequency of vibration, M is the mass per unit area of the membrane, and K_A is the compliance per unit area of the air space, acting on the equivalent piston.

It is essential to avoid transverse vibration of the air contained in the box, and the units are therefore divided by partitions so that the divisions are small compared with the wavelength. To flatten the resonance curve and increase the band over which the absorber is effective, a blanket can be placed in the cavity as shown in Fig. 2.

These absorbers are most conveniently made rectangular and can either be recessed into the walls or mounted as boxes on the surface. In the present case surface mounting of the absorbers seemed to be the obvious choice since it is easiest to carry out and provides the necessary diffusion.



Fig. 3. Absorption curves of different groups of membrane units and total absorption curve for the range 50-1,000 c/s.



Fig. 4. Reverberation characteristics after re-treatment (a) empty, (b) with orchestra, (c) with orchestra and choir of about 200.

The first step in designing the new absorption treatment was to assess from the measured data, and from details given by laboratory measurements, what amount of absorption was provided by the existing surfaces of the studio and the hanging drapes of Cabot's quilt. Unfortunately, it is not always possible to rely on published figures of absorption coefficients, either because of differences in the mounting of materials, compared with the method used in the reverberation test chamber, or because no such data is available. This assessment showed that considerable extra absorption would be needed in the frequency range from 50 to 1,000 c/s, and that absorption should be reduced at frequencies above 1,000 c/s. Moreover, it would be necessary to grade the amount of absorption in order to smooth out the reverberation time curve into the desired shape. For example, considerably more absorption would be required at 60 c/s than at 125 c/s, and even more at 250 c/s.

Absorption Synthesis

It is possible, by selecting the frequency and total area of the membrane-type absorbers, to achieve any desired pattern of extra absorption, and at the same time the choice of these elements can be influenced by architectural considerations as to what arrangement would look pleasing when assembled in the studio. In this case four different resonant frequencies were chosen, namely, 62, 80, 250 and 300 c/s, and the amount of absorption provided by the different areas of these units is given in Fig. 3, together with the sum of the total absorption, which is seen to conform with the requirements outlined above.

At the same time it was desired or necessary to introduce other absorbent surfaces into the studio, and the extra absorption supplied by these had, of course, to be added to the totals. For example, it was decided to panel the whole of the dado, part of the rear wall and the sides of the orchestral rostrum with veneered wood panelling. Such panelling applied to battens over an air space in which is inserted a porous damping material (such as glass wool) provides a moderately efficient low-frequency absorbent of resonant type with a fairly wide frequency band. There is a theory (possibly fallacious) that wood enhances in some way the acoustical quality of an auditorium. However that may be, it is very practical and a satisfactory material æsthetically.

As already stated, it was also desired to add upholstered seating for the choir on the orchestral rostrum. This consists of long form-like seats with back rests upholstered with "Dunlopillo" padding. In order to ensure that the porous rubber padding could serve as a useful sound absorbent the covering chosen was a woven plastic fabric having a high degree of porosity. The material wears very well, is at the same time water-resistant, and can be easily cleaned by sponging.

The area of the wood block floor was increased, and the carpeted area correspondingly reduced both in order to lower the high-frequency absorption and to provide more space for orchestral players when unconventional layouts are required.

Special care was taken with the absorbent treatment of the rear wall above the balcony. This wall is sufficiently far from the normal microphone position to be liable to cause echo at the microphone. A double treatment was provided consisting of shallow depth (250 c/s) membrane units mounted on the wall, and in front of these a spaced-out treatment of 2in of rock wool covered by a perforated facing. This rock



Fig. 5. Pulsed gliding tone reverberation patterns of Maida Vale No. 1 Studio taken (a) before (Feb. 1951) and (b) after re-treatment (Oct. 1951). At these low frequencies the decay curves after re-treatment are steeper, smoother and have a more uniform average slope.

wool treatment is most efficient in the mid-frequency region and, owing to the low percentage perforation of the facing, the efficiency falls off fairly rapidly above 1,000 c/s. This is done to avoid lowering the reverberation time at these high frequencies, but the danger remained that some high-frequency reflections might be sent back to the microphone. The treatment was therefore mounted in a saw-tooth manner so that any reflections would be of a scattered nature.

Although the ceiling profile consists of flat planes these are set out approximately in the form of an arc, and it had been noted that some unwanted focusing of sounds resulted from this. Large projecting boxlike devices of varying sizes were, therefore, attached to the ceiling in a decorative pattern in order to break up any reflections from the ceiling.

Appearance

The membrane units are applied to the side walls of the studio in rows so that the horizontal lines are emphasized. This was done in order to break up the vertical lines caused by the roof-supporting piers which originally had the effect of making the orchestra appear very remote when seen from the gallery. At the same time the various amounts of projection of the units were mingled together to provide a maximum number of angle reflectors, thereby greatly increasing the diffusion.

The front part of the orchestral rostrum is constructed on a concrete slab over which is applied wood boarding with hardwood ply finish. In order to allow the wood to resonate—a requirement for such instruments as cellos and double basses where sound energy is believed to excite the floor through the spike of the instrument—a layer of corrugated cardboard was interposed between the boards and the concrete. The primary object of having a concrete foundation is to prevent reinforcement of heavy bass notes by boominess when, for example, tympani are sited on the rostrum. In order to ensure compact orchestral layouts, an important requirement both for concerted playing and best acoustical effect, the risers were reduced in width and the waste of space normally occasioned by the music stand bases was avoided by employing specially designed music stands which can be dropped into any of a large number of sockets mounted on the front of the risers. The back part of the rostrum for the choir is constructed on a tubular steel scaffolding frame, and the dimensions are arranged so that the chorus is as compact as possible consistent with reasonable comfort. The seating, which is undivided by arm rests to allow flexibility in layout, will accommodate choruses of up to 300. On the rare occasions when even larger choirs are used, extra seating can be installed at the rear of the rostrum or on portable rostra.

The results of recent reverberation measurements are shown in Fig. 4. It will be seen that the curves are now reasonably level and a marked improvement on the previous condition.

A new technique, already described,[2, 3] has also been used to compare the old and new conditions. This new method consists of radiating pulses of tone of slowly rising frequency into the studio, rectifying logarithmically the output from a microphone, and displaying it on a cathode-ray oscilloscope. Only the decay is shown on the oscilloscope. A series of reverberation curves is, therefore, obtained and photographed on a slowly moving film, giving the result shown in Fig. 5.

If these displays are carefully examined it will be observed that the decays in the modified condition are smoother than before. Furthermore, the long reverberation in the region below 100 c/s in the original condition no longer exists.

Aural Assessments

The measurements indicate a considerable improvement in the acoustics of the studio and this has been confirmed by its use in service. Considering the difficulties of acoustic design, criticisms have been surprisingly few. Most performers and conductors have considered it to be excellent, and the audiences who have heard it have also given it praise. The old boominess has disappeared. The low frequencies are now very clean, probably due to the type of bass absorption employed. Most musicians have been surprised at the "brightness," compared with the majority of concert halls, and the performers in an orchestra can hear each other well. In loud passages there is very little confusion, and even the wood-wind instruments succeed in making themselves heard. The broadcast results are very good because the studio has a clarity and spaciousness usually associated only with the best concert halls.

[2] T. Somerville. "Acoustics in Broadcasting." *Proceedings of the Building Research Congress*, 1951, Division 3, Part I, p. 53.
[3] "Studio Acoustics—New Technique of Measurement used by the B.B.C." *Wireless World*, October, 1951, p. 435.

1400-Mc/s RADIOPHONE

Novel Application for Master and Slave System of Frequency Control

By J. B. LOVELL FOOT,* A.M.I.E.E.

APART from their suitability for multi-channel wide-band systems, decimetre waves confer some benefits for simple point-to-point communication over an optical path. For example, as compared with the longer wavelengths, they allow the use of a reflector of simple construction and less than 2 ft in any dimension to beam the transmission. This reflector can be inexpensive and requires only a light mast for its support. The narrower beaming that is possible on the shorter wavelengths has several obvious advantages; for example, the equipment is less likely to pick up interference or to produce interference with other services. A higher degree of privacy is also obtained. Further, the r.f. power of the transmitter can be very small owing to the higher aerial gain obtainable.

The decimetre-wave system to be described is designed around the DET23 disc-seal triode valve which is operated to give an output of about 1 watt. This gives a range of up to 30 miles between suitable sites with a signal-to-noise ratio of about 20 db. Normally the frequency drift of a triode oscillator necessitates the use of either a wide-band receiver with a correspondingly poor signal-to-noise ratio, or a complicated system of frequency control of the local oscillators for both the transmitter and the receiver at both ends of the system. Direct crystal control of frequency is out of the question for a simple equipment, since it would be necessary either to pick out a high-order harmonic from the crystal oscillator and amplify it at very high frequency, or to use a large number of multiplier stages keeping a high level throughout the chain. Both techniques present serious difficulties.

The system adopted to provide an experimental link employs a "master and slave" principle. Two single decimetre-wave oscillators are employed, one at each end of the link. These were designed to give a good frequency stability by a rigid construction and light loading. The oscillator at the "slave" terminal is controlled in frequency by signals received from the "master" so as to keep the frequency difference between the two stations constant. In addition to providing the carrier, these oscillators also supply the voltage necessary for frequency conversion to the first i.f. in a double superheterodyne receiver.

The system imposes several important limitations:—(a) The frequency stability of the whole system is entirely dependent on the stability of one uncontrolled oscillator. (b) The frequency of the "go" and "return" carriers must have a difference equal to the first i.f. of the receivers. (c) Modulation at either terminal produces an audio signal in both receivers.

As an illustration of the first limitation (a), Fig. 1 shows a typical curve of frequency variations of the master oscillator over a period of 24 hours. The slow drift that takes place during warming up shows that the thermal capacity of the oscillator block is large. This has the effect of flattening out variations due to rapid changes of ambient temperature and, if the initial warming-up period is disregarded, a good stability is obtainable.

Limitations (b) and (c) may be regarded as advantages for certain applications. In the case of the former, since the transmitter and receiver local oscil-

* G.E.C. Research Laboratories, Wembley.



Fig. 1. Graph showing the variation of oscillator frequency over a period of 24 hours



(Right) *Fig. 2. Graph showing the variation of oscillator frequency with change of anode voltage*



Fig. 3. Block diagram showing the arrangement of the master and slave stations

lator functions are performed by one oscillator, it becomes unnecessary for the aerials to be elaborately shielded to prevent the local transmitter from blocking the receiver. The only precaution required is to prevent excessive current in the crystal employed as first mixer of the receiver.

As for (c) the reception of the modulation of the local transmitter provides side-tone and also proves that the distant transmitter carrier is being received, thus giving a check on both "go" and "return" radio signals. In cases where side-tone is undesirable, however, it can be balanced out by a special circuit combining the audio in the modulator with the audio from the receiver.

Method of Modulation.—When the anode voltage of a free-running oscillator is varied, an amplitude modulation and also a frequency modulation of the r.f. output is obtained. The latter is due to changes of the capacitance of the valve with changing space current. For a lower frequency oscillator, where the valve provides only a part of the capacity tuning the circuit, a considerable change of anode voltage would be needed to provide sufficient frequency deviation for an f.m. system. Since there are better ways of obtaining this frequency deviation without the disadvantages of simultaneously producing amplitude modulation the method is not normally used. In a decimetre-wave system, the case is different; a reactance modulator is very difficult to apply to the oscillator. On the other hand, because the capacitance tuning the circuit consists mainly of valve capacitance, sufficient deviation can be obtained by variation of the h.t. voltage without introducing a very large amplitude modulation. Fig. 2 shows the variation of frequency obtainable with change of anode voltage at these frequencies. A deviation of ± 100 kc/s was chosen as the condition for full modulation and the receiver was designed accordingly. Amplitude modulation is eliminated at the receiving end by the use of limiters.

A block diagram of the complete system is given in Fig. 3. Two aerials constructed with corner-type reflectors forming one unit are employed at each terminal. These are connected by concentric cables to an oscillator of the tuned-grid tuned-cathode type and the receiver respectively. The master station receiver on the left of the diagram comprises a chain of stages normally employed in a double superheterodyne.

The first mixer is a silicon crystal which is mounted in a cavity attached to the oscillator block, as shown in Fig. 4 and this is followed by an i.f. amplifier of 9.6 Mc/s. The i.f. is then changed to 3.9 Mc/s by mixing with the output from a 13.5-Mc/s oscillator. This second frequency change simplifies the amplifier as regards shielding, since the use of a high-gain amplifier, having the same frequency throughout, is avoided. The frequency stability requirement of the second oscillator does not call for any special precautions. The 3.9-Mc/s i.f. amplifier is followed by a limiter and an f.m. detector. Finally a single-stage a.f. amplfiier feeds the hand-telephone set.

In the transmitting chain, the hand-set microphone output is applied to the input of the modulator. This consists of a double-triode valve, one half of which operates as an amplifier and the other half as a cathode follower. The cathode follower is suitably matched to modulate the anode voltage of the deci-



Fig. 4. Diagram showing the arrangement of the oscillator and mixer unit.

metre-wave oscillator without the use of a modulation transformer.

The Frequency Control System.—The "slave" station on the right of the block diagram (Fig. 3) follows the same arrangement as the "master" station, but has the addition of a frequency control circuit shown in greater detail in Fig. 5. Use is made of the d.c. component derived from the f.m. detector of the receiver. When the local oscillator frequency is accurately tuned to produce the correct intermediate frequency after combining with the incoming signal, the detector is balanced and the d.c. potentials produced by the detector diodes at points A and B (Fig. 5) are equal. If, however, the local oscillator frequency is too high, or too low, the potentials at these points will change in a push-pull manner, the polarity depending on whether the mean intermediate frequency produced is too high or too low, and the voltage depending on the extent of the "error."



Internal view of slave equipment, showing on left-hand chassis oscillator unit and gear box. Power unit on right

Receiving and transmitting aerials are arranged as a single unit giving vertical polarization



The following electro-mechanical method interprets these voltage changes into a rotation of a tuning control on the "slave" oscillator in the direction to correct the frequency. Two independent RC oscillators V_1 and V_2 (Fig. 5) of stable design and similar characteristics operate at a frequency of 56 c/s. Each drives an amplifier which supplies power to a slow-running, clock-type synchronous motor. One of the resistance elements in the feedback circuit of each oscillator is replaced by a valve (V_3 or V_4) whose resistance is controlled by the d.c. voltage produced at the detector. At the balance point V_3 and V_4 are adjusted to have exactly the same frequency, but if the balance is upset owing to a change of frequency of the master oscillator, one 56-c/s oscillator increases in frequency and the other decreases in frequency, resulting in a difference between the speeds of the two motors. This difference in speed is transmitted, via a reduction gear, to a shaft on the slave oscillator unit. The shaft carries a frequency controlling cam which rotates until the correct intermediate frequency has been restored. The tuning cam is made of a low-loss insulating material and avoids inteference due to intermittent metallic contacts. It is so mounted in the cavity of the oscillator unit as to affect the capacity distribution and produce a nearly linear frequency change of 10 Mc/s for 180 deg rotation. The master oscillator is of similar construction but here the cam is arranged to provide a manual adjustment of the frequency and is controlled from the front panel.

If, for any reason, the slave oscillator frequency lies outside the output range of the f.m. detector; for example when the sets are first switched on, a frequency search is brought into operation in the following manner. The valve V_5 (Fig. 5) in parallel with the feedback resistance R is normally biased beyond cut-off by a potential developed by the limiter when a signal is being received. In this condition, the frequency of V_1 is unaffected. If, however, the signal is removed, V_5 assumes a conducting state, reducing the resistance across R, and causing the frequency of V_1 to change. Continual rotation of the tuning cam then takes place until the signal is again picked up and V_5 is restored to its normal condition. It will be seen that, for one revolution of the tuning cam, the slave oscillator frequency will rise to a maximum and then fall to a minimum. Owing to the reversal in the direction of this frequency change, there would normally be a reversal in the direction in which the frequency correction is applied for each 180 deg rotation of the cam. This difficulty was overcome by reversing the polarity of the d.c. input from the detector to the control circuit in step with the reversal of frequency change. This is carried out by the contacts S_1 and S_2 of the relay S/2. A contact, X, fitted to the cam shaft and arranged to open and close for each half revolution, controls the current to the relay, this ensures that the correct direction of control is always applied.

Aerials.—One of the illustrations shows an aerial unit. This consists of two centre-fed half-wave dipoles, each placed in a corner reflector made of sheet aluminium and measuring 20 in × 10 in across the opening. The transmitting and receiving pair are alike and are mounted side by side in a "W"



Fig. 5. Frequency control system of the slave station showing how the frequencies of the 56-c/s oscillators are controlled by the grid voltages of V_3, V_4, V_5

formation giving vertical polarization. The measured power gain for an aerial of this type is 9 db compared with a simple dipole and the horizontal beam width measured to points 6 db down is ± 15 deg.

Concentric cables connect the aerials with the equipment. Since most concentric cables have a high loss at the frequencies used in this equipment, (for a typical ½-in diameter polythene cable it is 0.4 db per yard) it is important to situate the equipment as near as possible to the aerial. By careful adjustment of the aerial length a standing-wave ratio of better than 1.2 was obtained. This adjustment was carried out using a line of variable length between the oscillator and the aerial, measuring the aerial output at a fixed point a few yards away. The aerial was then adjusted so that the least variation in power occurred for a change of a quarter of a wavelength in the length of the cable.

The Power Supply.—A stable oscillator frequency is obtainable only if the h.t voltage supply is also stable. To achieve this the output voltage of the a.c. supply unit included in the equipment is held in a fixed relationship with a voltage developed across a neon stabilizer by the use of an amplifier controlling the resistance of a pair of series-connected tetrodes. This arrangement not only provides a d.c. potential almost independent of change of a.c. input voltage over a wide range, but makes also the effective internal resistance of the power supply very low. This is important in order to avoid frequency pulling between the two 56-c/s oscillators. Experiments showed that the heater voltage stability was less important than the h.t. stability and no special precautions were taken.

Purpose of the Equipment.—The equipment was constructed as part of an experimental project to test the potentialities of such a simple system and to obtain information on the propagation of e.h.f. radio waves under special conditions. One example of its special uses has been in tests made on transmission through railway tunnels.[1]

Further tests were carried out over several point-to-point optical paths. The greatest range tried was between Hanger Hill, Middlesex and Woodcote Hill, near Reading, a distance of nearly 34 miles. Over this path communication was satisfactory, but the frequency control was operating at the limit of reliable locking. For shorter ranges the control operates well and is particularly free from overshoot and the generation of noises common to many mechanical control systems.

[1] *Wireless World*, December, 1950, pp. 456-458.

GRAMOPHONE MOTORS

Recent Trends in Design and Manufacture

SOME insight into precision engineering processes involved in the production of domestic gramophone motors and record changers was given by E. Mortimer (Garrard Engineering Co.) in opening the discussion at the January meeting of the British Recording Association.

Nowadays the governor-controlled motor has given place, except for special applications, to the constant speed induction motor, with a friction drive to the rim of the turntable. This lends itself to the design of simple change-speed mechanisms with interchangeable friction wheels for 78, 45 or 33⅓ r.p.m. Although simple in principle, careful design and manufacture are necessary to ensure steady running in this type of mechanism. A heavy turntable is ruled out in the interest of the life of the friction surfaces, and the motor is run in the saturated condition with constant slip at 1,340 r.p.m. up to a torque of 25gm-cm. A shaded four-pole stator is used and laminations for both stator and rotor are cut simultaneously and kept together to allow for variations in the composition of the raw material.

Turntable spindles are form-ground in one operation on special machines to ensure concentricity of the different diameters and tapers. Rotor spindles

are lapped as well as ground since surface finish, as well as clearance, is a vital factor in smooth running. Particular care is paid to the thrust bearing of the main spindle which is usually the primary source of low-frequency "rumble."

All rotors are electro-dynamically balanced before assembly, and the complete unit is given a 6-hour over-voltage test at 270V, followed immediately, while hot, by an insulation test. Speed and torque are checked stroboscopically with an air-brake load. A final listening test on the electrical output from the pickup is made for "wow," "flutter" or "rumble."

In the discussion which followed there was general agreement that any improvement upon the performance of the mass-produced motor would inevitably involve a substantial increase of cost. To the many speakers who asked for a unit intermediate in quality and price between the domestic types and "professional" models costing £20 or more, Mr. Mortimer explained that designs had been developed, but that at the present time all available materials were needed to supply the overseas demand for British domestic gramophone motors which found a ready sale in the face of strong foreign competition.

"SPORADIC E" CLOUDS

Abnormal Propagation Due to Patches of Intense Ionization

By D. W. HEIGHTMAN, M.Brit.I.R.E.

SINCE the end of the late war and the resumption of amateur radio activities, a great deal of interest has been aroused by the abnormal behaviour at times of v.h.f. signals due to sporadic E propagation. Radio amateurs in many parts of the world have experienced these phenomenal conditions which have been encountered on the 6-, 5- and 2-metre wavebands.

For several years now I have kept careful observation on the E layer's characteristics, including the drift of the patches, or clouds, of abnormally dense ionization over Europe and which were mentioned in a recent article in *Wireless World*.* Some of this work is referred to in my paper "Propagation of Metric Waves Beyond Optical Range" published in the October, 1950, *Journal of the British Institution of Radio Engineers*.

For these observations reliance was placed on signals from various known stations in Europe, reflected at oblique incidence, in the 30- to 60-Mc/s band. It was assumed that the point of reflection was mid-way (as has been done in the large-scale American amateur tests controlled by O. P. Ferrell).

Some of these results have yet to be analysed but in general the conclusions have been similar to those resulting from the American tests. Speeds of drift of "clouds" can vary over wide limits as can the direction of motion and area of clouds—so much so that at present it is not possible to see any regular behaviour of the phenomenon.

Ionosphere sounding stations may be too widely separated to allow accurate tracking of the E clouds. The intense centres often appear to be only a mile or so across, particularly at the commencement, thereafter spreading over a wider area, but with reduced density.

Some tests carried out with a Belgian amateur in 1949 indicated that these E clouds were the source of (or diverted) a noise radiation, similar to solar radiation (reception was in the 100-Mc/s region). This gave the interesting possibility of using beam aerials to track the source, though here complication by direct pickup from the sun would at times result.

As will be seen from my paper, I obtained good correlation between times of occurrence (on a local time basis) provided fairly wide areas were considered.

I am inclined to think of these clouds as being due to two or more variables, which would account for their random and largely unpredictable nature:—(1) a condition of the upper atmosphere which may be related to upper weather. (2) solar radiation (temperature zone type "E").

There seems in another case to be some connection between weather and ionosphere conditions, inasmuch as fast moving depressions (and severe gales) have frequently been observed to follow ionosphere storms by a day or two.

My observations show that higher frequencies were reflected at the last sunspot maximum, as would be expected, but that the actual number of occurrences on the lower frequencies is not necessarily less at the sunspot maximum.

Further useful information on the subject generally could be contributed by systematic observations on a fairly large scale by radio amateurs. Unfortunately in this country we do not have a Government-sponsored scheme for collection and analysis of the reports as in the U.S.A.

* "Propagation of V.H.F. *via* Sporadic E" by T. W. Bennington. *Wireless World*, January 1952, pp. 5-9.

Siting Direction-Finding Stations

MODERN radio direction finders are capable of extremely high precision and in most cases the accuracy of the bearings is limited only by the imperfections of the station site. There is much valuable information available on the effects of buildings, railways, trees and other topographical features, but it is widely scattered throughout the literature.

Radio Research Special Report No. 22, "The Siting of Direction Finding Stations" presents the available information on the subject in a single publication. The types of direction finders dealt with are mainly those with loop or Adcock aerials covering frequencies of from 100 kc/s to 300 Mc/s. The report is published by Her Majesty's Stationery Office for the Department of Scientific and Industrial Research and the price is 1s 6d (1s 7½d by post).

Ready NOW!

APPLICATION REPORTS

and circuit data on

BRIMAR VALVES



STIFF, LEATHERETTE, LOOSE-LEAF RING BINDER WITH GOLD-BLOCKED LETTERING Size 9" × 8"

IN order to meet the demands of engineers engaged in the electronic and allied industries for more complete information on Brimar Valves, a loose-leaf volume of Application Reports has been prepared. In addition to the usual technical information, these reports will contain measured performance data in typical circuits, together with comprehensive curves of the various valve parameters so necessary for the convenience of the circuit designer.

Current equipment Brimar Valves will be included in this service; new types as they appear will be covered by data sheets whilst the application data is being prepared.

The volume will also include circuit reports and other information which is issued from time to time by the Valve Applications Department.

The complete service will be available on an annual subscription of 20/- (including the issue of binders). Additional copies of individual reports can be obtained at 2/6 or 5/- each, depending on the type.

We anticipate a heavy demand for this service and, therefore, advise all who are interested to reserve their copy without delay. Send your enquiries to:

Publicity Department, (Application Reports),

Standard Telephones and Cables Limited

Radio Receiver Valve Division, Footscray, Kent *FOOtscray 3333*

Achieved!

SINGLE STYLUS QUALITY
WITH A
DUAL STYLUS PICK-UP

THE G.P. 29 TURNOVER PICK-UP CARTRIDGE

Yes, it is here. We have produced, in the G.P. 29, a dual stylus turnover cartridge which really does give smooth response on both standard and long playing records with the normal run of domestic gramophone and radio-gramophones. Only in exceptional cases is input correction required. Output is around 0.7 V. at 1,000 c.p.s. from Standard and about half that from L.P. records. The response characteristics of the two sides of the dual cartridge unit are tailored to give fine quality performance in both cases, and the result is not only well balanced reproduction, but little or no needle scratch. (Available to manufacturers only)

and also a **UNIVERSAL MICROPHONE..** *at a moderate price*



THE MIC 30 "HAND-STAND" MICROPHONE

This new Acos Model is designed to please most of the people all the time. It is a good quality hand microphone which will stand up or hang up when you want it to. The legs which convert it into a desk model are spring-loaded and fold unobtrusively into the attractive moulded microphone body when not in use. Frequency response is substantially flat from 50 to 5,000 c.p.s., and an On-Off switch with provision to close an extra circuit is incorporated. The price is moderate at £4 4 0 (retail).

SEE THEM AT THE R.E.C.M.F. EXHIBITION ON STAND 25

always well ahead

Remember that Acos components are used in *large numbers* by leading manufacturers (make sure that *your* new gramophone equipment incorporates an Acos pick-up). The complete range of Acos products, being shown at the Exhibition, includes various types of Crystal and Magnetic Pick-ups, Microphones, Hearing Aid Components (as used in the Medresco as well as many famous proprietary makes of hearing aids), Laboratory Instruments and fine quality components in plastic.

COSMOCORD LIMITED · ENFIELD · MIDDLESEX

Physiological Feedbacks

A Radio Man's Introduction to Cybernetics

By T. E. IVALL

THE animal brain and nervous system would never be able to control the body as precisely as they do if they simply relied on sending "blind" instructions to the muscles. What actually happens can be seen from Fig. 1. The brain knows what it wants done (desired result) and begins to send the appropriate control signals. While the muscles are performing, their progress is continually being reported back to the brain (muscle feedbacks) and compared with the desired result; then, according to the amount of discrepancy, the brain operates them so that the actual result approaches the desired result until finally the discrepancy is reduced to zero. In picking up a pencil, for example, the muscular action of the arm and fingers is regulated by a continual feedback of information on the amount by which the pencil is "not yet picked up," so to speak.

All this may look very complicated, but those who read the article on servo-mechanisms in the January issue will realize that it is, in fact, nothing more than a description of servo operation. Others, seeing Fig. 1, will probably infer negative feedback, which, of course (as Mr. Taylor pointed out), is virtually the same thing. All the mechanisms of the animal body are controlled on this principal and the negative feedback loops are provided by the circuitry of the nervous system. The natural function of these "servo systems" is to give stable operation and make the body adaptable to changes in the outside world—just as negative feedback stabilizes an amplifier against "environmental" changes in load, supply voltage, and so on. Without them we should not last for very long. The feedbacks which control the muscles of the limbs are necessary for mechanical stability in getting about the world, for avoiding danger and so on, but there are also comparatively slow-acting ones which do things like maintaining the body temperature against cold and adjusting the aperture of the eye pupils according to light intensity. On some we exercise voluntary control (picking up the pencil for example), while others are purely automatic and we are not conscious of them till they go wrong. A good many of the feedback loops are contained entirely within the body, but some are completed through the outside world *via* the sense organs; for example, when the eyes are brought into play to feed back "error-information" on what the hands are doing (the visual feedback loop in Fig. 1). Animals with these obviously have a great advantage over others. There are also loops which regulate the processes of the brain itself, feeding back from each stage to the previous one.

Sir Charles Sherrington began to make a really systematic study of physiological feedbacks as long



Fig. 1. Simplified block schematic showing how negative feedbacks in the nervous system are arranged for giving a self-stabilizing control action.



Right: Behaviour of interacting feedbacks in the brain is simulated by this machine—the "homeostat"—designed by W. R. Ashby. On top of the units are swinging magnets whose movements affect each other and produce complex patterns of behaviour. Each magnet is swung by magnetic fields from four coils energized by the outputs of the four units; the movements are converted into corresponding electrical variations by a liquid potentiometer and these are amplified to drive the coils. Stability is attained when all four magnets are central. The machine adapts itself to any "environment" (i.e. arbitrary hand settings) by automatically altering its own wiring until it finds an arrangement of feedbacks that produces this stable condition.

ago as 1893, but it is only recently that servo and feedback technique has developed into a complete subject of its own and provided the physiologist with a set of cut-and-dried theories and concepts. By thinking about the animal mechanisms in this engineering language he is now greatly improving his understanding of them. Likewise, the engineer is learning a lot by studying natural systems, particularly in the vast communications network of the nervous system. Neurophysiology and communications engineering, in fact, are becoming part of each other.

This idea of the biological and engineering sciences drawing analogies from each other is not by any means new, and in the past has been responsible for some of the greatest scientific achievements. In the days when engineering was concerned only with purely mechanical devices, the analogies were necessarily restricted to the mechanical systems of the body. William Harvey discovered the circulation of the blood, for example, because he was interested in the work on air-pumps that was being done at the time. Now, in what is perhaps the heyday of electronics and communications engineering, the analogies are all electrical. A new kind of machine has arisen, often having no moving parts, but nevertheless approaching much nearer to the animal machine in complexity. We have pick-up devices like microphones, photocells, thermistors, with obvious counterparts in the animal sense organs, and actuating devices like motors and solenoids comparable with the electrically operated muscles. Circuitry and communication channels clearly serve the same purpose as the nervous system—transmission of information—while automatic telephone exchanges and computors are, in a sense, "brains." Moreover, the behaviour of some of the electronic homing devices used in air navigation can be remarkably like instinctive animal behaviour.

All these analogies—many of which are really homologies because of the electrical properties of the animal body—have prepared the ground very effectively for the modern ideas which revolve around the central theme of feedback. What might be described as the bible of this modern movement is the book "Cybernetics" by Norbert Wiener, an American mathematician. Wiener uses this strange word cybernetics, an Anglicized version of the French *cybernétique*,* as a name for the general field given by his sub-title as "control and communication in the animal and the machine." The subject links control and communication engineering together into a common mode of thought that can be applied to any organized system—man-made machine, animal or human physiology, society in general. Modern Information Theory puts the "communication" side on a quantitative basis, while servo and feedback theory does the same for the "control" side. Many different fields are touched upon in the book, but the thread linking them all together is this idea of communication of information for the production of a self-stabilizing control action.



Fig. 2. (a) Sketch of a nerve cell, with inputs from other cells. The biggest nerve cells have a bulb diameter of about 0.002in, dendrites 0.1in long, and a fibre 0.0001in thick and 6ft long. (b) Type of graphical symbol used by physiologists to represent a nerve cell.

Nerve Communications

Now what about the circuitry of these feedback loops? How exactly does the nervous system transmit its information? The nervous system is a vast network of interconnected nerve cells spreading to all parts of the body, and it conveys the control signals as electrical impulses. Large groups of the nerve cells are massed inside the spinal chord, and there is a particularly large conglomeration in a bulb at the top of it—that is, the brain. External stimuli cause the sense organs to generate signals which travel inwards to the brain, and the brain uses this input of information about the outside world for deciding the appropriate control signals to send out to the muscles.

A single nerve cell, or one link in the feedback chain, looks something like Fig. 2. At one end (the input) there are some pick-up "roots" called dendrites, while the other end (the output) tails off into a long fibre. Anything up to a thousand output fibres of other cells connect on to the receiving dendrites. The cell is electrically polarized, with the outside maintained at about 0.1V positive with respect to the inside. In response to a certain patterned sequence of impulses from the other cells, the cell is triggered and fires a new impulse. This is transmitted down the length of the fibre as a kind of "travelling discharge" of the polarizing voltage, with a speed of anything between 1 and 150 yards per second. After the discharge has passed, each part of the broken cell wall automatically repairs itself, but it takes a certain amount of time to do so and this sets a limit to the number of impulses that can be transmitted per second; the cell does, in fact, cut off like a filter, at a repetition frequency somewhere in the region of 500-1,000 pulses per sec. The impulses are of more or less constant amplitude and it is their repetition frequency which indicates the strength of a signal (see Fig. 3), the system being something in the nature of a combination of p.c.m. and p.p.m. Like ordinary f.m., this has a great advantage in the presence of noise. Moreover, at every nerve cell the pulses are regenerated—as in a pulse-code telephony repeater—so that their sharpness is preserved no matter how long the transmission circuit.

Broadly speaking, then, the nerve cell is a kind of relay device, though its action is much more complex. As such it can be compared with a relay in any kind of communications system, but there is one system in which the comparison is particularly significant—that of the modern digital computor. Why? Because it immediately suggests a parallel between the com-

* Coined by Ampere to mean "the science of government" and derived from the Greek κυβερνητης meaning "steersman."

plex circuitry of relays in the computor and the mass of interconnected nerve cells constituting the brain. It suggests, in fact, that the brain calculates its outgoing control signals from the incoming "monitoring" signals by a process akin to digital computing. But how far is this true?

Digital computors use relays (electromagnetic or electronic) because they are robust and uncritical in operation. Although they have only two electrical states, open and closed, on and off, and consequently have to work on a scale of two (binary code) instead of the more familiar decimal scale, this is an advantage because there are no doubtful intermediate states to introduce error. These relays are arranged as a network of "gates," which determine the path through the computor of digit pulses from a central generator. Each relay makes a logical decision consisting of a simple choice between two alternatives: it either says "yes" and allows a pulse through, or "no" and stops it.

Obviously there is a certain similarity between the "yes-no" action of these relays and the action of the nerve cell, which also has only two states—pulse and no-pulse. Moreover, some of the computor "gates" are coincidence devices (Fig. 4 for example), and only open when triggered by a certain pattern of impulses from several inputs—again the same kind of behaviour as the nerve cell. Although the nerve cell is triggered by a time-sequential pattern, as distinct from the simultaneous pattern in Fig. 4, the logical operation is the same. (Note that the respective graphical symbols (Figs. 2 and 4) are similar, too.) It is possible, in fact, to analyse a network of nerve cells by logical algebra just as straightforwardly as a computor network. Thus it can be shown by physical examination that the network of cells in the brain has the right equipment for doing logical operations—and, of course, we know for a fact that the brain *can* think logically.



Fig. 3. (a) Record of impulses from a single fibre in an auditory nerve, showing how the p.r.f. increases as the sound stimulus to the ear gets stronger. (b) Single impulse recorded from a point on a nerve fibre, the "travelling discharge" taking nearly a millisecond to pass by.



Fig. 4. (a) Coincidence gating circuit that will only give out a signal when negative impulses are applied simultaneously to all three inputs. (b) Symbol for (a) used in logical circuit diagrams of digital computors.

Storage and Timing

There are two other rather interesting points of resemblance in this brain-computor analogy. The first is the memory, or storage of information. One system of storing digit pulses in the computor is to keep them circulating in an ultrasonic delay line, regenerating them every time round to preserve their amplitude and shape—just as a juggler "stores" more balls than he can actually hold by keeping them circulating in the air. The fact that storage can be achieved in this way by an electronic device has prompted neurophysiologists to think in similar terms about the brain, and they are now almost certain that part of our memory system consists of long and tortuous loops of nerve cells in which the brain signals are kept circulating by regenerative action. Memories can be eradicated simply by cutting the loops.

The other point of resemblance is the "clock," or system for providing a time scale. In the computor this is usually a crystal-controlled oscillator, to which the digit pulses throughout the machine are locked so that they have a time-position corresponding to a space-position on paper. Drawing an analogy from this, neurophysiologists have suggested that in the brain a similar function is performed by the 10-c/s electrical waveform known to electro-encephalographers as the alpha rhythm.* It is probably responsible for our sense of time and its regularity may have something to do with our ability to associate things into patterns and, indeed, our ability to reason. At any rate, the notion that the alpha rhythm is a timing oscillator, to which all the control signals of the body are locked, has been largely corroborated by experiment. A person is asked to press a bell-push haphazardly, whenever and as often as he likes, and the impulses obtained from it are displayed against his alpha rhythm, which is being recorded at the same time. Despite the random nature of the impulses, they show that the instants he presses the bell-push all bear the same fixed phase relationship to the alpha rhythm.

It seems likely that this timing waveform in the brain also serves as a kind of scanning mechanism. In television, scanning is used to convert a spatial electrical pattern, which would require an impossibly wide bandwidth to transmit all at once, into time-sequential signals that can be handled by a channel of practicable bandwidth. A similar thing happens

* "Studying Brain Waves," February 1952, p. 72.

in animal vision. The spatial image focused on the retina of the eye has to be converted into time-sequential signals so that it can be conveyed by a nerve channel of normal "bandwidth" to the exchange and computing parts of the brain. To do this, a "wide bandwidth" optic nerve channel, containing about a million parallel fibres, transmits the picture complete to the visual cortex, where it is reproduced, undistorted, as a spatial electrical pattern and then scanned. (Note that the familiar time-bandwidth dependence holds good in both television and physiological scanning.) Although this is only a tentative theory, it is nevertheless supported by the experimental evidence that we cannot read printed characters faster than 10 per second—the frequency of the alpha rhythm scanning waveform.

This spatial electrical image on the visual cortex plays an important part in the physiological feedback by which the eyes centre themselves on an object and follow it about if it is moving—say a bird in flight. (A good example, incidentally, of a feedback loop completed through the outside world.) The nerve cells on the visual cortex compute an electrical vector from the existing central line of gaze to the visual centre of the bird. This is relayed to the cells which control the eye muscles, which move the eyes so as to reduce the vector, until finally, by this process, the vector is brought to zero and the eyes are centred on the bird. If four electrodes are placed on the skull to pick up the electrical vector and the voltages from them are amplified and applied to a corresponding arrangement of deflector plates on a c.r.o. (two X plates and two Y plates), the spot of the c.r.o. follows the movement of the eyes exactly. This feedback mechanism is analogous to the automatic lock-and-follow searchlight and radar devices used in war for keeping the search beam trained on a moving target. Similarly, the feedbacks by which the eye guides the hand to grasp a moving object are analogous to radar-guided missiles.

Feedback Faults

Animal mechanisms and servo systems often exhibit the same kind of behaviour when they go wrong. Certain nervous diseases produce tremors of the limbs, for example, which are remarkably like the oscillatory effect known as "hunting" in servo-mechanisms, although there is no real evidence to show that the same kind of fault is responsible. Again, the brains of neurotic or epileptic people contain certain feedback loops which should give negative feedback but have changed round to positive feedback. They are unstable in the same way as an amplifier with spurious positive feedback loops is unstable, and with an epileptic it only requires a small triggering impulse to set the whole brain into a violent "motor-boating" oscillation and so cause a fit.

Since man is a microcosm of the society in which he lives, what has been said about control and communication in the animal body can also be applied to society in general. Communication by speech, writing, the press, films, radio, television, and so on, is essential to organized communities, and it tends to exercise the same kind of self-stabilizing control action as a negative feedback system. Without such communication, society would be in chaos, as would the body without a nervous system. Thus, people like historians, sociologists and economists, who study large-scale trends in society, are particularly interested in the notions about feedback, and, like the biologists, are turning to communications engineering for help in solving their problems. Economists, in particular, think that cybernetics will make the study of recurring booms and slumps into a really exact science. The present inflationary trend, for example, with wages and prices driving each other up, might be examined as a feedback which should be negative (giving stability) but has gone positive and produced regenerative action.

All this may seem to have come a long way from radio, but the whole point is that the theories from which biologists, economists, psychologists, sociologists and the like are deriving most benefit just now —Information Theory, for example—were originally devised by engineers to solve practical problems in communications. Moreover, it is from the practical techniques of radio, television and electronics that most of the really fruitful analogies are being drawn.

ELECTRIC WIRING REGULATIONS

ALL concerned in the installation of radio and television sets should know something of the regulations governing the electric wiring of dwelling houses if only in order to avoid some of the more serious pitfalls. For example, there are regulations governing the use of water pipes for earthing electrical equipment connected to the supply mains. Few will require the full regulations governing all types of installation, but there is now available a pocket-size abridged edition of some 80 pages which contains all the essential regulations for small dwelling houses.

Copies can be obtained from The Institution of Electrical Engineers, Savoy Place, London, W.C.2, and the price is 2s 6d. The full regulations, revised in 1950, are available also from the same address, price 5s with a paper cover and 7s 6d with cloth. Postage is included.

Educational Filmstrip

"THE Story of Television" is the title of a new filmstrip recently produced by Mullard in conjunction with the National Committee for Visual Aids in Education. Designed for students in the 11-16 age group, it traces the history and development of television from the first attempts to transmit pictures by wire to the latest developments utilized by the B.B.C. Television Service, and explains in simple terms how a programme is produced, transmitted and reproduced. The actual process of radio transmission between the studio and the receiving apparatus is not described at length as this is already covered in a companion filmstrip "The Story of Radio."

The filmstrip has 34 frames in black and white and costs 10s. It is available, with lecture notes, from the distributors, Unicorn Head Visual Aids, Ltd., at Broadway Chambers, 40, Broadway, Westminster, S.W.1.

Booklet Received

The B.B.C. Type "B" Disc Recording Feedback Cutterhead.—Technical and service data on this component and descriptions of associated amplifiers including circuit diagram and transformer winding details. Useful formulæ for disc recording. Pp.29+V; Figs. 16. Grampian Reproducers, Ltd., Hanworth Trading Estate, Feltham, Middlesex. Price 5s or $1.00 including postage.

F.M. IN GERMANY

V.H.F. Broadcasting Network : Recommended Receivers

WHILE the medium-wave broadcasting situation in this country is far from satisfactory, that obtaining in Germany is far worse. Under the Lucerne Plan (1934) the area now known as Western Germany had available five good channels, four fairly good and one bad, whereas, under the present Copenhagen Plan, it was allocated only three mediocre channels and four bad ones. It has, therefore, been decided by the broadcasting authorities in each of the Zones in Western Germany to introduce v.h.f. networks to supplement the existing stations.

In view of the discussions which will take place preparatory to the granting of the new Charter to the B.B.C.—in which the question of the introduction of a v.h.f. service is bound to loom large—some of the factors which have influenced the introduction of frequency-modulated v.h.f. in Western Germany are summarized in this article.

Dr. Werner Nestel, Technical Director of Nordwestdeutscher Rundfunk (N.W.D.R.), has contributed an informative article on the subject in the *Bulletin* of the European Broadcasting Union. He states that N.W.D.R., which serves the British Zone, has at its disposal only one mediocre m.w. channel and two bad channels. It is impossible even with the most careful use of these to cover even reasonably well the area which extends from the Danish frontier to Bonn in the south and Berlin the east. In fact, Dr. Nestel states the situation is so bad that the minimum field strength for an effective service can no longer be regarded as 2 mV/m but 4 mV/m and, in the case of the international common frequencies, some five times greater.

Before choosing an alternative system, preliminary tests were made with the following:—

(a) R.F. distribution over telephone circuits;
(b) R.F. distribution over electricity mains;
(c) a combination of methods (a) and (b);
(d) low-power shared-wavelength broadcasting (a very large number of very low-power transmitters on each frequency);
(e) short-wave broadcasting;
(f) amplitude-modulated v.h.f.;
(g) frequency-modulated v.h.f.;

The Technical Director of N.W.D.R. states that the preliminary tests established without doubt the far-reaching superiority of frequency-modulated v.h.f. The decision was therefore taken to build up as quickly as possible a network of v.h.f. transmitters with the object of giving complete coverage of the area served.

The fact that v.h.f. can result in improved quality of reception was not a deciding factor; the main reasons were: it permits the coverage of areas which cannot be served on medium waves and provides a service which can be complementary to the single programme necessitated by the synchronization of m.w. transmitters.

Amplitude modulation was given very serious consideration, but the decision in favour of f.m. is stated to have been based on the following reasons:—

1. Simple f.m. receivers are no more expensive



Standardized 10-kW frequency-modulated v.h.f. transmitter used by N.W.D.R. The fourth unit from the left is the output stage.

than those for a.m. (according to the German radio industry they are cheaper).

2. High-quality f.m. receivers are not more expensive than those for a.m., and they offer, in addition, the possibility of improved reproduction through the elimination of interference.

3. In addition to the area reliably covered by an a.m. transmitter of the same power, f.m. makes available a zone in which good reception is possible with the aid of high-quality receivers equipped with limiters. In this zone satisfactory reception is quite impossible with a.m.

4. A Europeon v.h.f. plan is practicable only if f.m. is adopted, since f.m. reception is possible with a signal-to-interference ratio of 5 : 1, whereas for a.m. reception a ratio of as high as 100 : 1 is required.

Of the two bands available (41-68 and 87.5-100 Mc/s), the higher was chosen despite the fact that it



Fig. 1. Service areas of the twenty-five v.h.f. transmitters in operation or due to be opened during 1952 by N.W.D.R. in the British Zone of Germany. The service area of the Berlin station is inset. In addition there are fifty-eight v.h.f. transmitters in, or planned for, the other areas of Western Germany.

provides fewer channels. On the question of channel separation, Dr. Nestel points out that the receiver stability, which cannot be improved very much, and the selectivity, which is not very great in the cheap receivers, as well as the bandwidth essential for f.m., prescribe a minimum separation between channels of 0.4 Mc/s. The channel separation of only 0.2 Mc/s customary in America would have led to more expensive receivers, and was not chosen for that reason. However, a separation of 0.4 Mc/s does not preclude the adoption of the American figure at a later date, when more selective receivers may be available. Only 31 channels are therefore available in the chosen band, necessitating a very careful allocation of frequencies for good coverage over a large area while allowing for subsequent complete coverage with a second, and perhaps even a third, programme. Dr. Nestel contends that the number of channels available, if carefully exploited, is quite adequate to solve any broadcasting coverage problems that could possibly arise in Europe. Careful consideration was also given to the question of possible interference from powerful transmitters in neighbouring countries.

Horizontal polarization has been chosen mainly because it provides better propagation in built-up areas and is less susceptible to motor-ignition interference.

Standardized Transmitters

The disposition of the transmitters in the area served by N.W.D.R. is shown in Fig. 1. It is anticipated that the entire network of twenty-five stations will be operating by the middle of this year. On this sketch map is shown the measured or estimated field-strength contours in three reception zones:— A, more than 50 mV/m (permitting the use of cheap receivers with indoor aerials); B, 5-50 mV/m; and C, 1-5 mV/m necessitating the use of both a good receiver and good aerial. On the question of aerials, it is interesting to note (Fig. 2) how the field-strength varies with the position of the dipole in different parts of a building; incidentally, the N.W.D.R. recommends the use of a folded dipole fixed to the window-sill.

So far as transmitters are concerned, it has been found, contrary to previously held views, that it is possible to obtain an output efficiency of well over 50 per cent. By taking into account the additional power fed to the aerial circuit from the penultimate stage by the earthed-grid amplifier, an apparent efficiency of 65 per cent may be attained, which is comparable with the efficiency of transmitters in other frequency bands. Modern 10-kw v.h.f. transmitters require for the entire transmitter a power intake of only 22.5 kW. For the first transmitters, the American example was followed and stage outputs of 0.25, 1, 3 and 10 kW were chosen. It was, however, soon found that this was unnecessary, and more recent transmitters have a smaller number of stages, the requisite higher power amplification for each stage being achieved without difficulty.

N.W.D.R. has standardized 10-kW transmitters for the network, which, with an aerial gain of 8, gives an effective radiated power of more than 50 kW. This gives a field strength of 1 mV/m (according to the international definition, at 10 m above the ground) at a range which, for reasons of wave propagation, may still be regarded as within the fading-free service area. Such field-strengths are regarded as adequate for the use of cheap aerials and cheap receivers. A further increase of the transmitter output and the field-strength at the receiver would have led to difficulties in the allocation of channels on account of the extra range which must be expected as a result of tropospheric propagation.

The high-efficiency 10-kW transmitters incorporat-



Fig. 2. Representative relative signal-strengths measured in different parts of a building. The figures in parentheses give the signal strength as a percentage of that in the roof.

Coupling device for feeding 10 kW at v.h.f. to an aerial atop a mast radiating medium waves at 100 kW.



ing few stages which were developed as a result of these considerations have become so straightforward and small and consist of so few parts (no coils, no capacitors, only quite simple cylindrical circuits not liable to failure) that they are now very much cheaper than the equivalent a.m. transmitters for other bands.

It is noteworthy that the v.h.f. aerials have in some instances been erected at the top of existing medium-wave mast radiators. The coupling device for feeding 10 kW at v.h.f. to an aerial on a 100-kW m.w. mast radiator is illustrated.

Dr. Nestel points out that the real key to the success of a v.h.f. broadcasting system is the provision of inexpensive receivers. The German radio industry was initially against the introduction of v.h.f. broadcasting because of the supposed high cost of producing adaptors and complete receivers. It was, however, shown that the provision of limiters and discriminators, which permit of reception with an input of only a few microvolts but necessitate a considerable outlay in valves and components, although orthodox, were generally unnecessary with the signal provided by N.W.D.R. This deviation from what has become general practice in America made available two very simple receiving circuits which, it is stated, do not require one single component more than a.m. circuits: —

1. The super-regenerative circuit, and,
2. Frequency-discrimination by means of a diode using the slope of the selectivity characteristic.

The cheapest receivers and adaptors use super-regeneration for which the Post Office and the broadcasting authorities jointly have made stringent regulations requiring that the interference produced in the super-regenerator must not get into the aerial circuit. Adaptors, costing between DM 27 and DM 50, which can be added to any existing receiver, employ a recently developed triode-pentode. The pentode has an untuned grid circuit and merely serves as a separator between the aerial and the actual receiving valve. It thus suppresses radiation and ensures that the main tuning circuit is unaffected by the aerial circuit. The actual receiving circuit, then, consists of an ordinary triode acting as a super-regenerator. The production of the quenching frequency is completely controlled, even during fluctuations in the mains voltage. Following the super-regenerative stage is an audio-frequency filter-equalizer, consisting of a capacitor and resistor. The output of this one-valve circuit is adequate for direct coupling to the audio-frequency stage of an existing receiver. The sensitivity of such simple circuits is about 0.1 mV.

The use of the second type of circuit recommended (diode discrimination using the slope of the selectivity characteristic) permits the production of a four-valve superhet receiver providing for f.m. reception, as well as the usual three a.m. wave-ranges. It employs an i.f. of 10.7 Mc/s in addition to the normal 468 kc/s (see Fig. 3). Some 80 per cent of the receivers now produced by the German radio industry cover the v.h.f. band. The difference in cost between a three-band superhet and one also covering the v.h.f. band is about DM 10. According to the latest available figures, the number of v.h.f. sets in use exceeds two million.

It must not be thought from the foregoing that only cheap receivers are being produced. Higher-priced receivers, incorporating all the refinements considered necessary to do full justice to f.m., are also being made.

In order to do full justice to the improved quality provided by v.h.f. broadcasting the German broadcasting authorities have extended the response of their studio equipment from the existing 10 kc/s to 15 kc/s, this extension covering all stages of the installation.

In the opinion of the author, the only solution of the wavelength problem in Europe lies in the adoption in all countries of v.h.f. broadcasting for all requirements beyond a single programme. This will, of course, mean an improved service on long and medium waves, as the majority of the m.w. channels could then be used exclusively and the separation extended from the present 9 kc/s to, say, 10 kc/s.



Fig. 3. Block schematic of a typical superheterodyne receiver providing v.h.f./f.m. reception in addition to covering the normal long (L), medium (M) and short (S) wavebands.

LETTERS TO THE EDITOR

The Editor does not necessarily endorse the opinions expressed by his correspondents

"Standardizing Television I.F."

WE have noted with considerable interest the editorial on this subject in your February issue, and feel that, on behalf of the television receiver manufacturers, we should comment, if only to let your readers know what the industry has been doing.

It is no secret that in 1949 a special Committee of this Association investigated the technical aspect of this particular subject of television i.fs, and that from this investigation emanated the theoretical case for the use of the 34-38-Mc/s band. Equally, there is nothing secret in the knowledge that at that time only one of the intended transmitting stations of the British five-channel system was in operation, so that actual experience of operating conditions in such a system was largely conjectural.

There has been, since, a transformation in both transmission and reception; three stations are operating, a fourth is due to be opened in less than a month; and the five-channel receiver has come to be typical of current design for the normal domestic television receiver. This has meant that industry has been able to gain considerable practical experience which was not available to it in 1949. Broadly, the position today is that there are two schools—those of the "low" i.f. and those of the "high" i.f., and it is at this point that B.R.E.M.A. has deemed it opportune to resuscitate its special Committee and to set it the task of making a practical re-examination of the advantages and disadvantages of intermediate frequencies which can be employed. This practical re-examination must obviously take into consideration not only technical aspects (of which statistics form as important and accepted part as any) but also those economic factors without which any technical solution would be reduced to one of academic value only.

It may thus be adjudged that a quick decision is not likely to be as readily available as your article suggests; there is, moreover, a danger that a quick decision which neglects the allocation of a correctly proportioned weighting to all relevant factors may aggravate rather than ease the situation. The story of the development of sound broadcast and television systems throughout the world contains an adequate quota of the wrong decisions at the wrong time, pointers which should be accepted as of fundamental significance in attempting to solve this problem of television receiver intermediate frequencies with the sweet reasonableness and rationality which we, as you, are confident will be applied.

S. E. ALLCHURCH, Secretary,
British Radio Equipment Manufacturers' Association.

"Hot Stylus Technique"

YOUR report (February issue) on M. C. Philip's short address at the B.S.R.A. meeting on 21st December is of considerable interest as it directs attention to a disc recording topic that has received scant attention in the British technical papers.

The method appears to be due to Columbia Records Inc., of New York, in whose laboratories development work was undertaken early in 1948 by William S. Bachman and his colleagues and described in the issue of *Audio Engineering* for June, 1950.

Equipment for commercial use of the technique has been available in the U.S.A. from such well-known companies as Fairchild and Presto for years, but it is gratifying to be able to mention that significant research in the method has been done in this country by Arnold Sugden, of A. R. Sugden and Co. (Engineers), Ltd., Yorkshire. Suitable attachments for hot stylus recording have been incorporated in Mr. Sugden's microgroove apparatus for some time.

I am not sure that your note makes it clear that many experimenters (including myself) prefer to wind the coil directly on the sapphire tip near the junction of the jewel and the dural shank proper for maximum heat transference. Currents of the order of 0.4-0.5A may be employed and the stylus temperature does not seem to be critical for good results. Some workers claim a reduction in surface noise of as much as 20db and the accompanying curves show relative frequency-response losses of normal and hot stylus recordings at various groove diameters (78 r.p.m. and standard pitch).



Torquay, Devon. DONALD W. ALDOUS.

"Television Ghosts"

I HAVE read with great interest the article by J. A. Hutton in your March issue and would like to mention that an improved performance can be obtained from the double H if folded dipole elements are used. In addition, by a careful choice of broadside and reflector spacings it is possible to arrange the array feed impedance to match into a standard 75-ohm feeder cable.



The closer broadside spacing of 0.4λ in the aerial shown in the accompanying photo results in a lower forward gain, although the front/back, front/side ratios remain substantially the same.

Commercial double H aerials are manufactured by Wolsey Television, Ltd. (Model B/AH) and Aerialite, Ltd. (Model 69).

Edison Swan Electric Company, K. W. KING.
London, W.C.2.

I HAVE read J. A. Hutton's very interesting article (your March issue) and, as a result of independent investigations carried out by my company, would like to confirm his findings, and to emphasize some important conclusions that, I think, may be drawn from them.

It is obvious that an anti-ghosting aerial (in the present state of the art) cannot be sold "over the counter." The article thus serves a useful additional purpose as a warning against extravagant claims for a "general purpose" anti-ghosting aerial, unless a new and proven technique

is evolved. It also brings to mind the possibility of similar problems arising, locally, within the service areas of the Scottish and Welsh transmitters.

Considerable thought should be exercised before buying, or selling, television installations in anticipation of the transmission, if the site possesses the contour features described by Mr. Hutton. F. R. W. STRAFFORD.

Belling & Lee, Ltd., Enfield, Middx.

"Valve Voltmeter Without Calibration Drift"

SINCE the publication of my article in the January issue, my attention has been drawn to Patent No. 636,212 granted to C. Morton. This patent is in respect of push-pull amplifiers in which the ratio of negative feedback to the two halves is critically variable, with the objects: (1) of compensating for any differences in the characteristics of the two halves and so balancing out residual zero instability; and (2) varying the performance by varying the load resistance.

Although my objects in devising the valve voltmeter circuit shown in my Fig. 4 were quite different (viz., to use so much negative feedback as to swamp zero instability without the need for an adjustment, and to make the output voltage equal to the input, regardless of load resistance), this circuit is formally very similar to one of those shown in Mr. Morton's specification.

The main difference between the two circuits is that in mine R_1 and R_2 are provided for eliminating any residual inequality between input and output voltages. Although these are not included in Mr. Morton's specification, by a suitable choice of values and by suitably varying their ratio, it would be possible to use them for the purpose that forms the main claim in the patent, which would then appear to cover the circuit I described. Provided, however, that there is no provision for varying the feedback ratio so as to obtain a critical balancing-out of zero instability, the valve voltmeter does not appear to come within the scope of the patent.

Before completing my article I made a lengthy search of valve voltmeter circuits, including the comprehensive compilation of American practice in the recent 2nd edition of Rider's "Vacuum-Tube Voltmeters," and found nothing similar to mine, until notified of Mr. Morton's patent. I understand, however, that a pH meter embodying the circuit in question (though operating in a substantially different manner from my valve voltmeter) is now manufactured by the Cambridge Instrument Company under this patent.

Bromley, Kent. M. G. SCROGGIE.

Aerial Propaganda

RECENT letters have been critical of suggested commercial advertising on British broadcasting. It seems possible, however, that the listening public would benefit if one example of Radio Luxembourg were followed by the B.B.C. Those who wish to hear that station properly are advised over the air to put up good outdoor aerials as a means of improving reception! A. G. CLARKE.

Longsight, Manchester.

"Why 47?"

REGARDING "Cathode Ray's" article on preferred values (February issue), I trust you will bear with me, but as I see it, if this system is established exactly as is described it can hardly be reliable.

If, for example, I require a resistor of 50 ohms ±20% and obtain instead one of 47 ohms ±20%, then any actual value from 37.6 to 40 ohms, which this nominal 47 may well be, is beyond the tolerance permitted by my desired value. The possibility of such an error must surely exist for any desired value to a greater or lesser extent—unless, of course, this value corresponds to a preferred value. It would appear, therefore, that for satisfaction at ±20% I must obtain the nearest preferred value at ±10%.

London, W.11. F. M. SPEECHLEY.

Pulse Testing

READERS of M. V. Callendar's article (your February issue) may be interested to know that "pulse" testing of television receivers was introduced as a production line test in this factory in 1949 when the first vestigial sideband receivers were produced. Since then this has been a standard production test for all television receivers.

I strongly support Mr. Callendar's assertion that a test of this nature can control the large variations in picture quality inevitable with normal alignment methods and ensure a far greater consistency in the performance of receivers.

I demonstrated equipment for pulse testing at the Television Society Exhibitions of 1949 and 1950 and at the lecture referred to in the article. E. A. F. MOSS.

Bush Radio, Ltd., London, W.4.

Radio Indiscipline

I SUPPOSE it is a sign of the times in which we live, in which we are motivated largely by "me first and blow you" sentiments, but I must confess that as one of the old hands going back to coherer days I am shocked at the indiscipline of present-day radio operators.

Recently, during a distress call off the East coast, the indiscriminate jamming by unnecessary calling was awful, but was far exceeded on Sunday, December 9, when there were three distresses at the same time in the North Sea and coast stations spent most of their time trying to enforce silence; most of their efforts were ignored. Two operators, after repeated warnings, were told "report for you" and several more were threatened.

I should hesitate to pick out any nationality worse than others on these occasions mentioned, for candidly there was little to choose, but it is to be hoped that some drastic action will be taken when the "reports" go in—they were deserved in every case. Wm. A. RICHARDSON.

Ashford, Kent.

"Trustworthy Valves"

WHEN a valve is no longer an expendable accessory but a component no more liable to failure than other components, and wired into position like any other components; then, surely, the last vestige of excuse for purchase tax would disappear. ROBERT C. BELL.

Ambleside, Westmorland.

Broadcasting Coverage

AS one of the unfortunate persons unable to receive an interference-free Home Service programme, may I plead for some action by the B.B.C. The "relay" stations at St. Leonards, and elsewhere, are no solution, except for those living within two miles' range of the stations.

I was under the impression that a re-allocation of frequencies within the United Kingdom was being considered and suggest that if the Brookman's Park and Start Point transmitters change frequencies a marked improvement would result. At the moment the West of England Home Service transmission fades too heavily to be of any programme value in East Sussex, and nothing can remove the 2-kc/s whistle from the Home Service transmission.

Meanwhile, I hope the Postmaster-General has not forgotten that we still await his decision on a.m./f.m., and ask that in the near future the Wrotham transmitters be operated for the benefit of the general public.

Sedlescombe, Sussex. P. A. COOMBES.

THE "BELLING-LEE" PAGE

Providing technical information, service and advice in relation to our products and the suppression of electrical interference

R.E.C.M.F. Exhibition

The Radio and Electronic Component Manufacturers Federation are once again holding their private exhibition at Grosvenor House, Park Lane, from the 7th to the 9th of April.

The majority of the invitations are sent to industrial technicians, consulting and practising engineers, technical bodies, the Supply Ministries, and the Services. We know that a large contingent of overseas visitors will also be present; the emphasis on export being particularly prominent this year.

We cordially invite any readers of this page who may be visiting the exhibition, to inspect our Stand No. 23.

Power and Field Strength

We hope that our readers who are situated in the South West, and in the area that will be served by Wenvoe, are taking an interest in what we write about Kirk o'Shotts. Practically the same problems arise prior to and immediately after the opening of each transmitter. But in general, people do not appear to take much interest until they are "next on the list." The Scots did not take much interest until Holme Moss began to reach



Graph showing approximate increase of field strength upon switching from 5 kW to 50 kW transmissions.

completion, then their enthusiasm became enormous. By the time you read this, Kirk o'Shotts will have been officially opened, and presumably on full power. i.e., increased in power from 5 to 50 kW. This does not mean that the signal will be ten times greater. The increase in field strength will be in the order of the square root of the power, something between three and four times.

"Multirods" and Gales

In the early part of the year two busy people found time to write and tell us about their "Multirods," which remained intact and weathered the storms which caused so much damage round our coasts. We cannot help feeling that the ability of the aerials to withstand such conditions has created a good impression.

"Multirod" 4-element array.

Mr. John Probert, of Redruth, Cornwall, a Radio Service Engineer, wrote and told us that at the Lizard Point the N.W. gale was recorded at 99 m.p.h. His location was even more exposed and he estimated the wind velocity to have been 110 m.p.h. Mr. Probert says "at 2 a.m. the experience of such a wind is a frightening thing." Locally the gale was considered as the worst for 26 years.

Mr. Wm. Johnson Jnr., a radio dealer in Lerwick, Shetland, wrote to tell us that his "Multirod" has stood up to the recent gales recorded at 106 m.p.h. His aerial stands very high on a flat roof and pointing out to sea in a S.S.W. direction.

Bell Interference on Buses.

This fact is important in many ways. For example, the bell circuits on the buses in Edinburgh are giving trouble. Edinburgh is twenty-odd miles from the transmitter, and bells do not generally give much trouble except under fringe reception conditions, it is our opinion, that those in buses operating in the city area could be left as they are until Kirk o'Shotts is on full power. Then, if they are still a nuisance, they should be dealt with. All vehicles likely to enter fringe areas should have suppressors fitted to all troublesome circuits.

A Statement of Fact

It has come to our notice by indirect means, that in Hebden Bridge a dealer has found that a "Doorod" indoor aerial gives best results against ghosts. The siting of the "Doorod" is very critical and slight movements to other locations in the house bring back the ghosts. This is just a statement of fact. It only confirms that anything is worth trying, but anybody suggesting that our famous "Doorod" should be sold or recommended as a layer of "ghosts" should have his brain tested. But we take our hats off to the dealer in question for persevering till he found something useful.

Would You Believe It?

A member of the public writes asking whether if he removes the directors from his "Multirod" aerial (thereby converting it to an "H") this will give him a better picture in black and white instead of brown!

Spring Cleaning?

No aerial will last for ever. All aerials will last longer if maintained regularly; a good time to do this is when the house is being painted and ladders are about.

Examine the aerial. Yes—and have it painted!

P.S.

Did you know? A motor car can seriously interfere with electronic research and television reception.

Fit a "Belling-Lee" suppressor L.1274 or L.630 to the distributor lead, does not affect engine performance and helps an industry

Written 28th February, 1952.

BELLING & LEE LTD

CAMBRIDGE ARTERIAL RD., ENFIELD, MIDDX., ENGLAND



NOW...

rectifier

for A.F. Second detectors.
A.G.C. rectifiers. Muting circuits.
Contrast expansion and compression.
Level indicators.
Modulation depth indicators.
Ringbridge modulators. Limiters.
Automatic frequency control.
Non-linear resistances.

Designed for input levels in excess of 0.5 Volts at frequencies below about 5 Mc/s., the SenTerCel TypeM-1 single element selenium rectifier measures only $\frac{1}{8}$ in. in thickness and $\frac{9}{32}$ in. in dia., and weighs only 0.015 oz. Efficient and inexpensive, the M-1 is the smallest rectifier so far produced; and, because in most cases it will replace a thermionic rectifier, the cost and complication of a valve base and associated wiring is also saved, and a source of heat removed.

AVERAGE CHARACTERISTICS	
Self Capacity	20 pf
Forward resistance at 5 V.D.C.	12 kΩ
Rev. resistance at 5 V.D.C.	20 MΩ
Max. peak inverse Voltage	50 V
Min A.C. input	0.5 V

Standard Telephones and Cables Limited

RECTIFIER DIVISION - WARWICK ROAD, BOREHAM WOOD, HERTS Elstree 2401 Telegrams SenTerCel Borehamwood

WORLD OF WIRELESS

This Year's Exhibitions • Experimental Television for Schools • International Standards • Marconi Memorial

Shows

THE date of the nineteenth National Radio Exhibition has been announced by the R.I. Council —August 26th to September 6th at Earls Court. Details are not yet available, but it is planned to organize it on similar lines to last year's show.

On April 7th the components show, organized by the Radio & Electronic Component Manufacturers' Federation, opens at Grosvenor House, Park Lane, London, W.1. The exhibition, to which admission is restricted to those who have a professional, industrial or trade interest in components, will be open from 11 to 6 on the 7th, 10 to 6 on the 8th and 10 to 5 on the 9th. Tickets are obtainable from the R.E.C.M.F., 22, Surrey Street, London, W.C.2.

A list of the fifty or so exhibitors at the Northern Radio Show, which opens at the City Hall, Manchester, at noon on April 23rd, is given elsewhere in this issue. The normal hours of the show, which closes on May 3rd, will be 11-10.

As was the case last year, the Physical Society's exhibition of scientific instruments and apparatus will overlap the R.E.C.M.F. Show; it will be held from April 3rd to 8th at the Imperial College of Science and the Huxley Building, South Kensington. Tickets, valid for specified days, are obtainable from the Society, 1, Lowther Gardens, Prince Consort Road, London, S.W.7. The exhibition opens daily at 10 a.m., but on the first day admission will be limited to members and the Press until 6. It closes at 9 on the 3rd, 4th and 7th and at 5 on the 5th and 8th.

New Television Stations

AS in the case of the Scottish station which opened on March 14th, the Welsh transmitter at Wenvoe (Cardiff) will initially operate on low power. The Asst. P.M.G. stated that it was hoped to open the station—using the standby vision (5-kW) and sound (2-kW) transmitters—in August. He said that it was too early to announce when the high-power transmitter would be completed. The station will operate in channel five (63.25 Mc/s sound, 66.75 Mc/s vision).

The 50-kW E.M.I. main transmitters for both the Kirk o' Shotts and Wenvoe stations employ low-level modulation. The main advantages of this principle are that it reduces the number of stages and the size of the transmitter, yet giving a substantial increase in its overall efficiency. The 12-kW sound transmitters for these stations are provided by Standard Telephones & Cables. The Wenvoe transmitter will be linked with the London studios by cable.

International Television

THE recent decision of the Belgian Government to adopt two standards of television, 819-lines (French) and 625 (Flemish), to facilitate the exchange of programmes with neighbouring countries, emphasizes the need — if it required emphasizing—for the adoption of an international standard.

Whilst it seems almost impossible to reach agreement internationally on the number of lines to be used—the latest figure suggested is 729!—it is noteworthy that the representatives at a recent meeting of the International Television Committee voiced their preference for standardizing the bandwidth at 7 Mc/s. The countries represented were Belgium, France, Germany, Italy, Netherlands, the U.K. and the Arab States. The U.K. representative on this committee, set up in 1947 to encourage international collaboration in the field of television techniques, was Dr. R. C. G. Williams, chief engineer, Philips Electrical.

Anglo-U.S. Scholarships

WITH the object of contributing to industrial productivity in this country, 75 scholarships are to be awarded this year by the Ministry of Education for the study of production in the United States.

Thirty-five of the awards will be tenable for one year (from September) for the study of production technology and will be open to students who hold good honours degrees in either pure science or technology. Applicants must have had at least two years' industrial experience and be at present working in industry or research associations or teaching. Applications must be received by April 16th. The remaining forty awards, open to persons between the ages of 23 and 35, are for the study of management, for which the closing date is April 30th.

Return passages to the United States will be met from public funds. Full details may be obtained from the Ministry of Education (F.E. Division 1), Curzon Street, London, W.1.

School Television

SIX schools in North London have been chosen to participate in the experimental transmission of television programmes for schools for four weeks beginning on May 5th. The vision signal will be radiated by one of the O.B. transmitters set up at Alexandra Palace using a frequency between 180 and 200 Mc/s. It will be necessary, therefore, for schools to be equipped with frequency converters, which will be provided by the B.B.C., to enable standard receivers to be used. To avoid the possibility of interference from the London station, receivers will operate on the Kirk o' Shotts' frequency (56.75 Mc/s). Sound will be conveyed to the schools by P.O. land line.

The choice of schools has been governed largely by the radiation pattern of the O.B. aerial to be used.

Standard Frequencies

THE American National Bureau of Standards wishes to have reports from users of the standard frequency transmission services conducted by stations WWV (Washington) and WWVH (Hawaii). Users are asked to complete a questionnaire from which it is hoped to obtain information helpful in increasing the usefulness of the service and to assist the C.C.I.R. in the study of the possibilities of providing a world-wide standard frequency and time signal service.

Dr. R. L. Smith-Rose, director of the Radio Research Station, Ditton Park, Slough, Bucks, is collecting reports originating in this country and copies of the questionnaire are obtainable from him.

Television Convention

CONTRARY to the usual practice of the I.E.E., attendance at the Convention on the British Contribution to Television (April 28th-May 3rd) is not confined to members of the Institution. The registration fee for the ten 2-hour technical sessions, which will cover the whole field of television "from studio to viewer" is 30s. A number of visits of technical interest have been arranged.

Radio Plaques

AS was anticipated, the London County Council has decided to waive its ruling not to erect a plaque until at least twenty years after the death of the celebrity they wish to honour in the case of Marconi, as they did recently for Baird. Within

the next few weeks a plaque with the wording "Guglielmo Marconi, 1874-1937, the pioneer of wireless communication, lived here in 1896-7" is to be erected on 71, Hereford Road, W.2.

Among the 200 or more already erected are plaques to Faraday (48, Blandford Street, W.1), Clerk Maxwell (16, Palace Gardens Terrace, W.8), and Baird (22, Frith Street, W.1).

A.P.A.E. Show

THE annual exhibition organized by the Association of Public Address Engineers will be held at the Horseshoe Hotel, Tottenham Court Road, London, W.1, on May 29th from 10 to 8. In addition to the exhibits of a number of manufacturers of sound recording and reproducing equipment, there will be a display of "ideas" used by members in their P.A. work for which prizes will be awarded.

Readers of *Wireless World* may obtain tickets gratis from the Secretary, Alex. J. Walker, 394, Northolt Road, South Harrow, Middx.

PERSONALITIES

Sir Ernest Fisk, who has been with Electric and Musical Industries, Ltd., since he came to this country from Australia in 1944, has resigned from the managing directorship of the company and the various offices he held in companies within the E.M.I. Group. For four years prior to going to the antipodes in 1910 he was with Marconi's. In 1913 he assisted in the formation of Amalgamated Wireless (Australasia), Ltd. (A.W.A.), of which he became chairman in 1937, the year he was knighted. Sir Ernest played a prominent part in antipodean radio and received the first direct transmission from this country to Australia in 1918.

Peter E. M. Sharp, A.C.G.I., B.Sc. (Eng.), A.M.I.E.E., who, since 1949, has been Industrial Officer (electronic equipment) with the Council of Industrial Design where he was responsible for the selection and organization of communications and electronic exhibits at the Festival of Britain, has joined the Commercial Department of the Telegraph Construction and Maintenance Co., Ltd. (Telcon), where he is specializing in communications cables and systems. Prior to joining the Council of Industrial Design he was responsible for the production of technical publications issued by Standard Telephones & Cables.

T. C. Macnamara, who on leaving the B.B.C. Planning & Installation Dept. (of which he was in charge) in 1950 joined the Board of Scophony-Baird, has resigned from the Board in order that he can devote himself exclusively to development work with High Definition Films, Ltd., of which he has been technical director since its formation last year, with the backing of Pye, Ltd., the J. Arthur Rank Organization and British Lion Films.

John Kier, who has been with Marconi's since 1915, when he joined the Company as a sea-going wireless operator, has been appointed assistant general manager of the marine group of companies—M.I.M.C. Co., Radio Communication Co., and Marconi Sounding Device Co. After serving as an instructor at Marconi House he held various head office appointments and in 1929 went to Brazil as managing director of the Companhia Nacional de Communicacoes Sem Fio, which later became

JOHN KEIR

the Companhia Marconi Brasileira. He returned to this country in 1946 and in 1951 became manager of the Service Division, for which he will still be responsible in his new post.

E. B. Rogers, manager of the Service Department of Mullard's Valve Division, recently completed his twenty-fifth year with the Company, and, to mark the occasion, he was presented with an inscribed clock and a cheque. He joined the Company as service manager and throughout has been responsible for testing and reporting on all returned valves and electron tubes. Mr. Rogers took a first-class P.M.G.'s Certificate in 1915, joined Siemens Brothers as a wireless operator and in 1918 became a wireless instructor at the Royal Naval Barracks, Chatham. He was an amateur transmitter (2WY) in 1919.

H. L. Oura, M.B.E., B.Sc., who has been appointed managing director of Acoustic Products, Ltd., of South Ruislip, Middx., joined E. K. Cole, Ltd., in 1946 to take charge of their Western Development Unit at Malmesbury, Wilts. Prior to that he was for many years with the Gramophone Company and was a director of E.M.I. Engineering & Development, Ltd.

C. A. Ingram, M.A. (Cantab.), who has been secretary of the Radio Section of the I.E.E. since 1947, has resigned to go to the Stanmore Research Laboratories of the G.E.C. He joined the I.E.E. editorial staff in 1946, prior to which he was a Naval radar officer.

D. M. Sheil-Small, general manager of Alfred Imhof, Ltd., has been appointed a director of the company. For the last ten years he has been concerned with the development of the company's engineering interests.

C. H. Davis, Assoc. I.E.E., who recently became sales manager of the Electronic Engineering Dept. of Hallam, Sleigh & Cheston, Ltd. (Birmingham), will operate from the company's new London office at 299, New King's Road, Fulham, S.W.6. He has been sales agent for the company since 1946, prior to which he was, for three years, employed as a technical officer in the Admiralty Signal Establishment.

G. Darnley-Smith, who is managing director of Bush Radio, Ltd., and Cinema-Television, Ltd., has been elected chairman of the Radio Industry Council in succession to **J. W. Ridgeway,** director of Edison Swan, Ltd., and manager of the company's Radio Division. Mr. Darnley-Smith was chairman of the R.I.C. in 1947 and was vice-chairman last year. He has been chairman of the Industry Television Policy Committee since its formation in 1948.

G. A. Marriott, B.A., is the new vice-chairman of the R.I. Council. He is manager of the valves and electronic devices department of the G.E.C. and a director of the Marconi-Osram Valve Co. He is also chairman of the British Radio Valve Manufacturers' Association (B.V.A.).

P. H. Spagnoletti, B.A., M.I.E.E., who is director and general manager of Kolster-Brandes, Ltd., and manager of the Brimar Valve Works of Standard Telephones & Cables and **E. K. Balcombe,** managing director of A. J. Balcombe, Ltd., were re-elected chairman and vice-chairman respectively of the British Radio Equipment Manufacturers' Association (B.R.E.M.A.).

K. S. Davies, B.Sc., A.M.I.E.E., this year's chairman of the Radio Communication and Electronic Engineering Association (R.C.E.E.A.), was recently appointed to the new executive post of director of engineering created by Murphy Radio "to bring into closer relationship all the radio engineering and production activities" of the company. He joined Murphy's in 1933 and since the war has been general manager of the electronics division. He was previously with Standard Telephones and Cables.

C. G. White, director and general manager of the marine division of Kelvin and Hughes, is the new vice-chairman of R.C.E.E.A.

T. Somerville, co-author of the article "Orchestral Studio Design" in this issue, graduated from Glasgow University and joined the B.B.C. in 1929. From that date till 1942 he was concerned with field strength and propagation measurements, becoming head of the section devoted to this in 1936. In 1942 he transferred to the Design and Installation Department of the Corporation, where he stayed for a year with the recording section. He was then put in charge of the recording section of the Research Department. The a.f. and acoustics sections also subsequently came under his charge.

H. R. Humphreys, who, with T. Somerville, contributes the article "Orchestral Studio Design," joined the B.B.C. in 1949 as architect concerned with all acoustic design and treatment of studios. He was doing research work on acoustics and sound insulation at the Building Research Station of D.S.I.R. for four years prior to joining the B.B.C. and from 1931 until 1945 was with E.M.I. as a technical writer.

J. B. Lovell Foot, contributor of the article "1400 Mc/s Radiophone" in this issue, joined the Radio Group of the G.E.C. Research Laboratories in 1928, after completing a course in electrical engineering at University College, Southampton. Before the 1939-45 war, he was engaged in the early work on v.h.f. equipment, and has had a wide experience in the development of radio transmitters and receivers.

Prof. E. W. Marchant, who writes on "Pre-Heaviside Propagation Theories" in this issue, has been at Liverpool University, of which he is now Emeritus Professor of Electrical Engineering, since 1901. He graduated B.Sc. from London University with honours in physics and mathematics. Prior to going to Liverpool, Dr. Marchant was chief assistant at the Finsbury Technical College under the late Prof. Sylvanus P. Thompson. He was closely associated with Duddell in the development of the oscillograph.

John A. Howie, who contributes the article on Indian radio manufacture in this issue, graduated B.Sc. (Hons.) in chemistry and physics from University College, Southampton, in 1933. He joined E.M.I. in 1936 and was engaged on the selection, specification and processing of all the materials used in radio manufacture. For three years prior to leaving E.M.I. in 1943 he was Assembly Factory manager. Mr. Howie joined E. K. Cole, Ltd., in 1943 to assist in the re-occupation of the Company's Southend factory which had been partially closed since 1940. In 1946 he took charge of the shadow factory at Rutherglen, Lanarkshire, and converted it for the production of car sets and electrical equipment. From 1949 until January this year he has been resident director and general manager of National-Ekco, Bombay.

OBITUARY

Lord Marley, who died on February 29th at the age of 67, made wireless telegraphy his speciality during his Naval career. Dudley Aman, who was created a baron in 1930, was at one time on the staff of the late Admiral Sir Henry Jackson, and, before retiring from the Service, was attached to the Royal Signal School, Portsmouth.

Edmund T. Flewelling, inventor of the super-regenerative circuit bearing his name (sometimes spelt Flewellyn), died in Massachusetts on December 30th. His single-valve super-regenerator obtains its quenching action by the choice of grid resistor and capacitor and by tightening the reaction coupling to cause squegging. In recent years Mr. Flewelling turned his attention to electro-acoustics, on which he contributed a number of articles to the American Press.

IN BRIEF

Television Tasting of scenes for films is in use at the Elstree studios of Associated British Pictures, where, with the aid of Marconi equipment, film executives and technicians will now be able to see on large screens rehearsals taking place in adjacent studios and more readily assess the value of a production.

Silver Jubilee of the Television Society, founded in 1927 "for the furtherance of study and research in television and allied problems," will be marked by a dinner at the Waldorf Hotel, Aldwych, London, on April 25th.

American Marconi Memorial.—A bust of Marconi was unveiled by Marchesa Marconi in the studios of KDKA, Pittsburgh, at the conclusion of a series of broadcasts commemorating the first transatlantic transmission.

Australian Amateur Activities.—During the Jubilee Royal Adelaide Exhibition, being held from March to May, the South Australian Division of the Wireless Institute of Australia will maintain a transmitter on the 7- and 14-Mc/s bands. Special commemorative QSL cards are being used to acknowledge reports.

V.H.F. for the "Queens"?—Anthony Fell, M.P., chairman of Rees Mace, announced recently that his company (the marine offshoot of Pye) had put up a scheme to install a v.h.f. radio-telephone system for the use of passengers on the *Queen Mary* and *Queen Elizabeth* when the ships were approaching Southampton. Mr. Fell stated that, largely because the Post Office had as yet done nothing about suitable v.h.f. shore stations, it was not possible for this offer to be taken up.

Electronics Summer School.—A series of lectures intended to show "both the designer and the user of electronic equipment how far engineering problems are circumscribed by physical laws", has been arranged for the Summer School on Electronics organized by the Dept. of Electrical Engineering, Birmingham University. The tuition fee for the course (July 14th—19th), which is intended for engineers and others of university degree or similar standing in electrical technology, is £2.

Television is among the fifteen specialist subjects covered by courses to be held in this country for overseas students under the auspices of the British Council. The course, which will be run from September 21st to October 4th, is designed for senior radio engineers. Details are obtainable from the British Council's offices in this country and overseas.

E.M.I. Employees' Successes.—Two junior employees of E.M.I. Engineering Development have achieved distinction in the Higher National Certificate examination in Electrical Engineering. The Page Prize, awarded by the I.E.E. to the best candidate in the country who obtains distinctions in all the compulsory subjects of the final year of the Higher National Certificate in Electrical Engineering, has been given to E. R. Robson, who is engaged on transformer design work. D. H. Pentelow, who is concerned with the design of test gear, has been awarded an Institution Prize by the I.E.E. for outstanding merit in the H.N.C. final year.

British Marine Radar equipment is fitted in over 800 foreign ships in addition to 1,400 or more British ships. Some 200 of the latter are still using the ex-Naval Type 268 set.

B.S.R.A. has accepted the invitation to become an "institution in union" with the Royal Society of Arts which has power to extend such invitations "provided that the primary object of such learned bodies is the promotion of arts, manufactures or commerce." The annual dinner, convention and exhibition of the Association will be held at the Waldorf Hotel, Aldwych, London, W.C.2, during the week-end May 16th-18th.

Information Theory in the field of telecommunications is the subject of a symposium which it is planned to hold at the Institution of Electrical Engineers in September. Offers of papers from both this country and abroad will be welcomed by Professor Willis Jackson, Electrical Engineering Dept., Imperial College, London, S.W.1, from whom copies of the preliminary programme may be obtained.

Electronics in Atomic Research.—Physicists and engineers who wish to obtain specialized knowledge of electronic instruments used in nuclear physics, radiochemistry and work with radioisotopes, are being offered a week's course at the Atomic Energy Research Establishment, Harwell (May 19th-23rd). Applications for admission to the course, for which the fee is 12 gns. plus 6gns for meals, accommodation and transport, should be made to the Electronics Division, A.E.R.E., Harwell, Didcot, Berks.

Soviet Standard Sets.—All broadcast receivers produced in the U.S.S.R. after January 1st will conform to the specification of the State Standard Receiver issued by the Council of Ministers of the U.S.S.R. It is learned from the *Bulletin* of the International Broadcasting Organization that there are four categories of receiver graded, so far as mains sets are concerned, according to the maximum undistorted power output.

Radio Facilities.—A new edition of the Radio Facility Charts has been issued by the Ministry of Civil Aviation showing the full Airways System for the U.K. including the radio navigational aids. Each of the eight sheets costs 3d.

Mechanical Handling.—The third exhibition and convention devoted to mechanical handling is to be held at Olympia from June 4th to 14th. Tickets



BUSINESS RADIO. Interior of one of the mobile stations used by Marconi's to carry out a survey for prospective users of v.h.f. business radio. The equipment shown in this "headquarters station" includes five- and ten-watt transmitter receivers on the bench and a rack-mounted fifty-watt transmitter.

for the exhibition are obtainable from the organizers, the Associated Iliffe Press, Dorset House, Stamford Street, London, S.E.1. Tickets for the convention will be obtainable at the exhibition only.

INDUSTRIAL NEWS

B.R.E.M.A.—At the annual general meeting of the British Radio Equipment Manufacturers' Association the following member firms were elected to the Council (the representative's name is in brackets):— A. J. Balcombe (E. K. Balcombe), Bush Radio (G. Darnley-Smith), E. K. Cole (G. W. Godfrey), A. C. Cossor (J. H. Williams), G.E.C. (M. M. Macqueen), Gramophone Co. (F. W. Perks), Kolster-Brandes (P. H. Spagnoletti), McMichael Radio (C. G. Allen), Philips (A. L. Sutherland), Pilot Radio (H. L. Levy), Pye (C. A. W. Harmer) and Ultra Electric (E. E. Rosen).

A Record number of receivers and chassis (590,000) were exported from this country last year, it was stated at the annual meeting of B.R.E.M.A.

Emitron Valves and cathode-ray tubes are now recognized as officially branded B.V.A. products. The makers, Electronic Tubes, Ltd., have just issued a list which shows several complete receiving ranges and gives characteristics, base connections and prices.

Radar Scanners.—It is announced in the annual report of Marconi's W.T. Co. that the company has acquired Scanners, Ltd., of Gateshead-on-Tyne, who are engaged on the design and manufacture of radar scanning equipment.

Pye in Italy.—An agreement has been completed between Pye, Ltd., of Cambridge and Radio Minerva, of Milan, for the manufacture of Pye television receivers under licence in Italy.

Racal, Ltd., formed just over a year ago to provide an aeronautical and radio consulting service, with offices at 41, Kingsway, London, W.C.2, have issued a duplicated news sheet, "Racal Review." In it details are given of the parent company and the subsidiaries, Racal Engineering, Ltd., Canadian Aviation Electronics (Overseas), Ltd., and Racal (Canada), Ltd. The chief engineer of Racal Engineering, which has a factory at 274, Worton Road, Isleworth, Middx, is D. A. Webb, who was, until recently, with the Ministry of Civil Aviation.

H. J. Enthoven & Sons hope to have the new section of their "Superspeed" resin-cored solder factory at Croydon open early this month. The new plant will provide for the production of cored ribbon solder, coloured-cored solder and various fluxes as well as the normal resin-cored wire solder.

Marconi's are to supply two 100-kW air-cooled transmitters, with paralleling equipment providing an output of 200 kW, for installation at Kalundborg for the Danish broadcasting service. The company is also equipping the Omdurman (Khartoum) broadcasting station with a 50-kW transmitter.

Plessey Co. announce that H. T. Parker is undertaking a detailed marketing survey for the Plessey group in Australasia and will return via Canada and the U.S.A. He left on February 20th and will be away about six months.

Rees Mace, the marine subsidiary of Pye, are to fit three of the Tate and Lyle sugar ships with Pye PTC 115 radio-telephone sets in order that the crews can avail themselves of the G.P.O. Thames radio-telephone service.

A. H. Hunt (Capacitors), Ltd., have reorganized their sales section. R. C. W. Clarke is now responsible for Government contracts, O. G. Cox and E. A. Benwell (hitherto technical sales representatives in the Radio, Electronic and Industrial Division) become joint sales managers of the division, while John Moor continues as sales manager of the section dealing with the wholesale and retail service trade.

Taylor Electrical Instruments announce the reintroduction of their Model 130A insulation tester, which has two ranges, 200kΩ-1,000MΩ (500V max) and 20Ω-100kΩ (50mV max).

Multicore.—All correspondence for Multicore Solders, Ltd., should now be sent to the company's new premises, Multicore Works, Maylands Avenue, Hemel Hempstead, Herts (Tel.: Boxmoor 3636). The office at Mellier House, Albemarle Street, London, W.1 (Tel.: Regent 1411), is being retained for executive purposes only.

Radio Heaters, Ltd., of Wokingham, Berks, manufacturers of Radyne industrial radio heating equipment, have opened a London office at 46, Gray's Inn Road, London, W.C.1 (Tel.: Chancery 8354).

Kolster-Brandes have opened a distribution and service depot at 87, McAlpine Street, Glasgow, C.3 (Tel.: Central 1779). Although both television and broadcast receivers are stocked, only television sets will be serviced.

MEETINGS

Institution of Electrical Engineers

Radio Section.—Symposium of papers on micro-wave links at 5.30 on April 9th.

Convention on "The British Contribution to Television" from April 28th to May 3rd.

The above will be held at the I.E.E., Savoy Place, London, W.C.2.

Cambridge Radio Group.—"Radio Astronomy" by K. E. Machin, M.A., at 8.15 on April 1st at the Cavendish Laboratory, Cambridge.

Mersey & North Wales Centre.—Discussion on "Should Broadcasting be Superseded by Wire Distribution?"; opener, P. P. Eckersley at 6.30 on April 3rd at the Liverpool Royal Institution, Colquitt Street, Liverpool.

North Midland Centre.—"The Sutton Coldfield Television Broadcasting Station" by P. A. T. Bevan, B.Sc., and H. Page, M.Sc., at 6.30 on April 1st at 1, Whitehall Road, Leeds, 1.

North-Western Radio Group.—"High-Gain D.C. Amplifiers" by W. Kandiah and D. E. Brown at 6.15 on April 2nd at the Engineers' Club, Albert Square, Manchester.

Scottish Centre.—Faraday Lecture on "Sound Recording—Home, Professional, Industrial, and Scientific Applications" by G. F. Dutton, Ph.D., B.Sc. (Eng.), at 7.0 on April 22nd at the Royal Technical College, Glasgow.

North-East Scotland Sub-Centre.—Faraday Lecture (see above) at 7.30 on April 24th at the Music Hall, Aberdeen.

South Midland Centre.—Discussion on "The Position of the Cathode Ray Oscillograph in Electrical Engineering"; opener, W. Wilson, D.Sc., B.Eng., at 6.30 on April 7th at the James Watt Memorial Institute, Birmingham.

South Midland Radio Group.—"Radar Sonde" by F. E. Jones, Ph.D., B.Sc., at 6.0 on April 28th at the James Watt Memorial Institute, Great Charles Street, Birmingham.

Southern Centre.—Faraday Lecture on "Sound Recording" by G. F. Dutton, Ph.D., B.Sc.(Eng.), at 6.30 on April 7th at the Guildhall, Southampton.

British Institution of Radio Engineers

London Section.—Discussion on "V.H.F. and U.H.F. Broadcasting"; opener, P. Adorian (president), on April 3rd.

"Current Radio Interference Problems" by E. M. Lee, B.Sc., on April 16th.

Both meetings will be held at 6.30 at the London School of Hygiene and Tropical Medicine, Keppel Street, Gower Street, London, W.C.1.

North Eastern Section.—"V.H.F. Broadcasting: the Case for Amplitude Modulation" by J. R. Brinkley at 6.0 on April 9th at Neville Hall, Westgate Street, Newcastle-upon-Tyne.

South Midlands Section.—"Acoustics and the Radio Engineer" by E. G. Richardson, B.A., Ph.D., D.Sc., at 7.15 on April 16th at the Winter Gardens, Malvern; also at 7.15 on April 17th at the Exhibition Galleries, Public Library, Rugby.

North Western Section.—"V.H.F. Broadcasting: the Case for Amplitude Modulation" by J. R. Brinkley at 7.15 on April 30th at Reynolds Hall, College of Technology, Manchester.

British Sound Recording Association

London.—Discussion "Fact and Fancy; with particular reference to present-day gramophone records" at 7.0 on April 18th at the Royal Society of Arts, Adelphi, London, W.C.2.

Manchester.—Inaugural meeting of the Manchester Centre at 6.0 on April 24th at the Engineers' Club, Albert Square, Manchester, 2.

Institution of Electronics

North-Western Branch.—Lecture on "Pumps and Vacuum Technique" by D. Latham, B.Sc. (W. Edwards & Co.), at 7.0 on April 18th at the College of Technology, Manchester.

Television Society

London.—"A New Television Recording Camera" by W. D. Kemp, B.Sc. (B.B.C.), at 6.45 on April 2nd at Film House, Wardour Street, London, W.1. (Joint meeting with the British Kinematograph Society.)

Radar Association

"Projection Television Receivers for 4ft × 3ft Screen" by V. Valchera (Valradio) at 8.0 on April 1st at the Bedford Corner Hotel, Tottenham Court Road, London, W.C.1.

Society of Relay Engineers

"Cable for Television Relay Systems" by H. J. Dixon and J. D. S. Hinchcliffe (B. I. Callender's) at 2.30 on April 29th at 21, Bloomsbury Street, London, W.C.1.

Institute of Practical Radio Engineers

Thames Valley Branch.—Discussion on service problems at 8.0 on April 1st at the Wheatsheaf Hotel, Kingston Market Place, Kingston-on-Thames, Surrey.

FOUR-WAY ELECTRONIC MIXER



This unit has 4 built-in, balanced and screened microphone transformers, normally of 15-30 ohms impedance. It has 5 valves and selenium rectifier supplied by its own built-in screened power pack: consumption, 20 watts.

Suitable for recording and dubbing, or large P.A. installations since it will drive up to six of our 50 watt amplifiers, whose base dimensions it matches. The standard model has an output impedance of 20,000 ohms or less, and any impedance can be supplied to order.

Manufactured by:

VORTEXION LIMITED

257-263, THE BROADWAY, WIMBLEDON
LONDON, S.W.19

Telephones : LIBerty 2814 & 6242-3

Telegrams : "Vortexion, Wimble, London."

"Why will the deep-toned vessel with contracted mouth have a much deeper and lower sound in its percussion when it has a narrow mouth than when it is wide?"
Leonardo Da Vinci. 15th century.
The New Vessel of Radio
LYRIC

These exquisite models are scientifically designed and constructed by the 'Sculptured Sound' laminated process, blending richness of appearance with maximum acoustic efficiency . . . Available in Modern and Antique finishes . . . A departure from the orthodox veneered wooden cabinet at no greater cost.

THE LYRIC

The ideal bass reflex or infinite baffle corner piece. Will house single or twin speakers. 37 ins. high. 33 ins. wide. approx. 7 cubic ft. With or without speakers.

THE DORIC

A companion piece to the Lyric for housing equipment. This highly convertible cabinet can be used as ● Televisor ● Radio-Gram ● Bass Reflex, supplied with or without speakers. 37 ins. high. 22 ins. wide. 15 ins. deep.

Write for Free Illustrated Brochure and sample finishes.

Sculptured Sound

SALI LTD., ST. LEONARD'S ROAD, WINDSOR, BERKS.

Pre-Heaviside Propagation Theories

By E. W. MARCHANT, D.Sc., F.C.G.I., Hon.M.I.E.E.

Early Attempts to Explain Long-Distance Transmission

WHEN Marconi made his classic transatlantic experiment in December 1901 and received on a kite aerial in Newfoundland the "S's" sent out by the 12-kW transmitter at Poldhu in Cornwall, a good many scientific people were very sceptical about the signals having actually come through. They knew that there was a mountain of water 160 miles high between the transmitter and the receiver and could not believe that, since wireless waves travel in straight lines like light, they could have climbed over the top of this mountain.

At that time I had the good fortune to see a good deal of Lord Kelvin, and even he was among the sceptics. Marconi was regarded with considerable suspicion by many professional physicists, because he tried experiments which seemed bound to fail. Today everyone agrees that it was his persistence in the face of much criticism that led to the rapid development of wireless. He was convinced that it would be possible to send signals by wireless all over the world, though he did not know how it would be done. He did not bother about theory but made his transatlantic tests to show that he was right.

As soon as long-distance wireless had been demonstrated, scientists began to work out theories to explain it. The strength of signal that was to be expected if diffraction was responsible was worked out very completely by Professor Watson, a pure mathematician at Birmingham University. He showed that this could not be the explanation, as the signals were many times as strong as they were calculated to be on this theory.

It had been found in the South African war that wireless was very limited in its range over the dry and arid soil of many parts of South Africa. The signals received from a transmitter in South Africa were much weaker than those received at the same distance from the same transmitter in England, and very much weaker than those received over the same distance over sea. The use of aerials that were not conspicious, but arranged in troughs cut in the ground, had been studied intensively in Germany just before the outbreak of the 1914-18 war, and Sommerfeld had worked out a theory of transmission by earth currents, but this also had been shown to provide a very inadequate explanation of the effects observed.

In a paper to the Royal Society W. Eccles had calculated the effect of ionization on the velocity of transmission of electromagnetic waves through a medium, and had shown that the velocity was greater in such a medium than in one that was not ionized. If ionization increased with increasing height above the earth's surface, this phenomenon would explain the bending or refraction of the waves round the curvature of the earth. From 1912 to 1914 a number of measurements were made in Liverpool of signals sent out from the Eiffel Tower through the kindness of General Ferrié, who was in charge of the wireless transmitting station. These were described in a paper before the Institution of Electrical Engineers in London and a very interesting discussion was provoked. The suggestion that some of the variations were due to reflection from clouds of ionized atmosphere was made and the effects described were explainable on this theory.

It is difficult to determine the first published suggestion that there existed a layer of ionized atmosphere in the upper regions, now known as the Heaviside Layer. Oliver Heaviside had a brother who was in the Post Office Telegraph service and there is no doubt that they must often have discussed the transatlantic transmissions that were of absorbing interest to all at work on the transmission of telegraph messages, and it is very fitting that the name of Heaviside should have been given to the layer which is now generally accepted as the explanation of long-range wireless.

In about 1916 I wrote a paper for the Radio Society of America showing how multiple reflection from the earth and the Heaviside layer could explain transmission over very long distances, and that the waves were more likely to be transmitted better over sea than land. It was Appleton, however, who determined the actual height of the layer from which the reflection came, by varying the wavelength of the transmitter and measuring the corresponding change in the strength of the signals received at a place sixty or seventy miles away. At such a distance the waves will travel directly, and also by reflection from the Heaviside Layer. The received signal is made up of the combination of the two. If these two waves arrive in phase the signal will be strong, if 180° out of phase, they will be weak. The difference in the lengths of the two paths can thus be easily calculated from the wavelengths corresponding to maximum and minimum strength, and the height of the reflecting layer estimated. It was by measurements of this kind that Appleton discovered the Appleton Layer above the Heaviside Layer. There may be other layers which have different effects on waves of different wavelengths.

EDUCATIONAL MATERIAL

TEACHERS and instructors in electronics will welcome the introduction of an educational service by Mullard providing a regular supply of information on recent developments in, and applications of, electronics enabling them to relate theory to practice. The recently instituted Mullard Educational Service provides registered teachers with technical publications, film strips, wall charts, assistance to individual instructors, and instructional and work sheets for class use.

Particulars are obtainable from the Technical Publications Dept., Century House, Shaftesbury Avenue, London, W.C.2.

DUALS

By "CATHODE RAY"

Two Formulas for the Price of One

NO; it is not a misprint, nor am I proposing to order pistols for two. Duals are not duels, though both are two-party relationships. The punctilious gentleman of chivalry wouldn't have a clue when it came to a dual. For it is really a mathematical concept, and the reason I have raised the matter now is to warn you that what has until recently been a rather highbrow preserve is likely to be all over the place before very much longer.

It is because of transistors. These, as most readers probably know by now, are germanium crystal triodes. Germanium diodes have been in commercial production for some time; most current television models contain several, replacing thermionic diodes. They need no heater supply or valve holder, they are smaller and lighter and less breakable, and their capacitance is exceptionally low. In due course, just as De Forest vastly extended the usefulness of the Fleming diode by putting a third electrode into it to make a triode, so two Bell Telephone research workers did the same with a germanium crystal and (presumably after a lot of messing about) found that it worked. We have heard about transistors from time to time, and seen them in scientific exhibitions, and have been warned that they are not suddenly going to supersede thermionic valves and that it may be a long time before they can be used commercially. But while it is wise for a firm hand to be kept on the information brake in case some lay journalist gets out of control, and although it is true that any transistor one has heard about yet is far behind thermionic valves as regards noise (to mention one thing), some of the recent disclosures indicate that transistors are going to make quite a hit, and probably earlier than the remote future. In particular, the junction type, in which the contacts are between whole layers of germanium having different impurities, instead of the point-contact arrangement reminiscent of the old crystal and cat-whisker, really deserves the description "sensational." Some while ago Dr. W. Shockley (who might be called the father of the transistor) demonstrated a complete oscillator no larger than a lump of sugar, drawing so little power that the watt-hour capacity of an ordinary l.t. accumulator cell would be enough to run it continuously for about 500 years!



Fig. 1. In parallel circuits such as this the dual form of Ohm's Law—with conductances instead of resistances, and current and voltage interchanged—is more convenient.

Although transistors resemble thermionic valves in many ways, including their ability to amplify and oscillate, in some respects they are different and even opposite. For one thing, instead of having a very high input resistance and low output resistance, the input is lower than the output. Instead of having grid bias voltage they have grid bias current—except that the "grid" is called the emitter. All this is very frustrating for people who have been brought up on valves. They—we—I have become so used to the way valves work and the kinds of circuits that get the best out of them that it is difficult to turn all this technique upside down and inside out—worse than having to draw a pattern while looking at it in a mirror. It was reassuring to find that it is not only dopes like me who experience this difficulty with transistors; even the bright research boys were not getting on too well with it until they thought of duality.

It would be possible, of course, to work out the principles of transistor circuit design from the start, as a fresh subject, just as was done with valves. But look at all the years that has taken. And even if it is agreed that designers have had their wits sharpened a good deal since then, and that many more of them are on the job, you must set against that this upsetting effect of trained habit. The more practised one is in valve circuit design, the greater the mental effort needed to change over to transistors.

That is where duality comes in. Like other mathematical devices, it doesn't create new knowledge. But it does reduce the effort required to dig knowledge out from the facts one has. Duality is really a systematic analogy. You know how analogies are often used to try to make things clearer. Sometimes they only make confusion worse confounded. But most learners do feel a little comforted when an invisible and rather abstract idea like electrical potential is presented to them with the aid of an analogy—height above sea level. Seeing and knowing the effects of height above sea level on the flow of liquids through pipes, they can visualize better what electric currents do. The danger of analogies such as this is that they are not perfect. They break down in places. For example, resistance to the flow of water in a pipe is not inversely proportional to its cross-section area, as is the resistance to the flow of electricity in a conductor.

In duality the analogy is perfect. Knowing it to be perfect, and knowing the relationships between one set of things, we can find the relationships between the other set of things—their duals—merely by substituting the appropriate symbols. For instance, there is duality between certain mechanical and electrical systems; the dual of electrical resistance is mechanical resistance, that of inductance is mass, that of capacitance is the reciprocal of elasticity, that of current is velocity; and so on. And the very people who, as students, probably gained their first ideas of electricity from what they already knew about springs and flywheels often make so much progress with electrical laws and relationships that they carry some of it back into mechanics. The behaviour of electrical circuit arrangements has been so thoroughly studied and worked out into equations that it is sometimes easiest to tell how a given mechanical system will behave by translating its measurements into mechanical ohms, henries, etc., and then applying the known

electrical equations and methods of analysis and calculation. This is particularly useful in mechanical systems that are closely interlinked with electrical systems, such as loud speakers and gramophone pickups.

But there are duals within the electrical camp itself. Here are some of them in parallel columns :

Current, I	Voltage, V or E
Resistance, R	Conductance, G (=1/R)
Inductance, L	Capacitance, C
Reactance, X	Susceptance, B
Impedance, Z	Admittance, Y
Series Connection	Parallel connection

For every relationship established between any of these, a dual relationship can be discovered by substituting the symbols in the other column. The most obvious example is Ohm's Law, which can be expressed in symbols as :

$$E = IR$$

Substituting the symbols in the opposite column we get :

$$I = EG$$

which is also true, and is sometimes more useful ; for example, with parallel circuits. Ohm's Law in its usual form is not at all well adapted for finding the current I in the Fig. 1 circuit. The extension $I = E/(R_1+R_2+R_3)$ is no good, because it applies only to resistances in series. But since the dual of a series connection is a parallel connection, the dual equation can be adapted directly as $I = E(G_1+G_2+G_3)$. To find the total current one just adds up the conductances of the parallel branches and multiplies them by the applied voltage.

And so with inductance and capacitance. Suppose one has got the length of finding that the voltage across an inductance can be calculated from :

$$E = 2\pi fLI$$

Then there would be no need to start from the beginning to find the corresponding equation for capacitance. Making use of dualism converts the inductance formula into :

$$I = 2\pi fCE$$

I suggest that this dualism is a useful tip for aiding the memory, and for checking formulae against one another. But in the more elaborate circuits a little care is needed.

Fig. 2 is a slight advance in complexity. If E in (a) is kept constant while its frequency is varied through resonance, I increases to infinity at the peak of resonance and then descends on the other side. Correspondingly, in (b), if I is kept constant, E at resonance must be infinitely great. We can fill in the analogy in detail. The total reactance in (a) is :

$$X = 2\pi fL - \frac{1}{2\pi fC} = \omega L - \frac{1}{\omega C}$$

Because inductive and capacitive reactances work in opposition, the total is the *difference*, not the sum. That is a fact of Nature. But to pick on capacitive reactance as the negative one is merely a convention. However, having done so, we must stick to it through thick and thin.

The dual of the above reactance equation is the susceptance equation for the dual circuit arrangement (b) :

$$B = \omega C - \frac{1}{\omega L}$$

Because inductance is the dual of capacitance, the convention that capacitive reactance is negative leads to inductive susceptance being negative and capacitive susceptance positive. Dualland is upside-down in other ways. To see how, consider both of these circuits when the frequency is, say, *above* resonance. That makes ωL greater than $1/\omega C$, so the net reactance in (a) is inductive, or positive ; and as regards phase the voltage leads the current. But in (b) the fact that the inductive reactance is the greater means that its effectiveness as a current path—its susceptance—is less, and its current is more than cancelled out in the main circuit by what goes through C. So the circuit as a whole is capacitive and the current leads the voltage.

This Fig. 2 circuit with its infinite current or voltage is of course quite unreal, but it can be elaborated into something resembling a practical tuned circuit (Fig. 3(a)) by inserting resistance R in series with C and L.

The formula for series impedance :

$$Z = \sqrt{R^2 + \left(\omega L - \frac{1}{\omega C}\right)^2}$$

can at once be converted by dualism into the one for parallel admittance (b) :

$$Y = \sqrt{G^2 + \left(\omega C - \frac{1}{\omega L}\right)^2}$$

And of course the dual of $E = IZ$ is $I = EY$. At resonance, Fig. 3(a) behaves as if C and L were



Fig. 2. The dual of (a) — a series circuit, shown with its current resonance curve — is (b), a parallel resonant circuit with a voltage resonance curve.



Fig. 3. More practical tuned circuits, with resistance in (a) and conductance in (b) to represent the losses.

short circuited, leaving only R ; and the dual of a short circuit is an open circuit, so (b) behaves as if L and C were removed, leaving G, which is the reciprocal of the dynamic resistance.

Duals and Equivalent Circuits

It is necessary to guard against a possible misunderstanding. The symbols I have used are simply to distinguish one circuit parameter from another—inductance from resistance, and so on. They are *not* intended to mean that L in Fig. 3(b) necessarily has the same value as L in Fig. 3(a) ; still less that G in (b) is 1/R in (a). The risk of confusion might exist if one happened to have in mind the fact that it is possible to find values for L, C and G in (b) which *at any one frequency* would make this circuit behave towards the generator exactly the same as (a); but these values are not the same as those in (a). In other words, this duality device, which enables a formula for one type of circuit to be derived at once from that for the dually related one, must be kept quite distinct in the mind from the equivalent-circuit device, which enables one circuit arrangement to be substituted for another without affecting whatever it is connected to, provided that suitable component values are chosen for each frequency.



Fig. 4. Generator circuits equivalent to a valve ; (a) constant voltage ; (b) constant current.



Fig. 5. These two arrangements, illustrating Kirchhoff's two laws, are duals of one another.

Fig. 6. These two main types of filter circuit, T and π are particular examples of Fig. 5.

The next example is one I have discussed before,* and the fact that it was in connection with circuit equivalents does not really contradict what I have just said, because any circuit has equivalents. Fig. 4(a) is the well known "valve equivalent circuit" or "equivalent generator," and (b) is a generally less well-known variety. But that is by the way ; the feature I want to point out just now is that they are duals of one another. (a) is a constant-voltage generator, with the anode resistance of the valve in series. (b) is a constant-current generator, with the anode conductance ($1/r_a$, or g_m/μ) in parallel. Representing this constant-current generator by the same symbol as the generator in (a) would tend to suggest that its internal resistance was zero and might make one wonder how there could be any voltage across it, whereas actually one has to imagine that its resistance is infinite. To overcome this difficulty, the dotted arrow symbol has been suggested in America.

Either (a) or (b) can be used to calculate what one gets out of a valve when a given load is connected to the output terminals ; but (a) is particularly suitable for finding the current through a given load impedance connected to a triode and (b) the voltage across a load admittance connected to a pentode (for a pentode with its very high internal resistance is nearly a constant-current generator). In the first arrangement r_a must be added to the load impedance to find the total impedance through which E drives the current, and in the second g_a must be added to the load admittance to find the total admittance across which I sets up the voltage. If (as is usual in an r.f. pentode) g_a is very small compared with the load admittance it can be neglected.

Before we get on to transistors there is another duality about circuit arrangement that ought to be noted. Usually, when students have taken in Ohm's Law, they go on to Kirchhoff's Laws. The interesting thing just now is that there are two of them, duals of one another. The first—or is it the second ? I can never remember—says that when a number of currents meet at a point, such as in Fig. 5(a), the sum of them, reckoned all towards or all away from the point, is always zero. And the other law says the corresponding thing about voltages round a loop, as at (b). The lines here are not meant to be short-circuits ; each can include as many as you like of anything—impedances, valves, generators, etc. If these same two dual circuit structures are drawn slightly differently, and some typical components shown (Fig. 6), we see the two general types of filter, T and π. These are, in fact, duals. Series L is replaced by parallel C, and vice versa. So it is not necessary to work out the equations for both types of filter ; when one has been done, those for the other can be derived by duality substitution.

And now for transistors. It was obvious all along that crystal triodes were analogous to thermionic valve triodes, but it soon became clear that the analogy was upside down. And that suggested applying dualism to the valve circuits to find the corresponding circuits for the transistors. I have already mentioned that where a valve uses negative voltage bias a transistor uses positive current bias. Severe distortion takes place in a valve if the voltage bias is removed

* "That Other Valve Equivalent" April 1951, p. 152.

and grid current flows; correspondingly there is distortion in the transistor if the current bias is removed and voltage builds up across the input (emitter to base).

On the output side, we have already noted (in connection with Fig. 4) that a pentode is approximately in dual relation to a low-resistance triode, as regards circuit arrangement at least. But the dualism extends to the interchanging of current and voltage. This is not very well brought out by published characteristic curves, because those for pentodes are always plotted as current against voltage, just the same as for triodes—compare Fig. 7(b) with (a). But if the pentode curves (b) are replotted as voltage against current (c) the likeness to (a) is obvious.

The types of transistor for which data have been published have output characteristics of pentode shape (Fig. 8). The main practical difference is that the "h.t." voltage applied to the collector (corresponding to the valve anode) is negative. But unlike the pentode the transistor's dual relationship to the thermionic triode includes the input as well as the output. In fact, one could say that transistors are rather like low-power output pentodes worked under grid-current conditions, requiring slightly positive grid bias voltage.



Above: Fig. 7. (a) shows the characteristic curve shape for a triode and (b) for a pentode. If (b) is replotted with current and voltage interchanged the result (c) is very similar to (a).

Right: Fig. 8. Typical transistor curves, being similar to Fig. 7 (a) with current and voltage interchanged, indicate an approximate dual relationship to the thermionic triode.



Below: Fig. 9. Basic tuned-anode tuned-grid valve oscillator circuit (a) compared with corresponding (dual) transistor oscillator circuit (b).



Amplification Duality

Apart from the transistor "h.t." being negative, the weakest thing about this comparison is that in the pentode the output voltage is not mainly controlled by grid current as such, but only in so far as the variation of grid current means that the grid voltage is varying; whereas in the transistor it is the emitter current that controls the collector output current.

So it is natural that μ, which is the ratio of anode voltage change to grid voltage change (at constant anode current), should have as its transistor analogue (α) the ratio of collector current change to emitter current change (at constant emitter voltage).

The only thing that radically spoils the dualism between the thermionic triode and crystal triode is the collector voltage and current being negative. Whereas there is the well known reversal of sign between input and output when a valve is working in an earthed-cathode circuit, there is no such reversal when a transistor is working in a corresponding (earthed-base) circuit. So in deriving the dual of a valve circuit, one has to remember to add to the normal procedure a sign reversal.

Although designers seem to find dualism a great help, as a means of applying the vast accumulation of experience of valve circuits, it is not altogether plain sailing. It is one thing to arrive at the appropriate set of equations, and even the theoretically best circuit; but in practice it is rather disconcerting when the grid bias battery (or other source of constant voltage) is found to have given place to a constant-current generator. However there is a way out, for a constant-current generator in series with an input or output coupling impedance can be replaced by a parallel-fed constant-voltage generator.

In fact, the outstanding effects of the dual transformation are to interchange series with parallel and capacitance with inductance. Perhaps the simplest and most obvious example is to compare the tuned-anode tuned-grid oscillator circuit with its transistor counterpart, Fig. 9(b), which needs no explanation. So as not to obscure the issue, all feed supplies have been left out. If I were to follow up what readers may have already found to be rather a tough meal with full details of transistor circuit design, the risk of indigestion would be considerably increased. After all, we are not likely to be able to buy transistors in the shops for some while yet, so a wealth of detail would be rather premature. But I do believe they may be near enough for the mentally alert to be glad of a little advance warning of the sort of technique that is being used. And even if practical transistors fail to come our way, it may be helpful in other directions to be aware of duality.

RADAR REFLECTORS

WITH the increasing use of radar as a marine navigational aid (some 1,400 British Commonwealth merchant ships are now equipped) there is a growing need for navigational buoys to be readily distinguishable on the p.p.i. A symbol appearing with increasing frequency upon charts is "Ra. Refl.," indicating that a buoy or beacon is fitted with a radar reflector. More than fifty of these "raflecs," as they are colloquially known, are now in use around the coasts of the United Kingdom, while it is understood they are in greater use off the east coast of N. America.

Fundamentally, the best reflector is a flat metal plate, but this would only be effective were the radar beam always directed at right-angles to it, which is, of course, impracticable.

A review in a recent issue of *The Scanner* (house journal of Decca Radar, Ltd.) compares figures for dihedral and polyhedral reflectors on both stationary and moving objects. While the response from a reflector with two surfaces (4ft high by 1½ft wide), forming a right-angle, is stated to have increased the detection range of a specified lighthouse from 8 to 18 miles, it is necessary to add a third surface—forming a cone—when using a reflector on a buoy to compensate for the vertical tilt. These corner reflectors are normally used in clusters forming a multi-trihedral reflector as illustrated.

Tests show that a 12-in corner reflector 6ft above the water is detectable 5.4 miles away with a scanner 50ft above sea level; this is decreased to 4.6 miles in a rough sea. The intensity of reflections from a reflector buoy passed at 3.75 miles using Decca marine radar Type 159 is given in Fig. 1.

The use of reflectors is not confined to navigational marks, and it has been found that a collapsible reflector, which can be readily assembled and run up to the masthead of a ship's lifeboat, increased the detection range of such a craft from less than 2 miles to about 4.5 miles.

Pentagonal cluster of corner reflectors used in "raflec" trials by the National Research Council of Canada.

Fig. 1. Intensity of reflections from a radar reflector buoy passed at 3.75 miles. The vertical scale gives the number of times the echo was received in ten revolutions of the scanner.



NEWS FROM THE CLUBS

Birkenhead.—Meetings of the Wirral Amateur Radio Society, which now has nearly thirty licensed amateurs among its members, meets on alternate Wednesdays at 7.30 at the Y.M.C.A., Whetstone Lane, Birkenhead. The April meetings will be held on the 9th and 23rd. Sec.: A. H. Watts, 14, Grange Crescent, Hooton, Cheshire.

Birmingham.—At the April 25th meeting of the Slade Radio Society, R. Ledger, of the G.E.C., will talk on "Electric Traction." Meetings are held at 7.45 at the Parochial Hall, Broomfield Road, Erdington. Sec.: C. N. Smart, 110, Woolmore Road, Erdington, Birmingham.

Coventry.—The next meeting of the Coventry Amateur Radio Society will be held on April 28th when there will be a lecture on communication receivers. Meetings are held on alternate Mondays at 7.30 at the Y.W.C.A., Queen's Road, Coventry. Sec.: K. G. Lines, 142, Shorncliffe Road, Coventry.

East Grinstead.—Readers in the East Grinstead (Sussex) district who are interested in the formation of a radio society, are invited by Frank Glynn (G3GVZ) to communicate with him at The Mount, 13, Station Road, East Grinstead, Sussex.

Ilford.—Lectures on capacitors, valves and technical literature are scheduled for the month's meetings of the Ilford & District Radio Society. On the 3rd H. J. Cozens, of T.C.C., will talk on capacitors; 10th, "Radio Valves: Manufacture and History," by G. P. Thwaites (S.T.C.); and 17th, "Technical Articles and Books," by Geoffrey Parr (Chapman & Hall). Meetings, to which visitors are welcome, are held every Thursday at 8 at St. Albans Church Hall, Albert Road, Ilford. Sec.: C. E. Largen, 44, Trelawney Road, Barkingside, Ilford, Essex.

Leicester.—"Tuned Circuits: with special reference to the 144 Mc/s band" is the subject to be dealt with by R. Weston at the meeting of the Leicester Radio Society at 7.30 on April 7th at the Holly Bush Hotel, Belgrave Gate, Leicester. Sec.: A. L. Milnthorpe, 3, Winster Drive, Thurmaston, Nr. Leicester.

Southend.—By the death of Henry H. Burrows, O.B.E., the Southend and District Radio Society has lost its president, who was also a founder member of the society. We are advised by the club's temporary secretary (T. W. Hudson) that the judging of entries for the Pocock and Hudson cups (for home-built gear) will take place on April 4th. Sec. (*pro tem*): T. W. Hudson, 27, Park Road, Southend-on-Sea, Essex.

MARCONI

serves

mankind



Marconi was a lone thinker who revolutionised communications by methods "the entire meaning of which no one before him had recognised." There is a great contrast between his crude copper-sheet aerial and the Marconi equipment which televises such programmes as the opening of the new House of Commons and the sessions of the United Nations. But there is also a great similarity—Marconi's tradition of service to mankind.

MARCONI'S WIRELESS TELEGRAPH COMPANY LTD · CHELMSFORD · ESSEX

THE GREATEST ADVANCE TOWARDS PERFECT REPRODUCTION

AM ING



THE NEW TONE COLOUR UNIT PLUS THE AZ TYPE AMPLIFIER £32.10.0

SOUND SALES LIMITED
DEMONSTRATIONS at our London Showroom:
LLOYDS BANK CHAMBERS, 125 OXFORD STREET, W.1 (Entrance in Wardour Street)
Telephone: GERrard 8782
(Works: West Street, Farnham, Surrey. Telephone: Farnham 6461)

N.P.L. CERTIFIED PERFORMANCE

WESTON *Test Sets*

High sensitivity, wide range coverage, robust construction and simplicity in operation have established "Weston" as the pre-eminent instruments for the testing and servicing of radio and television equipment and also for laboratory and research work. Full details will gladly be supplied on request.

ABOVE *Weston Model S.75. 53 ranges for measuring A.C. and D.C. current and voltage, resistance and insulation.*

RIGHT *Weston Model E.772 Analyser. Sensitivity as on Model S.75—namely 20,000 ohms per volt on all D.C. ranges and 1,000 ohms per volt on A.C.*

SANGAMO WESTON LIMITED
ENFIELD, MIDDLESEX

Tel: Enfield 3434 (6 lines) & 1242 (4 lines) Grams: Sanwest, Enfield

Branches: Glasgow, Manchester, Newcastle-on-Tyne, Leeds, Liverpool, Wolverhampton, Nottingham, Bristol, Southampton, Brighton.

RADIO HEATING

Typical Installations in Two Modern Industries

ALTHOUGH the two basic methods of radio heating—dielectric heating and induction heating—are now very well known, there is always some fresh interest to be found in the new methods of application which are constantly arising. Take, for instance, two of the latest installations by Radio Heaters, Ltd.—a dielectric heater for a plastics factory and an induction heater for a motor works.

The dielectric heater, installed for British Moulded Plastics Ltd., should be of particular interest to radio people because it plays a vital part in the manufacture of the unusually large moulded plastic cabinet of the Sobell "Stargazer" console television set. Normally, a plastic moulding is made by applying heat and pressure to the raw material—blocks of compressed powder—until it flows into the required shape. This, however, would have been unsuitable for commercial-scale production of the "Stargazer" cabinet as it would have taken too long and required an inconveniently large press. It was therefore decided that the 32 lb of powder blocks should be "pre-heated"

Dielectric heater for pre-heating the compressed powder blocks used in the manufacture of the plastic television cabinet shown below. Closing down the lid automatically switches on the power and a process timer switches it off.



Below: *The threaded sections of these pins are being annealed by heating in the long coil on the left.* **Below, right:** *Using a different rotating table, the tappet pads on the rocker arms are being hardened by heating in the small coil (right) and quenching in the two oil jets.*







Back view of induction heater, showing the oscillator valve in the top section and the power unit below.

into a near-plastic condition first, so that less time would be needed for "curing" and the easier flow of plastic would make possible the use of a reasonable size of press.

Ordinary methods of heating are not altogether satisfactory as the powder has poor thermal conductivity and does not get heated uniformly throughout. Radio heating, however, gives uniform distribution of heat in a very short time, so a radio dielectric heater was chosen to do the job. In this, the powder blocks are placed between two metal plates and the capacitor so formed is included in an oscillator circuit working at about 19 Mc/s. The equipment delivers 6 kW of r.f. power into the blocks and the dielectric loss effect raises their temperature to 70-80 deg C in 8 minutes. As a result of this treatment the curing time of the plastic is reduced by 30-40 per cent and only about half of the normal pressure is required to produce the moulding.

The induction heater, installed at the Ford Motor Company's Dagenham Works for treating small metal parts, exemplifies well the special ability of this type of equipment for giving very localized heating. It has three work coils, which can be connected in turn to an r.f. oscillator, and these heat the parts by the well-known eddy-current and hysteresis effects. The first coil is for hardening, to a depth of $\frac{1}{16}$in, the side wearing surfaces of a ball on the end of a steering arm. The ball is placed inside it and an operator switches on the r.f. power; then, at the end of 27 seconds, a process timer switches off and turns on a water supply to quench the hot metal. The second coil is for annealing steel pins over their threaded length only. A number of them are loaded on to a rotating table, and as this is indexed round the threaded sections pass through the coil. Each pin remains in it for 30 seconds, then cools down for a while before being ploughed off down a chute. The third coil is for hardening the tappet pads on rocker arms. Again a rotating table is used, but this time each tappet pad remains in the coil for 10 seconds then is indexed straight into a quenching jet of oil.

The r.f. oscillator for this installation uses a single valve in a Colpitts circuit working at about 400 kc/s, and the 8-kW output goes to the work coil via an r.f. transformer. A point of special interest is that the grid leak is formed by a number of lamps connected in series. This is often done in r.f. heating equipment as it greatly reduces the grid current variations which occur when the load on the oscillator is altered.

SPINNING PARABOLIC REFLECTORS

MAKING parabolic reflectors for electric lamps and heaters is more or less a bread-and-butter job for the metal spinner, but turning out the giant versions used in e.h.f. radio stations is an altogether different matter. The one in the picture, for instance, is 8ft 6in across, and had to be made out of several pieces of aluminium welded together because no rolling mill could supply a one-piece sheet big enough for the job. Spinning these jointed sections is a considerable feat of skill, for the metal has to be made to "flow" smoothly into the required shape and this is not easy when there are any irregularities, such as these welds, in its crystalline structure. The makers, Precision Metal Spinnings of Stratford-on-Avon, tell us that they are hoping to produce even larger spinnings—up to 12ft in diameter—by the same method.

Work in progress on one of the reflectors.

Radio Manufacture in India

Production Problems of Indigenous Industry

By JOHN A. HOWIE, B.Sc. (Hons.)*

The author, who has had practical experience of setting up a radio factory in India, outlines some of the problems which have been solved in the process of manufacturing many thousands of high-quality receivers each year using Indian labour with British co-operation and technical guidance.

IN 1947 the Indian Congress Government found itself faced with the gigantic task of organizing a population of some 350,000,000 multi-lingual and largely illiterate peoples into a coherent nation. They inherited the All-India Radio broadcasting service which had been organized more or less on the lines of the B.B.C., but its transmitters covered only a very small proportion of the country and, in any case, less than one in a thousand of the population owned a radio receiver. A Ministry of Communications and Broadcasting was therefore set up to expand A.I.R., promote the Rural Broadcasting Service (which installs and maintains community receivers in the villages and broadcasts special programmes to them) and encourage the formation of an indigenous radio industry.

Two companies had already been formed to manufacture radio receivers in India: the National Radio and Engineering Company of Bombay, a subsidiary of the Tata group of industries, and the Radio & Electrical Manufacturing Company of Bangalore, owned by the Government of Mysore State and operating at that time in association with the Philco Company of Great Britain. The National Radio Company commenced production in 1947 of a small three-valve t.r.f. mains receiver, preset to one m.w. station and known as "The People's Set." This was designed and made entirely by Indians, all the components, with the exception of valves and loudspeakers, were manufactured in Bombay. Although it was offered at a list price of only Rs.95 (£7 3s)—less than half the price of the cheapest imported receiver—it proved unpopular and production ceased in 1948. The principal reason for this was the short transmitting periods and unattractive programmes of the local A.I.R. stations which were the only broadcasts receivable on the People's Set, because of its limited range. The company, therefore, decided to associate with a foreign manufacturer and a new joint company called the National Ekco Radio and Engineering Co., Ltd., was formed in association with E. K. Cole, Ltd.

The Radio & Electrical Company of Bangalore, under the technical guidance of the British Philco Company, constructed and equipped a large factory designed to produce 100,000 receivers per annum, including all components, but in 1948 their association with Philco was dissolved, and in the following year they commenced assembly of kits imported from the International General Electric Company, Inc., of America.

The promise of Government support encouraged a large number of small concerns to produce battery receivers, mostly of rather odd design, made largely from war surplus valves and components left behind by the British and American armies. There are now about sixty of these small concerns with an average individual output of less than 500 sets per annum.

In 1948 Murphy Radio (India), Limited, was set up in Bombay to assemble kits imported from the parent company, and Philips and H.M.V. at Calcutta began to change over to partial local assembly.

The most recent additions have been Tesla (India), Limited, assembling kits imported, apparently at very low prices, from the State-owned Tesla Company of Czechoslovakia and the Birla Bros., subsidiary Indian Plastics, Limited, set up under the technical guidance of Leland Instruments, Ltd., of London. The Government of India restricted imports of complete receivers from 1948 but granted special "blanket" licences to indigenous manufacturers for the import of necessary components and materials.

Thus the foundations have been laid for a new industry in which British, Continental, American and unaided Indian interests are all represented.

The potential market is, however, limited, for less than five per cent of the population can hope to own anything as expensive as a domestic radio receiver. Even so, this provides a potential demand of about three million receivers. The number of licence holders is still only slightly more than six hundred thousand.

The total annual sales is at present less than one hundred thousand, of which about thirty per cent are imported receivers, another thirty per cent are made by the small Indian assemblers, and the remainder are manufactured by the larger companies mentioned above. Last year the National Ekco company alone produced more than twenty thousand receivers.

The remaining 95 per cent of the population (totalling over 300,000,000) are potential customers only for community receivers, and so far only about 3,000 of these receivers have been installed. Elaborate plans have, however, been made by Central, Provincial and State Governments for the equipment of all the 700,000 Indian villages, but the necessary finance has yet to be found.

The design, manufacture and use of village community receivers in India is a separate story which cannot be adequately dealt with in the compass of this article but it is probable that these highly specialized receivers will play an increasingly important part in the Indian radio industry during the next few years.

Meanwhile the domestic market should continue to

* Formerly National Ekco Radio and Engineering Co., Bombay.

take about 100,000 receivers per annum unless a general business depression sets in. If and when the ambitious plans for progress of the Indian Government, including a higher standard of living for the middle classes and great expansion of electrification of homes, mature, the demand should increase substantially—probably to 300,000 per annum—but it is too early yet to estimate the probability of these plans proving economically possible. Vast sums of money are already being spent on new hydro-electric projects and the expansion of industry, but, simultaneously the population is increasing at the rate of 5,000,000 per annum and maintenance of even the present standard of living is proving increasingly difficult.

Listener Requirements

The Indian listening public divides sharply into two categories, one being the rural population, almost unchanged in outlook and habit from their forebears of earlier centuries, and the other the inhabitants of the larger cities who have acquired many "westernized" tastes and interests. All-India Radio is attempting to meet these diverse requirements by operating a comparatively large number (27) of low-powered m.w. transmitters in the cities, combined with 15 higher-powered s.w. transmitters, chiefly from Delhi, to provide more general coverage. Financial stringency prevents their operating these transmitters for more than a few hours each day, and even these limited periods have to be shared out among broadcasts in a number of different languages. A fairly close parallel would be the planning of programmes to suit all the peoples of Europe on a budget equal to a tenth of that of the B.B.C.—the number of different languages and the overall area to be covered both being of the same order.

The Government of India still refuses to sanction commercial broadcasting, but recently two commercial s.w. transmitters, one in the small Portuguese territory of Goa on the West coast, and the other in Ceylon, have gone into service and have become very popular. Radio Ceylon in particular broadcasts continuously each day from a 75-kW transmitter and has probably become the most important single factor in stimulating the sales of domestic receivers in India. Overseas broadcasts, especially those from British, American and Australian stations, are listened to regularly.

It follows, therefore, that the Indian market demands really adequate s.w. reception, which is a very different thing from the novelty value s.w. performance usually provided for the British or Continental markets. Moreover, the climate and the prevalence of dust and insects quickly destroys both the receivers and the reputation of the manufacturers unless thoroughly reliable and fully proofed components are used.

Tropic-proofing

Many reputable manufacturers have spent a great deal of their own and Government's money studying tropicalization for the past ten years, but too much reliance has been placed on extreme, accelerated tests, such as the Inter-Service K110 test and, since 1946, tropic-proofing specifications have tended to be diluted by price considerations.

Any manufacturer who sincerely wishes to determine the performance of his products under tropical conditions is recommended to expose complete receivers to a temperature of 95° F and a relative humidity of 95 per cent continuously for one month preferably in the presence of some of the more virulent moulds which flourish under these conditions, and then examine the appearance and measure the performance of the receivers while still in that atmosphere. The results are apt to be discouraging, but these conditions are only little more severe than those experienced regularly during a large part of each year in the homes of his potential customers and, more significantly, in the shops of his Indian dealers, where his products may lie for several months before sale.

Because so many of the urban listeners live in flats, they are unable to fit efficient aerials and earths. Interference from lifts, fans, refrigerators, etc., is heavy and the mains voltage fluctuates widely due to overload. Under these unfavourable conditions and the prevailing high humidity, sensitivities of less than 50 microvolts for 500 milliwatts output, correspondingly high selectivity and signal/noise ratio and an output at not more than 10 per cent distortion of at least 1.5 watts are really essential for reception of distant s.w. broadcasts at enjoyable quality and volume in the cities.

For battery receivers, the reduced background noise and interference and the better aerial facilities usually available in rural districts make sensitivity of the order of 100 microvolts for 50 milliwatts output and peak outputs of 250 milliwatts adequate.

Bandspreading, frequency stability and a visual tuning indicator are desirable. The use of textiles for speaker grilles is inadvisable because of the

The author checking a tool-shaping machine. Pieceparts and components are produced in the National Ekco Radio and Engineering Company's factory in Bombay.



Left: *Winding paper capacitors for which air conditioning is essential.* Right: *Receiver chassis at the circuit comparator test bench.*

ravages of cockroaches, and completely waterproof cabinet construction and finishing are essential. At the same time, prices must be kept within limits. A receiver which would sell at £16 plus purchase tax in this country costs at least £30 in India because of the imposition of 44 per cent duty on C.I.F. value and the high distribution expenses. The "Official" list retail price is, moreover, increased by about 25 per cent because nearly all Indian customers expect to receive a large discount off the list price as a result of a prolonged haggle with the dealer.

Production Problems

The radio manufacturer in India starts off with a number of difficult administrative and technical problems to overcome. The large-scale mass production of receivers is probably one of the most efficient industries in this country, but no one who has attempted to compete with these large producers on a comparatively small scale will claim that it is easy. The production of tropicalized all-wave receivers in a hot, humid and industrially backward country is infinitely more difficult, especially when they must be competitive with imported receivers. There is little future in importing kits and confining manufacture merely to assembly and test because the landed cost of a complete kit is not sufficiently less than that of the corresponding finished receiver.

The comparatively low Indian labour rates must be utilized by making a large proportion of the piece-parts and components and thus saving the import duty charged on these items. To do this without excessive capital expenditure or overhead charges demands a fair amount of ingenuity in scaling down the elaborate organization, machines and tools commonly employed by the big producers. For example, the use of a 100-ton power press and an elaborate tool to blank and pierce chassis in one operation is efficient when large numbers are required and labour costs are high, but three or four cheaper tools set up successively in a smaller press can be made to produce quite a range of different chassis with appropriate withdrawal or addition of punches.

Similarly, the use of mechanized assembly lines looks impressive to visitors and earns its keep at high outputs, but ordinary benches are cheaper and more flexible for smaller rates of production. On the other hand, no relaxation in accuracy or quality can be permitted because "trouble-shooting" and component replacements on the assembly lines are just as expensive in any country and a "renovated" chassis always looks what it is.

The Indian universities and technical institutes annually turn out hundreds of matriculates and engineering graduates who are intelligent and enthusiastic but sadly lacking in practical experience and initiative. With patient training and firm leadership they can be turned into reliable production staff, but very few of them have executive capacity. Nevertheless, the National Ekco Company and two other manufacturing companies are each staffed by Indians with a British manager.

Many types of working-class Indians also make good "raw material" for radio production, but the lack of industrial background demands much more extensive training and a greater degree of supervision. Indian girl assembly workers are intelligent and dexterous but, even after training, cannot achieve more than about 60 per cent of the output of British girls because of their inferior physique and the enervating climate. This is also true of the men but, as a good Indian factory worker does not cost more than 30s per week (which is appreciably higher than the average wage paid in other industries), labour costs per receiver are lower than in this country.

Practically all materials, with the exception of certain types of steel, mica, shellac and varnishes, have to be imported, although locally made non-ferrous sheets, rods and fabricated parts produced from imported ingots are available in suitable qualities and at competitive prices. The National Ekco Company manufactures all types of radio transformers, chokes and coils, together with paper and mica capacitors, and sells them to other assemblers, but at present there is little other component manufacture in India. All materials have to be very carefully stored and protected against corrosion due to the high humidity and contamination by dust and insects.

This also applies to machine tools and plant, which must be cleaned and oiled daily.

A State radio factory was projected for the production of all Services requirements, including valves and components, but this proposal appears to have been dropped because of its prohibitive cost. When the Indian radio industry has developed further it is probable that contracts will be issued to it for the development and manufacture of most types of communication gear, receivers and components.

The numerous police forces are also using considerable numbers of mobile transceivers and public-address equipment, and the large Indian Posts and Telegraph factory at Bangalore is buying some of its components from commercial radio manufacturers. Recently an Atomic Energy Commission has been set up to exploit India's resources of radio-active minerals and already small quantities of electronic apparatus have been designed and made in India for this Commission. It is noteworthy that the Government of India has included radio manufacture in a list of fourteen strategic industries selected for special encouragement and would apparently welcome the investment of further British capital in this industry, particularly if the production of valves and components were undertaken.

Completed receiver undergoing the final test.

Simplified Aerodrome Approach Aid

Combination of 3-cm Radar and Metre-wave Direction Finder



Ekco prototype 3-cm radar approach aid combined with a v.h.f. direction-finding receiver.

MANY aerodromes do not handle a density of traffic sufficient to justify the high cost of full GCA (ground-controlled approach) equipment. However, there is generally still need for a radio aid to landing in poor visibility, and, to meet such a need, a simplified and cheaper type of equipment has been developed by E. K. Cole, Ltd. The apparatus, which was recently demonstrated experimentally at Southend Municipal Airport, consists of a 3-cm radar installation producing a narrow pencil-like beam of radiation combined with a metre-wave direction-finding receiver (116-132Mc/s). The radar beam does not scan in the usual way but the "dish" aerial is mounted on the rotatable shaft which carries the v.h.f. aerial, and is arranged so that the axis of the radar beam coincides with the null position of the d.f. aerial. The radar dish is controllable independently in elevation but not in azimuth.

The radar display tube is calibrated in nautical miles and scales show the elevation angle of the radar beam and the azimuth angle of the d.f. aerial. Adjustable contacts on the scale-drives illuminate lamps which indicate when the aircraft is within certain prescribed limits of the desired course, when it deviates, and whether the deviation is in azimuth or in elevation.

The necessary changes in course, and in altitude, are conveyed to the aircraft by radio-telephone.

In the illustration can be seen two horizontal hand-grips and above the right-hand one is the c.r.t. indicator, while clamped to the hand-grip is the microphone. Above are the scales.

The operator uses the horizontal hand-grips to rotate the radar dish and d.f. aerial (azimuth search), while for elevation search the grips are twisted about their axis. The v.h.f direction finder and radar approach aid can be operated by one man.

An improved model is in course of development in which the operator can be seated and operate the azimuth control by a hand wheel and elevation control by foot pedals.

COSSOR ELECTRONIC INSTRUMENTS

DOUBLE BEAM Model OSCILLOGRAPH 1049



This instrument is designed to meet the requirements of Industrial Concerns and Research Laboratories who require to measure phenomena of zero or very low frequency and to make photographic records of transients requiring a high photographic writing speed.
The Oscillograph incorporates the Cossor 4" flat-screen Double-Beam tube (type 89) operating at 2 K.V. but provision is made for operation at 4 K.V. when maximum spot brightness is required.

The amplifier circuits are direct-coupled throughout and provide independent amplifying channels for the Y1 and Y2 Beams with a gain of 900 and 25 respectively from zero frequency to 100 Kcs. Input signal voltages and frequency may be measured on either channel using the calibrated dials and special anti-parallax graticule. The direct-coupled time base is arranged to provide a repetitive and triggered scan with a time range of 1.5 seconds to 150 microseconds and can be synchronised from a pulse derived either from the internal work circuits or from an external source. A continuously variable control adjusts the amplitude of the sync. or trigger signal and selects the polarity of the pulse from which synchronisation is desired. A Z modulation system is incorporated for time-marking purposes. Stabilization against mains variations up to 10% is provided for amplifiers and cathode ray tube supplies. Long-period stability is reached within 5-10 minutes of switching on.

D.C. PRE-AMPLIFIER Model 1430



This instrument is a directly coupled pre-amplifier of high stability which has been designed for use with a further amplifier or with a recording device. Used in conjunction with a Cossor Model 1049 Double-Beam Oscillograph it will give a maximum overall gain of 45,000 and a maximum sensitivity of approximately 0.75 mV/cm. The frequency range is from D.C. to 30 Kc/s.

The input and output switching has been designed so that the instrument may be used to amplify either balanced or unbalanced input signals, and will provide a balanced or unbalanced output as required from either kind of input signal. The arrangement also makes it possible to check the amplifier balance and the setting up of the recording device without disconnecting the signal input or output leads.

COSSOR ELECTRONIC INSTRUMENTS

Write for fully descriptive leaflet to your usual wholesaler or to :—

A. C. COSSOR LTD., INSTRUMENT DIVISION (DEPT. 1), HIGHBURY GROVE, LONDON, N.5

Telephone: CANonbury 1234 (30 lines) C1.35



CERAMIC SWITCHES

For applications where only the best is good enough. Stators and rotors of "Frequentite" ceramic. All contact members of silver alloy.

Wright and Weaire Limited

138, SLOANE ST. LONDON S.W.1 TEL SLOANE 2214 5 - FACTORY SOUTH SHIELDS, CO. DURHAM.

SUCCESS?

In Radio, Television, and Electronics there are many more top jobs than engineers qualified to fill them. Because we are part of the great E.M.I. Group we have first-hand knowledge of the needs of employers, thus our Home Study courses are authoritative and based upon modern industrial needs. Alternatively, our courses will prove equally valuable to you in furthering your hobby.

START HERE

POST THIS COUPON NOW

E.M.I. INSTITUTES, Postal Division, Dept. 16, 43, GROVE PARK ROAD, CHISWICK, LONDON, W.4.
Please send, without obligation, your FREE BROCHURE.
I have marked the subjects which interest me.
☐ Mechanical Eng. ☐ Electrical Eng. ☐ Draughtsmanship.
☐ Radio. ☐ Television. ☐ Production Eng. ☐ Automobile
☐ Aeronautical Eng. ☐ General Cert. of Education
Eng. ☐ Civil Service.
(Matric). ☐
Also Courses for A.M.I.Mech.E., A.M.I.C.E., A.M.Brit.I.R.E., A.F.R.Ae.S., CITY and GUILDS EXAMS. in Mech. Eng., Elect. Eng., Telecommunications, etc.
Other Subjects .....
NAME .....
ADDRESS .....

E.M.I. INSTITUTES The College backed by the Industry

E.M.I. SCHOLARSHIPS

YOUNG MEN aged 17-19 with G.C.E. and at least one year's further study in Mathematics and Physics have a wonderful opportunity to train for an interesting career with the greatest Electronic Group in the Commonwealth.

ONCE A YEAR a limited number of E.M.I. Scholarships are awarded for a four-year course in Electronic Engineering. With this Scholarship and grants, Students may become almost self-supporting while still under training. During the course the Student's progress and welfare are the main considerations.

Send for details of this Scholarship immediately.

Selected applicants will be required for a personal interview in London in early September.

Next Course commences in London on October 14th.

E.M.I. INSTITUTES

(Dept. 16N), 10, PEMBRIDGE SQUARE, LONDON, W.2. Tel: BAYswater 5131/2.

Associated with "H.M.V." MARCONIPHONE COLUMBIA ETC

High-Tension Delay Circuit

Relay-Operated Protective Device

By D. CLEMENTS

THE arrangement to be described is applicable to mains-driven power units where a capacitance input filter is used. It provides a delay in applying the full h.t. voltage to capacitors and other components until the load is of sufficient magnitude to prevent the voltage rising to a dangerous level. In the event of the load failing, the voltage is immediately reduced to its former safe level.

The circuit has several advantages over the conventional thermal delay system, and calls for fewer components; one relay is the only extra component required. The delay is only as long as that needed for the load to present itself, and, if the load is not forthcoming, the device does not switch and the voltage remains at a safe level. If the load fails the circuit reverts to its original condition and the voltage is reduced. Relay contacts do not have to make or break any excessive voltages or currents.

Fig. 1 shows the circuit before power is switched on. C_1, which is normally the reservoir capacitor, is switched in parallel with the first smoothing capacitor C_2 by relay contacts A_1, the relay coil A/1 being in series with the smoothing choke L_1. When power is first switched on, the smoothing circuit L_1, C_1 and C_2 is connected as a choke-input filter and, providing there is a small h.t. drain, the voltage across the capacitors does not rise above the effective value of the alternating voltage applied to the rectifier. Since there is no appreciable load current the relay A/1 does not operate.



Fig. 1. Circuit of h.t. supply fitted with a relay to reduce the output voltage while the valve heaters are warming up.

When the load current has increased to a value that will keep the final voltage down to a safe level (i.e., when the heaters have warmed up) the relay operates and the capacitor C_1 is switched to its conventional position in the circuit as a reservoir capacitance. The h.t. voltage now rises to its normal "on load" value.

Until the operation of the relay, C_1 is charged to the voltage across C_2 so that the contacts, on switching, do not have to "make" any excessive voltage. The only current carried by the relay contacts is that of the ripple current in C_1.

If, when power is switched on, the heaters are already hot and current flows, the relay will immediately operate and there will be no delay. Conversely, if the load should fail during operation, the relay immediately becomes de-energized and the circuit reverts to its original condition to give reduced h.t. voltage as previously explained.

The load which is required initially to limit the h.t. voltage to a given safe level is almost entirely dependent on the value of the inductance L_1. If the maximum permitted level of this voltage is the effective value of the applied a.c. (0.9 of r.m.s. value), then the load resistance R_L must satisfy the expression,

$$R_L < \omega L_1 \frac{E_o}{E_i}$$

where $\omega = 2\pi \times$ lowest ripple frequency

$\frac{E_o}{E_i} = \frac{\text{Output voltage}}{\text{Lowest-frequency ripple component}}$

In the case of full-wave single-phase rectification $\frac{E_o}{E_i} = 1.5$ and if the supply frequency is 50 c/s then, approximately, R_L (max) $= 10^3 \times L_1$. In the above expressions the value given for R_L includes the resistance of the inductance plus the equivalent valve and transformer resistances.

If the maximum permitted direct voltage is higher than that quoted above, and if electrolytic capacitors of the surge-limiting type are used, the load resistance may be considerably higher. Occasionally it can be omitted altogether, as when the leakage current of the electrolytics is sufficient to limit the voltage. It is usually best to find the resistance of R_L empirically using a meter to indicate the voltage across the capacitors (the relay is best made inoperative by means of a short circuit during this operation).

The relay A/1 may be of any type that will operate when the h.t. current rises to the appropriate value which, in the absence of more accurate information, may usually be taken as being approximately 75 per cent of the final h.t. drain. If a relay of greater sensitivity than necessary is used, it may conveniently be modified by a resistor R_1 in parallel. The value of this resistor is best found by wiring a variable resistance set to zero ohms, across the relay and, after switching on and allowing a suitable period for heaters to warm up, slowly increasing the resistance until the relay operates. A fixed resistor of appropriate value may now be substituted.

If a standard 3,000-type relay, fitted with one

change-over contact, is used, then approximately 75 ampere-turns are required to operate it. If the full winding space of the relay is used, T^2 approximately equals 250,000R where T is number of turns and R resistance in ohms. This gives rise to the following expression which may be of use to ascertain the suitability of a given relay when the resistance is known :—

$$\text{Minimum operating current in amperes} \approx \frac{1}{6.5\sqrt{R}}$$

TECHNOLOGISTS IN MEDICAL WORK

Young Professional Association

MOST electro-medical technologists are in the work for sheer love of it; for they get very little out of it in prestige or monetary reward. Nevertheless they are expected to know a lot about medicine as well as nearly everything about electronics, to be extremely adaptable, and to make silk purses out of sows' ears—hospitals being notoriously reluctant to part with money for new equipment. Many of them are practised in the art of designing unusual and specialized apparatus for medical people who refuse to entertain the idea of more than one control knob—and sometimes the result is such a good engineering job that it is taken up and developed commercially.

Two years ago an association was formed to look after the interests of these workers (there are fewer than 200 in this country) and make possible an interchange of technical information on the somewhat unusual work. It is called The Electro Physiological Technologists' Association (E.P.T.A. for short) and at the moment has about 50 members. The first issue of its official journal, *Proc. E.P.T.A.*, gives the objects of the Association as: (a) To exercise professional supervision over its members and to provide for them such definite status and recognition as may assist in the discharge of their duties provided that these activities do not in any way cause the Association to act as a trade union. (b) To devise means of testing the qualifications of candidates for admission to membership by examinations in theory and practice and to grant certificates and diplomas of qualifications to successful candidates. (c) To hold meetings and conferences for the discussion of scientific and technical matters and to co-operate with other learned bodies.

The president is Professor F. L. Golla of the Burden Neurological Institute, while the present Hon. Secretary is G. Johnson of Hurstwood Park Hospital, Haywards Heath, Sussex.

EXHIBITORS AT MANCHESTER

THE Northern Radio Show, organized by the Radio Industry Council, opens at the City Hall, Manchester, at 12 noon on April 23 for ten days. As will be seen from the appended list, the majority of the major receiver manufacturers are among the fifty exhibitors, but it is not confined to domestic radio. Although smaller than the National Radio Show, it will be representative of the radio industry in general. In addition to the receivers operating in the Television Avenue, exhibitors will be permitted to operate sets on their stands which will be fed from the exhibition control room. The television sound channel will be employed for public address. The price of admission to the show is 2s (children 1s).

Name	Stand No.	Name	Stand No.
Aerialite	22	J.B. Mfg.	2
Alba	15		
Ambassador	20	Kemsley Newspapers	48
Antiference	3	Kolster-Brandes	18
Argosy Radiovision	37		
		McMichael	19
B.B.C.	49	Marconiphone	23
Belling & Lee	44	Mullard	26
British Radio & Television	35	Multicore	39
Bush	33	Murphy	13
Cossor	32	Peto Scott	34
Decca	29	Philips	11 & 12
Defiant (Co-op)	9 & 45	Pilot	28
Dubilier	4	*Practical Wireless*	1
		Pye	10
Ediswan	43		
Ekco	24	Regentone	27
English Electric	42		
		S.R.M. Television	51
Ferguson	25	Stella	46
Ferranti	30 & 40		
		Telcon	38
G.E.C.	31		
Goodmans	47	Ultra	14
H.M.V.	17		
Hobday Bros	5	Vidor	16
Hunt	50		
		Wireless Trader	21
Invicta	41	Wolsey	36

Short-wave Conditions

Predictions for April

THE full-line curves given here indicate the highest frequencies likely to be usable at any time of the day or night for reliable communications over four long-distance paths from this country during April.

Broken-line curves give the highest frequencies that will sustain a partial service throughout the same period.


MONTREAL
BUENOS AIRES
CAPE TOWN
CHUNGKING
Mc/s
G.M.T.
FREQUENCY BELOW WHICH COMMUNICATION SHOULD BE POSSIBLE ON ALL UNDISTURBED DAYS
PREDICTED AVERAGE MAXIMUM USABLE FREQUENCY
FREQUENCY BELOW WHICH COMMUNICATION SHOULD BE POSSIBLE FOR 25% OF THE TOTAL TIME

Manufacturers' Products

NEW EQUIPMENT AND ACCESSORIES FOR RADIO AND ELECTRONICS

Miniature Earphone

LARGE and uncomfortable headphones are on the way out, thanks to the enterprise of hearing-aid manufacturers who are now adapting their miniature earphone design technique for general use. A recent example of this particular kind of miniaturization is the Amplivox



Amplivox miniature earphone.

E5 earphone, which is little bigger than a sixpence in diameter and weighs only ¼ oz. It is held in position by a flexible ear attachment (see picture)—although a stethoscope headset is available if required—and can be fitted with a plastic ear tip to close the ear canal against extraneous noise. The construction is robust and the plug and cord are designed to withstand the various strains caused by movement. The earphone is available in d.c. resistances of 2 to 2,000 ohms and it has a frequency response of 100c/s-4kc/s. The address of the makers is 2, Bentinck Street, London, W.1.

Signal Strength Meter

B.B.C. television transmissions are among others in the 40-70Mc/s band whose aerial signal strengths can be measured by an instrument recently put on the market by E.M.I. Sales & Service Ltd. Actually, it consists of three instruments in the one case — superhet receiver, signal generator and valve voltmeter—which it uses for the substitution method of measurement. Signals from the aerial are tuned in by the receiver and measured on the valve voltmeter, then the signal generator is substituted for the receiver and adjusted to give the same meter reading; the aerial signal strength—represented by the output of the generator—being read off from a calibrated attenuator. The instrument is completely portable, having its own vibrator power supply working from an internal 2-V accumulator. An a.c. mains charging unit is also incorporated to enable the accumulator to be charged when necessary.

The signal strength meter is obtainable from the Dealers' Service Development Division of E.M.I. Sales & Service Ltd. at Blyth Road, Hayes, Middlesex, and costs £75.



E.M.I. signal strength meter.

Two-speed Reduction Drive

THE new "Microdual" reduction drive produced by Transradio Ltd., 138A, Cromwell Road, London, S.W.7, is notable for the fact that it provides two gear ratios from a single control knob—you push in the knob for one (coarse adjustment) and pull it out for the other (fine adjustment). With the coarse adjustment (for searching rapidly over the dial) the drive from the knob goes direct to the pointer through a single reduction gear, but with the fine adjustment (for accurate setting) it goes via a layshaft which introduces additional reduction—this is brought into play by pulling out the knob and is held in place by spring-loading. The arrangement is claimed to have no observable backlash and there is a friction clutch which obviates overdriving. Several models of the reduction drive are available with different kinds of dials and scales and the gear ratios available are 1 : 8 with 1 : 100 and 1 : 15 with 1 : 200.

New TRIX Quality SOUND EQUIPMENT

MAINS & BATTERY AMPLIFIER



Model T620.

This 20 watt amplifier model T620 can be operated from batteries as well as from AC mains by the addition of a plug-in adaptor unit for 6 volts, thus adding, considerably to the variety of applications for which this amplifier is suitable.

This new model is similar in general design to the well-known 30 watt type T633B, and is fitted with the same controls, push-pull output with negative feed-back, high and low impedance outputs, etc.

HIGH FIDELITY MICROPHONE

Model G7808, moving coil type. New design, neat and unobtrusive, with die-cast alloy grille. Fitted with switch and plug and socket connection.

Send for latest catalogue and price lists of the Trix range of Sound Equipment.

THE TRIX ELECTRICAL CO. LTD.
1-5 Maple Place, Tottenham Court Road, London, W.1. 'Phone: MUSeum 5817
'Grams & Cables: "Trixadio, Wesdo, London"

AMPLIFIERS MICROPHONES LOUDSPEAKERS

RANDOM RADIATIONS

By "DIALLIST"

Resistors

QUITE A NUMBER of readers tell me that they have found unreliable resistors just as great a nuisance as I have. I'm not sure, though, that every resistor which shows a value differing wildly from that indicated by its colours is altogether to blame for the discrepancy. A good many, I believe, are "fried" during the process of soldering them into their places. A large (and permanent) change in their value may be brought about by overheating. Resistors are not the only components that can be injured in this way and one of the soundest of all rules for the constructor of electrical apparatus is: Make your soldered joints quickly. The four chief causes of slowness in soldering are: solder too hard for the job, flux not active enough, metal parts not properly cleaned, and iron not sufficiently hot. For radio work you can't beat a good cored solder of 60/40 grade—the 60 is the percentage of tin and the 40 that of lead. I like to have my bit so hot that if it is pressed on to a piece of newspaper for 4 or 5 seconds it leaves a slight singe mark. Then joints are so quickly made that components don't have time to get warmed up.

Scopes, Graphs and Grams

THE EDITOR of *W.W.* has the very sound plan of so standardizing the technical terms used by those who write in this journal that, so far as possible, each is always used with one meaning and one meaning only. A case in point is the cathode-ray oscilloscope, which to some is merely an alternative name for the c.r. oscillograph. In *W.W.* the words are not interchangeable: the oscilloscope means one kind of instrument; the oscillograph, another. The -scope part of oscilloscope actually signifies "look at"; hence the term oscilloscope is used to mean an instrument designed to enable you to look at voltage waveforms on the screen of a cathode-ray tube. But -graph means "write" or "record"; and so the oscillograph is an instrument containing a built-in camera, or other device, enabling a permanent record —an oscillogram—to be made of the effects appearing on the screen of the tube. A pity that all our technical names with Greek derivations have not been subjected to equally sensible rules. A photograph, for example, should be an instrument which records by means of light; and a photogram, the record it makes.

Is the Valve Doomed?

WONDERFUL though its performances undoubtedly are, the thermionic receiving valve has never seemed to me to be more than a temporary makeshift, likely to remain in use only until something better could be found. It has a whole heap of weak points, amongst which are its fragility, its comparatively high cost, the instability of its characteristics (which change as it ages with use), its poor input-output efficiency ratio, its proneness to distort the signal which it transmits and its short working life. By input-output ratio I do not mean just the gain, or the anode efficiency; I am thinking of the average domestic receiver's consumption of 40 or more watts from the mains for an output of one or two watts to the loudspeaker. A year or two ago the transistor made its appearance as a possible rival; and now comes the news of the development in the laboratory of the dielectric amplifier. Whether either of these will eventually provide the answer, one cannot yet say. I hardly think that either of them will, though one or other (or both) of them may set some genius thinking and experimenting along the lines which lead to the super-efficient amplifiers of the future. The time will undoubtedly come when the receiving valve will be as much of a museum piece as is the coherer to-day.

A Queer Fault

A WELLINGBOROUGH reader is kind enough to send me an account of a particularly baffling fault which he encountered in a broadcast receiver. The set worked normally for about 10 minutes after it had been switched on; then the volume fell to about half what it had been. Switch off for a minute or two and when it was switched on the same thing happened again. After a long and fruitless search for the cause of the trouble, he gave the semi-silent set an angry jab with his screwdriver to show what he thought of it. To his amazement, there was an instant return to full volume. Investigation showed that his screwdriver had administered a good sharp rap to a resistor. When the drop in volume again occurred, he gave the resistor another knock and once more all was well for some minutes. Replacement of the resistor cured the trouble—but what was wrong with the resistor itself! Taking it to pieces, he found that the resistive element, housed in a ceramic tube, was cracked in two near its middle. Tests showed that during the warming up period, after switching on the set, a carbon deposit formed and bridged the gap. This carbon burned off after some 10 minutes when the set was at work. The

ASSOCIATED ILIFFE TECHNICAL BOOKS

"WIRELESS WORLD" PUBLICATIONS

	Net Price	By post
MICROPHONES. By the Staff of the Engineering Training Dept. B.B.C.	15/-	15/5
FOUNDATIONS OF WIRELESS. M. G. Scroggie, B.Sc., M.I.E.E. Fifth Edition	12/6	13/-
RADIO VALVE DATA: Characteristics of 2,000 Valves and C.R. Tubes. 2nd Edition	3/6	3/9
TELEVISION RECEIVING EQUIPMENT. W. T. Cocking, M.I.E.E. 3rd Edition	18/-	18/8
SHORT-WAVE RADIO AND THE IONOSPHERE. T. W. Bennington. 2nd Edition	10/6	10/10
WIRELESS SERVICING MANUAL. W. T. Cocking, M.I.E.E. 8th Edition	12/6	12/11
RADIO LABORATORY HANDBOOK. M. G. Scroggie, B.Sc., M.I.E.E. 5th Edition	15/-	15/5
WILLIAMSON AMPLIFIER. Articles on Design of a High-quality Amplifier. By D. T. N. Williamson	3/6	3/9
GUIDE TO BROADCASTING STATIONS. Compiled by "Wireless World." 6th Edition	2/-	2/2

A complete list of books is available on application.

Obtainable from all leading booksellers or from

ILIFFE & SONS LTD., Dorset House, Stamford Street, London, S.E.1.

result of his assault on the resistor was presumably to shake off bits of the resistive element into the gap.

Mains Voltages

IN THE DAYS before the war the electricity authority placed a very definite limit on the amount by which the voltage of one's mains supply might vary from its stated value. If I remember aright, the maximum permissible variation was something like ±2-3 per cent. This is, of course, a dead letter to-day, when we are lucky if on a very cold day, a "cut" does not bring about a −100 per cent change! Being the proud possessor of a very accurate 0-300V meter for a.c., I take the voltage of my alleged 200-V, 50-c/s supply fairly frequently. In the past few months the lowest reading (outside "cuts," of course) has been 182V and the highest 208V, which means a variation of from −9 per cent to +4 per cent of the rated voltage. I am not grousing, for I realize that this kind of thing is just one of the minor horrors that the victors in a modern war must expect—and endure indefinitely. But such big upward or downward swings cannot be too good for the health of some electronic gear. The 6.3V heaters of valves, for instance, may have anything from about 5.75 to 6.5 volts applied to them. It says a lot for the reliability of our domestic radio and television receivers that they work as well as they do with these ups and downs in supply voltage and frequency.

Fame Indeed!

THE GREATEST HONOUR that can be conferred on a man of science is, I suppose, the adoption of his surname as a technical term. Unfortunately it is nearly always a posthumous honour, for comparatively few men, or women, live to bask in such glory. Madame Curie is one of those I can think of who have done so. Another honour accorded to but few men is the adoption of their names to form new words in a foreign language. The latest to achieve this is D. T. N. Williamson of amplifier renown. In the February issue of *Toute la Radio* I read on page 58: *Notre correspondant a construit son Williamson . . . dans un unique coffret*—"our correspondent has built his Williamson in a single cabinet." Williamson has not yet reached the summit of fame indicated by the spelling of his name with a small w, but one day we may see it recorded in print that some French enthusiast has built *un magnifique williamson!*



ROTARY SELECTOR SWITCHES

THESE efficient complete-Unit Rotary Selector Switches are specially suitable for meter-switching, tone-control, wave-change, etc. Manufactured to the usual high Bulgin Standards of quality and workmanship.

OVERALL dimensions are reasonable for all types of equipment; 1⅛in.ϕ, rear-projection ⅛in. Incremental Angle of movement, 20°. Shaft ϕ, "¼ in" (0.247in.–0.249in., for all ¼in.-bore knobs). Normal shaft-protrusion from bush, 1 ⅛in. Bush, ⅜in.ϕ × ⅛in. × 26 t.p.i. Panel locator for hole ⅜in.ϕ at ⅛in. crs. from bush hole.

MADE with heavily Ag.-plated Contacts with integral tags, for easy and reliable soldering of connections. Insulation of highest grade Synthetic sheet, average I.R. < 100MΩ at 500V. (max. test-V.) dry; good 'recovery' characteristics. Extremely low C.R., average 0.01Ω (10 mΩ) even under adverse conditions. Reliable and positive location-index mechanism. Type-tested for < 50,000 ops. at 16 c.p.m.

MADE with Break-before-Make *or* Make-before-Break contacting, moving contacts having an adequate factor of reserve-resiliency. These switches are used in the highest grades of instruments and equipment all over the world, because of their unfailing accuracy, consistency, and long life.

MAKE-BEFORE-BREAK TYPES

Illus. No.	*List No.*	*Poles*	*Ways*	*Total angle of Move't*
1	S.205	1	18	360°
2	S.206	2	9	160°
3	S.207	3	6	100°
4	S.208	6	3	40°
1	S.249	1	5	80°

(S.249 is an 'adding' switch, with 3 rotor contacts)

BREAK-BEFORE-MAKE TYPES

Illus. No.	*List No.*	*Poles*	*Ways*	*Total angle of Move't*
1	S.435	1	18	360°
2	S.436	2	9	160°
3	S.437	3	6	100°
4	S.438	6	3	40°

SEND FOR CATALOGUE
No. 190 WW
PRICE 1 - POST FREE

MANUFACTURERS OF RADIO AND ELECTRONIC COMPONENTS

BULGIN *Components*
A.F. BULGIN & CO. LTD
BYE-PASS ROAD BARKING
TELEPHONE [illegible]

UNBIASED

By FREE GRID

Contracting Out

THE Post Office van for detecting television pirates, described in the March issue, is of considerable interest, but I cannot agree with the *Wireless World* reporter when he states that, in addition to its primary object, the van could, by a rapid cruise round a given area, determine how many sets were in use at a given time.

The only figures which such a cruise would arrive at would be the number of television sets in operation which were owned by people so lacking in public spirit that they had not taken steps, by carefully screening the walls, floor and ceiling of their television viewing room with ferrous metal, to prevent interference to the ordinary anophthalmic listening of their immediate neighbours. Surely there cannot be any reader of *W.W.* with soul so dead to decency that he did not take immediate action on reading the article by M. G. Scroggie published two years ago this month and to which the writer of the recent note on the detecting van drew attention.

Talking of pirates, is it not time that the present system of licensing was abandoned in favour of a more realistic one?

In the case of ordinary sound broadcasting, there can hardly be a family in the country which does not own a receiver. Should not the demand for the £1 fee be sent automatically by the Income Tax inspector to the head of every family or taken into account when his P.A.Y.E. coding number is calculated. The Trade Union political levy example could be followed and the onus of contracting out placed on the shoulders of non-listeners who would subsequently be visited by a G.P.O. inspector to make sure that they really and truly did not possess a set; those who satisfied him as to this would be required to visit a hospital so that an investigation into their mental state could be made by electro-encephalography and other means.

Television licensing could, of course, be brought into line after the B.B.C. had completed its present constructional programme when some 80 per cent of the population will be within the television service area.

The Radiogramophonicon

IN the February issue I pointed out the need for an improved type of television set which would be provided with "pickup" terminals to enable you to enjoy visual recordings on the c.r.t. in the same manner as you can now enjoy sound recordings on the loudspeaker by using the ordinary pickup terminals of your set. I further suggested that eventually a complete home-entertainment instrument, including a radiogramophone, a television receiver and a visual reproducing unit, would be marketed.

As a result of this, a reader, who is also an inventor, has written to the Editor to draw attention to a brain child of his called the videograph, a prototype of which was illustrated and briefly described in the July, 1950, issue of *Electronic Engineering*. The videograph is an all-embracing home-entertainment instrument, not altogether unlike the one I had in mind. To quote the words of the article describing this new wonder it is "... a normal television receiver with the addition of a simple mechanism for running 16-mm talkie film in front of a small electrostatic c.r.t. which scans through it on to a photoelectric cell and electron multiplier, the output of which can be switched into the video output of the receiver. ..."

In his letter he states that I have shown myself not only unbiased but also unread. He evidently thinks he has forestalled me by eighteen months in describing an all-embracing radio plus video-cum-audio (*pace* Latin scholars) reproducing instrument, but I would point out that I first drew attention to a device of this nature nigh on a quarter of a century ago. At the same time, I mentioned that it was to be called by the none-too-euphonious name of radiogramoscope; presumably the issue of *Wireless World* for December 31st, 1930, escaped the attention of the videograph inventor.

It is true that the videograph of 1950 is a vast improvement on the old radiogramoscope of 1930, but, surely, this is no more than one would expect after twenty years, for after all, "this 'ere progress does go on." As Gibbon says in his "Decline and Fall," "All that is human must retrograde if it does not advance." But even the videograph, marvellous as it is, does not fulfil all I prophesied, as the visual recordings are just cine films and nothing more, whereas I envisaged recordings on film, disc or magnetic tape of the type Baird pioneered on discs long years ago. That I was not talking through my bowler may be seen by referring to the January, 1952, issue of the American journal *Tele-Tech* where we are told that television recording on magnetic tape is already practicable; in fact a recording unit was illustrated.

The correspondent makes the further point that videograph is a more elegant word than radiogramoscope. I would reply that the beautiful old English colloquialism "an't" (usually mis-spelt ain't) is also elegant but it ain't used in the pages of *Wireless World* because the Editor maintains that, despite its elegance, it ain't correct and proper like. The same criticism applies to the word radiogramoscope and I did not conceal my dislike of it when originally writing about it in *Wireless World* over twenty years ago.

The most appropriate name for an all-embracing instrument like that visualized would be "radiogramophonicon" or, if we make it a truly panhellenic word, "actinogramophonicon." Long words, but Lilliputian compared with the 58 letters of the longest Welsh name or the 169 of the longest Greek word. I would, however, suggest as abbreviations "ragron" and "akron," respectively.

Radiæsthesia

MY recent request for a definition of radiæsthesia and teleradiæsthesia (January issue) brought in such a wealth of information from all and sundry that I am quite unable to reply individually, and I hope that all who wrote will accept my grateful thanks.

"Information from all and sundry."

I was misled by the use of the prefixes "radi" and "tele" into thinking that it had something to do with ordinary and long-distance wireless communication and even with television. Actually, radiæsthesia is something which I have always known as rhabdomancy or, in plain English, dowsing. But don't think that teleradiæsthesia is just dowsing at a distance, for it is much more than that. It seems to be closely akin to, if not identical with, what is sometimes known as psychometry.

Is your amplifier good enough for use

by the B.B.C. and many Commonwealth and foreign broadcasting Corporations in Monitor systems and as a driver amplifier in the speech modulator chain of broadcast transmitters ?

by famous record manufacturers for disc recording ?

Professional audio engineers have chosen the TL/12 amplifier for the above applications to help bring to you the music on which you rely for your pleasure.

This is a unique distinction for an amplifier available to the general public

Used with the RC/PA/U pre-amplifier and the best available complementary equipment the TL/12 power amplifier gives to the music-lover a quality of reproduction unsurpassed by any equipment at any price.

These amplifiers are built to a tropical specification and they are distributed throughout the world. During 1951 orders totalling over 2,000 were received from the U.S.A. for RC/PA/U and TL/12 amplifiers for high quality radio/gramophone reproducers for the home.

This illustration shows the RC/PA/U pre-amplifier mounted in a console cabinet designed for armchair operation. The TL/12 amplifier is mounted in the base of the cabinet. The Leak Dynamic pick-up and Leak radio unit are also incorporated. This console was presented to Harold Rawlinson, Esq., conductor of the Insurance Orchestra Society, on the occasion of the Society's Silver Jubilee



RC/PA/U	"POINT ONE" TL/12
REMOTE CONTROL	TRIPLE LOOP FEEDBACK
PRE-AMPLIFIER	12 WATT AMPLIFIER
PRICE 9 GUINEAS	PRICE 27 GUINEAS

Craftsmanship is apparent on inspection. Performance is certified by the N.P.L.

★ A 28-page illustrated booklet describing these amplifiers and containing much information of interest to music lovers seeking the highest standard of reproduction is available free on request. ★

H. J. LEAK & CO. LTD. (Established 1934)

BRUNEL ROAD, WESTWAY FACTORY ESTATE, ACTON, W.3

Phone: SHEpherds Bush 1173 Telegrams: Sinusoidal, Ealux, London. Foreign: Sinusoidal London

ELPREQ PAGES



SERVICE DATA

100 service sheets, covering British receivers which have been sold in big quantities, and which every service engineer is ultimately bound to meet. The following makes are included: Aerodyne, Alba, Bush, Cossor, Ekco, Ever-Ready, Ferguson, Ferranti, G.E.C., H.M.V., Kolster Brandes, Lissen, McMichael, Marconi, Mullard, Murphy, Philco, Philips, Pye, Ultra. Undoubtedly a mine of information invaluable to all who earn their living from radio servicing. Price £1 for the complete folder.

Our folder No. 2 consists of 100 data sheets covering most of the popular American T.R.F. and superhet receivers "all dry" etc., which have been imported into this Country. Names include Sparton, Emmerson, Admiral, Crossley, R.C.A. Victor, etc. Each sheet gives circuit diagrams and component values, alignment procedure, etc., etc. Price for the folder of 100 sheets is £1. Post free.

INDUCTANCE TYPE ATTENUATORS



High fidelity enthusiasts will confirm that an ordinary wire wound volume control in series with a speech coil introduces distortion. We have some inductance type attenuators wound in a very compact manner with heavy stud contacts giving reactance tappings as follows: off 42, 34, 23, 13, 7.9, 4.3, 1.7 0 ohms. You will see that these tappings have been chosen to enable the control to be calibrated in decibels. Price 4/6 each.

5 VALVE AC/DC SUPER-HET



Long, medium and short wave in handsome wooden cabinet, illuminated glass dial with station names, A.V.C., and usual refinements. Size 11in. x 5¼in. x 7in. with B.V.A. valves and built-in aerial. 12 months' guarantee. Limited quantity only. £9.5.- or £3.2.6 deposit and balance over 10 months, carriage and insurance 5/-.

PRICE £9.5.-

ELECTRIC HEATERS

As previously offered but these few remaining have broken feet which makes them suitable only to be mounted permanently on the wall or floor, etc. Special price 15/-, carriage 5/6.



CHARGING SWITCHBOARD

This 550 watt 18 volts charging board is fitted into a steel case with doors and it comprises, three reverse current relays (cut-outs) one voltmeter, one main ammeter, two secondary ammeters, and three variable resistances for controlling load circuits—brand new in original cases £5.10.-, carriage 10/- extra.



VOLUME CONTROLS

We carry a full range of standard-size volume controls from 2K, to 2 meg. Prices are: less switch, 3/-; Single pole switch, 4/-; double pole switch, 5/-. We can also supply midget-type controls, less switch, 4/-; single pole switch, 5/9; double pole switch, 6/6. Each of these midget controls has a serial number and carries a 12-month guarantee by the makers; they are made on the new moulded track principle and really do perform well.

EXTENSION SPEAKER IN METAL CABINET

This has a 6½in. P.M. Goodman's Speaker, heavy magnet type, complete with an output transformer. It is fitted in grey steel case with perforated front and back, ideal for P.A. work in canteens, clubs, etc., 27/6 each.

SLIDER RESISTORS

Heavy Duty Type.
Size 7in. x 1¼in. 11 ohms 4.5 amp. 22/-; Size 9in. x 1¼in. 1.2 ohms 15 amp. 15/-; Size 13¼in. x 1¼in. 3 ohms 10 amp. 15/-.

LAMP HOLDERS

We carry a large assortment of dial lamp holders. Price 6d. each. Order by list numbers.



ALUMINIUM TUBE

Ideal for making T.V. aerials, etc. 1/6 ft.

ANNOUNCING THE OPENING OF A SPECIAL EX-W.D. DEPARTMENT TO HELP OVERSEAS AND HOME CUSTOMERS WHO REQUIRE SPECIAL EX-GOVERNMENT INSTRUMENTS AND GEAR.

We list here some of the equipment which is available (mostly in good used condition). Enquiries regarding these and other ex-Government items should be addressed to (Dept. F.F.) E.P.E. Ltd., Windmill Hill, Ruislip.
Please note at present telephone enquiries cannot be dealt with.

MODULATORS

BC 1203-A.	155
29	216
208	64

POWER UNITS

280	87
PP.32 A.R.	33
526	35

RECEIVERS

25	7601
R111-APR-5A	1622
1626	3515
3085	BC-639-A
1466	1132.A
1124	1139
3540	1120

TRANSMITTER RECEIVERS

1196	1133G
5043	3152
3174	

TEST EQUIPMENT

Cable Tester Type 209. Mains operated insulation tester up to 18 cores, breeze plugs, etc.
WAVEMETER Type 4. Covering 205-220 mc/s.
WAVEMETER 1191A. Covering 100-800 kc/s. 8-20 mc/s.
WAVEMETER 1617. Covering 460-600 mc/s.
WAVEMETER 1239. Covering 15-53 mc/s.
WAVEMETER W117. Covering 125 kc/s.-20 mc/s.
WAVEMETER 1615. Covering 20-26 mc/s. 25-34 mc/s.
WAVEMETER 1432. Covering 160-250 mc/s.
SIGNAL GENERATOR Type 106, Salford instruments 5-50 mc/s in 4 channels.
SIGNAL GENERATOR. T.F. 390 F3 Marconi Ekco 1.6-2.4 mc/s. 18-32 mc/s. 32-58 mc/s. 58-100 mc/s.
SIGNAL GENERATOR. T.F. 390 G3 Marconi Ekco, 1.6-2.4 mc/s 8-16 mc/s. 16-32 mc/s. 32-60 mc/s.
OSCILLATOR UNIT. Type 12A Covering 31-40 mc/s.
OSCILLATOR UNIT Type 55A, 1000-3000 c.p.s. 2.8-10 kc/s 9.8-30 kc/s.
MONITOR Type 25. CRYSTAL MONITOR Type 4A.
MONITOR Type 27 & 28.

COMPLETE RADAR INSTALLATIONS

Our technical department will help you when buying either complete Radar Installations or parts for them.

TEST SETS

44	219
160-A	239
210	240
211	276 x 2
165	205
76	292

MISCELLANEOUS

DRIVE UNIT Type 114.
RACK, Containing:
Panel Amplifier Type 6.
Power Unit Type 6.
SOUND REPRODUCING APPARATUS. Type 11.
STROBE UNIT. Type 61.
AMPLIFIER UNIT A.3562.
RELAY UNIT BC-687-A.
Buzzer Valve Type 2 (morse practice set).
Junction Box JB70A.

MANY OTHER UNITS AVAILABLE—SEND DETAILS OF YOUR REQUIREMENTS

ELECTRICAL INSTALLATION MATERIALS

In addition to our large range of radio accessories we also carry a good stock of electrical wiring accessories, details of a few of these and of cable can be found below :—

T.R.S. CABLES, 250 v. CLASS

3/.029 twin flat	1/4	yd.
3/.029 3 core flat	2/-	,,
3/.029 twin, with earth	1/8	,,
7/.036 twin flat	2/9	,,
7/.029 twin flat	2/-	,,
3/.036 3-core flat	2/8	,,
7/.029 twin with earth	2/4	,,
7/.064 twin flat	4/9	,,

LEAD COVERED CABLES 250 v. CLASS

3/.029 3-core	2/3	yd.
3/.036 3-core	3/8	,,
7/.044 twin	3/3	,,
3/.036 twin	2/-	,,
7/.099 twin	2/9	,,
7/.064 twin	5/-	,,

WAR EMERGENCY TYPE CABLES 250 v. CLASS

These are P.V.C. or rubber insulated, laid flat then braided with cotton and compounded :

7/.029 3-core flat	2/-	yd.
7/.044 twin flat	2/-	,,
7/.064 twin flat	3/3	,,

MULTICORED FLEXIBLES

All are suitable for mains work as the separate conductors are very well insulated, then they are covered overall either with hard rubber, plastic or waterproofed braiding :—

10 core	2/6	yd.
7 core	2/-	,,
5 core	1/-	,,

FUSE BOARD

Iron clad with conduit entry knockouts, 3 way, 15 amp. (6 fuses). Price 15/- each.
Other fuse boards in stock (wood and iron cased) up to 12 way.

LAMP HOLDERS

Bakelite type threaded for ⅜in. with HO skirt 1/6.
Bakelite type threaded for ⅜in. with HO skirt 2/-.
Bakelite type threaded for ⅜in. with switch and HO skirt 3/6.

EDISON SCREW. Cord grip, porcelain 4/6.

WELL GLASS FITTING with porcelain BC lamp holder threaded for ⅜in. less glass 10/-.

DOOR SWITCH. Single pole Crabtree 5 amp flush type switch in iron box with plunger, suitable for controlling lighting of telephone booth, etc. 4/6.

M.E.M. SWITCH FUSES. All insulated, double pole 250 v. 10 amp. 6/- each.

WATERTIGHT SWITCH. Iron clad ⅜in. conduit entry 7/6 each.

SURFACE SWITCHES. 5 amp A.C. bakelite. Price 1/6 each, or 15/- doz. 15 amp porcelain with polished brass cover. Price 1/6 each.

SHUTTERED PLUG. 5 amp 3-pin brown bakelite. Price 1/3 each, or 12/- doz.

SKELETON SWITCH. QMB single pole, square dolly, 3/3 each.

GUESS WHAT FOR £5

In our February "Guess What" competition you will remember that we asked for suggestions as to uses for our IF/AF amplifier. Quite a number of suggestions came in and it was difficult for us to determine which was the best. Three, however, were finally selected and prizes of £5, £3 and £2 have been sent to the lucky ones. In addition to this we have also sent a consolation prize to all who sent a suggestion.

This month we invite you to guess what the object is that we illustrate here. We offer prizes of £5, £3 and £2 for the first three correct ones opened and consolation prizes to all who send in entries regardless of whether correct or not.

There is no need to rush your entry to us you can send it when next ordering providing it reaches us on or before the first post 30th April.

SOMWEAVE

This really lovely loudspeaker fabric we offer at approximately a third of today's cost. It is 42in. wide and our price is 12/- per yard or panels 12in. x 12in., 1/9 each. This is also very suitable for covering plain wooden cases, for portable radio amplifiers, etc.

TUNING UNITS

American made units, available are TU5B, TU6B, TU9B, TU10B, TU13A, TU17A, TU25A, TU47, TU48, TU49, TU51, TU52, TU54, TU60. All 19/6 each, plus 3/6 carriage.



MAGNETIC T.V. TUBES



9in. G.E.C. Flat Ended.
Heater 6.3 v.

From 55/-

These tubes have had very little use and will probably give years of service.

TYPE 1. Have no faults whatsoever and have only had the smallest use. Price £5/15/- each.

TYPE 2. Have small ion burns otherwise in good condition. Price £3/15/- each.

TYPE 3. Have large ion burns but are useful as spare or when first testing out a circuit, or doing repairs etc. Price £2/15/- each.

NOTE: Callers to our Ruislip branch can see these tubes demonstrated but whether you see it or not we guarantee a 'working' tube. If not calling please add 7/6 each tube for packing and postage.

BLANK CHASSIS

18 S.W.G. Aluminium

7 x 3½ x 2	5/-	16 x 10 x 3	8/3
9½ x 4½ x 2½	5/9	16 x 8 x 3	8/-
10 x 8 x 2½	7/-	11½ x 10 x 3	7/6
10 x 5½ x 2½	6/6	16 x 12 x 3	8/8
10 x 9 x 3	7/3	19½ x 9 x 2½	8/3
12 x 9 x 2½	7/3	20 x 10 x 3	10/-
14 x 9 x 2½	7/6	21½ x 9½ x 2½	10/6
14 x 10 x 3	8/-		

Orders by post are dealt with by our Ruislip depot. To avoid delay address to:— E.P.E. Ltd., Dept. 2, Windmill Hill, Ruislip, Middx.

ENAMELLED WIRE
(On wooden reels).

S.W.G.	2 oz. Reel	4 oz. Reel
16	1/3	1/10
18	1/3	2/-
20	1/4	2/2
22	1/5	2/4
24	1/6	2/6
26	1/7	2/8
27	1/8	2/9
28	1/8	2/10
30	1/9	3/-
31	1/10	3/1
32	1/10	3/2
33	1/11	3/3
34	1/11	3/4
36	2/-	3/6
38	2/2	3/10
40	2/4	4/2

TINNED COPPER WIRE

S.W.G.	2 oz. Reel	4 oz. Reel
16	1/3	1/10
18	1/5	2/-
20	1/4	2/2
22	1/5	2/5

DOUBLE SILK COVERED WIRE.

S.W.G	2 oz. Reel	4 oz. Reel
16	1/3	1/10
18	1/3	1/11
19	1/5	2/3
20	1/6	2/6
22	1/8	2/10
23	1/9	3/-
24	1/9	3/-
26	1/11	3/4
27	2/-	3/6
28	2/1	3/8
29	2/2	3/10
30	2/3	4/-
31	2/4	4/2
32	2/6	4/6
33	2/9	5/-
34	2/10	5/2
35	3/-	5/6
36	3/2	5/10
38	3/6	6/6
39	3/9	—
40	4/-	7/6
41	2/3	—
42	2/6	—



SHEET PAXOLIN

Invaluable for when you are experimenting. Size 6in. x 6in., 1/-. Size 12in. x 8in., 2/-. Size 12in. x 12in. 3/6. Size 24in. x 12in., 6/-.

CLIX 15-AMP FOOT SWITCH PLUG

Made to B.S.S. specification, shuttered in moulded bakelite case. 8/6 each.

Orders under £2 add 2/6, under £1 add 1/9. Postable items can be sent C.O.D., additional charge approx. 2/6. List 6d. Early Closing days: Wednesday, Ruislip; Saturday, City.

ELECTRONIC PRECISION EQUIPMENT

WINDMILL HILL, RUISLIP, MDX. Phone: RUISLIP 5780

152-153 FLEET STREET, E.C.4. Phone: CENTRAL 2833

ELPREQ PAGES

10,000 VALVES AT PRE-BUDGET PRICES

You will have read this statement by us on many occasions during the past months. Actually, of course, we have not so many valves at pre-Budget prices now as we had six months ago, but because we have always been valve specialists the above statement is still true, and below is a list showing most of the type numbers of our pre-Budget stock at the time of preparing this page. Many types are available only in small quantities; also where we have only one or two of a type then obviously we cannot have some at each branch. So should you want one, before making a special journey to collect it, ascertain that it is definitely available at the branch to which you intend to call.

In addition to those listed we have available at post-Budget prices, i.e. double tax, many other types which, together with those listed here, make our valve range almost complete, and we can confidently claim to be the premier people in the valve business.

TYPES

ACDD
AC HFP
ACHL
ACHLM
ACME
ACP
ACPEN
ACPNDH
ACPT PEN
ACP1
ACP4
ACSZPEN
ACTH1
ACTH4
AC TZ
AC VH
ACVP1
AC2 HL
AL60
APP4A
APP4 A8
APP4B
APP4C
APP4E
APP8E
AP141
A8L125
A8/4180
AZ1
A5E
A11C
A20B
A30B
A35A
A36C
A40A
A70B
BLL32
BL64
BR302
BTH80
BVA42
BVA43
BVA44
BVA45
BVA47
BVA48
BVA56
B2
B21
B30
CBL1
CBL31
CL4
CL33
CP220
CR54
C1
C1C
CZ
C5B
C9
C10
C10B
C20C
CE3B
C30B
C95A
C95C
C96B
C98N
DAC32
DA30
DC P
DC 80
DCP11
DCP11 HLDD
DC 2A
DC 25G
DC 25GVM
DC 35L
DDA13
DDL4
DD PEN
DDTR13
DDT2
DDT4
DDT16
DDT4
DD40
DD13
DD14
DD40
DD41
DD101
DD202
DD620
DD2530
DEH619
DET19
DF32
DF51
DF92
DH
DH2
DH24
DH30
DH63
DH64M
DH75
DH76
DH77
DH81
DH150
DK91
DL
DL810
DL2
DL2M
DL33
DL35
DL63
DL67
DL82
DL86
DL93
DL94
DL14S
DL74M
DN41
DN143
DPT
DT215
DV80
DW2
DW30
DW4 350
DO26
DO24
DO28
D1
D3
D41
D42
D43
D63
D77
D92
D400
D416
D3507A
EAB1
EAF41
EAF42
EBC3
EBC33
EBC41
EBF2
EBF11
EBF80
EBL21
EB4
EB34
ECC31
ECC35
ECC91
ECH11
ECH21
ECH42
ECL80
EC3
EC81
EC83
EC91
EB30
EF3
EF6
EF8
EF9
EF11
EF13
EF22
EF37A
EF39
EF41
EF42
EF50
EF55
EF80
EF91
EF92
EH2
EK2
EK3
EL2
EL3
EL11
EL33
EL35
EL41
EL42
EL82
EL91
EM4
EY51
EY91
EZ2
EZ35
EZ40
EZ41
EZ80H
FC2
FC2A
FC4
FC13
FC13C
FC141
FT104
FW4,500
F8R
GR2
GU1
GU50
G4120
HD13
HD14
HD24
HPP13
HLA7
HL DD1320
HL2
L1
HL4
HL40
HL13
HL13C
HL21
HL21DD
HL23
HL23DD
HL41
HL41DD
HL42DD
HL44DD
HL73C
HL133
HL133DD
HL210
HL1320
HPB 13
HP13
HP210
HP211C
HP215
HP2115
HP4101
HP4101C
HP4106
HP4106C
HP4106G
HP4108
HP4115
HR2
HR2S
HR210
HVU1
HW20L
H2
H2MN
H4D
H13
H20
H30
H42
H63
H141D
IRV120 350S
J240
KBC32
KCF30
KF35
KK32
KL4
KL32
KL35
KTW61
KTW61M
KTW63
KTW73
KTW74
KT2Z
KT24I
KT2B3
KT2
KT4
KT5
KT24
KT30
KT31
KT32
KT33C
KT35
KT44
KT61
KT63
KT66
KT66DD
KT66S
KT71
KT72
KT74
KT76
KT81
KT230
KT263
KW32
K23B
K30G
K30K
K33A
K33B
K40N
K50N
K52
K70B
K70D
K90A
K183
K404
LB210
LD2
LD210
LG210
LL4
LP2
LP220
L1
L2
L2DD
L13
L21DD
L63
L77
L410
M2E
ME920
MHD4
MHL4
MHL13
MH4
MH41
MH206
MH4103
MH4106
MH4106
MKT4
ML4
ML6
MP PEN
MR1
MS PEN
MS PENB
MSP4
MSP41
MS4
MS4B
MS4C
MU4105
MVSPEN
MVSPENB
MX40
NHL 13
NHL13L
NH4106
N14
N16
N17
N18
N30
N42
N77
N78
N142
N145
N147
OC16L
OD3
OM4
OM6
OM9
O202
PA1
PA80
PD220
PD220A
PD3521
PENB4
PENDD 1340
PENDD 2530
PENDD 4020
PENDD 4021
PEN4DD
PEN4VA
PEN23
PEN24
PEN25
PEN30C
PEN40DD
PEN45
PEN45DD
PEN48
PEN220
PEN220A
PEN231
PEN383
PEN453DD
PEN3520
PJ10
PL32
PL36
PL38N
PL81
PN1ML
PM2A
PM2B
PM2HL
PM3
PM12
PM12M
PM14
PM20
PM22
PM22A
PM22D
PM24A
PM24M
PM25
PM26E
PM26E
PPL4
PP2
PP3 250
PP3 425
PP5 400
PP5B
PP5C
PP5E
PP13A
PP24
PP24B
PT250
PV29
PV495
PX230
PX2408W
PY30
PY32
P2
P41
P61
P140N
P215
P220
P220A
P425
P430
P610
P625A
QP21
QP22A
QP22B
QP25
QP42
QP230
RB41
RB120
RC1030 1300
RF120
RG12D60
RK34
RV12P2000
RX210
R8
SD2
SD4
SD20
SE211
SE211C
SG220
SG2026W
SG410
SP4A
SP6
SP2B
SP2D
SP4
SP4B
SP13
SP13C
SP13B
SP20
SP22
SP41
SP42
SP42P
SP61
SP210
SP215
SP220
SP1320
SP2220
SQT4
SZ210
SU25
SU61
SU215G
SW1
S3DD
S4A
S4V
S8
S23
S130
S215VM
S217
S410
S410N
S435N
S1328
TBC14
TBL14
TBL44
TB053
TB10E
TB12E
TB622
TB5013
TB9020
TDD2A
TDD13
TDD13C
TDD25
TE564
TF44
TH2
TH4
TH13C
TH21C
TH29DA
TH30
TH30C
TH223
TH2321
TM1
TM14
TP22
TP23
TP25
TP26
TP220
TP320
TP2020
TSE4
TSP4
TT4
TT4A
TX4
TX21
T6
T20
T31
T32
UAF41
UAF42
UBC41
UBF80
UBL21
UB41
UCH21
UCH42
UD41
UFW29L
UF41
UF42
UL41
UL44
UL46
UM34
UR3
UR3C
UR13
UU7
UU9
UU30 250
UU41
UU80 250
UX6
UY21
UY41
U4
U17
U21
U25
U35
U37
U50
U52
U71
U74
U76
U82
U146
U281
U404
U916
U920
VMP4G
VM4K
VO28
VO13
VO135
VP2
VP2B T
VP2B
VP2D
VP4
VP4C
VP13
VP13A
VP13C
VP13K
VP13X
VP14
VP20
VP23
VP28
VP41
VP41E
VP80
VP133
VP210
VP210DD
VP1320
VP1322
VR1C
VR3
V312
V872
V914
V1907
V5116
WD142
WE1
WE3
W76
W77
W81M
W142
W143
W145
X7
X14
X17
X20
X24
X31
X41C
X53
X64
X71M
X73
X73M
X76M
X78
X81M
X142
X143
X148
X150
X410
Y13
Y53
Y220
ZD
ZDE
Z14
Z21
Z22
Z26
Z62
Z66
Z77
OZ4
01307M
1A4E
1A4G
1A5GT
1A5GT G
1A6
1A6E
1B4
1B4E
1B8-208
1BC1
1B7G
1B42
1B122
1C1
1C5GT C
1C8
1C7G
1D6
1D7G
1FW4A
1F2
1F3
1F5G
1F6
1F7GH
1G4G
1G6G
1H4G
1J6
1LA4
1LA4E
1LA6
1LB5
1N5GT
1P10
1P11
1Q5G
1Q5GT
1RF120
1R8
1R5
1S4
1S5
1T4
1T5GT
1V
2
2A5
2A6
2A7
2A8
2D4A
2D4B
2D13
2D13C
2D17
2P
2YR215
2X2
2Z3
3A4
3Q6
3V4
3Y4
4D1
4THA
4TPB
4TSP
4XP
4.100 BU
5U4G
5X4G
5Y3G
5Y3S
5Y4
5Z3
6AC7
6AE5
6AE6
6AG7
6A3
6A6
6A7
6A8G
6BA6
6BE6
6B5
6B7
6B7G
6B7M
6B8
6B8G
6C4
6C5
6C5GT
6C6
6C7
6C8
6C9
6C10
6D2
6D3
6D4
6D6
6E6
6F1
6F5
6F5GT
6F6
6F7
6F7E
6F8
6F13
6F14
6F15
6F16
6F33
6G5G
6G6G
6H6
6H7
6H6Z
6J5
6J7
6J8
6K5
6K6
6K7
6K8
6LD20
6LFG
6L5
6L6G
6L7G
6L18
6L19
6N6GT
6N7
6P5
6Q7
6Q8GT
6R7
6SA7
6SA7G
6SF7
6SG7
6SH7
6SJ7
6SK7
6SL7
6SN7
6SQ7
6SS7
6S7
6T7
6U7
6U7S
6V7
6W5
6W7
6X5
6Y4
6ZY5
6Z3
7A2
7A7
7B5
7B7
7C5
7C6
7C7E
7D3
7D5
7Q7
7S7
7Y4
8A1
8D2
9D2
10C1
10D1
10D2
10F1
10F3
10F9
10LD11
10P14
11D3
11D5
12A5
12A6
12A7
12AT7
12AX7
12E5
12J7
12K7
12K8
12SA7
12SQ7
12SF3
12SJ7
12SK7
12SQ7
12SK7
12Z3
13VPA
15
15A2
15D2
15E
18
19
20C
20D1
20D2
20F2
21A
22EN41
24
24A
24E
24G
25A6
25B5
25L5
25L6
25Y5
25Z5
26
27
28D7
30
31
32E
33
34
35
35L6
35Z4
35Z5
36
36E
37
38
39
41
41E
41MDG
41MH
41MHL
41MLF
41MP
41MPG
41MPT
41MRC
41MSG
41MTA
41MTL
41MTS
41MXP
41STH
42
42A
42E
42MP PEN
42MPT
42PTB
43
43IU
44E
45
45IU
45Z5
46
47
48
49A
50A5
50L6
50T6
55
56
57
58
59
61BT
61SPT
62BT
62DDT
62TH
62VP
66KU
67PT
70A7T
71A
78
78A
79
77
78
78E
79
80
82
83
84 6Z4
85
89
101
104V
105605
110
118A
1177
1177Z8
120
124
130A
130B
154V
161
164V
185R8
185BT
202DDT
202MPG
202STH
202VP
202VPB
203THA
210DDT
210DG
210HF
210HL
210LF
210RC
210VPT
215P
215SG
220B
220HPT
220P
220PA
220PT
220TH
220VPB
220VS
220VSG
222JH
225DU
230PEN
230XP
240QP
244V
299L4
301
302THA
303
304
307A
329
340
354
354V
4020T
402P
402PEN
410HF
410PT
415PG
415XP
423PT
425P
425XP
484V
523
607G
646
686
717A
802
807
904V
954
955
994V
1215GT
1506
1619
1632
1642
1701
1801
1821
1904
1912
1915
1920
1927
1928
1934
2050
2059
2101
2102
2103
2151
2200T
2201PT
6153T
6336A
9004
13201A
1179GT G

TRANSFORMER BARGAINS

All by famous makers.

200 mA., 340-0-340 v. 6.3 v. at 4 amps., 5 v. at 4 amps., 4 v. at 3 amps., unshrouded but fully impregnated, a really first-class transformer. Price 25/-.

150 mA., 425-0-425 v. 6.3 v. at 6 amps., 6.3 v. at 6 amps., 5 v. at 3 amps., 4 v. at 2 amps., 4 v. at 1 amp. Price 65/-.

150 mA., 350-0-350 v. 6.3 v. at 4 amps., 5 v. at 3 amps., upright mounting. Price 32/6.

80 mA., 300-0-300 v. 6.3 v. at 4 amps., 4 v. at 3 amps., half shrouded drop through. Price 18/6.

80 mA., 320-0-320 v. 6.3 v. at 4 amps., 5 v. at 3 amp ., half shrouded drop through. Price 19/6.

70 mA., 230-0-230 v. 6.3 v. at 3 amps., 5 v. at 2 amps, fully shrouded upright mounting. Price 22/6.

60 mA. 260-0-260 v. 6.3 v. at 3 amps., 4 v. at 2 amps., half shrouded drop through. Price 16/6.

60 mA., 260-0-260 v. 4 v. at 4 amp ., 4 v. at 2 amps. Price 16/6.

T.V. TRANSFORMERS

TYPE 1.—Fixed Primary H.T. Secondary 425-0-425 v. at 250 mA. 4 v. at 6 to 8 amp., 4 v. at 5 to 6 amp., 5 v. at 2.5 amp., 2 v. at 1 amp. Dimensions are 4½in. × 4in. × 4¼in. Price 27/6, plus 2/6 packing and postage.



TYPE 2.—Primary as Type 1 H.T. Secondary 300-0-300 v. at 150 mA. L.T. 7.5-0-7.5 v. at 3 amps. and 4 v. at 3 to 4 amps. Dimensions are 4½in. high × 4in. × 3¼in. Price 17/6, plus 2/- postage and packing.

AUTO TRANSFORMERS

For operating 100 v. apparatus off 230 v. mains or vice versa.

Totally enclosed 50-75 watts 20/-

Totally enclosed 100-150 watts 32/6

Open Type, 100-150 watts 25/-

FILAMENT TRANSFORMERS

6.3 v. at 1 to 1.5 amps., standard type for receivers. Price 6/6.

6.3 v. at 1.5 to 2 amps., standard type. Price 8/3.

2 v. 2.5 amps., highly insulated for television. Price 7/6.

RADIO CHEMICALS CLEAR CEMENT

Almost instantaneous drying for coil winding and all repairs, 1/6 per tube.

"ENAMACLEAN." For safely removing the enamel off the finest wires, 2/- per tube.

RADIOGRAM CABINET

Console Type Cabinet with full grained walnut finish, will take standard type auto change gram unit. Price £12/10/-, or £4/3/6 deposit.

Radio Chassis to suit, £10/19/6, plus 7/6 carriage and insurance.

Auto Change Units, three-speed, £15/10/-. Standard, £11/15/-.

Special Offer. Cabinet, Radio Chassis and Standard Changer, £34 or £12 deposit.

A POWER PACK FOR 15/-



Efficient power supply, O.K. for operating a receiver, amplifier, instrument or other device requiring up to 60 mA. at approx. 250 v. Parcel consists of filament transformer, rectifying valve, smoothing resistor and 16 × 16 mfd. 350 v. Electrolytic condenser. Note the filament transformer will supply enough current to operate 3 or 4 other 6.3 valves.



THIS MONTH'S SNIP

only £10.19.6

7 VALVE, 5 WAVE-BAND RADIO CHASSIS

A famous set by a famous manufacturer. Undoubtedly a serious listener's receiver. Among many special features are a H.F. stage and tuning indicator. Tunes up to 11-metre band. Price new less all valves, less speaker, £10/19/6, carriage and packing 15/-, partly returnable. A.C. mains and car-battery models are available.

H.P. TERMS. £3/13/6 deposit and 10 monthly payments of 16/9.

DEMOBBED VALVES

Gives the commercial equivalents of many thousands of Service valves, and conversely give service equivalents of commercial types, an invaluable publication recently revised. Price 2/3.

AUTO-CHANGE GRAM UNITS

Single speed and 3-speed models available from stock. The one illustrated is the Collaro 3-speed model with dual-purpose pick-up. Price £15/11/9, carriage paid.

Orders by post are dealt with by our Ruislip depot. To avoid delay address to Electronic Precision Equipment, Ltd., Dept. 2, Windmill Hill, Ruislip, Middlesex.

EX-GOVT. CATHODE RAY TUBES

Note :—All these tubes have green fluorescence.

VCR97. Brand new and unused these are not the "cut-off" type. Gives full picture. Price 42/6, carriage and insurance 5/- extra.

5CP1. 5in. electrostatic, American manufacture—medium persistence, suitable for T.V. or 'scope, in original cartons, 19/6, carriage and insurance 2/6.

VCR139A. 2½in., 27/6, plus 2/6 carriage etc.

VCR516. 9in. magnetic tube, long persistence which makes it rather unsuitable for T.V. Price £2/10/-, postage and insurance 10/-.

CV3776. 5in. electrostatic medium persistence suitable for experimental T.V. or 'scope work—unused 22/6, plus 5/- carriage etc.

VCR138. 3½in. electrostatic short persistence, suitable for T.V. and ideal for 'scope work, 27/6, plus 3/6 carriage, etc.

VCR112. 5in. electrostatic, persistence not known, 22/6 each, plus 5/- carriage, etc.

CV966. 6in. electrostatic, persistence not known, 22/6 each, plus 5/- carriage, etc.



EX-ROYAL NAVY SOUND POWERED TELEPHONE

These require no batteries, and will go for long periods without attention. Complete with generator and sounder which gives a high pitched note, easily heard above any other noise. Also fitted with an indicator lamp which in quiet situations can be used instead of the sounder, or where several 'phones are used together will indicate which one is being called. Size 7½in. × 9in. × 7½in., wall mounting, designed for ships' use, but equally suitable for home, office, warehouse, factory, garage, etc. Price 37/6 each, plus 3/6 carriage.

ADJUSTABLE THERMOSTAT



These have silver contacts rated at 1 amp. 250 v. and can be adjusted to operate from 70° to 900° F. These are suitable for directly controlling aquarium heaters, electric blankets, etc., 3/6.

Orders under £2 add 2/6, under £1 add 1/9. Postable items can be sent C.O.D., additional charge approx. 2/6. List 6d. Early closing days: Wednesday, Ruislip; Saturday, City.

ELECTRONIC PRECISION EQUIPMENT

WINDMILL HILL, RUISLIP, MDX. Phone: RUISLIP 5780

152-153 FLEET STREET, E.C.4. Phone: CENTRAL 2833

D. COHEN

RADIO & TELEVISION COMPONENTS

MAINS TRANSFORMERS

These transformers are all famous radio manufacturers' surplus and are fully interleaved, impregnated and guaranteed.

Primary 200-250 v. P. & P. on each, 1/6 extra.

350-0-350, 100 m.a., 4 v. 4 amp., 4 v. 2 amp., upright or drop-through, **16/-**.

300-0-300, 100 m.a., 6 volt 3 amp., 5 volt 2 amp., **17/6**.

250-0-250, 100 m.a., 6 v. 3 amp., 4 v. 3 amp., 4 v. 3 amp., **17/6**.

250-0-250, 60 m.a., 6 v. 4 amp. (to be used on common heater chain with 6 x 5 rectifier), **13/6**.

280-0-280, 80 m.a., 6 v. 3 amp. 4 v. 2 amp., drop-through, **14/- Drop thro'**, 350-0-350 v. 70 m.a., 6 v. 2.5 amp., 5 v. 2 amp., **14/6**

280-0-280, semi-shrouded drop-through. 80 m.a., 6 v. 3 amp., 5 v. 2 amp., **16/6**.

Semi-shrouded, drop-thro' or upright mounting 280-0-280, 80 m.a., 4 v. 6 amp., 4 v. 2 amp., **12/6**.

Auto-wound, H.T. 280 volts at 360 m.a., 4 v. 3 amp., 2 v. 3 amp., or 6 v. 3 amp. Separate 4 v. 3 amp. rectifier winding (upright or drop-through), **18/6**.

350-0-350, 120 m.a., 4 v. 4 amp., 4 v. 3 amp., drop-through, **21/-**.

Auto-transformer, various combinations of voltages including 110 v. 70 watt, and 3 4 volts windings at 1 amp., 2 volt 1 amp., drop-through or upright mounting, **10/6**.

Heater Transformer. Pri. 230-250 v., 6 v. 1½ amp., **6/-**; 2 v. 2½ amp., **5/-**. P. & P. each **9d.**

P.M. SPEAKERS

	with trans.	less trans.
2½in.	—	13/6
3½in.	—	11/6
5in.	15/-	12/6
6½in.	14/6	11/6
8in.	17/-	14/6

10in. M.E. Speaker Field Coil, 1,100 ohms, speech coil 2-3 ohms, 17/6.
P. & P. on each of the above 1/- extra.

6½" energised Television Speaker by PLESSEY. Field resistance 68 ohms with humbucking coil. Will pass up to 300 mA, require minimum 200 mA to energise. These are cheaper than a T.V. choke. **9/6** each. 2 for **18/-**.

Constructor's Parcel, comprising chassis 10½ × 5½ × 2in., with speaker and valve holder cut-outs, 5in. P.M. speaker with transformer, twin gang with trimmers, pair T.R.F. coils long and medium iron cored, four valve holders, 20K. volume control and wave-change switch. Post paid **21/-**.

Volume Controls, by famous manufacturer. Long spindle less switch, 50K., 500K., 1 meg., **2/6** each. P. & P. 3d. each.



PERSONAL PORTABLE CABINET

in cream-coloured plastic; size 7 × 4½ × 3in. Complete 4-valve chassis scale and 3 knobs. Takes miniature 90 v. and 7½ v. batteries. **9/-**, post paid.

2½in. P.M. Speaker to fit above, **13/6**. Miniature output transformers **5/-**. Miniature wave-change switch **1/6**. Miniature 1-pole 4-way used as Volume and Off **1/6**. 4 B7G valve holders, **2/-**. Midget twin gang ½in. dia., ¾in. long and pair medium and long-wave T.R.F. coils ½in. long × ¼in. wide; complete with 4-valve all-dry mains and battery circuit **8/6**. Condenser Kit, comprising 11 miniature condensers, **3/6**. Resistor Kit, comprising 12 miniature resistors, **3/-**.



View of chassis as it would look when assembled with valves inserted.

Pensolda 6 volt Light Weight Soldering Iron, weight 3½ ounces complete with 1½ yards circular flex, and suitable heater transformer. Primary 230/250 volts, **10/6**. Post & pack., **1/9**.

ELECTROLYTIC CONDENSERS

32 mfd., 350 working	2/6	25 mfd., 25 working	1/2
16 x 24, 350 working	5/-	100 mfd., 12 v. working	1/3
4 mfd., 200 working	1/3	250 mfd., 12 v. working	1/-
40 mfd., 450 working	3/9	16 mfd., 500 wkg., wire ends	3/3
16 x 8 mfd., 500 working	5/-	8 mfd., 500 v. wkg., wire ends	2/6
16 x 16 mfd., 500 working	5/9	8 mfd., 350 v. wkg., tag ends	1/6
8 x 8 mfd., 450 working	3/6	50 mfd., 25 v. wkg., wire ends	1/9
32 x 32 mfd., 200 v. working	2/-	10 x 6 x 2 x 2 mfd., 500 v. wkg	5/-
1 mfd., 500 v. working	1/6	16 x 8 mfd., 350 v. wkg	3/-
32 x 32 mfd., 350 working	4/-	50 mfd., 250 v. wkg	1/9
32 x 32 mfd., 350 working and 25 mfd., 25 working	6/6	Ex-Govt. 8 mfd., 500 v. wkg., size 3½ x 1½, 2 for	2/6
50 mfd., 12 v. working	1/6	Post paid.	

MAINS or BATTERY SUPERHET PORTABLE COILS. Comprising medium-wave frame aerial and long-wave loading coil, used as aerial coils. Midget iron-cored screened L.M. osc. coils., complete with circuit I.F. frequency 465 Kc., **9/6**.

METAL RECTIFIERS, 250 v. 60 m.a., latest midget Selenium type, **6/6**, post pd.

OUTPUT TRANSFORMERS. Standard type 5,000 ohms imp., 2 ohms speech coil, **4/9**; Push-pull 6 v. 6 matching 10-watt 2-ohms speech coil, **6/9**. 42-1 speech coil 2 ohm with extra feed-back winding, **4/3**; Miniature 42-1 2-ohm speech coil, **3/3**.

SET OF 3 BROWN KNOBS marked "wave change," "tuning," and "volume," **1/6**.

6-VOLT STANDARD 4-PIN VIBRATOR **8/6**

EXTENSION-SPEAKER CABINET
5in. speaker, complete with volume control and 2 yds. gold flex, in a really outstanding cabinet in silver and green. Ideal for bedrooms, etc. Worth double. **23/6**, post paid.

TELEVISION MASKS

White Rubber. 9in. with glass, **10/6**. 15in. white rubber mask, soiled, **12/6**, plus 1/- P. & P.

All-Dry A.C. Mains Supply Unit size 3¼in. long x 2¾in. wide x 1¾in. deep. We can supply a complete all-dry circuit, using the above Midget Components to incorporate the above Power-Unit, **19/6**, post paid with circuit.

Midget Bakelite Cabinet. 7in. x 5¼in. x 5in. c/w. 5-valve s.h. chassis, m. od. long-wave scale and back (takes std. twin gang condenser and 3½in. speaker). **15/-**. P. & P. 1/6.

Wave-Change Switches. 6-pole 3-way, **2/-**; 4-pole 3-way, **1/9**; 5-pole 3-way, **1/9**; 3-pole 3-way, **1/9**; 2-pole 1-way midget, **1/3**; 2-pole 1-way, **1/3**; 9-pole 3-way, **3/6**. P. & P. 3d. each.

Pre-Aligned Midget 465 Kc. Q. 120, **9/-** per pair, post 6d. **Miniature 465 Kc. I.F.s.** Q. 120, per pair, **10/-**.

465 Kc. Midget I.F.s. Q.120, size 1¼in. long, 1in. wide, ¾in. deep, by very famous manufacturer. Pre-aligned adjustable iron-dust cores, per pair, **12/6**. **465 Kc. Iron-Cored.** Q.120, size 3½ x 1in. dia., **7/6**.

Iron-Cored 465 Kc. Whistle Filter, 2/6.

T.V. Chassis. Size 9½ x 9½ x 3½in., **3/-**.

Standard 465 Kc. I.F.s. Q.120 iron-cored, 3½ x 1½ x 1¾in., per pair, **9/6**.

Valve Holders. Paxolin international octal, **4d.** each. Moulded international octal, **7d.** each. EF50 ceramic, **7d.** each. Moulded B7G, slightly soiled **6d.** each.

Line Cord. 3-way 0.3 amp. 180 ohms per yard, **1/3** per yard. **Ceramic P.F.S.** 3 each of the following: 330, 220, 180 and 82, **2/6**.

Trimmers. 5-40 pf., **5d.**; 10-110, 10-250, 10-450 pf., **10d.** Three-bank, 50 pf., **1/3**. Four-bank, 50 pf., **1/6**.

Twin-Gang .0005 Tuning Condenser, 5/-. With trimmers, **7/6**. Post and packing 6d. **Twin-Gang Midget .00037** with perspex dust-cover and trimmers, **8/6**. Post and pkg. 6d.

Mains Droppers. 0.3 amp., 460 ohms, tapped 280 and 410, **1/6**; 0.2 amp., 717 ohms, tapped at 100 ohms, vitreous, **1/6**; 0.3 amp., 950 ohms, tapped 700 and 825, **2/6**; 0.2 amp., 1,000 ohm, vitreous, tapped, **2/6**. P. & P. on each 3d.

Volume Controls by famous manufacturer. Long spindle and switch, ¼, ½, 1 and 2 meg., 4- each; 20, 25 and 50 K., **3/6** each. Post and packing 3d. each.

Constructor's 465 kc. I.F. Kit, comprising 4 double pie wound coils on ¾in. Aladdin formers, 4 iron cores, 2 cans 3½ x 1⅝ x 1¼in., four hundred pf. silver mica 5%, and two paxolin mounting panels, **4/6**, post paid.

Television Chassis: Size 9½ x 9½ x 3½" 18 gauge steel cadmium plated complete with 5 coil cans size 1½ x 1" with iron cored former. These are wound for television frequency. **6/6** each.

***Terms of business:* Cash with order. Dispatch of goods within 3 days from receipt of order. Where post and packing charge is not stated please add 6d. up to 10/-, 1/- up to £1 and 1/6 up to £2. All enquiries and Lists, S.A.E.**

D. COHEN

RADIO & TELEVISION COMPONENTS

LINE & FRAME SCAN COIL (removed from chassis), low impedance line, high impedance frame.



LINE & E.H.T. TRANSFORMER 5 Kv. (removed from chassis). Rectifier winding EY51. Will match scan coils. Both items 25/-. Not sold separately.

HEATER TRANSFORMER. Primary 230-250 v., Secondary 2 v., 2.5 amp. 5/-.

FRAME O.P. TRANSFORMER, inductance 10 hen., ratio 10-1. 9/6.

FRAME BLOCKING OSCILLATOR TRANSFORMER. Price 4/6.



SMOOTHING CHOKE. 2 henry 200 mA. Price 3/6.

SAME AS ABOVE, but complete with 2 ½-watt resistors, 1 ½-watt, .001 miniature Hunts and 5,000 ohm 3-watt vitreous. 5/-.

THREE WAVE BAND COIL PACK, iron-cored coils, 16-50, 180-550, 1,000-2,000 metres I.F. frequency 465 Kc. Size 4½in. x 1½in. x 2½in., 24/-, post paid. Double-ended perspex trimming tool given free with each pack.

AMPLIFIER CABINET in cast aluminium, with chromium plated grille complete with 5-valve chassis, with transformer and electrolytic cut-outs in 18 gauge aluminium. Size 12 x 8½ x 5½in. Sloping front. Knobs not supplied. 25/-.

CONSTRUCTOR'S PARCEL, comprising 5-valve superhet chassis with I.F. and electrolytic cut-outs, size 13 x 6½ x 2½in., complete with 3-wave band scale (new wave lengths), size 11½ x 4½in. approx., drum, drive spindle, back plate, two pulley wheels and five International Octal Paxolin valve holders. 11/6 post paid.





CABINET, as illustrated, requires repolishing. Size 19½in. x 12in. x 9in. Size of scale cut-out 8½in. x 4½in. 15/- post paid.

CONSOLE CABINET, requires repolishing. Size 33in. x 20in. x 13in. with sloping front, 3 bars across fret. Size of scale cut-out 8½in. x 4½in. FOR PERSONAL SHOPPERS ONLY. 30/-.

MOTOR MOUNTING BRACKET in 12-gauge aluminium. Post and packing 1/-. 7/6 each.

TELEVISION CHASSIS 19 valve-holder cut-outs. Complete with 5 Amphenol Octal valve holders and various tag panels. Size 14½ x 12 x 1½in. 18 gauge aluminium. Post and packing 1/6. 10/-.

AMPLIFIER CHASSIS, 18 gauge aluminium, 5 valve holders, transformer and 2 electrolytic cut-outs, size 11½ x 7½in., sloping front. Post & packing 1/-. 4/- each.

CHOKES
100 mA. 10 hen. 7/-.
60 mA. 8-10 hen. 4/9.

P.M. FOCUS UNIT. For any 9in. or 12in. tube, except Mazda 12in., state tube, 12/6.

P.M. FOCUS UNIT. For Mazda 12in., 15/-.

Similar to above, but with front adjustment. 2/6 each extra

R. & A. mains energised 1,600 ohm field, O.P. transformer, 5,000 ohm impedance. 18/6, post and packing 2/-

ROLA 5in. P.M. with O.P. transformer. 16/6.

6-IRON CORED COILS on Aladdin formers 13.5-50 metres, 198-550 metres, 950-2,000 metres. Tuned with a .0005 gang, I.F. frequency 465 Kc. Complete with circuit. 8/6.

ION TRAPS for Mullard or English Electric tubes. 5/-, post paid.

23 HIGH STREET (Opposite Granada Cinema), ACTON, W.3

Hours of Business: Saturdays 9—6 p.m. Wednesdays 9—1 p.m. Other days 9—4.30 p.m. Telephone: ACOrn 3981

GARLAND BROS. LTD

LEAK



THE LEAK "POINT ONE." TL/12 12 watt triple loop feedback amplifier, price **27 guineas**, and the RC/PA/U remote control pre-amplifier, price **9 guineas**, need no introduction. Their quality and craftsmanship, unsurpassed anywhere in the world, have been given tangible recognition by orders from the B.B.C. and other national broadcasting authorities, and from quality enthusiasts everywhere.

ROGERS



We have no figures on the number of "Williamsons" built and sold since its first introduction in the pages of this journal, but it must surely be among the most popular amplifiers of its class in the world. The quality and finish of the Rogers Version is second to none. Price of the amplifier is **£29**, and of the pre-amplifier and tone compensation unit with engraved control panel **£10 7 6**. Other Rogers products featured by us include the "Junior de Luxe" 10 watt amplifier at **£25 10 -** (with engraved control panel), the "RD Baby de Luxe" at **£17 10 -** (with pre-amplifier and engraved control panel), the "RD 9 Kcs. Rejector Unit" at **£3 15 -**, and the "RD GP20 Adaptor Unit," providing accurate compensation for standard and L.P. Recordings with Acos GP20 Pickup.

GARLAND ACIV AMPLIFIER

We can now give immediate delivery on this amplifier. Specification is as follows : Maximum output, 11.5 watts. Frequency response, flat from 20 c.p.s. to 30,000 c.p.s. Total harmonic distortion, measured at 1,000 c.p.s. for 8 watts output with tone controls at zero setting, less than 0.2 per cent. 26 db negative feedback over output transformer, output valves, phase splitter and driver. Two inputs, requiring respectively 0.03 v. and 0.25 v. for total output. Treble and bass boost controls. Power supplies for tuner unit or magnetic recording pre-amplifier. Input socket for magnetic recording pre-amplifier. The valves used are 6SH7 triode, 6SH7 pentode, 6SH7 triode, KT61, KT61, 5Z4. The output transformer is a Goodman H.6, specially wound for us, with primary inductance 100H, ten-section wound, giving negligible leakage inductance and self-capacitance, thus permitting a high level of feedback without phase-shift or instability. The output is for 3.75 ohms or 15 ohms. The amplifier is supplied assembled and tested, for use on A.C. mains, 200-250v. Price is **£14 14 -**, carriage forward. Crate is charged £1, refunded on return carriage paid to us.

MODIFICATION UNIT UE2. A pre-amplifier and oscillator unit, designed for use with the above or similar high quality amplifier, thus providing the finest possible magnetic recording and reproduction, limited only by the characteristics of the tape desk or table used. An EF37A low-noise pre-amplifier is used, and an oscillator supplying h.f. bias and erase sufficient for the highest coercivity tapes. A neon is used for recording level indication. No power supplies are incorporated : these are normally supplied by the main amplifier. The unit is supplied assembled and tested. Price is **£5 5 -**, plus carriage 5/-.

ACOUSTICAL

The Acoustical Quad 12 watt amplifier, priced at **£35** including pre-amplifier, is of particular appeal to the musician, containing as it does provision for elimination of sum and difference harmonics and compensation for increase in distortion in the actual programme signal at different settings.

CONNOISSEUR. The Connoisseur two-speed motor is designed and made to laboratory standards, for those who want the best. The two speeds, 33⅓ and 78 r.p.m., are selected by a switch ; the turntable is 12in. diameter with precision ground and lapped main spindle running in phosphor bronze bearings ; the synchronous motor is vibrationless and is suitable for playing standard, transcription and microgroove recordings. Price is **£22 18 8** including purchase tax. The Connoisseur super-lightweight pickup, for use with the above, has interchangeable heads for standard and microgroove recordings. The armature system, which is fitted with semi-permanent sapphire, is easily replaceable. The price, complete with two heads, is **£10 0 8**.

LOUDSPEAKERS FOR HIGH QUALITY REPRODUCTION. Among our large stocks of loudspeakers, the following are specially recommended for high quality reproduction and suitability for use with the other audio equipment mentioned on this page.

12in. Vitavox K12/20, 15 ohm	£14	0	0
12in. Goodman Axiom 150, 15 ohm	£10	5	6
12in. Goodman Audiom 60, 15 ohm	£8	12	6
12in. Wharfedale 12 C.S., 15 ohm	£9	0	0
10in. Wharfedale Golden, 3 ohm	£5	7	6

EDISWAN 3-SPEED AUTO-CHANGERS. Plays eight 78 r.p.m., ten 33⅓ r.p.m. or 45 r.p.m. records. Replaceable double-pointed sapphire stylus, **£23 13 -**.

THE GARLAND TAPE RECORDER

As pioneers in the field of magnetic recording in a reliable but inexpensive form, it gives us great pleasure to introduce the Garland Tape Recorder.
This is not a kit, but a complete assembly, ready to plug into the mains. No wiring or soldering to be done—just plug in and recordandplayback from radio, microphone or pickup. Incorporating the new Lane Tape Table and the UE7 Amplifier, housed in a handsome walnut veneered cabinet, and supplied complete with a 1,200ft. reel of Scotch Boy high coercivity tape and a spare spool.
For A.C. mains, 200-250 v. Demonstrations at Deptford and Lewisham.

UE7 MAGNETIC RECORDING AMPLIFIER. A six valve record-playback amplifier suitable for use with high impedance heads. Features include variable bass and treble lift, neon recording level indicator and built-in oscillator supplying h.f. bias and erase sufficient for the highest coercivity tapes. High grade output transformer and 8in. P.M. speaker included. Controls are mounted on separate metal panel. The amplifier is supplied assembled and tested, for A.C. mains, 202-250 v. Price is **£11 11 -**, plus 7/6 carriage.

PRICE £35, plus 15 - carriage. Crate charge £1 (not charged if you undertake on your order to return crate carriage paid to us).

THE NEW LANE TAPE TABLE. A new and greatly improved version of the popular "Lane." New features include the use of three motors instead of one as before, and very fast wind-on and rewind (under one minute), thus enabling particular recordings to be selected rapidly. As before, heads are high impedance on mumetal laminations, with half-thou gap, giving a half-hour playing time on each side of a 1,200ft. tape reel. Price is **£16 10 -**, plus 10/- carriage. Crate is not charged provided undertaking is given on order that it will be returned carriage paid to us, otherwise charged £1.

LITERATURE ON MOST OF THESE ITEMS IS AVAILABLE ON REQUEST

COLLARO 3 RCS11 3-SPEED AUTO-CHANGER. Non-mixing, plays eight 7in., 10in. or 12in. records at 33⅓, 45 or 78 r.p.m. Supplied with two plug-in pick-up heads incorporating sapphire styli, and made by Acos. Price £18 14 1, including P.T.

COLLARO RCS11 SINGLE-SPEED AUTO CHANGER. Non-mixing, plays eight 78 r.p.m. 10in. or 12in. records. Supplied with Acos made plug-in pick-up head incorporating sapphire stylus. Magnetic, price £11 14 11, incl. P.T. Crystal price, £12 3 2, incl. P.T.

COLLARO AC47 SINGLE-SPEED TURN-TABLE MOTOR. Centre-drive governor-controlled heavy induction motor, for A.C. 100-130 v. and 200-250 v., with 12in. turntable. Variable speed. Price £6 13 4, incl. P.T.

COLLARO AC514 RECORD PLAYER. For 78 r.p.m. records. Rim-drive motor, with auto. stop, turntable, pick-up with plug-in magnetic head. Price £6 9 -, incl. P.T.

DECCA THREE-SPEED GRAM. MOTORS. For 33⅓, 45 and 78 r.p.m. Instant single-lever speed selection. For A.C. only, 100-250 v. 50 cycle operation. Price (incl. P.T.), £7 3 4.

DECCA TURNOVER PICK-UP. A high fidelity crystal pick up with turnover head (two sapphires) for use on the above or other multi-speed motors. Price (incl. P.T.), £3 19 4.

ACOS GP38 HIGH FIDELITY CRYSTAL PICK-UP. Limited supplies of this famous pick-up are again available. Price £3 11 5, incl. P.T.

LUSTRAPHONE MOVING COIL MICRO-PHONES. Type CS1. Response substantially flat to 8 kc/s. Impedance 20 ohms. Fitted with switch, £5 each. Type CS1/Z. As above, but impedance 200,000 ohms, £5 12 6 each.

MAGNETIC RECORDING TAPE. Emitape, Grade A, 600ft., 21 - ; 1,200ft., 35 -. Scotch Boy (Durex), 1,200ft., 35 -.

ROTARY CONVERTERS. Ex-Admiralty, input 24 v. D.C. ; output 230 v. 50 c.p.s. at conservative Admiralty rating of 75 watts ; in heavy steel case with plastic front panel ; stepped voltage control ; A.C. meter 2½in. 0-250 v. Very good condition, but meter glass may be cracked. For callers only, £5 10 -.

LIGHTWEIGHT RELAYS. By Advance Electric Co. of Los Angeles. 28 v. 1,000 ohm SPCO. Contact current 1.5 A. at 110 v. Weight, 1¼ oz. approx. Size including fixing, 1¾in. x 1¾in. x ¾in. approx. Single hole fixing. 3 6 each.

CERAMIC SWITCHES. 5PBW ; extra contacts up to three can be easily fitted and riveted stop removed. Silver plated contacts. ¼in. dia. spindle ¼in. long from end of bush ; spindle drilled and tapped and flatted. 3 6 each.

OUTPUT TRANSFORMERS. Varley DP47. Primary 10,000 ohms Anode to Anode. Secondary 3.75 ohm plus 3.75 ohm, in parallel for 3 ohm speakers, in series for 15 ohm speakers. 10 watts rating. Enclosed in bakelite case, 28 6. Single-ended 44:1 ratio, 60 mA. rating. Matches most tetrode and pentode output valves to 3 ohm speakers, 4 3.

L.F. CHOKES. 10 H 500 mA., 15 - ; 15 H. 120 mA., 12 6 ; 20 H. 100 mA., 12 6 ; 17 H. 60 mA., 4 6 ; 100 H. 20 mA., 4 6 ; 70 H. 20 mA., 4 6. All ex-govt. or ex-manufacturers.

FLUORESCENT CHOKES. For 80 watt tubes. Ex-government, of rough appearance but electrically sound. With each one free a 7.5μF P.F. condenser which may or may not be sound, 9 6 each.

INSULATED TERMINALS. Black moulded screw-top type, 4 for 3 -, 7 6 per doz. ; 58 - per 100.

HANDLES. Make your equipment portable with these. Substantial moulded alloy, sprayed green, will take whole hand comfortably. Four-hole fixing, tapped 2BA, 1 3 each, four for 3 9.

REACTION CONDENSERS. Bakelite cased, mica dielectric. Not surplus. 0.0005μF, 3 4, 0.0003μF, 3 4.

METAL RECTIFIERS. Type MR2, 125 v. at 100 mA. Two in series required for mains voltage. Price 4 - each. Type 14D/972. 250 v. 25 mA. (with reservoir condenser). Small size, ideal for test equipment, also in place of 14D/36 in T.V circuits. Price 6 6 each. 6 v. 1 A. half-wave (or full wave with C.T. trnsr.), price 5 - each ; 12 v. 1 A. bridge, price 8 6 each ; 12 v. 4 A. bridge, price 22 6 each.

AMPLIFIER AC11. This popular amplifier is still available for those who desire good quality at a low cost. Output is 5 watts, and volume tone, and controls are incorporated. High-grade output transformer. H.T. and L.T. supplies are from mains transformer, thus isolating chassis from mains. Amplifier wired and tested £6 2 6, plus 5 - carriage.

TELEVISION MAGNIFYING LENS. 9in. clear, 55 - ; 9in. filter, 60 - ; 12in. clear, 75 - ; 12in. filter, 80 -. Carriage and packing 5 - each all types.

EX-GOVT. POTENTIOMETERS

Value	Track	Wattage	Spindle length	Price
50Ω	W.W	5	Preset	2 6
100Ω	W.W	1	Preset	1 9
500Ω	W.W	1	5/16in.	1 9
1kΩ	W.W	3	¼in.	2 6
1kΩ	W.W	5	¼in.	2 6
2kΩ	W.W	3	Preset	1 9
2kΩ	W.W	6	¼in.	3 -
3kΩ	W.W	5	Preset	2 6
3kΩ	Carbon Trop.	2	¼in.	1 9
5kΩ	W.W	2	¼in.	2 6
5kΩ	W.W	5	¼in.	3 -
5kΩ	W.W	5	¼in.	3 -
8kΩ	W.W	5	¼in.	2 6
10kΩ	W.W	4	¼in.	2 6
10kΩ	Carbon Trop.	2	¼in.	2 -
10kΩ	Carbon	1	Preset	1 3
20kΩ	W.W	3	Preset	2 -
20kΩ	W.W	5	¼in.	3 -
20kΩ	Carbon Trop.	2	¼in.	1 9
25kΩ	W.W	2	¼in.	3 -
50kΩ	W.W (earthed slider)	3	¼in.	2 6
50kΩ	Carbon Mini.	½	¼in.	1 6
100kΩ	Carbon Mini.	½	¼in.	1 6
200kΩ	Carbon	1	¼in.	1 9
500kΩ	Carbon Trop.	½	¼in.	1 6
500kΩ	Carbon Trop.	2	¼in.	1 9
500kΩ	Carbon Mini.	½	¼in.	1 6
1MΩ	Carbon	1	¼in.	2 -

All new and unused. Spindle diameter ¼in. in all cases. Quantity prices on application.

CARBON RESISTORS. Large and comprehensive stocks at following prices : ½ w., 4d. ; ¾ w., 5d. ; 1 w., 6d. ; 2 w., 9d. ; 4 w., 1 - each. Among the values available at press date are the following :

Quarter Watt : 10, 12, 13, 20, 22, 33, 39, 43, 51, 56, 68, 82, 100, 150, 180, 220, 270, 300, 330, 390, 430, 450, 470, 560, 680, 700, 1 k, 1.5 k, 2.2 k, 2.4 k, 2.4 k, 2.7 k, 3.2 k, 3.3 k, 3.9 k, 4 k, 4.7 k, 5.6 k, 6.2 k, 6.8 k, 7.5 k, 8 k, 10 k, 12 k, 15 k, 16 k, 18 k, 20 k, 22 k, 24 k, 25 k, 27 k, 30 k, 33 k, 36 k, 39 k, 40 k, 47 k, 50 k, 56 k, 60 k, 62 k, 68 k, 82 k, 100 k, 120 k, 180 k, 220 k, 270 k, 330 k, 350 k, 390 k, 470 k, 500 k, 600 k, 680 k, 750 k, 820 k, 1 m, 1.5 m, 2 m, 2.2 m, 2.7m, 3.3 m, 4.7 m, 5 m, 6 m.

Half Watt : 27, 30, 43, 68, 82, 120, 130, 150, 270, 300, 400, 470, 500, 560, 600, 680, 750, 820, 1 k, 1.5 k, 2.2 k, 2.4 k, 3.9 k, 5.1 k, 6.2 k, 8.2 k, 10 k, 12 k, 13 k, 15 k, 18 k, 20 k, 27 k, 39 k, 40 k, 50 k, 60 k, 68 k, 100 k, 500 k, 560 k, 600 k, 680 k, 820 k, 1.5 m, 2 m, 2.2 m, 2.7 m, 4.7 m.

One Watt : 20, 27, 33, 50, 56, 68, 82, 120, 240, 330, 470, 600, 750, 1.2 k, 1.5 k, 1.8 k, 2.2 k, 2.4 k, 3 k, 3.9 k, 4.7 k, 6.8 k, 8.2 k, 18 k, 20 k, 22 k, 24 k, 30 k, 50 k, 55 k, 68 k, 70 k, 80 k, 100 k, 330 k, 470 k, 680 k, 750 k, 1 m, 1.2 m, 1.8 m, 3.3 m.

Two Watt : 47, 220, 270, 470, 600, 1 k, 1.5 k, 3 k, 3.3 k, 4.3 k, 6 k, 8 k, 8.2 k, 10 k, 18 k, 22 k, 27 k, 30 k, 47 k, 50 k, 68 k.

Four Watt : 20 k, 40 k, 56 k, 68 k, 240 k, 470 k.

HIGH STABILITY RESISTORS. 1% ½ w. : 10 k, 25 k, 1 - each. 1% 1 w. : 1 m., 1 3 each. 2% ½ w. : 4 k, 10 k, 13 k, 55 k, 250 k, 1 m, 9d. each. 5% ½ w. : 39 k, 10 k, 39 k, 75 k, 130 k, 600 k, 8d. each. 5% 1 w. : 8 k, 510 k, 910 k, 1.8 m, 9d. each. 5% 2 w. : 10 m, 11 m, 12 m, 1 3 each. We have at press date large stocks of many of these values.

WIRE ENDED WIREWOUND RESISTORS. 4 watt : 50, 90, 1 3 each. 6 watt : 14, 25, 15 k, 1 8 each. 10 watts : 90, 170, 350, 950, 1 9 each, 12 watts : 5, 30, 40, 120, 150, 3.5 k, 15 k, 2 - each. 15 watt : 5, 100, 2.5 k, 3.6 k, 11 k, 30 k, 2 - each.

CLIP FIXING WIREWOUND RESISTORS. 25 watt : 4, 350, 717, 5 k, 10 k, 75 k, 2 - each. 45 watt : 14 k, tapped 2 k, at 2 3 each. 65 watt : 50 k, at 2 6 each. 200 watt : 430, 10 k, 20 k, 50 k, at 3 - each. We have large stocks of the heavier wattage resistors ; quantity prices on application.

CATHODE RAY TUBES. 5CP1, Electrostatic intensifier-type C.R.T., diameter 5in. max. second anode voltage 2 kv., max. intensifier anode voltage 4 kv., medium persistence screen. Brand new in original crate or carton, 22 6 each.

GERMANIUM DIODES. By leading manufacturers. Wire ended, glass enclosed type. Special offer at 4 - each, or 45 - per dozen.

MINIATURE TANDEM POTS. 30 k. plus 1.5 k. with S.P. switch. Spindle diameter ¼in. spindle length ¾in. from end of bush, 2 6 each.

VALVEHOLDERS. Ceramic : UX5 (807, etc.), 1 - each, 10 - doz. ; UX7 medium (1625, RK34, etc.), 1 - each, 10 - doz. ; B9G (EF50, etc.), 9d. each, 7 6 doz. Amphenol : Int. Octal, 9d. each, 7 6 doz. ; Br. 7p., 9d. each, 7 6 doz., Br. 5p, 9d. each, 7 6 doz. ; UX7 med., 9d. each, 7 6 doz. ; UX5, 9d. each, 7 6 doz. Paxolin : Br. 5, Br. 7, UX4, UX5, UX6, UX7, 6d. each.

HEATER TRANSFORMERS. Pri. 220-240 v., Sec. 6.3 v. 1.5 a., 7 6 each. Pri. 220-240 v. Sec. 6.3 v. 3 a., 11 6 each ; Pri. 205-225-245 v., Sec. 6.3 v. 3 a., auto-wound, 8 9 each.

B & L. TWIN FUSEHOLDERS. Totally enclosed type in Black Bakelite, for panel mounting, 2 - each.

AERIAL RODS. Copper plated steel. Fit into each other to make up any length aerial. Per doz. 2 - ; per gross, 18 - ; per thousand, £4 10 -.

METAL CUTTING SHEARS. A robust tool, one-inch blades, will cut up to 16 s.w.g. aluminium. Per pair, 2 - ; per dozen pairs, 21 - ; per gross pairs, £11.

TRIMMERS. Miniature ceramic air-spaced 3-30pF, 6d. each. Philips concentric type 3-30pF, 8d. each. Standard size ceramic air-spaced trimmers, 30pF, 1 - ; 50pF, 1 - ; 75pF, 1 3 ; ceramic compression type trimmers, 50pF, 6d. ; 50 + 50pF, 1 - ; 100 + 100pF, 1 - ; 200 + 500pF, 1 3 ; 1,000 pF, 9d.

T.R.F. COILS. For long and medium waves. With reaction winding, 6 9 per pair. Without reaction winding, 5 - per pair.

AMPLION TESTMETER. 10 Ranges A.C. and D.C. Up to 500 v. A.C. and D.C. Resistance up to 200,000 ohms, 1,800 ohms per volt A.C. and D.C. Price £5.

CLOSE TOLERANCE SILVER MICA CONDENSERS. 1,000pF (0.001μF), ± 1%, 1 3 each. 100pF (0.0001μF) + 1%, 9d. each. 400pF (0.0004μF) 1%, 9d. each.

HIGH CAPACITY PRECISION MICA CONDENSERS. We are again able to offer a complete range of these condensers, of which we have now sold over 25,000. Accuracy plus or minus 0.5 (point five) per cent. of stated value. Pure mica and copper foil or silver.

(a)	0.017970μF ... 1 3	(b)	0.023570μF ... 1 3
(b)	0.027400μF ... 1 6	(c)	0.035020μF ... 1 6
(d)	0.040710μF ... 1 6	(di)	0.048010μF ... 1 6
(e)	0.055820μF ... 1 6	(f)	0.065350μF ... 1 6
(fi)	0.082910μF ... 1 6	(g)	0.087460μF ... 1 6
(h)	0.108435μF ... 1 9	(i)	0.123750μF ... 1 9
(j)	0.147000μF ... 1 9	(k)	0.205276μF ... 2 -

Many standard values to better than 1 per cent. can be made up by parallel or other combinations of above, e.g., a + 2k = 1μF ; 2k + g = 0.5μF ; c + F = 0.1μF. (A table of over 150 series and parallel combinations of these condensers, invaluable in calculating filter networks, etc., is available on receipt of 2½d. stamp.)

CONDENSERS (pFs). 2, 4, 10, 15, 20, 30, 50, 75, 100, 160, 200, 6d. each, 5 6 doz. 220, 300, 330, 500, 1,000, 2,000, 4,000, 4,500, 4,700, 9d. each, 7 6 doz.

HIGH VOLTAGE MICA CONDENSERS. Ceramic feed-through type, 10C/2178, 0.0002μF 5 kv. wkg., 2 6 each.

HIGH VOLTAGE PAPER CONDENSERS : 10C/12541. In black bakelite cylindrical case, single screw fixing. 0.02μF, 5kv. wkg., 1 9 each.

S.W. TUNING CONDENSERS. 50 pF max., 3-hole fixing, spindle diam. ¼in. spindle length 1in., 1 6 each. 160pF (0.00016μF max.), upright mtg., with 4 fixing feet, spindle diam. ¼in., spindle length 1¼in., 2 3 each.

THYRATRONS. Type NGT1 (CV1141) 4 v. heater, anode volts 350. Anode current, peak 1 a., average 200 mA. Control ratio 40. 5-pin British base, with anode top cap, 6 6 each. 72 - per dozen.

HEAVY DUTY OUTPUT PENTODES. Type PT25H. 4 v. filament, British 5-pin base. Have been successfully used strapped as triodes in quality amplifiers, 5 - each, 48 - per dozen.

PRIORITY TO DEFENCE & EXPORT ORDERS.

ALL GOODS NEW AND UNUSED, OTHERWISE STATED. GOODS SHOWN AS EX-EQUIPMENT HAVE BEEN FULLY TESTED AND ARE IN GOOD WORKING ORDER. **PLEASE ADD POST OR CARRIAGE ON ALL ITEMS. KINDLY PRINT NAME AND ADDRESS.** POST ORDERS TO OUR DEPTFORD ADDRESS. EARLY CLOSING THURSDAY, OPEN ALL DAY SATURDAY

GARLAND BROS. LTD

CHESHAM HOUSE, DEPTFORD BROADWAY, S.E.8
TELEPHONE : TIDEWAY 4412/3

8 OBELISK PARADE, LEWISHAM S.E.13
TELEPHONE : LEE GREEN 4038

You're SURE to get it at

STERN'S

ESTABLISHED 25 YEARS

BUILD A PROFESSIONAL RADIO OR AMPLIFIER AT LESS THAN HALF TODAY'S PRICE

ALL KITS INCLUDE "EASY TO FOLLOW" POINT-TO-POINT WIRING DIAGRAMS

A MAINS OR BATTERY PORTABLE KIT

A Midget 4-valve Superhet Portable Set covering medium and long wavebands.
Designed to operate on A.C. mains 200-240 volts, or by an "Aldry" battery. The set is so designed that the mains section is supplied as a separate unit which may be added at any time. The Kit therefore can be supplied as an "Aldry" Battery Superhet Personal Set, which can then be accommodated in the Attache Case as illustrated above (size 9½in. × 4½in. × 7½in.). This is attractively finished in Dark Green or Blue Rexine (to order) as a Combined Mains Battery Superhet Portable Receiver, for which a polished Wood Cabinet is available to accommodate both Mains Unit and Battery together.
Circuit incorporates delayed A.V.C. and Pre-selective Audio Feedback. Kit is complete in every detail and includes ready wound frame aerials, fully aligned I.F. Transfs. and drilled chassis, etc. Overall size of assembled chassis 9½in. × 6in. × 3½in.
We can supply the set either as a complete Kit of Parts for **£10 7 6** (incl. P.T.) or the Chassis and Mains Unit, or for supplying the components separately. The complete Assembly Instructions, which include full price details (including prices of individual components), Circuit and Component Layout, etc., are available for **1/9** (incl. postage).

A T.R.F. BATTERY "PERSONAL" KIT



A complete Kit of Parts to build a Midget 4-valve Aldry Battery Portable set, covering medium wavebands.
Consists of Regenerative T.R.F. circuit, employing Flat Tuned Frame Aerial with Dense Iron Dust Cored Coil.
Valve line up, two 1.T.4's (R.F. Amp. and Det.), 1S5 and 3S4 output.
Kit is complete in every respect and includes drilled chassis and latest type Rola 5in. P.M. speaker. Overall size of assembled chassis 4½in. × 9½in. × 5½in.
We can supply the Complete Kit (less cabinet) for **£6 12 6** (inc. P.T.) or by supplying the components separately. The Complete Assembly Instructions, including individual component prices, Circuit and Component Layout, etc., are available for **1/-**, incl. post.

A KIT OF PARTS

Complete in every detail, to build a **3-valve Amplifier** for A.C. D.C. mains 200-250 volts.
Has an output of 3 watts, and incorporates a Tone Control.
Valve line up, 25A6, 6J7, U31.
Our price of **£4 18 9** for complete kit includes a matched 6½in. P.M. speaker.
This Amplifier can also be supplied assembled and ready for use for **£5 19 6**.

A MIDGET 4-STATION "PRE-SET" RECEIVER

A complete Kit to build a 4-Station "Pre-Set" Superhet Receiver for A.C. mains operation.
The Set is designed to receive any three stations on medium wavelength and one on long wave, each station being received by the turn of a Rotary Switch—No Tuning being necessary.
It is of midget size, being 8½in. × 4½in. × 7in. high, and has the performance of a far more expensive ready-made set, but can be built for half the price.



Price of complete Kit of Parts (including aligned I.F. Trans. and drilled chassis, etc.), **£9 15 -** (incl. P.T.) plus Cabinet **25/6**, or the components can be purchased separately. The complete Assembly Instructions, including Individual Component Price List, Circuit and Component Layout, etc., are available for **1/9**.

STERN'S "RADIO TUNER MANUAL." Price 2/6. (Price 3/- Post). Contains complete and detailed assembly instructions showing how to make:—
A **1-Valve T.R.F. Tuning Unit**, covering Long and Medium Wavebands.
A **4-Station "Pre-Set" Superhet Tuning Unit**, producing 3 Stations on Medium Waveband and 1 on Long Wave.
A **2-Valve Superhet Tuning Unit**, covering Short, Medium and Long Wavebands.
Each Tuner is for A.C. Mains operation. Circuit Diagrams and Practical Component Layouts are shown, together with complete component Price Lists.

THE WIRELESS WORLD MIDGET A.C. MAINS 2-VALVE RECEIVER

We can supply all the components to build this set, including Valves and Moving Coil Speaker for **£3 10 -**, including Designer's complete building instructions (these are available separately for **9d.**).

THE "SUMMER ALLDRY" BATTERY PORTABLE

As published in June issue of "Practical Wireless." We can supply, from stock, all the components to build this Midget 2-valve Portable for **£3 2 0** (less valves). This also includes dials, top panel and aly. sheet for chassis. The complete article and circuit, including Practical Layout and Price List, is available for **9d.**

PICK-UPS

Cosmocord "G.P.20," for standard records, **£3 11 5**; interchangeable (G.P.19) Head for L.P. records, **£2 3 4**.
Decca lightweight turnover Head type, for L.P. and standard records, **£3 19 2**.
Marconi, Standard, lightweight Magnetic, **£1 15 10**. Marconi Matching Transformer, **7/6**.
Goldring, Standard, lightweight, Magnetic, **29/6**.

THE WIRELESS WORLD 3-VALVE SET

A Midget 3-valve T.R.F. Receiver for operation on A.C. mains, covering long and medium wavebands.
We are able to supply all of the components to build this set, as designed, and specified in the Feb. 1950 issue, including the drilled chassis, valves and moving coil speaker, etc., at the following prices:—
To construct complete chassis, less dial and drive assembly, **£5 5 0**. Ditto, including dial and drive assembly, **£6**.
To construct the complete set, including dial and drive assembly and cabinet, **£7 3 6**.
Overall size of cabinet is 7¼in. × 5¼in. × 11¼in.
A reprint of the designer's article, giving Circuit and Assembly Instructions (this is available separately for **9d.**), together with a Practical Component Layout is included with each of above assemblies.

BATTERY CHARGER KITS

All Kits incorporate Metal Rectifiers, and are for use on A.C. mains 220-250 volts. All Kits include an easily followed Wiring Diagram.
For charging 6 v. battery at 1½ amps., **£1 4 9**.
For charging 6 volt battery at 1½ amps., with Variable Resistor and Meter, **£2 9 3**.
For charging 12-volt battery at 1½ amps., **£1 9 3**.
For charging 12-volt battery at 1½ amps., with Variable Resistor and Meter, **£2 14 0**.
For charging 6 or 12 volt battery at 3 amps., **£2 1 0**.
For charging 6 or 12 volt battery at 3 amps., with Variable Resistor and Meter, **£3 8 3**.

THE WIRELESS WORLD MODERN CRYSTAL SET

Designed for the Pre-selection of THREE STATIONS to suit local conditions, each station being received by the turn of a rotary switch. We are able to supply all components, including drilled chassis to build this new type of Receiver, to the designer's specification, as published in Octoberissue, for **47/4** (including cost of selected coils).
A reprint of the designer's article (available separately for **9d.**), together with a practical component layout, make the assembly very easy.

★ *Send 6d. P.O. for our STOCK LIST, it shows "hundreds" of Wireless*
When ordering please include

STERN RADIO LTD., 109

Tel.: CENtral

THE "PRACTICAL WIRELESS" "MINI FOUR" BATTERY PORTABLE

A 4-valve battery superhet receiver designed to receive 4 Home Stations, three on medium waveband and one on long waves to suit local conditions. Each station is obtained on the set by the turn of a rotary switch. No tuning is necessary.



It is of midget size, being only 4½in. × 6½in. × 4¼in. when completely built, and is very easily assembled from diagrams supplied.

Cost of all components to build this set, in accordance with the design, including a drilled and cut chassis and panel, and new valves, is **£9 10 0** (or less valves for **£6 7 6**). Complete constructional data with a blue print, which shows the practical component lay-out and wiring diagram, together with an individual component price list, is available separately, **1 6**.

Our Mains Units available in kit form are suitable for use with this set.

A QUALITY "PUSH-PULL" AMPLIFIER KIT



A Kit of Parts to build a 6-6 watt Push-Pull Amplifier to operation on A.C. mains 200-250 volts.

Incorporates a simple arrangement to enable either a magnetic, crystal, or light-weight pick-up to be used.

A 10-watt Output Transformer is designed to match from 2 to 15 ohm speakers. Tone-control is incorporated.

The overall size of the assembled chassis is 10in. × 8in. × 7½in. high. Price of kit complete in every detail, including drilled chassis and valves, **£6 12 6**. Component layout is supplied.

Price of assembled chassis, supplied ready for use **£8 2 6**.

"PERSONAL SET" BATTERY ELIMINATOR

A complete kit of parts to build a Midget "All-dry" Battery Eliminator, giving approx. 60 volts and 1.4 volts.

This Eliminator is for use on A.C. mains and is suitable for any 4-valve Superhet Receiver requiring H.T. and L.T. voltage as above, or approx. to 60 volts.

The kit is quite easily and quickly assembled and is housed in a light aluminium case, size 4½in. × 11½in. × 5½in. Price of complete kit, with easy to follow assembly instructions **42 6**.

In addition we can offer a similar COMPLETE KIT to provide approx. 90 volts and 1.4 volts. Size of assembled Unit 7in. × 9½in. × 11½in. Price **47 6**.

You're SURE to get it at

STERN'S

ESTABLISHED 25 YEARS

TWO NEW DENCO ULTRA MIDGET SUPERHET COIL TURRETS
Both having a Rotary Turret Action

(a) The C.T.9 Turret consists of 4 STATION "PRE-SET" UNIT, from which any three Stations on Medium Waveband and one on Long Waves can be received by a turn of the Turret Switch.

(b) The C.T.10 Turret being a 3 Waveband Coil Pack, incorporating a fourth switch position providing for completely switching out Radio when using gram. The complete coverage is: Long Waveband 700 to 2,000 metres. Medium Waves 190 to 570 Metres and Short Waves 16 to 50 Metres.



The outstanding advantages these units have over other similar units can be readily seen, the main features being:

(a) Neat and Compact, the overall size being only 2¼in. dia. × 1¾in. deep.

(b) Fitting is simplicity itself, each Turret having one hole fixing and requiring only four connections.

(c) The Rotary Turret design switches the actual Coils, which incorporate variable iron dust cores, on to positive contacts, thereby reducing stray capacities to the absolute minimum.

(d) They are supplied Factory wired and aligned and have been designed to operate with any conventional circuit arrangement of 465 K.c. and due to their unique design are extremely sensitive and efficient.

Price: C.T.9 Turret, **42 10**. C.T.10 Turret, **52 -**.

A complete Receiver circuit together with leaflet containing all necessary data is included with each Turret. These can be supplied separately for **6d**.

THE FAMOUS W.B. "STENTORIAN" RANGE OF P.M. SPEAKERS.

Size.	Impedance.	Watts.	Price
2½in.	2-3 ohms	1	18 6
3½in.	,,	2	19 6
5in.	,,	2½	21 -
6½in.	,,	3	24 6
7in.	,,	3½	23 6
8in.	,,	5	32 6
9in.	,,	7	36 9
10in.	,,	10	44 6
12in.	15 ohms	15	£9

New Mins. Surplus Speakers. All 2-3 ohms 2½in. 15 -; 3½in. **14 6**; 5in. **14 6**; 6½in. **16 9**; 8in. **18 -**; 10in. **25 -**; New Type Rola, 3in. **21 -**; 4in. **22 6**.

Output Trans. Midget 60-1 (or 90-1) 1½in. × 1in. × 1¾in. **3 9**. 5-watt Multi-ratio, 12 tappings between 24-1 and 114-1 (some C.T.), **8 6**. Wharfedale, 12-watt, push-pull, multi-ratio, **25 -**. P.pull, 20-watt, multi-ratio, **37 6**, and many others.

New Electrolytic Condensers. Not Ex-Govt. All 450-500 volts: 8 mfd. (1¼in. × ¾in. dia.), **3 -**; 8-8 mfd. (1¼in. × 1in.), **4 9**; 16-8 mfd. (1¾in. × 1in. dia.), **5 6**; 16-16 mfd. (1¾in. × 1¼in. dia.), **5 9**; 32 mfd. (1¾in. × 1¼in. dia.), **5 9**; 32-32 mfd. 350 volt, **5 9**; Cardboard Tubular 4mfd. 500 v. **3 6**; 8 mfd. 500 v., **4 -**; 16 mfd. 500 v., **5 9**. Can. Standard size all 500 volts, 4 mfd., **3 6**; 8 mfd., **4 3**; 8-8 mfd., **5 9**; 16 mfd., **5 6**; 16-16 mfd., **7 9**; 32 mfd., **6 9**.

Denco I.F. Liner, for accurately lining 465 K.c. and 1.6 m.c. I.F. channels, and associate circuits. Battery operated, small and completely self-contained. **49 6**.

Potentiometers. New, non Ex-Govt. 2K, 5K, 10K, 25K, 50K, 100K, 250K, ½, 1 and 2 meg. Price, less switch, **3 9**. Price with S. Pole switch, **5 9**. Price with D. Pole switch, **6 6**.

Surplus Potentiometers. All standard with extended spindles, 5K, 10K, 15K, 20K, 25K, 50K, 100K, ½, ¼ and 1 meg. **2 -** each.

THE FAMOUS "SHAFTESBURY" RIBBON MIKE,

incorporating internal line Transformer having transformation ratio from ribbon impedance up to 200-600 ohms. Reduced from £10 10 0 to **£6 0 0**.

A special line to grid, 200-600 ohm, Transformer is also available.

Coils. Denco "Maxi Q," midget size, Litz wound on Polystyrene Formers, with adjustable iron cores. Available for Aerial H.F. and Oscillator 465 K.c. or 1.6 M.c., **3 11** each, or with reaction winding **4 9**. Denco Matched pair T.R.F. Coils for long and medium waves, **8 -** pr. Weymouth matched pairs of coils, for T.R.F. covering long and medium waves, **10 3** pr., or for Superhet covering Long, Medium and Short Waves, **12 3** pr. All types of Wearite "P" coils in stock at **3 -** ea.

Coil Packs. Osmor Midget Coil Pack. Size 3½in. × 2½in. × 1½in., covering S. M. and L. waves. Coils wound on Polystyrene Formers with adjustable iron cores ensure efficient performance. Factory wired and aligned. Price, including full circuits for Superhet 465 K.c. Unit, **52 -** (incl. P.T.). This Osmor Coil Pack is also available for Midget Superhet BATTERY Portable sets, including a matched ready wound Frame Aerial. Price **54 2** (incl. P.T.). **Weymouth** Midget 3½ × 2½ × 1¼in. covering S.M.L. w bands, for 465 Kc/s., employing Matched Iron Cored Coils on each w band, **51 6**.

Wearite Pack, 4½ × 3½ × 1¼in., Type 706, covers two short w bands and medium w band and Type 705 covers short-medium-long waves. Both for 465 kc/s. Incorporates gram. position, and employs adjustable cored coils, **53 4**.

All of the above Coil Packs include Switching, Padding and Trimmer Condensers.

L.F. Chokes. Midget 10 henry 250 ohms 40 mA., **4 6**. 20 hny. 250 ohm 60 mA. **6 6**; 20 hny. 300 ohm 100 mA; **13 -**; 5 hny. 50 ohm. 250 mA. **28 6**; 20 hny. 250 ohms 120 mA., **15 6**; 9 hny. 250 ohm. 120 mA., **8 6**; 18 hny. 200 ohm. 200 mA., **26 6**.

I.F. Transformer 465 K.c. New well-known manufacturer's surplus, ½in. × ½in. × 1¼in. Iron Core, **9 -** each and also size 1in. × 1¼in. × 2in. at **12 9** per pair. Each have adjustable Iron Core. Denco Iron Core, 465 K.c. or 1.6 m.c., 1¼in. × 1¼in. × 3½in. **19 6** pair. New Surplus 465 K.c. Iron Core, 4in. × 1½in. dia., **10 -** pr.

Transformers. (a) Input 230 volt, output 200 volt 25 m.a., and 6.3 v. 9 amp., **11 -**; (b) Input 230 volts, output 250 volts 30 m.a., and 6.3 volts 1 amp., **13 9**.

E.H.T. Transformer. Prim. 230 v. Sec. 5 Kv. and 4-volt tapped 2 volt, **59 6**. Do. but 4 Kv., **54 -**.

Heater Auto Transformers. (a) tapped 0 v. 4 v. 5 v. and 6.3 volts 3 amp., **10 9**; (b) 4 v. 3 amp. to 5 v. 2 amp. Reversible, **7 9**; (c) 4 v. 3 amp. to 6.3 v. 2 amp. Reversible, **7 9**.

Filament Transformer. Inputs 250 volts, outputs 6.3 v. 1½ amp., **8 3**; 4 v. 1½ amp., **7 6**; Input 200-250 v. output 4 v. (C.T.) 1½ amp., 4 v. 2 amp., 6.3 v. 2 amp. **15 6**. Input 230 v., output 6.3 v. (C.T.) 4 amp., **17 6**.

Metal Chassis, substantially made with four sides, 7in. × 4in. × 2in., **3 11**; 9 × 5 × 2½in., **5 3**; 10 × 6 × 2½in., **6 -**; 10 × 7 × 2½in., **6 3**; 12 × 9 × 2½in., **7 9**; 14 × 9 × 2½in., **8 3**; 16 × 8 × 2½in., **9 -**.

Mains Transformers. All New Stock with Primaries tapped for 200-250 volts. Secondaries (a) 250-0-250 volt, 80 mA. 6.3 v. (tapped 4 v.) 4 amp. and 5 v. (tapped 4 v.) 2 amp., **22 6** (also available with 350-0-350 volt at **22 6**). Stern's 350-0-350 volt, 100 mA., 6.3 v. (tapped 4 v.), 4 amp. and 5 v. (tapped 4 v.) 2 amp., **41 6**; (c) 350-0-350 volt, 150 mA. 4 volt 8 amp., 4 v. 3 amp., 6.3 v. (tapped 2 v.) 2 amp. and 6.3 v. 6 amp., **84 -**, and many other ratings.

Westinghouse Rectifiers. (a) H.T. 51. Rated 350-0-350 volts 100 mA., **35 -**; (b) H.T.52. Rated 350-0-350 v. 200 mA., **37 6**; (c) H.T.53. Rated 500-0-500 v. 200 mA., **50 -**.

Types. 14DE36, **11 3**; 16HT28, **12 6**; 16EHT36, **17 9**; 36EHT20, **13 10**; 36EHT35, **18 2**; 36EHT40, **20 6**; 36EHT45, **22 6**; 36EHT30, **24 10**; 36EHT60, **25 8**; 36EHT100, **29 5**; 36EHT13, **7 9**.

F Wave Bridge Rectifiers:

For charging 4 or 6 volts at 1½ amps.	**9 6**
For charging 6 or 12 volts at 1½ amps.	**13 6**
For charging 6 or 12 volts at 3 amps.	**21 6**
For charging 6 or 12 volts at 4 amps.	**24 10**
For charging 12 or 24 volts at 3 amps.	**25 9**

A Variable Resistor for control of Charging Equipment (or Models) up to 3 amps., **17 9**, or for 1½ amps. **15 -**.

Meter Rectifiers. Westinghouse 250 micro-amp., **12 9**; 1 mA., **11 9**; 5 mA., **6 9**.

Selenium Rectifiers. H.T. H. wave. 250 v. 50 mA., **6 6**. 250 v. 100 mA., **8 6**; 250 v. 170 mA., **15 6**.

Charger Transformers. Suitable for use with preceding Rectifiers. Each have tapped 230 volts. Outputs:

(a) 24 volts tapped 15 v. 9 v. and 4 v. at 3 amps., **25 0**;
(b) 30 volts tapped 15 v. and 9 v. at 3 amps., **26 3**;
(c) 15 volts tapped 9 v. at 3 amps., **21 -**; (d) 12 volts 1½ amps., **12 3**; (e) 15 volts tapped 9 v. at 6 amps., **24 3**; (f) 15 volts tapped 9 v. at 1½ amps., **15 9**; 12 volts 1 amp., **7 6**.

A Battery Charger Wiring Diagram is included with purchase of Charger Transformer and Rectifier.

Adjustable Mains Droppers. 1¼in. dia. × 2¼in. long. 15 amp. 1,500 ohms, **5 -**; (b) .2 amp. 1,000 ohms, **4 3**; (c) 3 amp. 600 ohms, **5 -**.

Television. We keep a very comprehensive range of T/V components. The Viewmaster T.V. Assembly Instructions showing Practical Layout and Price List in stock, price **5 6** (incl. post). We can supply all the specified components for the T/V ex stock either by way of individual components or by the published stages.

"G" Max Chassis Cutters. The quickest and most simple method of Chassis cutting consists of a die, punch and Allen screw.

To cut ¾in. dia. (B7G)	**10 6**
To cut ¾in. dia. (B8a)	**10 6**
To cut 1in. dia. (Octal)	**13 6**
To cut 1¼in. dia. (English)	**13 6**
To cut 1¼in. dia. (UF5)	**14 6**
Key for any of above	**1 -**

The new **Perobit Soldering Iron**, with instrument-tipped for use on A.C. or D.C. mains **22 -**. Spare elements and bits always in stock.

Ex-Govt. complete set of **Moving Coil Headphone**, and **Microphone** with headgear **12 6**.

Components and many KITS OF PARTS for both Sets and Battery Chargers. approx. cost of Post and Packing.

& 115 FLEET STREET, E.C.4

5814 and 2280

CLYDESDALE

Bargains in Ex-Service Radio and Electronic Equipment

COMMAND RECEIVER UNIT BC-455

A 6 valve Receiver Unit with 3 12SK7, 12K8, 12SR7, 12A6, range 6·9 mcs. I.F. 2,830 Kcs., in metal case 11 × 8¼ × 8in. less dynamotor. Used condition case dented.

CLYDESDALE'S PRICE ONLY **50/-** EACH — POST PAID

COMMAND RECEIVER CCT CBY 46129

U.S.S. version of the BC-453 for that sharp channel "Q" Fiver," range 505-190 Kcs. with 6 valves, 3 12SK7, 12K8, 12SR7, 12SG8GB, three gang tuning cond. etc., etc. Dim. — 11 × 8¼ × 8in. Finish black, less dynamotor. Unused, but case dented and less top lid.

CLYDESDALE'S PRICE ONLY **90/-** POST PAID

Circuits of BC-453 available at 1/3.

COMMAND TRANSMITTER CHASSIS

Partly stripped by the M.O.S., less valves, coil windings, crystal and dynamotor, but otherwise fairly intact. A fine basis for ideas in V.F.O. or Tx.
Original valve types 2-1625, 1626, 1629.
Conversion suggestions and circuits supplied. In aluminium case. Dim. 7¼ × 5 × 8¼in. Weight 8¼ lbs.

CLYDESDALE'S PRICE ONLY **15/-** POST PAID

COMMAND SPEECH MODULATOR BC-434

Command Modulator unit with valves, 1625, 1625, VR150/30 less dynamotor, otherwise complete in metal case 10¼ × 7¼ × 4¼in., handle depth 2¼in.

CLYDESDALE'S PRICE ONLY **37/6** CARRIAGE PAID

COMMAND TEST EQUIPMENT 1E-65-A

Command series Test Gear with 2 antennas, 2 test units, Mod. BC-406-B (or E) with 2 transistor, Antenna Relay, 2 Radio Control Boxes, 2 Racks, 6 Mountings, I.F. Shunt Unit, Control Unit NC-237 and 17 Cable Assembly.

CLYDESDALE'S PRICE ONLY **£22.10.0** CARRIAGE PAID

JEFFERSON TRAVIS UF-2 TRANSCEIVER CHASSIS

Partly stripped by the M.O.S., less valves, tuning inductance, etc. connections, but otherwise fairly intact. A fine basis for a transportable type two way radio. Original frequencies 60-75 mcs. Valves type 2-6X7, 1-5Z3. The Unit comprises two chassis with controls and speaker mounted on chrome plate etched steel panels, housed in cabinet finished black crackle, dim.: 15¼ × 10½ × 8¼in.

CLYDESDALE'S PRICE ONLY **£2.0.0** CARRIAGE PAID

JEFFERSON TRAVIS UF-1 POWER SUPPLY

Complete self contained vibrapack. Input 12 volts. Outputs 120/150 v. D.C. 30-50 mA. Choke capacity smoothed and 2 L.T. taps. Unused but vibrator, smoothing conds., etc., in metal case. Dim.—7 × 5 × 4in.

CLYDESDALE'S PRICE ONLY **25/-** CARRIAGE PAID

APS-13 T/R CHASSIS LESS VALVES

Partly stripped by M.O.S. Tx. section removed still contains 2 trimpotentiometers. I.F. Trans. motor generator B/O and other switches, etc., in metal case. 15¼ × 7¼ × 7in. Weight: 17¼ lbs.

CLYDESDALE'S PRICE ONLY **21/-** POST PAID

BC-625-A TRANSMITTER CHASSIS

Less valves, and partly stripped by the M.O.S. R.F. section in good order. Dim.—15½ × 7¼ × 6in. Separate Modulation Transformer and Choke supplied.

CLYDESDALE'S PRICE ONLY **29/6** CARRIAGE PAID

TRANSMITTER TUNING UNITS

Unused, but externally soiled, cases slightly dented and scratched. dim.—17¼ × 7¼ × 9in. approx.
T.U.5B., a few only at **35/-**.
T.U.6B., T.U.7B, T.U.8B, T.U.9B., T.U.26B.
1st grade at **22/6** each. 2nd grade at **18/6** each.

EX-U.S. NAVY TEST OSCILLATORS

TEX ARRE. A battery powered unit for alignment of TEX aircraft radio, produces, 245 mcs. H.F. Signal and 340 to 800 Kcs., tunable L.F. Signal. Using two 955 acorn tubes, a safety time switch, with indicator (20 minutes) is fitted. Unit is housed in black crackle case, 9½ × 7¼ × 7in.

CLYDESDALE'S PRICE ONLY **£7.9.6** CARRIAGE PAID

TEX-A ARR2. Similar TEX, has additional features, tone modulation, three 955 tubes, optional audio signal (switched) otherwise description and dimensions the same.

CLYDESDALE'S PRICE ONLY **£7.19.6** CARRIAGE PAID

Circuits available at 1/3.

U.S.A. PATT. MORSE KEY TYPE CJ8

Enclosed contact type as made by J. H. Bunnell & Co., and used in American Aircraft. Finish black crackle, complete with contact and tension adjusting screws. 10in. × 3¼ × 1¼ × 3in.

CLYDESDALE'S PRICE ONLY **12/6** POST PAID

TRANSMITTER UNIT T.1154

A 5 Range 10-5·5 mcs. 5·5-3 mcs. 300-200 Kcs. 4 valve 2 PT15, 2 ML6, Transmitter Unit, in metal case. Dim. — 14 × 10¼ × 8¼in. Power requirements (external) H.T. 1,200 VDC, 200 mA., L.T. 6.3 v. 4 A., 6 v. 2·5 A.

CLYDESDALE'S PRICE ONLY **£12.12.0** CARRIAGE PAID

RECEIVER UNIT R.1155

Communications and D.F. Receiver Unit. Ranges 18-7·5 mcs., 7·5-3 mcs., 1,500-600 Kcs., 600-300 Kcs., 300-75 Kcs 10 valves, 3 VR99, 3 VR100, 2 VR101, VR102, V1 103 "Magic Eye" Tuning Indicator, BFO, A.V.C. etc., in metal case, 15¼ × 9 × 9in. (Tested prior to despatch). Power requirements (EXTERNAL): H.T. 210 v. D.C. 60 mA. L.T. 6.3 v. 3.5 a.

CLYDESDALE'S PRICE ONLY **£13.19.6** CARRIAGE PAID

POWER UNITS FOR T.1154/R.1155

Type 32 or 32A. Input 12 volt 32A.
Type 33 or 33B. Input 24 volt 16A.
Output all types 1,200 v. 200 mA.
Type 34 or 34A. Input 6·3 volt 23A.
Type 35 or 35A. Input 12 volt 12A.
Output all types L.T. 7·2 v. 13A. H.T. 225 v. 110 mA.

CLYDESDALE'S PRICE ONLY **63/-** PER UNIT — CARRIAGE PAID

THE P40 V.H.F. RECEIVER UNIT Adm. Ref. W.7945.A.

A Crystal controlled 9 valve (2 EF54, EC52, 2 EF39, EB34, 6J5, 6V6) Receiver Unit, range 85-98 mcs. I.F. 2·9 mcs. with valves less crystal in louvred metal case, 11¼ × 5¼ × 4¼in. Finish grey. Power requirements, external (H.T. 175 v. D.C. 60 mA. L.T. 12·6 v. 2·5A).

CLYDESDALE'S PRICE ONLY **£4.19.6** EACH — POST PAID

S-440-B V.H.F. TRANSMITTER CHASSIS

Partly stripped by the M.O.S., less valves, tuning coils and crystal, but otherwise fairly intact. A fine basis for V.H.F. Tx. or 144 mcs. rig. Original frequencies 85-98 mcs., valve types 3 RK34, 2 6S7, 6V6. Housed in louvred case, finish grey crackle.

CLYDESDALE'S PRICE ONLY **27/6** POST PAID

NEW LIST No. 8.B

Giving details and illustrations of ex-service items and cancelling all previous lists and supplements.
NOW READY PRICE 1/6d. Price credited on first purchase of 10/- or over.

R.1155 RECEIVER A.C. MAINS

Receiver R.1155 with 7 valves, 5 wavebands, 18-7·5 Mcs (17-40 m.), 7·5-3 Mcs (40-100 m.), 1,500-600 Kcs (200-500 m.), 500-200 Kcs (600-1,500 m.), 200-75 Kcs (1,500-4,000 m.), S.M. Drive B.F.O., etc., etc. Dim.:—16½ × 9 × 9in.
POWER OUTPUT PACK, with 2 valves, 8in. L.S. etc., etc., dim.: 14 × 14 × 7in. Complete with linking cable and circuits.

CLYDESDALE'S PRICE ONLY **£21.0.0** CARRIAGE PAID

No. 9 SET MK. I RECEIVER UNIT, with Power Supply Unit. In original wood case

A ten valve 7/AFN3, 2/12SC7, 12Y4, Band-Pass, superhet receiver frequency range, 2 to 5 mcs. with built in calibrator, switched HT and "S" meter, RF and LF gain, B.F.O. etc., etc.
Separate Power Unit, operates from 12 v. D.C. or 115 v. or 230 v. A.C. OZ4 cold cathode rectifier, with spares kit, all valves, aerial, insulators, headphones.

CLYDESDALE'S PRICE ONLY **£10.0.0** CARRIAGE PAID

W.S.18 RECEIVER SECTION

Superhet Chassis, range 6-9 mcs. (50-33·3 metres) with 4 valves 3/ARP-12, etc., etc., on 8¼ × 8¼ × 1in. Chassis, front panel 9¼ × 3¼in.

CLYDESDALE'S PRICE ONLY **32/6** EACH — POST PAID

Circuit 2/3.

Also available with partly stripped (M.O.S.) Tx-section, no valves or meter, in metal carrying case. Dim.: 11 × 10 × 17in.

CLYDESDALE'S PRICE ONLY **42/6** EACH — CARRIAGE PAID

Circuit for 4/6.

THROAT MICROPHONES

Pair electro-magnetic throat pieces (7·5 ohms each) with strap, lead and jack plug. Ref. ZA13955.

CLYDESDALE'S PRICE ONLY **5/6** PER PAIR — POST 6d.

FOR EXPORT ONLY. WIRELESS SET NO. 38 MK. II—BRAND NEW

A haversack type transceiver range up to 5 miles. Frequencies 7·7 to 9 mcs. 5 valves, 4 ARP12, ATP4, operated from dry batteries, H.T. 120 v., L.T. 3 v. (not supplied) complete with headphones, Junction box, spares, satchel and instruction card. 4 complete units packed in wood case 27½ × 14 × 14in. **PRICE ON APPLICATION.**

TEST KIT, TYPE 6. Ref. 10S 720

For testing APN-1 Radio Altimeter Equipment. Comprising the Radio Altimeter F.M. Oscillator operating on 420 mcs. British version using mostly American Components including 2/955 acorns. Complete with Dynamotor for 24 v. D.C. operation (recess for alternative 6 v. and 1·5 v. batteries). In metal carrying case with handles and hinged lid, 18 × 15 × 10¼in.

CLYDESDALE'S PRICE ONLY **£7.19.6** CARRIAGE PAID

FLUXMETER WY.0023

Designed to calibrate the field of Magnets within the range of 500 to 4,000 guass and to determine their polarity. Complete with probe unit and contained in a hardwood case with hinged lid and handle. Instructions on lid. Dimensions: 11½ × 9 × 6in.

CLYDESDALE'S PRICE ONLY **£7.10.0** CARRIAGE PAID

CRYSTAL OVEN. (Few only)

Brand new, extremely sensitive with adjustable thermostatic control and thermometer. Built into a cork lined metal box 12 × 6¼ × 6¼in. Weight 5¼ lbs.

CLYDESDALE'S PRICE ONLY **£4.19.6** POST PAID

12 VOLT MOBILE AMPLIFIER

A compact 4 valve (2 EL35, EF36, ECC31) 3 stage Amplifier. Output 15 watts. Rotary generator power unit, input 12 volts 96 watts. Provision for 10 ohm. L.S., M.C. Mic, and Gram. In metal cabinet 13 × 9 × 9in.

CLYDESDALE'S PRICE ONLY **£10.10.0** CARRIAGE PAID

METAL (MINE) DETECTOR NO. 4

Of Cdn. design and construction, using 1T4 pentodes. Comprising TC Amplifier Search Coil, Sweep Pole, Control Box, Headphones, Test Unit and Rucksack. Complete less batteries in fitted transit case.

CLYDESDALE'S PRICE ONLY **£6.19.6** CARRIAGE PAID

AMPLIFIER A1271. LOU/549

A one valve (VR56 = EF36) Amplifier Chassis, with 400 ohm. 4M 2B Relay, 2 transformers, vol. control, cond., and resistors, mounted on rubber in a black finish metal case, 5 × 5 × 4¼in.

CLYDESDALE'S PRICE ONLY **10/6** POST PAID

PHOTO MULTIPLIER, Type 931A Assembly

Tube with resistor network and holder in light proof metal chamber. Only 3 connections to make.

CLYDESDALE'S PRICE ONLY **£3.19.6** EACH — POST PAID

INFRA RED IMAGE CONVERTER CELL

CLYDESDALE'S PRICE ONLY **15/-** EACH — POST PAID.

PANORAMIC GUNNERY TRAINER Mk. II

In original wood case.
Comprising 35 mm. Silent Film Projector with 300 watt lamp, 2,000 foot film magazine, Control Amplifier, 2 valve, 2051, 6 × 5 Hand Rewind Mechanism, etc. Dim.— 30¼ × 27½ × 11½in. Weight packed 2 cwt. 3 qrs. Operating voltage: 95-125 v. A.C. 60 c.p.s. 400 watts.

CLYDESDALE'S PRICE ONLY **£50.0.0** EACH — CARRIAGE PAID

MOVING COIL MIC/HEADPHONE ASSEMBLY

M.C. Headphones have padded earpieces, Microphone is Handset No. 7 with leads terminated in 5-way rubber socket (tank style). Brand new. Boxed.

CLYDESDALE'S PRICE ONLY **25/-** POST PAID

TEL-REC HANDSET NO. 9 ASSEMBLY

M.C. Headphones fitted with rubber earpieces. Microphone is Carbon Power type, with leads terminated in 5-way rubber socket (tank style). Brand new. Boxed.

CLYDESDALE'S PRICE ONLY **25/-** POST PAID

LOW IMPEDANCE HEADPHONES DLR-1

With metal strap headbands, lead and jack plug. Brand new. Boxed. Resistance approx. 50 ohms.

CLYDESDALE'S PRICE ONLY **12/6** PER PAIR — POST PAID

HIGH IMPEDANCE HEADPHONES

CHR-2 with wire headband and canvas neckstrap, resistance 4,000 ohms. Brand new. Boxed.

CLYDESDALE'S PRICE ONLY **21/-** PER PAIR — POST PAID

Order direct from :—

CLYDESDALE SUPPLY CO. LTD. 2 BRIDGE STREET GLASGOW · C5

Phone : South 2706/9 — Branches in Scotland, England and Northern Ireland

LASKY'S RADIO

"World Renowned for Service Reliability"

LASKY'S OWN TEST PRODS

Made for safety. Fused test prods. Fully insulated pencil type with retractable point. Contact is only made when desired by pressing top. Each prod contains a cartridge type fuse and spring.

LASKY'S PRICE **4/11** per pair (one red, one black). Post 6d. extra.

COIL PACKS

No. 1. 3 Waveb ands, 12-35 metres; 35-100 metres; 200-550 metres. ¼in. spindle, 1½in. long wavechange switch. Completely assembled and wired. Size: 4in. x 4in. x 3in. BRAND NEW.
LASKY'S PRICE **16/-** Postage 1/- extra. Circuit available price 1/-

No. 2. Midget Coil Pack, 3 waveb ands. Standard long, medium and short. ¼in. spindle, 2in. long wavechange switch. Completely assembled and wired. Size: 3¼in. x 1¾in. x 2¼in. BRAND NEW.
LASKY'S PRICE **24/6** Postage 1/- extra.
Circuit available, price 1/-

ALL OTHER TYPES AND MAKES OF COIL PACKS AVAILABLE

Osmor, Weymouth, Wearite, etc., etc.

COLLARO AUTOMATIC RECORD CHANGERS

Model RC.500. Magnetic pick-up	£11	15	7
Model RC.560. Xtal pick-up	£12	3	0
Model RC.811. 3 speed, with dual purpose pick-up head	£15	10	6
Model RC.611. 3 speed, with 2 crystal pick-up heads	£18	14	1

WEARITE LF. TRANSFORMERS. Type 550

Permeability tuned, 445-920 Kc/s. Type 551. Critically coupled, with top grid connection. Type 552. Closer coupling for feeding diode circuit. Q115, inductance 700 micro-henries at 465 Kc/s.
Bandwidth of each of the above transformers is 7-20 Kc/s at 9-20 dbs. Size: 3¼in. high, 1¾in. square. Supplied with fixing screws and nuts.
LASKY'S PRICE **6 6** each Post 6d. extra **12 6** per pair Post 1/- extra.

TANNOY HAND-POWERED MICROPHONE AND HEADPHONES (M/C).
LASKY'S PRICE **12 6** Post free. per set.

SMOOTHING CHOKES

70 mA. 40 H.	3 11
40 mA. 8 H.	3 11
40 mA. 10 H.	4 3
90 mA. 10-20 H.	4 11
120 mA. 10-20 H.	7 6
150 mA. 10-20 H.	10 6
150 mA. 3 H.	3 3
220 mA. 5 H.	10 6

Postage extra.

EXPANDED METAL SPEAKER FRET

Metal finished silver. Size: 12in. x 12in.
LASKY'S PRICE **4/3** per piece
Post 6d extra.

RADAR INDICATOR UNITS TYPE 162C

BRAND NEW IN MAKER'S ORIGINAL WOOD CASE. Contains 1 cathode ray tube, 6in. VCR517. Also the following valves: three SP61, one 6J5, three EA50, one D1. Dozens of components, coils, resistance, condensers, seven pot. meters, etc. Enclosed in metal case, size 12in. x 9in. x 10½in. Weight 30lb.
LASKY'S PRICE **75/-**
Carriage 7/6 extra.

FILAMENT TRANSFORMERS

All primaries 230 volts 50 c.p.s.

FIL. 2, 6.3 v. 1.5 a.	Price 7 11
FIL. 3, 6.3 v. 3 a.	Price 10 6
FIL. 4, 5 v. 3 a.	Price 4 11
FIL. 5, 6.3 v. 4 a.	Price 12 6

Special Transformer. 30 volts at 2 amps. with the following tappings — 3, 4, 5, 6, 8, 9, 10, 12, 15, 18, 20, 24 and 30 volts. Price 21/-
All fil. trans. 1/- extra per item postage.

OUTPUT TRANSFORMERS

Miniature Pentode (1S4, 3S4)	3 11
Midget Pentod: 40 mA	4 3
Multi-Radio Standard	6 11
Push-Pull, 80 mA. Ratios of 40 : 1 and 60 : 1	8 6
Push-Pull for PX4's	12 6
80 mA heavy duty, multi-ratio	12 6
10 Watt multi-ratio	16 11
30 Watt, 70 mA, Multi-ratio.	29 11
Bulgin intervalve transformers. Ratio : 4 : 1	3 11
5 : 1	5 11
Standard Pentode, 60 mA.	3 11

Postage extra.

ALL WAVE RADIO! AT HALF PRICE



- ★ 5 new valves.
- ★ 8in. Elac p.m. speaker.
- ★ Variable tone control.
- ★ Large edgelit dial, 7½in. square.
- ★ 2-speed tuning with nylon drive.
- ★ 4 watt output.
- ★ Sockets for p.u. and extension speaker.
- ★ 465 Kc/s I.F.
- ★ A.V.C.
- ★ Circuit diagrams.

Size of chassis: 15½in. wide, 8in. deep, 2½in. high.

NOT A KIT, BUT A FACTORY BUILT JOB. FULLY ALIGNED AND TESTED.

Enclose 2½d. stamp for full details, circuit diagrams and illustrations.

LASKY'S PRICE
£10 . 19 . 6
Complete with 5 valves and speaker.
Carriage and insurance 10/6 extra.

MAINS TRANSFORMERS

All 200-250 volts 50 c.p.s. primary. Finest quality, fully guaranteed.

MBA 3. 350-0-350 v. 80 mA., 6.3 v. 3 a., 5 v. 2 a. Both filaments tapped at 4 volts. An ideal replacement trans. Price 21/-
MBA 5. 350-0-350 v. 120 mA., 6.3 v. 4 a., 5 v. 3 a. With mains tapping board Price 27 6
MBA 6. 350-0-350 v. 100 mA., 6.3 v. 3 a., 5 v. 2 a. With mains tapping board Price 22 6
MBA 7. 250-0-250 v. 80 mA., 6.3 v. 3 a., 5 v. 2 a. Both filaments tapped at 4 volts Price 21/-
AT 3. Auto transformer. 0-10-110-200-220-250 volts, 100 watts Price 19 6
AT 4. Auto transformer. 100 volts and 250 volts. Step up or down. 60 watts Price 9 6
Postage 1/6 extra per transformer.

DECCA GRAM MOTORS

Single Speed	£3 14 4
Three Speed	£7 3 4

B.S.R. GRAM UNITS

3-speed unit, with pickup and change over crystal head. Supplied with two sapphire styli. £9 19 11

LARGE STOCKS OF RESISTANCES ALWAYS AVAILABLE

All values. Prices: 1/10th and 1/8th watt, 7½d. each; ¼ and ½ watt, 4d. each; 1 watt, 8d. each. Postage extra.

MIDGET VAXLEY SWITCHES

4 pole 3-way and 2 pole 2-way. Long spindle.
LASKY'S PRICE **2 11** each. Postage 3d. extra.

TABLE MICROPHONE STAND

Two sections, chrome plated. Crackle finished base.
LASKY'S PRICE **17/6**
Post, packing 2/6 extra.

CARBON POT METERS

All with long spindle, ¼, ½, 1 and 2 meg.
LASKY'S PRICE, less switch **3/3** each.
WITH SWITCH 4/3 EACH
All post extra.
Short Spindle and pre-set. PRICE 1/6 each. Post extra.

J RA/2. 10-12 WATTS CHASSIS AMPLIFIER

Uses an L63 feeding 2 KT61s in push-pull. Rectifier type. U50. Size: 8in. x 12in. on 2in. chassis
LASKY'S PRICE **£7/19/6**
Carriage and packing 10/- extra.
Send 3d. stamp for further details of J/RA/2 Amplifiers
FREE. With each amplifier a copy of "AMPLIFIERS". This book gives full details of the theory and practice of sound amplification. Normally priced 3/6.

ALL YOUR RADIO VALVE REQUIREMENTS AT LASKY'S

ANTENNA ROD SECTIONS

Each section is steel heavily copper plated, 12in. long and ¼in. in diameter. Any number of sections can be fitted together. LASKY'S PRICE 2/6 per doz.; 6/- for 3 doz.; 11/- per half gross; 20/- per gross. Post free.

P.M. LOUDSPEAKERS

All less o/trans. New and unused. First quality.

3in.	12 11
5in.	12 6
6½in.	12 6
8in.	14 6
10in.	28 6
12in.	75/-

SETS OF ENGRAVED KNOBS

1 each: Tuning, Volume, L.M.S.G., and Tone.
LASKY'S PRICE **4/-** the set. Post extra.

MAINS DROPPERS

All types from 2/6 each. 12 assorted, 25/-. Post free.

SOLON-HENLEY ELECTRIC SOLDERING IRONS

Brand new and unused. Supplied with fitted heavy rubber mains lead. Pre-Increase Prices.
Oval Bit. For 230/250 volts only.
LASKY'S PRICE **19/-** Postage 1/- extra.
Pencil Bit. For 200/220 volts only.
LASKY'S PRICE **21/-** Postage 1/- extra.

6 VOLT 90 A.H. CAR BATTERIES

Ex-American Army. Absolutely perfect, brand new and unused, in maker's original packing case. Size: 9in. wide, 7in. deep, 8in. high. In genuine hard rubber case.
LASKY'S PRICE **87/6**
Carriage 7/6 extra.

LASKY'S RADIO

Lasky's (Harrow Road) Ltd.,

370 HARROW ROAD, PADDINGTON, LONDON, W.9

(Opposite Paddington Hospital) *Telephones:* CUNningham 1979 and 7214

Hours: Mon. to Sat. 9.30 a.m. to 6 p.m., Thurs. half day 1 p.m. TERMS: Pro Forma, Cash with Order, or C.O.D. on post items only. Postage and packing extra, unless otherwise stated. All goods fully insured in transit.

LASKY'S RADIO
"Well Renowned for Service & Reliability"

TELEVISION CONSOLE CABINETS

DE LUXE BEAUTIFUL WALNUT VENEER

For 12in. cathode ray tubes. Beautiful figured medium walnut finish, with high polish. Fitted with shelf for receiver, glass, speaker baffle and fret, and castors for easy movement. Undrilled. Suitable for use with the Viewmaster, "Practical Television," "Practical Wireless," and "WirelessWorld" televisors.

LASKY'S PRICE
£8 . 10 . 0
Carriage 12/6 extra.

Outside dimensions of cabinet: 17½in. x 16½in. x 32in.

Why not convert your table receiver to a console?

Adaptor frames for fitting 9in. or 10in. C.R. tubes available if required.

W. B. PLESSEY & ALLEN T.V. COMPONENTS

Line EHT Trans., 27/6.
Frame Trans., 21/6.
3 Mc/s Boost Choke, 5/9.
Width control, 10/-.
Scanning coils, 29/6.
Main choke, 15/6.
Focus ring, 22/6.
Heater Trans.: WB/103, 37/6. WB/103A, 52/6.
C.R. Tube supports, front and rear, 18/9.

SUPPLEMENT YOUR E.H.T. FROM THE LINE FLYBACK, AND USE A LARGER C.R. TUBE, by using a BOOST E.H.T. KIT. Comprises one selinium rectifier, one 2-meg. resistance and two T.C.C. .001 mfd. 6 kV condensers. For converting 9in. T.V. receivers to 12in.

LASKY'S PRICE 20/-
Post Free.

METAL RECTIFIERS FOR TELEVISION

WX3	3 9
WX6	3 9
14A86	20 4
14D36	11 8
36 EHT 25 1.8 Kv.	14 6
36 EHT 35 2.5 Kv.	19 0
36 EHT 40 2.9 Kv.	21 7
36 EHT 45 3.4 Kv.	23 8
36 EHT 50 3.6 Kv.	26 1
36 EHT 100 7 Kv.	29 6

Postage 6d. per item extra.

FRAME BLOCKING OSCILLATOR TRANSFORMERS.
LASKY'S PRICE 4/6 each.
Post 4d. extra.

T.C.C. T/V CONDENSERS

100 mfd. CE10LE	14/-
250 mfd. CE10DA	10/-
2,500 mfd. 6 v.w. CE25AA	6/9

All other types in stock.

CATHODE RAY TUBES. All types and sizes available from stock. Brand new and fully guaranteed.

12in.	from £18 4 10
15in.	from £22 16 10
16in.	from £24 6 5
14in. rectangular	from £22 8 5

WENVOE & KIRK O' SHOTTS COILS for the VIEWMASTER. 10 coils and 4 filter coils, by Wearite. Exactly as specified in the construction data. Available from stock. **PRICE** 28/-, postage 1/- extra.

Everybody is Building THE VIEWMASTER



The Viewmaster television receiver can be built at home from standard parts. Wenvoe, Kirk o' Shotts, Holme Moss, Sutton Coldfield and Alexandra Palace operation. Brilliant high definition black and white picture. Superb reproduction. Uses 9in. or 12in. Cathode Ray Tube. Table or Console Model. Incorporates all the latest develop ments.

Television for the home constructor at its finest.

Send to-day for the CONSTRUCTION ENVELOPE, a 32-page booklet crammed with top-rate information and all the necessary data, also 8 full-size working drawings and stage by stage wiring instructions. Model "A" for use in London and Home Counties. Model "B" for use in Sutton Coldfield Area. Model C for Holme Moss. Model D for Kirk o' Shotts. Model E for Wenvoe.

Models A, B and E 5/- PER COPY. Post 4d. extra.
Models C and D 7/6 PER COPY. Post 4d. extra.

ALL COMPONENTS IN STOCK AND SOLD SEPARATELY

5in. CLOSED FIELD LOUDSPEAKERS. Ideal for television receivers. Less o/trans. 3 ohms. Will not affect your C.R. tube.
LASKY'S PRICE 17/6
Post 1/6 extra.

T.C.C. VISCONOL HIGH VOLTAGE CONDENSERS (Cathode ray).
.001 mfd. 6 kV. Price 4/6 each.
.001 mfd. 12.5 kV. Price 7/6 each.
.1 mfd. 7 kV. Price 15/- each.
All post extra.

Owing to the extreme shortage of metal and wire all goods are offered subject to being unsold and prices are liable to alteration without notice.

ENGRAVED KNOBS. 1¼in. diameter, ¼in. Spindle. For television, radio and amplifiers. All types. **PRICE** 1/5 each. Post extra.

AT LAST IT'S HERE. The very latest 8 kV. line transformer with variable inductance width control. The transformer is fully impregnated and screened, size 5" high, 4" wide, 3" deep. For use with EY51 and EL38 valves. This transformer is as used in the latest type televisions receivers.
LASKY'S PRICE 85/-
Postage 1/- extra.

SPECIAL OFFER LINE TIME BASE KIT. Comprises the above transformer, also an EY51, EL38, scanning coils (line and frame), 3 controls, line 1in. hold and shift—also 8 associated condensers and resistances.
LASKY'S PRICE £6 19 6
Postage 2/6 extra.

C.R. TUBE MASKS

9in. soiled	7/6
12in. good white	10/-
Brand new white	19/6
Special for flat-face tubes	22/-
Grey rubber sorbo, Flock sprayed	7/6

Postage 1/6 each extra.

TINTED SCREEN FILTERS. 9in.-10in., 18/6. 12in., 25/-. Postage 1/- each.

CO-AXIAL CABLE
Standard impedance.
Single screened, 1/- per yard.
Twin screened, 1/6 per yard.
Twin balanced feeder, 7½d. per yard. Post extra. Any length cut to your requirements. 10% discount on 50 yards or more.

E.H.T. TRANSFORMER FOR VCR97. Primary 200-250 v., 50 cps. Secondary: 2.5kV. 4 m.a.; 4v. 1.1a.; 4v. (CT) 1.5 a.
LASKY'S PRICE 45/-
Postage 1/6 extra.

TELEVISION PRE-AMPLIFIERS, for London frequency. 2 Stage, uses 2 6F13 valves. Completely wired, ready for use.
LASKY'S PRICE 19 6
(less valves)
Postage 1/6 extra.

VCR97 C. R. TUBES. BRAND NEW AND UNUSED. In makers original sprung wood transit case.
LASKY'S PRICE 40/-
Carriage 5/- extra.

ARMOUR PLATE SAFETY GLASS. For 9in. tubes 3/-, 12in. 4/- per piece. Post 1/- each.

LASKY'S RADIO

LASKY'S (Harrow Road) LTD.

370 HARROW ROAD, PADDINGTON, LONDON, W.9

(Opposite Paddington Hospital) *Telephone*: CUNningham 1979 and 7214

Hours: Mon. to Sat. 9.30 a.m. to 6 p.m., Thurs. half day 1 p.m. TERMS: Pro forma, cash with order, or C.O.D. on post items only. Postage and packing extra, unless otherwise stated. All goods fully insured in transit.

EX-A.M. COMMUNICATION RECEIVER TYPE R1155

BRAND NEW IN WOOD TRANSIT CASE. Aerial-tested before despatch. Supplied complete with 10 valves. Circuit: B.F.O., A.V.C., R.F. Amp., two I.F. stages, magic eye, etc. 4 frequency ranges: 16.5-7.5 Mc/s.; 7.5-3.0 Mc/s.; 1,500-600 Kc/s.; 600-200 Kc/s.; 200-75 Kc/s.

LASKY'S PRICE **£12 10 -**

Carriage (in wood case) 7/6 extra. Full modification data and circuit details supplied.

VIBRATOR PACKS

12 volt input. Fitted with synchronous vibrator. Brand new and unused.

No. 1. Output 250 v. 100 mA.

LASKY'S PRICE Less vibrator **20 -**

No. 2. Output 150 v. 50 mA.

LASKY'S PRICE Complete Less Vibrator 17/6.

Carriage 2/6 per pack extra.

No. 3. For use with P.C.R. Philips Communication Receiver. Supplied complete with metal rectifiers, and vibrator, etc. LASKY'S PRICE **39/6**

Carriage 5 - extra.

RECEIVER TYPE 25

Rx. section of TR1196 equipt. Size: 8½in. x 6in. x 6½in. Contains 6 int. octal valve holders, condensers, coils, tuning, etc. Ideal for conversion to an all wave receiver. In black metal case. LASKY'S PRICE **10/6** Carriage 3/6 extra.

CAR RADIO PLUG AND DISTRIBUTOR SUPPRESSORS

LASKY'S PRICE **1 -** each

10 - per dozen. Post extra.

EPICYCLIC DRIVES

Long 6in. spindle. Special double type. Standard reduction.

LASKY'S PRICE **2/6** each. Post 4d. extra.

STANDARD TYPE EPICYCLIC DRIVE

LASKY'S PRICE **1/6**

Post 4d. extra.

ALL YOUR TEST GEAR AT LASKY'S

LASKY'S NEW RANGE OF POSTAGE STAMP TRIMMERS AND PADDING CONDENSERS.

Paxolin. 5-35 pf. 40-50 pf. 70-100 pf.

LASKY'S PRICE 6d. each 5 - per doz.

350 pf. and 450 pf. Ceramic.

Ceramic 5-35 pf. 40-60 pf. 70-100 pf.

LASKY'S PRICE 9d. each 7/6 per doz.

LASKY'S PRICE 1 - each. 10/6 per doz.

PRESS BUTTON SWITCH UNITS.

Supplied with buttons. These units have many useful applications.

LASKY'S PRICE 3 way 1 11d. Post 6d. extra.

7 way 2 11d. Post 6d. extra.

LASKY'S RADIO

World Renowned for Service & Reliability

VALVES

At the lowest possible prices.

10,000 VALVES IN STOCK. A few examples.

PEN. A.4	12 10	1D5	11 -
VP41	12 10	APV4	12 11
Mc PEN	12 10	CV1	11 -
VP137	12 10	U16	11 -
VP133	12 10	ACTP	14 -
PEN3520	12 10	ECH3	14 -
		U26	11 -

ALL BRAND NEW AND FULLY GUARANTEED. SEND US YOUR REQUIREMENTS

½LB. TINS INSULATION TAPE.

1in. wide.

LASKY'S PRICE **2/6** per tin. Post 6d. extra.

TAG STRIPS. 2, 3, 4, 5, 6, 7 WAY.

LASKY'S PRICE **1d.** PER TAG, i.e., 4-way 4d.

6 and 12 VOLT VIBRATORS

4 pin type.

LASKY'S PRICE

Soiled **5 -** each. Post 6d. extra.

New **9/6** each. Post 6d. extra.

A GENUINE MINIATURE 2-GANG TUNING CONDENSER

No. 1. .0005 mfd. Size: 1¼in. deep, 1¼in. high, 1in. wide. ¼in. spindle. With fixing feet.

LASKY'S PRICE **6/6** each. Post 6d. extra.

No. 2. .0005 mfd. Size 2¼in. x 2in. x 1¼in. ¼in. spindle.

LASKY'S PRICE **7/6** each. Post 6d. extra.

SERVISOL

The cleaning fluid no service man can do without. Standard size half pint tins.

PRICE **5 -** per tin. Postage 9d. extra.

CABINETS FOR INTER-COM CHASSIS

Medium walnut finish drilled for switches, indicator bulbs, etc.

LASKY'S PRICE **25 -** Carriage 2/6 extra.

INTER-COM UNIT SCOOP

Manufacturer's surplus. Brand new. For 6 station operation, uses 3 valves, 1 each 25Z4, KT32, and 6J7. AC/DC mains. Fully assembled and wired.

AT A FRACTION OF USUAL COST.



LASKY'S PRICE **£5 . 5 . 0**

Carriage 2/6 extra.

Complete with all valves, speaker and indicator bulbs.

A FEW CHASSIS LESS VALVES, BULBS, AND SWITCH.

LASKY'S PRICE **35/-**

Carriage 2/6d. extra

WRITE FOR FURTHER DETAILS

HIGH VOLTAGE CONDENSERS

1 x 1 mfd. 2 kV. Price 5/6 each.

1 x 1 mfd. 5 kV. Price 19/6 each.

25 mfd. 2.5 kV. Price 6/6 each.

.1 mfd. 2.5 kV. Price 3/6 each.

Post 6d. extra.

TOGGLE SWITCHES

Bulgin S.P. Rotary on-off. Long spindle. LASKY'S PRICE **2/6** each

S.P.D.P. On-off switch.

LASKY'S PRICE **1/-** each.

Post extra.

ANTENNA RELAY UNITS TYPE CBY 29125.

BRAND NEW AND UNUSED IN ORIGINAL CARTONS. American Air Corps equipment. Contains a 0-5 mA moving coil meter, also relay, insulators, 0.75 amp heating element, switch, etc. A 50 pf. vacuum condenser 5 kV working. Fitted in black metal case, crackle finished, size 4½in. x 5in. x 7½in.

LASKY'S PRICE **16/6**

Postage 1/6 extra.

PLIERS

Round nosed. Various sizes.

LASKY'S PRICE **1/3** per pair Post extra.

SPEAKER CABINETS

For use with a 3in. speaker. Medium walnut finish. Ideal as extensions for the inter-com. units.

LASKY'S PRICE (Less speaker) **12/6**

Carriage 2/- extra.

HEADPHONES

DLR1. Low resistance, new and unused. Supplied complete with headband and cord.

LASKY'S PRICE **7/6** per pair. Postage 1 - extra.

AMERICAN AIR CORPS TYPE

Lightweight. Supplied complete with headband and cord.

LASKY'S PRICE **9/6** per pair. Postage 1 - extra.

CONDENSER CORNER

8 mfd. 500 v.w.	3 -
8 mfd. 450 v. w.	2/6
8 + 8 mfd. 500 v. w.	4/6
8 + 16 mfd. 500 v. w.	5/6
12 mfd. 50 v. w.	1 -
16 mfd. 450 v. w.	4/11
16 mfd. 500 v. w.	5/3
16 + 16 mfd. 450 v. w.	5/6
24 mfd. 450 v. w.	6/11
25 mfd. 25 v. w.	1/6
20 + 40 mfd. 350 v. w.	6/11
32 mfd. 450 v. w.	5/11
32 mfd. 500 v. w.	6/6
32 + 32 mfd. 350 v. w.	5/6
50 mfd. 12 v. w.	1/9
50 mfd. 50 v. w.	3/9
50 mfd. 350 v. w.	4/11
55 mfd. 350 v. w. A.C.	17/6
12 + 12 mfd. 350 v. w.	3/11
16 mfd. 350 v. w.	2/11
32 + 32 mfd. 350 v.w. and 25 mfd. 25 v.w. in one can	6/6

Postage extra.

CRYSTAL DIODES

Wire ends. Supplied with circuit. R.T.H. type.

LASKY'S PRICE **3/11** each.

G.E.C. type **4/6**, postage 3d. each extra.

EX-GOVERNMENT TEST INSTRUMENTS.

PERFECT CONDITION. Evershed and Vignoles, 250 volt bridge meg. tester. In leather carrying case.

LASKY'S PRICE **£18 18 -** Carriage extra.

CIRCUIT TESTING OHMMETER. By Evershed and Vignoles. In leather carrying case.

LASKY'S PRICE **£4 19/6** Carriage extra.

I.F.F. RECEIVER TYPE R3108.

BRAND NEW AND UNUSED. IN ORIGINAL CARTONS. Contains 8 new valves: 4 8P41, 1 EA50, 1 VR78, 2 CV6. Also a host of components, coils, condensers, resistances, etc. A motor generator with input of 24 volts, and output of 480 volts.

LASKY'S PRICE Carriage 3/6 extra. **25 -**

FULLY SCREENED TOP CAPS. International octal. LASKY'S PRICE 1/6 each. post extra.

BULGIN E.H.T. TOP CAPS. Fully insulated. LASKY'S PRICE 2 - each. Post extra.

THE MONTROSE AC/DC POCKET MULTIMETER. PRICE 45/-. Postage 2/6 extra.

METAL RECTIFIERS

No. 1. 125 volts at 60 mA. Price 3/11. Post 4d.

No. 2. 125 volts at 100 mA. Price 4/3. Post 4d.

Any number can be used together, either in series or parallel.

No. 3. 50 volts at 5 mA. Price 2/6. Post 4d.

No. 4. 800 volts at 5 mA. Price 9/6. Post 4d.

LATEST PUBLICATIONS

THE OSCILLOSCOPE BOOK. (87 pages)

Full constructional details of a comprehensive but inexpensive scope. Also an explanation of a wide range of tests using both this or any other scope. Fully illustrated

PRICE 5/-. POST FREE.

AMPLIFIERS. (64 pages)

Packed with all the gen on this vital piece of equipment. Distortion, instability, gain, hum, negative feedback, etc. 58 Diagrams. This is the book to help solve all audio problems.

PRICE 3/6. POST FREE.

INEXPENSIVE TELEVISION

Data Book No. 4. Covering London, Midlands and Holme Moss frequencies, using war surplus equipment.

PRICE 2/6. POST FREE.

"WIRELESS WORLD" RADIO VALVE DATA BOOK

Characteristics of 2,000 valves, and cathode ray tubes.

PRICE 3/6d. Post 6d. extra.

MONEY BACK GUARANTEE

Everything ordered from Lasky's is guaranteed to be as advertised. If you are not more than satisfied return goods for cash refund.

I.F. STRIP TYPE 194. An easily modified I.F. Strip recommended for T.V. constructors who want good results at moderate cost, or for those who have built televisors but are having trouble in the vision or sound receivers. Can also be modified for 2 Channel working as per details in "Practical Television" October issue. This 6-stage strip measures 18in. x 5in. x 3in. and contains 6 valves : VR65, 1 of VR92, and 1 of VR53 or VR56. Mod. data supplied. BRAND NEW. ONLY **45**/- (postage, etc., 2/6).

RDF 1 RECEIVER. A very powerful 14-valve receiver with 4 I.F. stages of 12 mc/s. with 4 mc/s. bandwidth. Will convert into a first-class T.V. receiver for 2 Channel working as described in "Practical Television," October and November issues, a reprint being supplied. Valve line-up : 5 of SP61, 2 of P61 3 of EA50 and 1 each CV63, EB34, EC52, 5Z4G. ONLY **49 6** (carriage, etc., 5/-).

10-VALVE 1¼ METRE SUPERHET ZC8931. For long-distance T.V. results. Valve line-up is 6 of VR65 2 of VR92, and 1 each VR136 and VR137 and the 12 mc/s. 6-stage I.F. Strip gives tremendous amplification with ample bandwidth of 4 mc/s. Easily modified. Full details supplied. ONLY **59 6** (carriage 5/-).

RECEIVER R.3118. The A.C. MAINS VERSION of the above ZC8931, having a built-in power pack for normal mains supply. ONLY **97 6** (carriage, etc., 7/6).

TRANSFORMERS

Manufactured to our specifications and fully guaranteed. Normal Primaries.

425 v.-0-425 v. 230 mA., 6.3 v. 6 a., 6.3 v. 6 a., 5 v. 3 a., 0-2-4-6.3 v. 3 a. ONLY **72 6**.

350 v.-0-350 v. 160 mA., 6.3 v. 6 a., 6.3 v. 3 a., 5 v. 3 a. ONLY **42 6**.

250 v.-0-250 v. 100 mA., 6.3 v. 6 a., 5 v. 3 a. ONLY **32 6**.

All above are fully shrouded, upright mounting.

Universal Mounting 350 v.-0-350 v. 80 mA., 0-4-6.3 v. 4 a., and 0-4-5 v. 2 a. ONLY **18 6**.

Top shrouded drop through 260 v.-0-260 v. 70 mA., 6.3 v. 3 a., 5 v. 2 a. ONLY **16 6**.

EHT for VCR 97 Tube, 2,500 v. 5 mA., 2 v.-0-2 v. 1.1 a., 2 v.-0-2 v. 2 a. ONLY **37 6**.

5.5 kV. EHT with 2 taps of 2 v. 1 a. ONLY **72 6**.

7 kV. EHT with 4 v. 1 a. ONLY **82 6**.

PLEASE ADD 1/6 POSTAGE FOR EACH TRANSFORMER.

CHOKES. 20 H. 80-120 mA., **9 6** ; 5 H. 200 mA., **6**/- ; 30 H. 100-150 mA., **12 6** (postage 1/-).

VCR97 CR TUBES. Another delivery of these famous tubes, all guaranteed tested and suitable for Television. ONLY **45**/-, carriage paid.

TRAIN TRANSFORMER, giving tapped outputs of 3 v., 4 v., 5 v., 6 v., 8 v., 9 v., 10 v., 12 v., 15 v., 18 v., 20 v., 24 v., 30 v. at 2 amps., from normal mains input. ONLY **17 6** (postage 1/-).

6in. MAGNIFYING LENS FOR VCR97 TUBE. First-grade oil-filled. ONLY **25**/- (postage 1/6).

"PYE" 45 MC/S. I.F. STRIP. Ready made for London Vision Channel. Complete with 6 valves EF50 and an EA50, and details of very slight mods. required. ONLY **57 6** (postage, etc., 1/6).

100 MICROAMPS METER. 2½in. Flush mounting. Widely calibrated scale of 15 division marked "Yards," which can be re-written to suit requirements. These movements are almost unobtainable to-day, and being BRAND NEW IN MAKER'S CARTONS are a "snip" at ONLY **39 6**.

EX-W.D. TRANSFORMERS. All heavy duty with 230/250 v. primaries. Type A has secondaries of 330-0-330 v. and 4 v. 3 a. ONLY **22 6**. Type B is an EHT transformer with secondaries of 2 v. 1.5 amps., 300 v. 10 mA., 520 v. 10 mA., 1,400 v. 2 mA. ONLY **21**/-. Type C is a Filament Transformer with secondaries of 6.3 v. 7.7 amps., 4.2 v. 2.5 amps., 4 v. 1 amp. ONLY **19 6** (postage 1/8 each item). ALL ITEMS BRAND NEW AND UNUSED.

Cash with order please, and print name and address clearly. Amounts given for carriage refer to inland only

U.E.I. CORPORATION

Radio Corner, 138 Gray's Inn Road, London, W.C.1. *Phone :* TERMINUS 7937.

(Open until 1 p.m. Saturdays. We are 2 mins. from High Holborn (Chancery Lane Station) and 5 mins. by bus from King's Cross.)

G2AK ***This Month's Bargains*** **G2AK**

PARMEKO H.D SHROUDED CHOKES. 8H at 250 mA. Weight 11 lbs. **16 6** each. Post and packing 1/6.

MOVING COIL HEADPHONES with moving coil microphone. Price 6/-. Post 1/-. Transformer to match 2/-. Balanced Armature L.R. Phones, **9 6** per pair.

TWIN RIBBON FEEDER. Heavy duty 300 ohm, **5d.** per yd. Standard K25 300 ohm ribbon, **9d.** per yd. Co-ax. cable, ¼in. dia. 50 ohm., **8d.** per yd., ½in. dia., **1/3** per yd. 7ft. length ¼in. dia. Co-ax. with Pye plug one end, **1/6**, post free. All other Co-ax. and feeder, plus 1/6 post any length.

POTENTIOMETERS. 5 watt wire-wound 20 k., 25 k., 2/- Carbon Type Potentiometers, 50 k., 100 k., 1 meg., 2 meg. 1/6.

TRANSMITTING TUBES. Type 807, 10/- ea. Type 813 New and Boxed **£3 10**/- each. Type 866A., **17/6** each. 3E29 (829B), **£4 10**/- each. Few only.

METERS. 2½in. Flush mounting M.C. 100 m/a., **12/6** each ; 2in. Flush M.C. 5 m.a., **7/6** ; 0.5 amp. thermo., **5**/- ; 4 amp. thermo, **5**/-. Special offer 2½in. flush 0—1 m.a. Rectifier Meter, scaled 0—10 volts, **22/6** each. Few only.

CERAMIC 2-bank, 4-pole, 4-way Switches, **3/9** each. Post free.

CERAMIC COIL FORMERS. 5in. long by 2½in. diameter ; threaded 24 grooves, **4/6** each, post free.

JONES PLUGS. 8-pin, male and female, **1/6** per pair, **12**/- per dozen pairs.

SHROUDED M.C. MIKE TRANSFORMERS. M.C. mike or line to grid, **5**/- each. P. & P. 1/-.

CARBON MIKE TRANS., 2/- each. P. & P. 6d.

COMPLETE SET (14) TUBES, for AR88 Receivers, **£6,** post free.

Carriage paid on all orders over £1 except where stated. Please include small amount for orders under £1.

Please print your name and address.

CHAS. H. YOUNG, G2AK

All Callers to ***110 DALE END, BIRMINGHAM***
'Phone : CENTRAL 1635.

Mail Orders to ***102 HOLLOWAY HEAD, BIRMINGHAM***
'Phone : MIDLAND 3254.

3-COLOUR TELEVISION FILTERS

These screens, delicately tinted to give blue skies, pink centre and green foreground will add to your viewing pleasure. Easily fitted.

For Screens 9" or 10" **10 9**, 12" **12 6**, 15" and 16" **19 6**

T.V. MAGNIFYING LENSES WITH STRAPS

9in. size makes 12in. picture. Clear type **55**/- ea.
9in. size makes 12in. picture. Filter type **60**/- ea.
12in. size makes 15in. picture. Clear type **75**/- ea.
12in. size makes 15in. picture. Filter type **80**/- ea.

Trade Enquiries Invited

MAYCO ELECTRIC 43 ROSEBERY AVENUE LONDON, E.C.1 Ter. 5958

TRANSFORMERS
COILS
CHOKES

TRADE ENQUIRIES INVITED

SPECIALISTS IN
FINE WIRE WINDINGS
MINIATURE DEAF AID TRANSFORMERS, PICK-UP
CLOCK AND INSTRUMENT COILS, ETC.

RADIOMENDERS LTD.
123-5-7 PARCHMORE ROAD, THORNTON HEATH, SURREY
LIVINGSTONE 2261 EST. 1933

Henry's
RADIO COMPONENTS
ELECTRONIC & TELEPHONE EQUIPMENT

5 Harrow Road, Paddington, W.2

PADdington 1008/9 and 0401

OSCILLOSCOPE TYPE 3BP1. We have pleasure in offering a 'scope designed primarily for simplicity and low cost at the same time giving reliable and consistent results. The Service engineer will find this an invaluable instrument due to its compactness, simplicity and speed of interpreting faults in radio receivers, checking transmitters, modulation, depth, etc.



SPECIFICATIONS :

Amplifier : Max. Gain, Peak to Peak = .3 volts per cm. Frequency response 10 c/s—100 k/c. Flat — 100 c/s to 50 k/c. Time Base : frequency range 5 c/s—30 k/c.

Dimensions : 8¼ × 6½ × 11½. Weight 17¼ lb. Black crackle finish.

Price : Brand New, **£14 14 0**, carr. pd.



POWER UNIT SS32. Complete with 5Z4G, VU120. .1 mfd. 2.5 kv. working. Relay and 80 v. trans. New condition **15 -**, post 1 6.



WALKIE-TALKIE TYPE "46" (case removed) complete with 6 valves. 2VP23, HL23, DD, QP25, TP25 and ATP4, aerial rods, I.F. trans., 1.6 mc/s. mike trans. in new condition, but less transmitting components and coils removed by M.O.S., **35 -**, carr. paid.



No. 38 "WALKIE TALKIE" TRANSRECEIVER (case removed), complete with throat mike, phones, junction box and aerial rods in canvas bag. Freq. range 7.4 to 9 mc/s. All units are as new and tested before dispatch. As supplied to Overseas police forces. **£4 19 6**, carr. 2 6.



PUSH-PULL OUTPUT TRANSFORMER. U.S.A. potted type primary, 10,000 ohms sec., 2 ohms, 8 ohm, 15 watts. **21 -**.

BOWTHORPE CONTINUITY METER. Dual scale 0-500 ohms and 100-200,000 ohms moving coil operated from 4½-volt internal battery. Size 6in. × 3in. × 4in. Original price **£8 19 -**. Our price, brand new, **£4 4 0**.

A COMBINED SIGNAL TRACER AND AUDIO OSCILLATOR

An easy-to-build unit that can be used for I.F. and Audio Signal Tracing, without any switching or tuning, including variable output oscillator for amplifier checking. Highly sensitive, responds to signals picked up from an ordinary receiving aerial.

The circuit is that of a high-gain 2-stage, resistance-coupled audio frequency amplifier, employing 3 miniature 1.4 valves, with a 3in. speaker in the Output of the Power Amplifier Stage. An added advantage being that as this unit is "All-Dry" it can be used with safety on A.C. or A.C./D.C. mains and battery sets. The complete kit with portable cabinet (size 6in. × 7in. × 6in.) and battery weighs only 4 lbs.

We shall be pleased to supply a complete kit for the construction of the above, right down to the last nut and bolt, including 2 1T4 and 1 1S4 valves, 3in. speaker and portable case and all-dry battery for **£4 19 6**. Concise instructions and circuits supplied. If preferred, circuit and instructions only can be supplied for **1 6**. If required this unit will be assembled and tested for extra charge of **15 -**. This is a highly efficient instrument, and a MUST for every radio man.

MAINS TRANSFORMERS. 250-0-250, 90 m.a., 6.3 v. 3 amp., 5 v. 2 amp., input 110 v. 250 v., **£1**, post 9d.
EX-MANUFACTURERS. 350-0-350, 100 m.a., 6.3 v. 4 amp., 5 v. 2 amp., input 200/250, **25 -**.
REPLACEMENT TYPE. 350-0-350, 90 m.a., 4 v. 6 amps., 4 v. 3 amps., input 200/250, **18 6**.
DUAL PURPOSE TYPE. 350-0-350 80 m.a., 6.3 v. tapped 4 v. at 3 amps., 5 v. tapped at 2 amps., 4 v., 2**8 -** (post 9d.).
GERMANIUM CRYSTAL DIODES, complete with full wiring circuit and diagram, **4 6**.
METAL RECTIFIERS. S.T.C. 200 volts 75 m.a., **6 -**; G.E.C. 6 volts 1 amp., **4 -**; Westinghouse 12 volts 2 amps., **12 6**; Pencil Type E.H.T., 600 v. 1 m.a., **4 7**; Pencil Type E.H.T., 1,000 v. 1 m.a., **6 -**; 12 v. 3½ amps., **17 6**.
S.T.C.R.M.2. 125 v. 100 m.a., **4 6**.
R.3515 I.F. STRIP. A complete I.F. Unit, comprising 6 5P61 I.F. stages, tuned to 13.5 mc/s., 1 EA50 diode detector, and 1 EF36 or EF39 output or video stage. A few modifications only are required to adapt this unit, which will give pictures of extremely good quality. Price, complete with valves and foolproof modification instructions, is **45/-**, plus 5/- carriage and packing. Limited quantity only.
E.H.T. TRANSFORMER for VCR97. Input 230 v., output 2,500 v. 4 v. 2-0-2, **39 6**.
E.H.T. TRANSFORMER for 5CP1. Input 230 v. output 3,250 v. 6.3 v. at 0.6 a/m, 2-0-2 v., **39 6**.
"HIGH-VOLT" R.F. OSCILLATOR. 5–7 Kv. at 250 μa., **£5 10 3**; 12.5 Kv. at 250 μa., **£10 10 -**.
RECEIVER R.1355.—As specified for "Inexpensive Television." Complete with 8 valves VR65 and 1 each 5U4G, VU120, VR92. Only **55 -**, carriage 7 6.
CONDENSERS. .1 mfd. 2,500 v.w., metal or bakelite, **2 6**. Electrolytics, 8 mfd. 450 v.w., **2 6**. 8 × 8 mfd., **4 -**; 16 mfd. 450 v.w., **3 6**; 16 × 16 mfd. 450 v.w., **5 -**. All midget Tubular Cans, cardboard sleeves. 60 mfd. × 40 mfd. 350 v.w., size 4¼in. × 1in. **7 6**. Bias Condensers, 25 × 25 mfd., 50 × 12, 12 × 50, **1 6**; 50 × 50, **3 -**. All new stocks—NOT surplus.
VIBRATOR POWER UNITS, 2 volt. As for Canadian 58 set. Completely smoothed, output 1.5 v. L.T. and 90 v. and 180 v. H.T. at 35 m.a. Complete in grey metal box. Size: 8in. × 3¼in. × 4¼in., **50 -**.
CATHODE RAY TUBES. VCR97, brand new, in original crates. Guaranteed for full picture on television, **45 -**, carr. paid. 3BP1, complete with base, holder and shield in metal case. Ideal for 'scope, **25 6**, 2 6 carriage.
KLYSTRON CV129. Brand new, **£3**.

If unable to call please send stamp for 28 page Comprehensive Catalogue.

C. MARKS & CO.

SPECIAL THIS MONTH :

T.V. CHASSIS (Manufacturer's Surplus). Brand New. Size 12in. × 16in. A complete T.V. set (sound, vision and time base) can be built on this chassis fitted with: 9 Mazda type valve holders, 5 SP.61, 2 SP.6, and 6 miscellaneous metals. Tagstrips are also fitted. An absolute bargain at **8.6**, plus 1.6 postage.

P.M. SPEAKERS (Manufacturer's Surplus). All well-known makes. 10in. (1948 model Z10L6), less transformer, **19.6**, plus 1.6 post. Six. (R.S.G. model 2006), less transformer, **15.6**, plus 1.6 post. Six., Type G6, less transformer, **12/6**, plus 1/- post.

SMALL MAINS TRANSFORMER COMPLETE WITH METAL RECTIFIER. Suitable for T.V. Pressing, Tuner Units and Test Equipment power supply. Input 220 v. 50 cps., output 200 v. 50 m.A, 6.3 v. 1.4 amps. **13.6**, plus 1.6 postage.

MAINS TRANSFORMER made by the Hammond Manufacturing Co. of Ontario. Input 110 watt, output 7 kV at 25 m.A. Size 10in. × 8½in. × 7½in. Suitable for Research Depts., etc., where high voltage at comparatively high current is required. Brand new at **£4.10** each, plus 1/6 post.

38 SET WALKIE-TALKIE REC TRANS. Frequency range 7.4 to 9 Mc/s. The ATP4 valve and S.R.S. switch have been removed by the Ministry, but these are supplied together with the 6 ARP12 valves. Special offer at **25/-**, plus 1/6 postage.

TRIMMER CONDENSERS. 100 pf + 100 pf Ceramic (No. 10 D.T.S.), **9/-** doz., plus 6d. post. Single 100 pf. Ceramic at **4.6** doz., plus 6d. post. Paxolin type 100 pf. + 100pf. and 100 pf. + 50 pf. at **4.6** doz., plus 6d. post.

SILVER MICA CONDENSERS. 500 pf., 50 pf. at **5/-** doz.
MOULDED MICA CONDENSERS (wire ends). 500 pf. at **6/-** doz.

POTENTIOMETERS. 100,000Ω with Switch. Brand new. All well-known makes. **2.6** each, **24/-** doz.

ELECTROLYTIC CONDENSERS. 8 mfd. 350 v. (Micropack) at **1.6** each. 16 + 16 mfd., 500 v. at **3.6** each.

TANNOY POWER MICROPHONE INSET (Cat. No. Y.A. 2815) for Tele. L.B. No. 1, 2 and 3. Brand new, **2/-** each, plus 6d. post.

IMPULSE MOTOR. Mounted on "A valve" chassis with valve holders, etc., **7.6** each, plus 1/- post.

VEEDER COUNTER. 0-9999. Suitable for checking number of turns in coil winding, etc., **5.6** each.

DIAL LAMP HOLDERS. M.E.S. type. Solder tag or clip-in fixing, **4.9** per doz. Large quantity available at special price.

OCTAL VALVE SCREENED GRID TOP CAPS. 3.6 doz., plus 6d. post. Large quantity available at special price.

9SA VALVE HOLDERS (Paxolin) at **3.6** doz., plus 6d. post.
MAINS VOLTAGE SELECTING PANELS with shorting plug, **4.6** doz., plus 6d. post.

68 COMMERCIAL ST., NEWPORT, MON. Tele. 4711
also at **25 Wyndham Arcade, Cardiff**
All mail orders and enquiries to Newport branch please

1 KW TELEGRAPH TRANSMITTERS. Two HF 300's output. Operation 3.5 mc to 16 mc.

RCA TRANSMITTERS. Type ET-4336. Complete with speech amplifier, crystal multiplier and VFO units. Brand new.

NAVY MODEL COLLINS TRANSCEIVERS. TCS9, Complete sets.

No. 12 TRANSMITTERS. With coupling units, remote control, etc.

AR-77's, NC45, HRO and others.

AUTOMATIC HIGH SPEED TELEGRAPH EQUIPMENT. "BOEHME" (U.S.A.). Up to 400 signs per minute on line and wireless.

NAVY MODEL TBY-8 TRANSMITTING-RECEIVING EQUIPMENT. Output 0.75 watts on M.C.W. telegraphy and 0.5 watts on telephony. Frequency range **28-80** mc.

All above items in excellent working condition.

Working demonstration upon request.

TX VALVES 803, 805, 807, 814, 861, 866A, DET-16 and many others.

Large stock of Tx condensers, crystals and other components. Alignment and repair of communication receivers and all other short-wave equipment undertaken.

P.C.A. RADIO

Transmitter Division :—
The Arches, Cambridge Grove, London, W.6. *Tel. RIV 3279*

Receiver Division :—
170 Goldhawk Road, London, W.12. *Tel. SHE 4946*

THE WORLD'S GREATEST BOOKSHOP

FOYLES
FOR BOOKS

Stock of over 3 million volumes

New, secondhand & rare Books on every subject. Large Technical Books dept.

Subscriptions taken for magazines.

119-125 CHARING CROSS ROAD LONDON W.C.2

Gerrard 5660 (16 lines) ★ *Open 9-6 (inc. Saturdays)*

LYONS RADIO Ltd.

L.T. MAINS TRANSFORMERS. Primary : 200-250 v. 50 cps. Secondaries : 2, 4, 5, 6, 8, 9, 10, 12, 13, 18, 20, 24 and 30 v. at 2 amps. total loading. Brand new and guaranteed. **PRICE 21/-**, postage 1/6.

TRANSMITTERS TYPE T1403A. These transmitters were designed for R.A.F. ground use and should require but little modification for "Ham" use. Built into attractive metal cabinets approx. 20 × 14 × 14in. with hinged lid. Frequency range 2to7 Mc/s. Comprises crystal oscillator (For M.O. operation, if required, a plug-in unit can be supplied, for **19/6**) buffer and 807 output stage with 6V6 or EL33 modulator. Output power 40 watts C.W. or 10 watts R.T. Aerial tuning arrangements for working into unbalanced aerials up to a quarter wave. Facilities for local/remote control and send/receive. No power supply but requires 500 v. at 200 m.A. H.T. and 6.3 v. at 3 A. L.T. Meters fitted for aerial and anode current. Supplied with instructions and circuit diagram and all valves in new unused condition. **PRICE £12.** carriage £1. (10/- returnable on crate).

0-3500 VOLTMETERS. Moving coil, 3½in. dia. projecting pattern with built-in resistance. Basic movement 5m.A. **PRICE 25/-**, postage 1/6.

HIGH VOLTAGE CONDENSERS. 1.5 mfd. 4000 v. wkg. 9 × 8 × 1¼in. ; 10 mfd. 1000 v. wkg. 8½ × 4 × 2in. ; 0.4-0.4 mfd. 2500v. wkg. 8½ × 4½ × 3½in. **PRICE 10/9** each. 1 mfd. 2000 v. wkg. at 140 F. 5d. × 2½ × 1¼in. **PRICE 7/6.** 0.25 mfd. 1500 v. wkg. or with 2 in series near enough 0.1 mfd. 3000 v. wkg. 3 × 2 × 1¼in. **PRICE** 2 for 3/9 or 6 for 10/-.

3 GOLDHAWK ROAD (Dept. M.W.), SHEPHERDS BUSH, LONDON, W.12. *Telephone:* **Shepherds Bush 1729.**

WALTON'S of WOLVERHAMPTON

Television & Radio Constructors, why not shop from home?

Send your list of requirements, our quotation will follow by return ; you will be amazed at the value we offer. Our spring clearance list is now ready. Send 3d. in stamps and s.a.e. to-day. Here are a few examples:- Batteries, many types available; Meters; Transformers :- Mains input 24 volt, 2 amp out, **12.6** post 1/-; Motors; Electric Fire Elements; Aerial Rods; Accumulators; Dipole Aerials for all stations **17.6** each plus 2.6 passenger train, etc., etc.

WALTON'S WIRELESS STORES
48, STAFFORD STREET, WOLVERHAMPTON

A MINIATURE MAGNETIC LIGHTWEIGHT EARPHONE

The new Amplivox E.4 Earphone has been primarily developed for use with office dictating machines, industrial equipments and hearing aids where a highly sensitive, lightweight, miniature receiver is needed.

Available in D.C. resistances 2-2000 ohms ; frequency 100-4000 c.p.s. ; diameter .835" depth .420" ; weight ½ oz.

AMPLIVOX LTD.
2 Bentinck Street, London, W.1

UNIVERSITY RADIO LTD.

Offer Guaranteed Used Equipment at Attractive Prices

Very Latest Model Avo Valve Characteristic Meter, series 2, 1952 model, as new. Complete with charts and all leads £48 10 0
Taylor 85A A.C. D.C. Test Meter, 20,000 o.p.v. As new ... £14 10 0
Munts Resistance Capacity Bridge, model CRB, perfect and as new £10 0 0
Taylor Circuit Analyser, Model 20A, perfect and as new £11 10 0
Avo Model 40, as new £12 10 0
Avo Model 7, as new £14 0 0
Taylor A.C./D.C. Test Meter, model 90A, as new £9 10 0
Taylor-Windsor Wobbulator, model 55A, as new £12 10 0
Latest Model Avo Wind-range Signal Generator, as new £23 0 0
Avo Valve-Testers, 1948-49, as new £12 0 0
Taylor 65B Signal Generator, as new £12 0 0
Radio-Vision Hambander, as new £12 10 0

Avo (1948) Signal Generator, as new £11 0 0
Universal Avo Minor, as new ... £7 10 0
Eddystone 640 Receiver, complete with valves. Perfect and as new £22 10 0
MCR-1, complete with coils, power-pack, 'phones, etc. As new £8 0 0
Taylor 120A A.C. D.C. Test Meter, as new £7 0 0
Triplett (U.S.A.) Valve-Tester, in portable metal case, 115-250 volts, complete with instruction book. As new £9 10 0
Hartley Turner Latest Model P.M. Speaker, as new £11 10 0
Weston (U.S.A.) Test Meter, model E772, A.C./D.C., 20,000 o.p.v. in portable case, complete with leads, etc. In perfect condition and working order £15 0 0
Taylor 45A Valve-Tester, with charts. Complete and perfect ... £13 10 0

We have a variety of Re-entrant, P.M. and large Horn-type Speakers.
Pam 25-watt Amplifier, with M.c. mike and gram inputs. Complete with all valves and as new £18 10 0
Ekco 1951 Model 10-wave-band, press-button Table Radio. As new and unscratched £22 0 0
Ardente Mobile 15-watt 12-volt Amplifier, complete with re-entrant Speaker and microphone. In perfect condition and working order £15 10 0
AR88, model LF, chassis and speaker in wooden case, complete and perfect with all valves £28 10 0
Triplett (U.S.A.) Signal Generator, 10 bands. Direct dial calibration, 100 kc/s. to 120 megs. Crystal check. Built-in output meter 115 to 250 volts A.C. As new £25 0 0
Eddystone 504, complete and as new £32 10 0

We need good used equipment urgently, and are prepared to pay spot cash on sight. TO SELLERS SENDING PER POST OR RAIL PLEASE NOTE: state whether cash per registered post, Telegraph money order, or cheque preferred.

Wharfedale Twin Speakers, in Wharfedale Corner Cabinet. Owing to storage cabinet requires re-polishing. Otherwise perfect. Original price £52. Our price £30 0 0
ARM, Model D, complete and perfect with all valves £50 0 0
Cossor Double-Beam Oscilloscopes, models 339 and 339A, as new £37 10 0
Ex-W.D. Oscillator Unit, reference No. 10V-16001, audio oscillator, 20 cycles to 40,000 cycles. Built-in A.C. power-pack. Complete and perfect £14 0 0
Mullard Resistance Capacity Bridge, as new £7 0 0
Triplett (U.S.A.) Signal Generators, 100 kc/s. to 32 megs., direct dial calibration, A.C. 110 to 250 volts, complete and as new, with booklet £12 10 0

Hartley Turner 1950-1951 quality Tuner Unit, with valves and as new £9 0 0
Taylor 47A, combined Valve-Tester and A.C./D.C. Test-meter. Complete with all charts, etc. Perfect ... £16 10 0
Connoisseur 78 r.p.m. Motor and Turntable. As new £14 10 0
Hallicrafter's S 27 Receiver, complete and perfect. With booklet £37 10 0
Ardente 20 watt Amplifiers, with M.C. microphone and gram inputs. Complete with all valves. May require slight attention, but all major components in these are guaranteed. Each £8 0 0
Leland Audio Oscillator, 20 cycles to 20,000 cycles. A.C. 200 to 250 volts. Complete and perfect £21 10 0

Sound Sales DX+1 Tuner Unit complete with all valves and perfect £12 10 0
Sound Sales 6 watt Quality Amplifier, complete with Sound Sales Tone-control Unit. As new £13 10 0
As above, 12 watts £14 10 0
1947 M.S.S. Tracking Gear, less cutting head. Perfect £10 10 0
As above, with cutting head. (M.S.S.) £17 10 0
M.S.S. 1947 Disc Recording Deck, complete with Cutting head, motor, turn-table, etc. Perfect. Less amplifier £26 10 0
M.S.S. Disc-Cutting Needles (steel), limited quantities only. Per packet of 12. Post free 5 0
Evershed's 500 volt Megger in leather case, 0-100 megohms. As new £19 10 0

WE NEED AR 88's - BC 221's - 348's - 342's ALSO COSSOR DB'SCOPES 339A OR 3339 ETC.

Voigt "Domestic" Corner Horn, unpolished. Unused. Less Speaker Unit £32 10 0
Voigt H.C. Corner Horn, less Speaker unit. Sprayed stone-colour. As new £19 10 0
Ward 12 volt D.C. to 230 A.C. Rotary Converter, with built-in radio filter unit, 100 watts, 50 cys. 1 phase. As new £11 10 0
We have various Extractor Fans in stock. A.C. 6-14in. blades. New, first-class makes at bargain prices.
Collaro RC49 Mixer-Changer. As new £12 10 0
Collaro RC500 Record Changer. As new £9 0 0
Pye Workshop Test Rack, Ref. No. 940020, complete and as new £35 0 0

Hallicrafter's Sky-Rider (pre-war), 5-10 meter Receiver, complete and perfect with built-in power pack and speaker £12 10 0
S.T.C. Ball and Biscuit Moving Coil Microphone, model 402/C. As new £10 10 0
Magnavox 66 Duode, as new, with output transformer £5 10 0
B.T.H. RK Senior mains energised Speaker. As new £3 10 0
Everett Edgcumbe Flux-Meter in portable case. As new £8 10 0
Taylor Oscilloscope Model 30. Complete and perfect £17 10 0
Descaphone Office Intercommunication Master Unit, with 4 extension speakers A.C./D.C. Brand new and perfect £14 10 0

Collaro De Luxe Microgram in portable lizard-skin case. With built-in amplifier and speaker. Non-auto-change. As new £14 10 0
Air-King (U.S.A.), portable wire-recorder, complete with mike and spare reels of wire. A.C. 110 to 250 volts. As new £28 10 0
R-107, complete and perfect £14 10 0
Qualtape Tape Deck with spare spools. As new £10 10 0
Evershed's Wee Megger, 500 volts, in leather case. As new... £10 10 0
We have various other types of Evershed's Meggers, Ohmmeters, Bridges, etc., in stock.
To cash and carry customers (trade or private) we shall allow special discount so that we can avoid cost of time, packing and delivery. This applies to all goods in our stocks.

★ We have a large selection of British and U.S.A. Valve Testers, Test-Meters and Signal Generators, etc. Your enquiries are welcome. S.A.E. please.

THESE ITEMS ARE ONLY A SMALL SELECTION FROM OUR STOCK OF EQUIPMENT. YOUR ENQUIRIES FOR ANYTHING THAT YOU MAY NEED WILL BE WELCOME. WE HAVE OTHER EQUIPMENT ARRIVING DAILY!

CASH OR CHEQUE WITH ORDERS. ALL ITEMS LISTED RE CARRIAGE EXTRA.

22 LISLE STREET, LEICESTER SQUARE, LONDON, W.C.2

OUR BRANCH AT 39a (opposite) IS OPEN ALL DAY THURSDAY.
Phone: GERrard 4447, 8582 and 5507. Hours 9 to 6. Thursdays 9 to 1.

TYPE 22. 12-VOLT TRANSMITTER RECEIVERS (similar to Type 19). 2 to 8 Mc/s. 12/14 watts output. New condition. Complete. **£22.** Carriage paid.

TYPE 18. 2-VOLT TRANSMITTER RECEIVERS. 6-9 Mc/s. New condition. **£16/10/0.** Carriage paid.

6-VOLT VIBRATOR UNITS. Complete in black steel case 7¼in. x 5¼in. x 3¼in. Output 200 volts, 40 mA. Price **22/6.**

ARMY PRACTICE MORSE KEY AND BUZZER SETS New and boxed. **6/6.**

RF24 UNITS. Converted to 28 Mc/s Band. Variable tuned with 100-1 geared S.M. Dial. Complete with plug and leads for immediate use. **£3.**

MAINS TRANSFORMER. Input 200/240 v. Output 350-0-350 or 250-0-250 volt, 80 mA, 4 and 6.3 v. 4 a. and 4 and 5 v. 2 a. Price **21/3.** Input 200/240 v. Output tapped 3, 4, 5, 6, 8, 9, 10, 12, 15, 18, 20, 24, 30 volts, 2 amps. **21/3.** All with one year's guarantee.

NEW MINIATURE VALVES. DL72, CK512AX, 9/-; 6AG5, **10/6**; 9001, 9002, **7/6**; 9003, **6/6.**

D.P.D.T. RELAYS. Operate at 200/300 volts D.C. 6 mA. **13/-** D.P. make and break, **8/6.** We can supply any type of voltage and contacts at varying prices.

NEW SELENIUM RECTIFIERS. F.W. 12/6 volt 3 amp., **14/6**; 4/5 amp., **28/-**; ½ amp., **5/6**; 250 v/120 mA., H.W., **9/6.**

MICROAMMETERS. 2" 0-500, **14/6.**

10HY. 120MA. BRASS SHROUDED CHOKES, 7/6.

TYPE IN34—GERMANIUM CRYSTAL DIODES, 5/6.

POLAR—TWO GANG VARIABLE CONDENSERS. ·00015 Mfd. Large quantity available. New. Offers please.

All the above Post Paid from: **Dept. W.W.,**

The RADIO & ELECTRICAL MART

253B PORTOBELLO ROAD, LONDON, W.11

Phone: PARK 6026

UNIVERSAL ELECTRONICS

London's Largest Selection of High Quality Communications and Test Equipment.

R.C.A. Perfect condition. AR77 **£37/10.** AR88 from **£50 0**
HALLICRAFTERS. Perfect Condition, SX24 ... **£30 0**
SX28 ... **£45 0**
EDDYSTONE. 640, as new ... **£23 0**
CR100 Receiver, as new ... **£28 0**
CR150 Receiver, as new ... **£45 0**
HRO's. Senior and Junior. Complete with coils, from ... **£30 0**
AVO Model 7, as new ... **£15 10**
Universal Avominors. Perfect ... **£6 15**
AVO Battery Signal Generator. Perfect ... **£11 10**
MARCONI Signal Generator Type 30 ... **£45 0**
Marconi Valve Voltmeter ... **£22 0**
Marconi Instruments Valve Voltmeter, TF887, AC/DC, as new ... **£40 0**
COSSOR Double Beam Oscilloscopes, from ... **£40 0**
LEEVERS RICH Disc Recorder with Amplifier, Speaker ... **£35 0**
ACE Tape Recorder. Good condition ... **£38 0**
PYE "Dolphin" Marine Transmitter/Receiver... **£100 0**
PAM 25 watt Amplifier, Speaker and Player complete ... **£35 0**

We have many items of VHF Equipment which we have no space to list—Receivers—Cavity Wavemeters—Klystrons—Magnetrons, etc.

All Inquiries Invited. S.A.E please.

Shop hours: 9.30 a.m. to 6 p.m. Thursdays to 1 p.m.

Phone: GERrard 8410 (Day)
MEAdway 3145 (Night)

OUR ONLY ADDRESS

27 LISLE STREET,
LEICESTER SQUARE, LONDON, W.C.2

COILS • COILS • COILS

T.R.F. • SUPERHET • FILTERS • PACKS
TELEVISION COILS • I.F. TRANSFORMERS

FOR DEPENDABLE COMPONENTS CONTACT

OLYMPIC RADIO COMPONENTS

COIL WINDING SPECIALISTS & MANUFACTURERS

224, HORNSEY RD., N.7. **NORTH 2914**

ALL SECTIONS OF THE ELECTRONIC INDUSTRY IN THE U.K. AND OVERSEAS ARE INVITED

To send for our 1952 Wholesale Price List, giving full details of A.W.F. Loudspeaker replacement Cone assemblies, for quick, cheap, repairs in your own Workshops. A.W.F. Chokes and Transformers for all Electronic replacements. A.W.F. Repairs to Speakers, Transformers, Vac. motors, Gram motors, etc., Current stocks of Tungsram and other valves, T.C.C. and Dubilier capacitors, Erie Resistors and Pots. Brass B.A. Screws and nuts. Tallon Cabinets and all the specified components for View Master and Electronic Engineering Televisors, and hundreds of bargain lines. Viewmaster envelopes, etc., for Kirk O' Shotts now available. We specialise in giving overseas dealers rapid service, and have full experience of all export packings.

SEND YOUR TRADE CARD (Trade Only Supplied), with 3d. Inland U.K. or 2/- Overseas Air Mail (stamps or P.O.).

A.W.F. RADIO PRODUCTS
TATLER CHAMBERS THORNTON ROAD
BRADFORD YORKS
TEL. 24008 GRAMS & CABLES "TESTUBE"

TELEVISION
INTERFERENCE Suppressor! 23

For the alleviation and cure of the interference with Televisors from motor cars, lorries, vans, etc.

Fit in a second!

A.F. BULGIN & CO. LTD
BYE PASS ROAD, BARKING, ESSEX

TELEVISION

for "Fringe" and "Long distance" viewers is vastly improved with the SPENCER-WEST type AC/3 Pre-Amplifier. The specification includes a first stage neutralised triode c.thode coupled to a grounded grid triode. The optimum arrangement for best "noise factor." Self-contained power supply unit complete with correctly adjusted interference filter. Price complete, **10 gns.**, from your Dealer or direct. Leaflets, etc., on request.

Conversion units type AC/4 for Holme Moss/London, or Sutton Coldfield or Sutton Coldfield/London, etc. Double oscillator mixer stage and R.F. stage for correct reception with absence of mixer noise and radiation to other receivers. Price complete with 5 valves and self-contained power supply unit, **15 gns.** Leaflets on request.

SPENCER - WEST
QUAY WORKS, GT. YARMOUTH
Phone: Gt. Yarmouth 3009

WE BELIEVE OUR OFFERS OF GOVERNMENT SURPLUS EQUIPMENT TO BE THE MOST COMPETITIVE IN THE TRADE. WE GUARANTEE A PROMPT CASH REFUND ON ANY UNSUITABLE ITEM RETURNED WITHIN 7 DAYS OF RECEIPT.

H.R.O. RECEIVER (one only). Complete with HRO power pack for 230 v. A.C. and Loudspeaker to match. 4 coils. 100-200 kcs., 1.7-4 mcs., 3.5-7.3 mcs. and 7-14.4 mcs. Excellent condition, **£19**, plus 10/- part carr.

EDDYSTONE 358J. 7 valves, 9 coils. Continuous coverage, 90 kcs. to 31 mcs. Separate power pack and Loudspeaker to match, **£20**, plus £1 part carriage and packing. Excellent condition.

EDDYSTONE 750. As new (Not surplus). First **£40**, save £29 10, carr. paid.

EX-N.A.A.F.I. 4-VALVE MEDIUM WAVE BATTERY RECEIVERS. 8in. PM speaker. No valves, **25/-** each to clear, carriage 5/-. Condition good.



G.E.C. VHF RECEIVERS. 10 valves. Available in three frequency ranges. "A" 128-131 mcs. "B" 95.5-100 mcs., "C" 78.5-82 mcs. Crystal controlled. (No crystals). State frequency required. As illustrated, 10in. x 8in. x 7in. Weight 22 lbs. A gift at **49/6**, plus 5/- carriage. Excellent condition.

1143A AIRCRAFT TRANSMITTER RECEIVER. Power pack control box, etc. Perfect order. A snip at **£25**, carriage paid.

WAVEMETER W1117. 7 ranges. 125 kcs. to 20 mcs. Power requirements 2 v. L.T., 120 v. H.T., 4½ v. G.B. Microammeter 0-500. Excellent condition **£6**, plus carriage 5/-.

20 WATT TRANSMITTER. For 10, 20 or 40 m. Specially built for us by a leading amateur. Professional finish. Highest quality parts. 6V6 triTet osc. 6L6 doubler PA, 6J5 modulator. 6V6's in class AB1 black crackle cabinet 19in. x 11in. x 9in. MA meter. Really powerful TX at less than retail cost of parts, **£20**, carriage paid.

SPERRY DIRECTIONAL GYROS. Part No. 640370. 160 brand new units available. Enquiries from bulk buyers invited.

TELEVISION PRE-AMPLIFIER. As illustrated. Over 2,500 now sold. Suitable for any B.B.C. TV transmission. Instructions supplied. Power requirements, 6.3 v. L.T. 200/275 H.T. Fitted with EF50. Remaining small quantity **10/-** each, post paid.

EKCO TELEVISION PRE-AMPLIFIERS. 5 channel. Slightly used but look as brand new. Guaranteed perfect. Fitted with Mazda 6F12, list price 42/-, 5 only **25/-** each, post paid.

12 VOLT CAR RADIO. Comprises a type 455 receiver expertly modified by us and fitted with volume control and on/off switch. Tunes medium waveband. Power obtained from the dynamotor which is very quiet in operation. Supplied complete with WB 5in. PM loudspeaker fitted with output transformer. Size 11in. long, 4¾in. wide, 5¼in. deep. Brand new throughout. Excellent performance, **9 gns.**, carriage paid.

CRYSTAL MULTIPLIERS for ET4336 transmitter. New condition. Less valves and ma meter **25/-**, carriage paid.

HAVE YOU AN ET4336 TRANSMITTER TO SELL ? We want to buy a few.

AMPLIFIERS, TYPE 1A271. Brand new. Size 5in. square. Fitted EF36 relay, potmeter, 2 trans. etc., **10/-**, post paid.

RADAR VALVES. Type 8012, brand new, **10/-** each.

VCR97 CATHODE RAY TUBES. Complete with base, **39/6**, part carriage 2/6.

FOCUS COILS for Triode or Tetrode or Tubes, **16/9**, post 1/-.

G.E.C. 6 VOLT 1 AMP. RECTIFIERS, 6/6, post 9d.

.00016 WAVEMASTER SHORT WAVE TUNING CONDENSERS, 5/6, post 6d.

HEADPHONES. DLR No. 1, **7/6**, post paid.

PAMPHONIC P.A. SPEAKERS. 10in. high flux unit (not surplus). Handsome maroon cellulose metal cabinet 20 x 9 x 13in., impedance 3 ohms. Price **55/-**, carriage 4/-.

VIEWMASTER PARTS

Send us your Order. Good Stocks available.

Enquiries must be accompanied by 2½d. stamp.

H.P. RADIO SERVICES LTD.

BRITAIN'S LEADING RADIO MAIL ORDER HOUSE

55 COUNTY RD., LIVERPOOL 4. Est. 1935. Tel. Aintree 1445

For Quality Bargains Always

-Best Buy at Britain's

SPECIAL OFFER. Ex-Admiralty Amplifier chassis, complete in metal case with lid. Size 17in. x 8in. x 12in. FOR A.C. MAINS OPERATION 200-250 volts 50 cycles. Contains a complete power pack—husky choke, 1000 volt working paper block smoothing condensers and mains transformer. This has a tapped input—210, 230, 250 volts, and the outputs are 350-0-350 v. 150 mA., 6.3 v. and 5 v. The circuit diagram of the unit is included and the original valve line-up was 6J7, 6K7, 6V6 and 5Z4. It should be an extremely simple job to convert this into a standard A.F. amplifier. Certain relays have been removed and the unit is supplied less valves. Condition is as new. This is a real snip at only **39/6** plus 5/6 carriage. Get your order in early as only a limited number are available. We can thoroughly recommend this item as being one of the BEST BUYS we have offered for some time.

RESPONSER UNIT TYPE R3118. 15 valve 1½ metre superhet for A.C. mains 200-250 volts 50 cycles. This unit would be extremely suitable for alteration to T.V. or the Wrotham transmission on 90 megs. Contains 2-EF54, 1-EC52, 6-SP61, 1-P61, 1-5Z4G, 3-VR92 and 1-Y63. Supplied complete with valves for **97/6** plus 7/6 carriage.

6in. MAGNIFYING LENS FOR VCR97, SCP1, ETC. First grade, oil filled Perspex, special price **22/6** plus 1/6 post. Almost doubles your picture area.

SPECIAL PURPOSE VALVES. VT501 (TT11) **3/-** ; 954 **2/6** ; 955 **4/-** ; VR136 (EF54) **6/6** ; E1148 **2/6** ; VR65A (SP41) **3/-** ; VR65 (SP61) **3/6** ; 2C34 (RK34) **3/-** ; 8308 **8/6** ; Hundreds of other types in stock. Postage 6d. extra on 1-4 valves.

EF50 (VR91) RED SYLVANIA American types at **8/6** each. Brand New, British makes also available at **5/-** each, tested.

SPEAKERS. Brand new and boxed. Moving coil P.M. Truvox 6½in. at **13/6** ; Goodmans 10in. 15 ohm voice coil **35/-**.

CO-AX CABLE. Brand New 75-80 ohm at **1/-** per yard—minimum 10 yards. This is standard ½in. dia.—not ex-Govt.

PAXOLIN VALVEHOLDERS. International octal at **4/3** per dozen.

CERAMIC TWO BANK SWITCH. Each bank four pole two way. List price £1/1/-.—Our price **4/6**.

METAL RECTIFIERS. 12 v. 2 A. full wave bridge **12/6** plus 6d. post. Miniature H.T. rectifiers, type RM2—125 v. 100 mA. at **4/3** each or two for **8/-**. Selenium rectifiers 150 v. 40 mA. at three for **10/-** post paid. 230 v. 60 mA. at two for **10/-** post paid. 12 v 5 A. full wave bridge rectifiers at **17/6** plus 6d. post.

HEAVY DUTY RECTIFIERS. Funnel cooled, full wave, 30 volt 20 amp. Selenium. Each rectifier consists of 20 discs size 112 mm. Brand new and boxed at **£4/10/-** plus 3/6 carriage.

STANDARD TRANSFORMERS of current manufacture. Two types both standard primaries. Universal mounting. (1) 350-0-350 v. 80 mA., 0-4-5 v. 2 A., 0-4-6.3 v. 4 A. (2) 250-0-250 v. 80 mA., 0-4-5 v. 2 A., 0-4-6.3 v. 4 A. Both these transformers are brand new and boxed, fully guaranteed and priced at only **18/6** plus 1/- post.

30 VOLT TRANSFORMER, standard primary, secondary 30 volts 2 A., tapped at 3 v., 5 v., 6 v., 8 v., 9 v., 10 v., 12 v., 15 v., 18 v., 20 v., 24 v. Has countless uses, i.e., for chargers, train sets, filament transformer, etc. Price **17/6** plus 1/- post. Brand new, boxed and guaranteed.

MULTI-PURPOSE TRANSFORMER. Upright mounting, primary 230 volts 50 cycles Secondaries 500-0-500 volts 400 mA., 300 volts 100 mA., 4 volts 7A., 10 volts centre tapped 1A, 12 volts 1A centre tapped, 6.3 volts 3 Amp. centre tapped. Size 6½in x 6½in x 7½in. Brand New **59/6** plus 5/- carr.

AMERICAN CONDENSERS. .01 mF., 1000 volts, .02 mF. 750 volts, at **7/6** per doz. .005 mF. 1000 volts., .002 mF. 1000 volts at **6/-** per doz. All metal cased tubulars wire ended. Micamold ditto .1 mF. 350 volt at **7/6** per doz. Small Mica Condensers—.001 mF. CM2ON at **6/-** per doz.

COMMAND RECEIVERS. We have two types of these well known sets, one covers the Top Band, 1.5 to 3 Mc/s. (100-200 metres) and the other 6-9 Mc/s. (33-50 metres). Both these receivers are in brand new condition and contained in black crackle cases. Complete with six valves and circuit diagram, less dynomotor at **£4/10/-** carriage paid. Valve types employed : RF—12SK7, F.C.—12K8, 1st I.F.—12SK7, 2nd I.F.—12SK7, Det. and B.F.O.—12SR7, Output-12A6.

AMERICAN CAR OR STORAGE BATTERY. 6 volt 90 A.H., Brand new and individually boxed. Hard rubber cases size 8¼in. long, 6½in. wide and 7½in. high. Price **79/6** plus 5/- carriage.

We have a large range of units and components, some of which are in insufficiently large quantities to advertise. We suggest you pay us a visit to secure some real bargains. Many items are of interest to Schools, Laboratories, Manufacturers and others connected with the Electronic industry.

CHARLES BRITAIN (Radio) Ltd.

11 UPPER SAINT MARTIN'S LANE
LONDON, W.C.2 TEM 0545

3 minutes from Leicester Square Station (up Cranbourn Street)
Shop Hours 9—6 p.m. (9—1 p.m. Thursday) Open all day Saturday.

OUTSTANDING OFFERS FOR EXPORT ONLY

U.S.A. Radio & Radar Equipment
RCA TRANSMITTERS, Type ET-4336-B, H.K.L.
Westinghouse AIRCRAFT TRANSMITTERS, Model GO-7.
TRANSMITTERS RECEIVERS SCR-536.
TEST EQUIPMENT IE-46 (Signal Generators I-196-B, Frequency Meters BC-906-D, Radio Receivers BC-1066-B).
Model ASE-1 RADAR AIRCRAFT EQUIPMENT (200 Units).
AN/APS-3 Coastal Defence RADAR.
Hallicrafters SCR-299, 399 and 499 (BC-610).
Western Electric SCR-517-B.
RADAR Mk. 26 (Models 3 & 4).
INTERROGATORS-RESPONSORS BM-1 (and BN-1).
REPEATER-INDICATORS AN/APA-1.
RADAR INDICATING EQUIPMENT, Model VF.
AIRCRAFT RADAR EQUIPMENT APS-3, 4 and 6.
GISHOLT-BALANCING METERING UNITS.
AN/APN RADIO ALTIMETER EQUIPMENT.

Spares (Radio and Radar—U.S.A.)
Full range of spares for most U.S.A. Naval, Aircraft and Ground Radar and Radio Units. Crystals (for SCR-610 and AN/TRC).

British T.R. (X. 42, W/S No. 58, W/S No. 11, W/S No. 17).

Power Units, Wavemeters, Motor Generators, Dynamotors and large quantities of various components.

Aircraft Instruments and Accessories
Large selection of Bendix Instruments. Aircraft Generators and Motor Assemblies. Oxygen installations.

Individual Test Certificates and A.I.D. Certificates can be supplied upon request.

Enquiries to
BRITISH SAROZAL LTD.
(Export Branch)
1 BRISTOL HOUSE, SOUTHAMPTON ROW, LONDON, W.C.1
Telephone: HOLborn 6763-4-5 Cables: Sarozal, London
OVERSEAS BUYERS ARE CORDIALLY INVITED TO VISIT OUR WAREHOUSES, SHOWROOMS AND LABORATORY

THE DE HAVILLAND ENTERPRISE HAS VACANCIES AT HATFIELD, HERTS.

For Draughtsmen of all grades for work of high National Importance.

Posts are permanent and progressive for able and energetic men in mechanical, hydraulic, electrical and electronic fields.

Senior designers and juniors anxious for interesting and entirely new work are needed at once.

Write in confidence, giving particulars of education and experience stating whether British born. Interview expenses refunded.

Apply to the local Employment Exchange or scheduled agency.

DEALERS & SERVICE ENGINEERS

HOME AND OVERSEAS TRADE

Large stock of servicing accessories for Radio and Television Receivers.
COILS — POTENTIOMETERS — RESISTORS — LOUDSPEAKERS
CONDENSERS — MAINS TRANSFORMERS — CHOKES
Many other useful, low-priced items.
Send for our monthly bulletin, which always announces special bargain lines.

Trade only supplied.

V.E.S. WHOLESALE SERVICES LTD.,
11, GUNNERSBURY LANE, W. ACTON, W.3.
Telephone: ACOrn 5027.



RELAYS AND KEY SWITCHES

LARGEST EX-GOVT. STOCK IN GT. BRITAIN

Types 600-3000 Relays—Siemens High Speed
Also A.C. 400 volts 50 cycles

Uniselector Switches, Telephone Switch-boards, Telephone Components Plugs, Jacks, Handsets — **Government Contractors.**

JACK DAVIS (RELAYS) LTD. (DEPT. W.)
36 PERCY STREET, LONDON, W.1
Phones: MUSeum 7960 LANgham 4821

POLYTHENE
H. F. EQUIPMENT
(AMBYTHENE BRAND)
COIL FORMERS
CHOKES
STAND-OFFS
FEED-THROUGHS

Send for Particulars and Samples

AMPLEX APPLIANCES (KENT) LTD.
19 DARTMOUTH ROAD, HAYES, BROMLEY, KENT
(RAVensbourne 5531)

L. WILKINSON
Wholesale and Export
19, LANSDOWNE ROAD, CROYDON
Phone: CRO 0839 Telegrams: "WILCO" CROYDON

RELAYS P.O. TYPE 3000
RELAYS SIEMENS HIGH SPEED
RELAYS TELEGRAPH 4131C
UNISELECTOR SWITCHES
KEY SWITCHES
HANDSETS P.O. TYPE
PHONE PLUGS AND JACKS
SELENIUM RECTIFIERS
BATTERY CHARGERS
BRIEZE PLUGS AND SOCKETS
YAXLEY SWITCHES
FUSE BOXES I.C.
SIPHAN PLUGS AND SOCKETS
ELECTRICAL COMPONENTS

SLYDLOK FUSES
RESISTORS, WIREWOUND, ETC.
POTENTIOMETERS, WIREWOUND, etc.
CONDENSERS
VALVEHOLDERS B9A, ETC.
TEST EQUIPMENT
SLOW MOTION DRIVES
SANTON AND ARROW SWITCHES
KLAXON MOTORS
GLASS INSULATORS
15 AMP D.E. KICK SWITCHES
GLOSSY CABLE
METERS
M.E.S. BULBS

Large Stocks held at Competitive Prices

Wireless World Classified Advertisements

Rate 7 - for 2 lines or less and 3/6 for every additional line or part thereof, average lines 6 words. Box Numbers 2 words plus 1/-. Address replies: Box 0000 c/o "Wireless World" Dorset House, Stamford St., London, S.E.1. Trade discount details available on application. Press Day: May 1952 issue, Tuesday, April 1st. No responsibility accepted for errors.

WARNING

Readers are warned that Government surplus components which may be offered for sale through our columns carry no manufacturers' guarantee. Many of these components will have been designed for special purposes making them unsuitable for civilian use, or may have deteriorated as a result of the conditions under which they have been stored. We cannot undertake to deal with any complaints regarding any such components purchased.

NEW RECEIVERS AND AMPLIFIERS

UNIVERSAL ELECTRONIC PRODUCTS, 56 Marylebone High St., London, W.1. Welbeck 4058.

SPECIALISTS in the design and manufacture of high fidelity reproducing equipment from 5-100 watts for domestic or industrial purposes. Our new twin channel amplifier (type U.E.57), with independent bass and treble outputs, provides the most satisfying standard of reproduction we have yet experienced. It is now being demonstrated in our showrooms daily (we close Thursday 1 p.m., Saturday 4.30 p.m.), and we invite those who seek perfection from recorded music to hear this superb instrument. We also offer tuning units or complete chassis designed and constructed to individual requirements.

12-watt high quality amplifiers, bass and treble boost; £12.15/-. lists.—Broadcast & Acoustic Equipment Co., Ltd., Tomoland, Norwich. [0065

MIDLAND RADIO COIL PRODUCTS offer a service for the production of high quality amplifiers and radio equipment to specification, list of standard products available, suppliers of audio and radio equipment to the Northamptonshire Education Authority.—Enquiries to 28 Winstanly Rd., Wellingborough. [6536

WHY buy a cabineted receiver; our model ES54 R/G chassis now available for installing into your own gram cabinet; a 5-valve **all-wave** superhet, fully wired and aerial tested, easily fitted, handsome glass d.a., 4 watts output, variable n.f.b., 2½d stamp for illustrated brochure; trade inquiries invited.—Bayly Bros., 46, Pavilion Drive, Leigh-on-Sea, Essex. [8268

TELRAD ELECTRONICS, 70, Church Rd., Upper Norwood, London, S.E.19.—Designers and manufacturers of Telrad quality amplifiers, established as the most outstanding value in high-quality amplifiers, thanks to faithful reproduction at unrivalled price; these unique amplifiers are first choice of the enthusiast, built to satisfy the discriminating ear, bass and treble independently controls, providing widest possible variation to suit all recordings and varying acoustic properties of one room with another; full details on request.—Write, call or 'phone Livingstone 4879.

RECEIVERS, AMPLIFIERS—SURPLUS AND SECONDHAND

R1155 receiver, power pack, speaker; £10.—101, The Avenue, Pinner 5101. [8282

A107 communication receiver, less case, perfect condition; £11 or offer.—Box 7282. [8193

TELEVISION Cossor circuit, 15in tube, good condition; £50.—40, Crespigny Rd., Henson 7153. [8251

ARMSTRONG EXP 119 chassis, 9 wavebands, 10 valves; offers.—10, Broadoak Walk, Fishponds, Bristol. [8280

AMPLIFIER, KT 66s, ECC32, 6Q7; tone control, tuner, power pack; Connoisseur pick-up, motor, all in walnut cabinet; Goodman speaker, located York; offers to—Box 7296. [8245

LEAK TL 12-point one amplifier with leak RC/PA/TC pre-amp, only 60 hours' use, perfect, £24 complete with plugs and leads.—White 90, Fairbank Rd., Bradford. Tel. 42812. [8298

FOR sale, high-quality television set by well-known manufacturer, 12in screen, in excellent condition and well-made cabinet.—Apply Raby, 1, Dorset Square, N.W.1. Paddington 1841. [8191

AMAZING offer.—Only 350 6-valve short-wave AC battery sets at only 15/- each, contained in metal cases with 5 VR21s, 2 VR15s, 1 VR22; first come, first served.—Send P.O.s, inc. 1/6 carr., to Kaye Electrical Distributing Co., 11, St. Anns Rd., Harrow, Middlesex. [8204

EXCEPTIONAL bargain, cancelled export order.—Rack, 20in×4ft 5in, containing two 25-watt amplifiers, mixer for 2 p.u.s, mic. and radio, two R.F. Tuner three power supplies, four separately controlled L.S. output, monitor 25 valves, bitavox P.A. Horn speaker; first offer of £80.

CAN be inspected at Expert Gramophones, Ingerthorpe, Great North Rd., London, N.2. Tel. Mountview 6975. [8211

THE TYPE CFB
Acknowledged the ultimate in Audio transformer design. Incorporates latest grain orien ated strip wound "C" core. Full audio range with absolute minimum distortion.

THE TYPE WWFB
Built to the authentic Williamson specification Eight section secondary. Stock types 0.95 ohm, 1.7 ohm, 3.6 ohm and 7.5 ohm. 20 watts output. Minimum distortion.

THE TYPE HS.MU
Hermetically sealed in oil, fully screened provide reduced field 40 db at 50 c/s. Specially produced to operate under all climatic conditions.



THE TYPE P.P.O.
A push-pull unit rated 12 w. for 0.7 per cent harmonic distortion at 50 c/s. Six standard models, matching 4,000 to 12,000 ohm anode loads, secondary to match 15 or 3.7 ohm loads. For immediate delivery.

The above represent some of the Partridge products (the result of over 20 years' specialisation) built from original formulae supplied or from the Partridge research department. Partridge Transformers are used by the Royal Aircraft Establishment, The Admiralty, War Office, British Railways, B.E.A., National Coal Board, etc.

Technical data sheets available on request.

PARTRIDGE
TRANSFORMERS LTD
BOEBUCK ROAD KINGSTON BY-PASS TOLWORTH SURREY
TELEPHONE ELMBRIDGE 6741/4

RECEIVERS, AMPLIFIERS—SURPLUS AND SECONDHAND

ARMSTRONG a.c.-d.c. 7-valve chassis, 8 watts output, 10in Goodman speaker, purchased Oct. 1951, on guarantee; £15.—Box 7290. [8214

HRO Rx's and coils in stock, also AR88, BC348R, CR100, etc.—Requirements please to R.T. & I. Service, 254, Grove Green Rd., London, E.11, Ley. 4966. [0055

LOUDSPEAKERS—SURPLUS AND SECONDHAND

SALE: acoustical 8L15 loudspeaker; quality reproduction; £10, plus carriage.—Box 7295. [8284

WHARFEDALE corner cabinet, walnut, 15ohm input, excellent condition; £34.—Box 7345. [8270

HARTLEY TURNER 10in speaker, £7; matched output transformer, £2.—Wilson, Greengates, Watchetts Drive, Camberley. [8225

VOIGT HC horn with bass chamber fitted Epoch 99K 15Ω PM speaker; £10/10.—Carpenter, 36a, Bridge St., Pinner. Tel. Pinner 652. [8255

VITAVOX Bitone loudspeaker in polished walnut cabinet, cost £50, bargain, £28; also Epoch 18in cinema speaker, diaphragm damaged, £6.—Roper, 84, Goldthorn Hill, Wolverhampton. [8265

NEW DYNAMOS, MOTORS, ETC.

HF. alternators, 1,500 cycles, 80 volts, 25 amps.; motor driven, 220v d.c., brand new.—F.W.S. Co., 69, Church Rd., Moseley, Birmingham. [6155

BATTERY chargers, 4 models, 2-6-12v, 1-2-4 amp D.C.; any mains voltage; also larger types special transformers, chokes, test gear, interior car heaters, etc.—The Banner Electric Co., Ltd., Hoddesdon, Herts. [0122

ALL types of rotating electrical machinery up to 20kva available, including rotary converters, rotary transformers, motors, petrol and diesel-engined generating plants, alternators and d.c. generators. We are also in a position to quote for power transformers; as actual manufacturers we will be glad to quote for any quantity for home or export.

DIESEL Electric generating plants, 5kva, 250v a.th push-button remote control, starting equipment ready for use, £275.

ROTARY transformers, input 20v d.c. outputs 6.5v d.c. and 500v d.c., permanent magnet field, 20/-; ditto, input 28v d.c. and 1,200v 70ma d.c. output, energised field, 35/-; ditto, input 12v d.c., output 500v, 90ma d.c., energised fields, 35/-; reasonable delivery.—CHAS. F. WARD, Lordscroft Works, Haverhill, Suffolk. Tel. 255. [0059

THE Pearce new model diesel alternator plant, on welded steel frame, 250/1/50 5kva, plus 52v 15a d.c., Petters latest AVAL air-cooled diesel engine belt-driven alternator, self-energised, automatic voltage control by winding on stator, at govern. speed 1,500 rpm, d.c. output trickle charges or charges lighting and starter battery up to 15amps. 24v lighting is used when plant is not in use; starting and stop by remote control push-buttons; complete with main switch & fuses, battery cables, 24v 72 amp/h batt, instruction book, spares, engine covered by Petters Ltd. 12 months' service, £260, free delivery 100 mls. London, where remote start and stop not required, but only push start on plant reduction of £6/10; a few from stock others quick delivery; if you collect, or we deliver, battery is charged and a 10 cu. ft. concrete bed given free.

ALTERNATORS, four pole 1,500 rpm., "press-button start," automatic voltage control without external equipment; type as fitted in above plant, 110/1/60 or 230/1/50, 5kva, wt. 240lb, £72 del.; also 110/1/60 or 230/1/50, 6kva, wt. 300lb, £95 del.; 8kva, £77; 6kva, £102; f.o.b. Liverpool or London docks; Please state direction of rotation at pulley end.

ALTERNATORS, 250/1/50, 400VA, self energised, 5,000 rpm, ball bearing, £22/10 del.; please state if for television; voltage regulators 50/- extra.

TELEVISION, guaranteed interference free, special rotary converters, fitted radio and television filters, wt 60lb, d.c. to 250v a.c., input 12V, 200VA out, 24v, 50v and 110v d.c., output 250 V.A., £25/10 del., with resistance converters, run direct from lighting plant, also converters for radiogram and general use, inputs and outputs as above.

THE above are the latest products of British manufacture, and are guaranteed for one year, fullest details of plant, alternators, or 400VA alt. and rotary converters, by return post; state which required.

PLEASE see displayed advert., page 106, for S.T.C. selenium rectifiers; terms c.w.o., pro forma invoice c.o.d. (most goods only).—T. W. PEARCE, 65, Great Percy St., W.C.1 (near Angel). [0014

DYNAMOS, MOTORS, ETC. SURPLUS AND SECONDHAND

ROTARY converters, one 200v d.c. input, 250v a.c. output; also one 110v d.c. input, 250v a.c. output, £9 each; also ½hp d.c. 200v motor, practically new, £3/10.—Roper, 84, Goldthorn Hill, Wolverhampton. [8266

HIGH-FIDELITY OR REALISM

People are saying that there is too much talk about high-fidelity and not enough about realism. So much emerges from our correspondence and we are always being asked what we think about it. Only the other day a man wrote and told us he had spent a small fortune and still couldn't get good results from L.P. records. Did we find that? We replied that *our* customers consider 78's dead.

Perhaps we are to blame in not saying more frequently that as well as speakers we make gramophone equipment which has a really staggering performance. Our prime job is making speakers, good speakers, but we have always had to cater for the man who doesn't like other people's amplifiers and what not. We don't know why. It seems to us a comparatively simple business to make a good amplifier. We do not suppose we know anything more about amplifiers than do amplifier specialists, but it may be that, as the producers of the 215 speaker, our standards of realism in reproduction are so high that we do have to take more care in reaching the final result.

Be that as it may, we are constantly being asked to supply the whole bag of tricks so that someone else can get the results we get, from L.P.'s and everything else. And the gratifying thing is that our charge for this is lower than most "high-fidelity" equipment, even if it can't be bought from every dealer in the land. Our equipment is not labelled high-fidelity because we have no interest in other fidelities, but what we have done is to take the machine-like quality out of reproduction so that you can delude yourself into believing you are present at the actual performance.

That is one of the reasons why Hartley-Turner reproduction sounds different from all the others. You may not like it at first, but if your final aim is to get into your home what you heard in a concert hall, then you must concentrate less on "high-fidelity" and more on realism. And that calls for some reorientation of your outlook on sound reproduction.

Send for our free catalogue today.

It contains no sales talk.

H. A. HARTLEY Co. Ltd.

182 HAMMERSMITH ROAD LONDON W.6

Phone: RIV. 7387

DYNAMOS, MOTORS, ETC., SURPLUS AND SECONDHAND

ROTARY converters d.c. to a.c., one Ward input 250v output 250v 8.7 amps .8 pf, one ditto but input 210v, one E.D.C.C. input 220v ouput 250v 8.7 amps .87 pf, offers invited.—Metropolitan Relay, 69, Lavender Hill, London, S.W.11. [8242

TRANSMITTING EQUIPMENT

GATES type MO-2555-X radio transmitting equipment.—Box 7285. [8196

MAGSLIP transmitters from 10/-; ideal for remote control of radio apparatus, including Antenna direction indication; stamp for details.—ENGINEERING FACILITIES, LTD., 29, Rea St., Birmingham, 5. [7507

TEST EQUIPMENT—SURPLUS AND SECONDHAND

FOR sale owing to closing down of department.—
1 Muirhead multi ratio bridge type D.297 A.
1 Sg meter range 50 KC/s 50 MC/C.
1 Cossor ganging oscillator model 345.
1 Avo meter type model 7.
1 Meter electronic E.44.
5 Advance signal generators, 2 B.C. 3, serials 669 and 755, 1 D.1, serial 115.
OFFER invited by Kaysales, Ltd., 27/30, Basinghall St., London, E.C.2. [8287

OFFER required for Plessey standard No. 2 Wavemeter, condition as new.—Box 7295. [8252

65B sig gen and 45A portable; offers; want tape equ.—Greaves, 3, Mountview Rd., N.4. [8276

MARCONI universal impedance bridge, TF375D, new condition, £50; Cossor 339 oscillograph, £38, little used.—Gerry, Bank St., Newquay. [8285

OFFERS required over £30 for Avo electronic testmeter, Avo mains signal generator and Avo universal minor, all in near new condition.—56, Downs Side, Belmont, Surrey. Vigilant 4553. [8258

SIGNAL generators, oscilloscopes, output meters, valve voltmeters, frequency meters, multi-range meters in stock; your enquiries are invited.—Requirements to R.T. & I. Service, 254, Grove Green Rd., London, E.11. Ley. 4986.

NEW GRAMOPHONE AND SOUND EQUIPMENT

FRITH RADIOCRAFT Ltd., offer from stock:—
COLLARO 3-speed auto-changers; basic 3-RC-511 unit without pickup heads, £12/9/5. Acos GP27 pickup heads in three types, standard, long-playin' or dual-purpose, £3/2/4 each; complete unit with dual-purpose head, metal table cabinet, £18/15; ditto in de luxe walnut cabinet, £26/16/2.
COLLARO 3-speed single record players; basic 5-514 unit without pickup heads, £8/4/2; GP27 heads as above.
COLLARO single-speed auto-changers RC-500, magnetic PU £11/16/9; crystal PU, £12/2/11.
COLLARO AC-514 single-speed r/p unit, mag PU, £6/-/5.
PLESSEY multi-speed auto-changers to play 8-10 records 10in and 12in mixed at 33 or 78 rpm, or 8-10 records 7in only at 33 or 45 rpm; Acos dual sapphire head, £25/1/-.
CONNOISSEUR super de luxe 2-speed motors with 12in machined turntable, instant change from 33 to 78 rpm, £22/18/8; de luxe pickups with twin heads and sapphires, £10/0/8. Connoisseur Stroboscopes for 33 and 78 rpm at 25-50 and 60 c/s, 5/11.
W. B. "Stentorian" speakers, 2½in 18/6, 3½in 19/6, 5in 21/-, 8in 32/6, 9in 56/9, 10in 44/6; dual concentric types 10in £6/15, 12in £17/17 or with transformers £7/15 and £8/18.
GOODMANS 12in speakers, Audiom 60, £8/12/6, Axiom 150, twin-cone, £10/5/6, Celestion P-44 speaker, 12in P.M., 4 watts, £4/5. Ekco moulded plastic speaker grille 16½in×12in cream or gold, entirely free from resonance, 6/6 plus 1/5 post; sample on request; Escutcheon mouldins, flexible cream plastic 5/16in U section, 1/6 per yard.
RESLO ribbon microphones type URA £7/10, moving coil type VMC £6.
ACOS crystal microphones MIC 21/1 or 22/2 for floor or desk stand, fitting, £6/6/1; table stands, 25/-; 3-section folding floor stands, £5/7/6.
RECORDING tape EMI 65A, 65B or H60, 35/-; Scotch Boy (Dures), 35/-; Philips, £2; all 1,200ft reels, spare reels 4/-.
RECORDING motors, BSR SR-1, 52/-; SR-2, 25/-; FP-10 clockwise or anti-clockwise, 38/-; Collaro ditto, 42/-.
AMPLION multi-range meters, 1,800 ohms per volt, 9 ranges, £5; Pullin series 100 multi-range meters, 10,000 ohms per volt, 21 ranges, £11/11.
FRITH Radiocraft Ltd., 69-71 Church Gate, Leicester. Tel. 58927. [8034

MAG. tape record-playback amplifiers (not kits), for "Lane" (single and 3 motor types) and "Qualtape" decks, etc.
JUNIOR model, 4 watts output (6K6), fre. range 20 to 18,000 cps, with suitable tone correction (neg. feedback, etc.), 12gns; with cathode ray level indicator, 14gns.
SENIOR model, 12 watts output (6V6s in p. pull), excellent tonal quality, 16gns; with c.r. lev. ind., 18gns.
ALL screened head leads, plugs, etc., included.
Oscillator (6V6), inputs for "mike," radio and gram on all models.
SPECIAL "Qualtape" junior amplifier, with neon level indicator, 13gns.—All enquiries:
HARDING ELECTRONICS, 120a, Mora Rd., Cricklewood, London, N.W.2. [8215

LP records by post, order with confidence. Each record individually inspected and carefully packed, orders over £2 post free, under £2 please add 1/-; LP Record catalogue, 1/6 post free.
ROGERS DEVELOPMENTS Co. (M.O. Dept.), 116, Blackheath Rd., Greenwich, S.E.10. [8104

ALEC Davis SUPPLIES Ltd

DEPT. W.W., 19 TOTTENHAM COURT ROAD, LONDON, W.1. MUSeum 4539 2452

LANE TAPE TABLE, complete with heavy duty motor, erase and playback heads, £16 10 -, plus 10 - carriage and packing.

OC 2 OSCILLATOR COIL. For use with high or low impedance heads. 19 - plus 6d. post.

SCOTCH BOY MC-1-111 MAGNETIC TAPE. 1,200ft coil, £1 15 -.

LUSTRAPHONE DYNAMIC M C MICROPHONES. Low impedance type £5. High impedance type £5 12 6, plus 1/- post.

5-VALVE 3-WAVE BAND SUPERHET CHASSIS in kit form, complete with 8in. speaker. A really first class kit. All new components. £9 19 6, plus 2/6 carriage.

3-VALVE PLUS METAL RECTIFIER. 2-wave band T.R.F. kit, complete with speaker and cabinet. Nothing else to buy. £6 15 -, plus 2/6 carriage.

A.D.S. 4/W. QUALITY AMPLIFIER incorporating a pre-amplifier stage with bass boost. Also suitable for use with a radio feeder unit. Complete set of components for above amplifier including cabinet, £7 15 -. Complete amplifier constructed and fully tested. £9 17 6.

A.D.S. 10W. PUSH-PULL AMPLIFIER. Low and high level inputs. 5, 7 or 15 ohms output. Details on request, £12 17 6, plus 2/6 carriage.

A.D.S. MEDIUM-WAVE RADIO FEEDER UNIT. EF36 R.F. Amplifier. EF36 Triode connected detector. Thus units is ideal for quality reproduction of local transmissions. Power required 200 v. 15 m/a., 6.3 v. 3 a. Complete in black crackle cabinet, £6 12 6, plus 1/6 carriage.

SPEAKERS.
2in. 3 ohms W.B Stentorian 19 6
3in. 3 ohms ELAC ..... 15 -
8in. 3 ohms Manufacturers' surplus 17 6
10in. 3 ohms Manufacturers' surplus 39 6
All plus 1/- post.

"DENCO" ALIGNMENT OSCILLATOR D.A.O.I. This unit provides a modulated signal for the alignment of the I.F. Amplifiers, etc. The two standard frequencies of 465 kc/s. and 1.6 mc/s. are selected by the turn of a switch. Price 49 6, plus 1/- post.

MANUFACTURERS' SURPLUS. 465 kc/s. I.F.T. at 7 6 a pair, plus 9d. post.

10 MC/S. I.F. TRANSFORMERS at 2/- each, plus 6d. post.

EMI SENTERCEL RECTIFIERS, 125 v. 100 m.a., 4 - each.

OSMOR "Q" COILS. Aerial H.F. or OSC 13-2,000 M in 8 ranges, 4 - a coil.

DENCO TYPE "C" T.R.F. COILS. Medium and Long Wave, 8 - a pair.

THE CHANCERY LONG PLAYING ATTACHMENT. Converts your 78 r.p.m. player to 33⅓ r.p.m., £3 12 6, plus 1/- post.

2-GANG .0005 Midget Var Condenser, 7 6, plus 9d post.

MAINS TRANSFORMERS. (All upright mounting).
Pri. 200-240 v. sec. 3 v., 4 v., 5 v., 6 v., 8 v., 9 v., 10 v. 12 v., 15 v., 18 v., 20 v., 24 v., 30 v., at 2 amps. price 21 -, plus 1/- post.
Pri. 200-240 v., sec. 250-0-250 v. 60 m/a., 6.3 v. 3 a., 5 v. 2 a., 21 -, plus 1/- post.
Pri. 200-240 v., sec. 350-0-350 v. 80 m/a., 6.3 v. 3 a., 5 v. 2 a., 27 6, plus 1/- post.
Pri. 200-240 v., sec. 350-0-350 v. 120 m/a., 6.3 v. 5 a., 5 v. 3 a., 39 9, plus 1/- post.
Pri. 200-240 v., sec. 425-0-425 v. 150 m/a., 6.3 v. 4 a., 5 v. 3 a., 52 6, plus 1/- post.
Pri. 200-230 v., sec. 6.3 v. 1.5 a., 7 6 plus 6d. post.
Pri. 200-240 v., sec. 12 v. tapped 6.3 v. 3 a., 21 9, plus 1/- post.
J.B. SL5 wave band Spin wheel dial and drive, 27 6.
J.B. SL6 3 wave band dial and drive, 26 6.
J.B. Full vision 3 wave band dial and drive, 13/-. All post 1/-.

L.F. CHOKES.
20 h., 120 m.a., 370Ω, 16 6.
15 h., 150 m.a., 200Ω, 16/-.
10 h., 150 m.a., 200Ω, 15/-.
10 h., 100 m.a., 410Ω, 9/-.
15 h., 60 m.a., 300Ω, 5 6.

MIKE TRANSFORMERS.
60-1 ratio for carbon mike, 8 9.
100-1 ratio for moving coil mike, 9/-.

WHARFEDALE OUTPUT TRANSFORMERS.
OP3 ratios 30, 60 and 90-1, 8/-.
Type "F" ratios 30, 45, 60 and 90-1, 9/-.
O.P.8., ratios 12, 18, 24, 30, 36 C.T., 48 C.T., 60 and 72-1 C.T., 13 9.
W.12, 15/1, 22/1, 45/1 C.T., 30/-. All 9d. post.

L.M.S. COIL PACKS. Complete with circuit, 23/-.

FULL MAIL ORDER FACILITIES

Shop Hours: Monday-Friday 9-5.30 p.m.
Saturday 9-1.

GEE—RADIO

ALUMINIUM SHEET, undrilled, 16 S.W.G. Sizes available : 12in. x 12in., 24in. x 12in., 24in. x 24in., 36in. x 24in., 5/- per sq. foot.

80 OHM STANDARD ¼in. DIA. CO-AXIAL CABLE, 1/- per yard.

90 v. and 1½ v. EX-GOVT. DRY BATTERIES, in good condition, 7¼in. x 4¼in. x 3¼in., 4/6.

B.T.H. 16 mm. SOUND PROJECTOR, complete in perfect order, with screen. One only, **£105.**

12in. P.M. LSPEAKER, Truvox, 3 ohm, S/coil, 55/-.
10in. P.M. LSPEAKER, Elac, 3 ohm, S/coil, 25/-.
5in. P.M. LSPEAKER, Goodmans, 3ohm, S/coil, 12/11.

MAINS TRANSFORMERS. Primary 200-250 v. tapped. Sec. 350-0-350 at 150 mA., 6.3 at 4 amp., 5 v. at 2.3 amp. Ex-E.M.I., **25/-.**

50 OHM 40-WATT W/WOUND VARIABLE RESISTORS on porcelain formers, 3in. dia., 7/6.

C.R. TUBE 3¼in. VCR138 (ECR35), complete with mask, mu-metal screen and base, **40/-.**

EXIDE 2 v. at 15 AMPERE EX-GOVT ACCUMULATORS, 4/6.

MANSBRIDGE CONDENSERS. 2 mfd. at 2,500 v. at 140° F. Size 6 x 5¼in. x 2¼in. Type 1418, **10/-.** Also 4 mfd. 1,200 v. at 160° F. Size 4¾in. x 3¼in. x 2¼in. Inverted mounting, **10/-.**

813 CERAMIC 7-PIN VALVE HOLDERS (new), **9/6.**

RECORDING TAPES. Emitape, **35/-**; Scotch Boy, **35/-**; G.E.C., **30/-.** Spare spools, 4/-.

COLLARO RECORDING MOTORS, clock or anti-clock rotation. Either type, **42/-** each.

EX-GOVT. RADIO INTERFERENCE SUPRESSORS. Small size, 4in. x 4¼in. x 2in. Type SC/1266, **5/6.** Large type, size 8in. x 7¼in. x 2in., Ref. SC/968, **9/6.**

HELLERMAN TOOL KIT, comprising of sleeve expander tool, oil and 250 sleeves in one carton, **17/6.** Tool only, **9/6.**

ROTARY CONVERTORS, Ex-Govt. 12 v. D.C. input to 230 v. A.C. 50 cycles, output 150 watts. Complete in carrying case. Containing voltage control, sliding resistor, mains switch, input and output sockets. In perfect order, **£8/10/-,** carriage 10/-.

MAGNETIC SWITCH RELAY, type E, 24 v. at 25 amps., Ref. SC/849, **8/6.**

5 mA. METER RECTIFIERS, 7/6.
280 v. H/W 80 mA., 6/-.
12 v. 4 amp. F/bridge, **18/6.**
12 v. F/bridge at 2 amps., **12/6.**
24 v. F/bridge at 1 amp., **15/-.**
R.M.1 and 2, 125 v. H/Wave at 60 and 80 mA 4/-.
R.M.3 125 v. H/Wave 100 mA., 5/-.

COLLARO 3-SPEED RECORD CHANGERS, R.C.3/521, with dual head, **£15,** or with two crystal heads, **£18/14/-.** Also Collaro single speed, 78 r.p.m. record changers at **£12/10/-** R.C. 500. Carriage 5/-.

Terms : C.W.O., C.O.D. or Pro-forma. Orders under 20/- plus 1/6 for P.P.

15 LITTLE NEWPORT ST., LONDON, W.C.2

GERrard 6794/1453

NEW GRAMOPHONE AND SOUND EQUIPMENT

TAPE recorder motors, 250v a.c., powerful, quiet, brand new, 15/11; post, etc., 1/1.—K. W. Logan, Westalley, Hitchin, Herts. [6469

SOUNDMIRROR tape recorder, suitable high or low coercivity tape, complete with external mike; £50.—Haynsons, 14, St. Mary's, Bedford. Tel. 5568. [0148

MAGNETIC tape new high coercivity Emitape 55/- spool 1,200 feet tape decks, blank recording discs, 10in. 5/- from stock; full trade terms.
SOUND DISCS (SUPPLIES), LTD., 178, Bispham Rd., Southport, Lancs. Tel. 88155. [7765

9Kcs whistle can be attenuated with a high Q toroidal coil fitted as series or parallel resonant crt, easily adjusted aurally, coil only, 35/-; can be used also as inductance standard, accuracy 2%.
BEL SOUND PRODUCTS, Co., Marlborough Yard, London, Archway, N.19. [0187

THREE speed record players, walnut finish (with lid) fitted B.S.R. MU.14 motor at £11/5/; complete with Chancery dual cartridge crystal pick-up £15/5/; with Decca X.M.S. magnetic pick-up £18/5/; any make fitted to order; MU14 motor at new reduced price of £6/8/6 post free.
RECORD filing cabinets for the Connoisseur in hand French polished oak, walnut or mahogany from £13/15; sizes to hold 300 or 500 discs, specials to order.
SAND-FILLED corner speaker enclosures, non-resonant (as described by G. A. Briggs in his book "Sound Production") in walnut finish, from £15.
BASS-REFLEX cabinets suitable for any size speaker, solidly constructed from hardwood, plywood and Weyrac; any type of cabinet made to customer's own specification.
DETAILS for 2½d stamp from—"Phase-In" Speakers, 99, Ash Bank, Bucknall, Stoke-on-Trent. [8005

CINE VOX disc recording equipments, type C70 for high-quality recordings from existing microphone equipment, price from 26gns; also available as a complete channel inclusive of mic., amplifier and playback equipment, at 70gns; type C7 for highest quality professional requirements—recorder mechanism at 48gns, or complete channel at 110gns; demonstrations arranged in London.
PLEASE write for details to K.T.S., Ltd., 60, Aylward Rd., London, S.W.20. (Liberty 2426.) Callers by appointment only. [0209

"MAGNETIC Tape Recorder Construction" (8/6), besides explaining the theory also gives full constructional data, sketches, instructions for aligning and testing a complete high-fidelity recorder; 7½ m.p.s. wow-free reproduction, fast rewind, low noise-level, kit of precision-made mechanical parts supplied which makes assembly of desk a simple matter of drilling and mounting.—DMELS, 15, Corstorphine Hill Rd., Edinburgh. [7950

GRAMOPHONE AND SOUND EQUIPMENT —SURPLUS AND SECONDHAND

SIMM DR49A professional disc recorder, in strong case, perfect; £100.—Box 7394. [8281

MARCONIPHONE AC 100M auto-changer; £6/6.—Carpenter, 36a, Bridge St., Pinner. Tel. Pinner 652. [8254

B.S.R. disc recording unit for sale, almost new, 2 microphone and stoneleras; £160.—Cambray Studios, Cheltenham. [8182

SIMON DR49A disc recorder (no amplifier), as unitplate, £80; CDP ditto, £12; 2 M.S.S. CH/4 cutterheads, with equalizers, £5 each.—Box 7345. [8370

SALE, tape recorder assembly, "Qualtape" deck (two motors), complete, "Audigraph" amplifier kit (inc. valves and part built); "Audigraph" (Tampsa) Record/Playback and erase heads; instructions; all as new.—Box 7347. [8275

NEW COMPONENTS

CRYSTAL microphone inserts (Cosmocord mic-6), guaranteed brand new; 15/6, post free.
RADIO-AID, Ltd. (Retail Dept.), 29, Market St., Watford. [9056

EVERYTHING for home constructor, chassis, condensers, coils, valves, resistors, gram units, speakers, test gear, Viewmaster kits, etc., cash or H.P.; stamp for lists; quick service, no Govt. surplus offered.—James H. Martin & Co., BCM/EDBWA, London, W.C.1. [7694

FOR really good results you can do no better than use Osmor coils and coilpacks. ask anyone of experience! Send 5d (stamps) today for beautifully-drawn free circuits, our new coil-data leaflet, and latest lists of matched radio components. A speedy mail order department is at your service, and remember, all Osmor lines are guaranteed. (Trade enquiries invited.) Dept. C.W.1.
OSMOR RADIO PRODUCTS, Ltd., Bridge View Works, Borough Hill, Croydon. Tel. Croydon 5148/9. [0046

TELEVISION-coilsets, all with video chokes; Viewmaster, Pract. Wless, E.Eng.; London 16/6, Midland 19/6, H/Moss 21/-, Scotland 25/-, ⅝in canned cored targets, screened TV formers, as used WW, FM, Rx 2/- ea.; Viewmaster, total cost abt £58, mostly 14-day delivery; Wireless World sensitive superhet, coilsets 62/6, 9F strips 62/6, defn. coils 48/-, line trans 65/6, blocking trans. (frame) 15/-, remainder from 60 days' delivery; Williamson high Q TRF feeder coils, on ⅝in poly formers, MW or LW 9/6 pair; ¼in, ⅜in TV formers, 7d and 10d, add 2d (tappane); material supply position may preclude immediate dispatch in some cases; trade inquiries invited.
BEL SOUND PRODUCTS, Co., Marlborough Yard, London, Archway, N.19. Arc. 5078. [0185

Armstrong
THE CHASSIS PEOPLE



The prestige of Armstrong chassis is firmly based upon many years of constant endeavour to produce reliable and efficient receivers at an economical price. Our present range of chassis will even further advance the already high reputation enjoyed by our receivers. We are delighted to give demonstrations in our showroom and our illustrated catalogue will be sent on request.

MODEL EXP 125 14-VALVE ALL-WAVE RADIOGRAM CHASSIS

5 Wave Bands covering from 10.9 to 550m and 800 to 2,000m. R.F. Pre-Amplifier. Two I.F. Stages with Variable Selectivity. Bass and Treble Controls. 15-Watt Push-Pull Output. For A.C. Mains. **£36.15.0,** plus P.T.

MODEL RF 104 10-VALVE ALL-WAVE RADIO CHASSIS

4 Wave Bands. R.F. Pre-Amplifier. Two I.F. Stages with Variable Selectivity. 10-Watt Push-Pull Output. For A.C. Mains. **£24.0.0,** plus P.T.

MODEL EXP 73 8-STAGE ALL-WAVE RADIO CHASSIS

3 Wave Bands. Variable Selectivity. Fly-Wheel Tuning. 8-Watt Push-Pull Output with Negative Feed Back. For A.C. Mains. **£17.15.0,** plus P.T.

TELEVISION
The new ARMSTRONG TELEVISION CHASSIS, model TV.15, incorporating a 12" C.R.T., is now available for distribution.

PRICE: 53 GUINEAS
TAX PAID

Unfortunately, owing to the limited supply of material, the Chassis is at present available only for the London Service Area. Please send for full details.

ARMSTRONG WIRELESS & TELEVISION **CO. LTD.**
WARLTERS ROAD, HOLLOWAY, LONDON, N.7
Telephone : NORth 3213

DUKE & CO.

SALVAGE RADIO-GRAM CHASSIS. Price £9 17 6 for a 1950 All-Wave chassis with latest type midget valves (BVA series). This superhet receiver was made to sell at three times this price. Tested and guaranteed. Money refunded if not satisfied. With built-in switch gram position, you can build this into your own gram cabinet, and save yourself pounds. Write own for details of valve line-up and chassis sizes without obligation.

PERSONAL RADIO. Price £5 19 6. 4 valve TRF kit with complete instructions for assembly. Our popular receiver for A.C. or A.C./D.C. with choice of walnut brown or ivory plastic cabinet. Assembled ready for use, 35/- extra. This set can be built with the minimum of experience, and is guaranteed to give complete satisfaction. Postage and packing 3/6 extra.



TRANSFORMERS. Price 12/9. An outstanding bargain in Mains Transformer offers. Salvage stock, new, tested and guaranteed for three months. 260-0-260, 63 m.a., 2 a. Postage 2/-. Standard O.P. transformers. Brand new, for midget and personal receivers with normal O.P.v. Made by Radio Spares Ltd. Price 7/9 each. Postage 1/-.

TYPE 22 1196 S'HET RECEIVER. Price 7/9 each. A real Bargain. For short wave reception. These sets convert easily to battery or mains receivers. We supply a free drawing for mains modification with each set. The valves and some parts have been removed but the following remain: 4 Tuning Condensers, 32 fixed condensers, 28 resistances, Trans. switches, V Controls, V holders, Dial, seat chassis and all small parts. Postage 2/-.

ELECTROLYTIC CONDENSERS. 16×16 mfd. 500 v.d.c., 4/9 each. 12+12 mfd. 350 v.d.c., 4/9 each. 8+8 mfd. + 350 v.d.c., 3/9 each. 8 mfd. 350 v.d.c., 2/9 each. 1 and .01 mfd. 350 v.d.c., 20/- per 100. Buy 50 mfd. 12 v.d.c. 9d. each. 4 mfd. 300 v.d.c., 9d. each.

Mail orders: 621 Romford Road, Manor Park, London, E.12. GRA. 6677
Retail Sales: 219 ILFORD LANE, ILFORD, ESSEX. ILF. 0295

OPPORTUNITIES IN RADIO

Get this FREE Book!

ENGINEERING OPPORTUNITIES

reveals how you can become technically qualified at home or a highly paid key-appointment in the vast Radio and Television Industry. In 144 pages of intensely interesting matter, it includes full details of our up-to-the-minute home study courses in all branches of **TELEVISION and RADIO, A.M. Brit. I.R.E., City & Guilds, Special Television, Servicing, Sound Film Projection, Short Wave, High Frequency, and General Wireless Courses.**

We definitely Guarantee

"NO PASS—NO FEE"

If you're earning less than £14 a week this enlightening book is for you. Write for your copy today. It will be sent **FREE** and without obligation.

BRITISH INSTITUTE OF ENGINEERING TECHNOLOGY
388a SHAKESPEARE HOUSE, 17/19 STRATFORD PLACE, LONDON W

BIET

NEW COMPONENTS

SUPACOILS various range of coils are now obtainable from your local radio dealers. If you have any difficulty in getting supplies write to our office for complete catalogue or send 2/6 for our new constructor's handbook of circuits, sent, formulae, etc.—SUPACOILS, OFFICE, 98, Greenway Avenue, London, S.17. 10153

COMPONENTS—SURPLUS AND SECONDHAND

C. J. EMMS, Ltd.

RECTIFIERS, full wave bridge type, as follows: 1 amp. 12 or 6v, 5/6; 3 amp. 12 or 6v, 12/6; 4 amp. 12 or 6v, 15/-; 5 amp. 12 or 6v, 17/6; 7 amp. 6 or 12v, 22/6; 24v 1 amp, 11/-; 24v 3 amp. 25/-; 24v 4 amp. 30/-.

NEW sliding resistance sets from 1 to 4 amp 14Ω to 12 amp 1Ω, 7 in all, 30/- per carton.—264, Colberne Mews, London, S.W.10. Fremantle 3941. 10201

HALLICRAFTER Skyrider Model 23, perfect, 1154, transmitter, communication receivers in stock. Hammerling super Pro, H.R.O. Senior, C.R.100, A.R.88D., A.R.88LF., etc., all in perfect order. R.1155 receivers in new condition. your enquiries are invited for rotary convertors and recific motors, mos, sides and types available from stock; special clearance of F.H.P. electric motors, 35/-. 110v-250v a.c.

UNIVERSAL a.c./d.c. motors, suitable for sewing machines, 40/- each. 12v-15v a.c./d.c. motors with extended spindle suitable for models, etc., 9/5. 20 watt P.A. rack mounting amplifier, new and complete, with heavy duty a.c. power pack, 200-250v, PX25 P.P. output, £5/10, less valves; new moving coil microphones, hand type, heavy duty and complete with 12yd screened cable, £3.15.; 20ft telescopic tubular T.V. mast, 18/6 each; large selection of test equipment; multirange meters, valve testers, signal generators, oscilloscopes, bridge meggers and meggers, etc., all at reasonable prices; hand bearing prismatic compasses, perfect, 45/- each; very large stocks of transmitting valves, Klystron, of all types, send us your requirements; special offer of new, hot ex-W.D., mains transformer, semi-shrouded 200-250v tapped primary, 250-0-250, 100ma, 5v 3amp, 6v 4amp, 21/6 each, large stocks of L.T. transformers special sizes and ratings wound to specification; auto-record changers in stock from £15.2.6 to £18.10; switchboard mounting voltmeters, amp-meters, various ranges a.c. and d.c. available at cheap prices to clear; large stocks of enamelled wire, 18 and 20 s.w.g., D.S.C. No. 15 U.S. base, American valves available. Special offer H.R.O. coils, 48-96 m/s and 180-450 k/s, 4/5 each; quantity of 12in and nickel chrome wire available, type 74 indicator units, complete with tube, as new, £6 each. Hallicrafter Super Skyrider SX28 in stock. Evershed bridge meggar 500v 1½kw. e.d.c. rotary converter, 220 d.c./250 a.c., complete with Izranic starter, £28. Large selection of American Pyranch high-voltage working condensers, 0.5 m.a meter rectifiers, 8/6 ea.

HAMMERLUND B.C. 779B, perfect order, rack mounting £42.10. Q-Max. Q-5-10 receiver, new £56, prices do not include p.&p. age.

SERVICE RADIO SPARES, 4, Lisle St., W.C.2. Gerrard 1734 10168

V.H.F. receiver, type 1481, complete with valves, £7.10.

BENDIX frequency meters, type BC221.

THROAT microphones, 5/6 each.

LORD antivibration mountings, 8lbs @ 10lbs, £8 per 1,000.

TELESCOPIC aerial for No. 19 set Mark II.

POWER unit for No. 19 set, U.S.A. and British Mark II, 25/-.

VOLTMETER MC DC 3,500 volts, 3½in projecting type, 45/- each.

EIMAC vacuum condensers 100pfd, 20,000 volts; 15/- each.

MICA condensers, American types, bulk quantities only, types X.S. Sanzamo, Solar A2 etc., 2kv to 5kv, vitreous enamelled resistors from 40 ohms to 50,000 ohms, wattages 25, 50, 75, 100, all at 4/- ea.

COMMAND receiver Bendix drives from 5in to 25ft long, 5in 5/- each; from 2ft to 8ft, 8/6 ea.; from 15ft to 25ft, 16/- ea.

McELROY ADAMS MFG. GROUP, Ltd., 46, Greyhound Rd., Fulham, W.6. Tel. Fulham 1184-9. Cables, Hallicraft London. 0196

MAGSLIPS at 1/10 to 1/20 of list prices. Huge stocks, please state requirements.—K. LOGAN, Westaway, Hitchin, Herts. 16369

T.V. tube, 9in, MW22-14C, little used, also mask and magnifier, offers.—Box 7351.

SOUTHERN RADIO SUPPLY, Ltd., 11, Little Newport Street, London, W.C.2. See our displayed advertisement page 108. 10016

MIKES, lone, single phones, 1/6; .001 mica, 1/500 tub, 6d; .05/600, .006, 6d, 5+25, 35v, 1/-; resistor panels from 4d; No. 18 set coils, 6d; post extra, s.a.e. lists.—ANNAKIN, 25, Ashfield Place, Otley, Yorks.

STOCKTAKING offers.—Speakers, all 2-5 ohms, 5in 12/-, 6½in 12/6, 8in 14/-, 10in 17/6; O/trans, pentode, tapped, 5/9, h/duty, 4/6, w/centre, semi-midget, 4/-, and 2-way, 17/sp, 1/8w, 2/6, stnd. size, all values, mon/sw, 2/9, w/sw, 4/3, ¼-meg S/midget DP/sw, 5/-; electrolytics, all fresh stock, 450vw, 8mfd, 2/3, 16, 5/-; 8×8, 5/9, 8×16, 4/6, 16×16, 4/6, 32×32, 6/-, 32×32×16, 350v 6/-, 500vw 8mfd, 2/9, 16, 5/9, 8×8, 4/6, 3-valve a.c./d.c. amplifier kit, less valves, 47/6, m coil, 0-500v meters, 7/9, 0-40 amp 6/6; cored solder, 4oz, 3/9, r/conds, .0005, 5/6; crystal diodes, w/ends, 5/-; droppers, 2 and 3, 4/3; co-ax cable, ½in, 80-ohm, 12/6 doz. yds.; component list available.—Radio Unlimited, Elm Rd., London, E.17. Tel. Key. 4015 10062

"You can rely on us"

FOR CLEAN COMPONENTS AT COMPETITIVE PRICES

MIDGET I.F. TRANSFORMERS.
465 K.cs. Wearite M466 13/16" square 1 13/16" high 10/6 each. Super midget, 13/16" square 1¼" high 10/6 each.

QUALITY OUTPUT P.P. PULL TRANSFORMERS.
MR 7, 10 watts, 12 ratios, fitted with Terminal Panel, 18/9.
MR 15, 18 watts 11 ratios, secondary 1 to 30 ohms, primary 2,000 to 18,000 ohms, 41/6.
MR 30, 30 watts, 11 ratios, Max. Current 170 m.a., Primary and Sec. as MR 15, 49/6.
PA40L, 15 watts, 6L6 Class A, 4 ratio, Primary 5,000, 42/-.
PA24L, 10 watts PX4, 4 ratio, 33/-.
All new transformers, NOT surplus.

EXPERIMENTAL TRANSFORMERS.
Standard Primary 200-250 v., Secondary 3 v. to 30 v. at 2 a., 24/-.

COILS.
Wearite "P" Coils all ranges, 3/- each. Weymouth "H" coils 3/6. "K" coils 4/9. T.R.F. pair with reaction, MW/LW 7/6.

COILPACKS MW/LW/SW.
Bargain offer, Superhet pack for 465 K.cs I.F., 25/- each.

LOUDSPEAKERS.
WB 2½" 17/3, Plessey 5" T.V. Type 14/9, 6" TV Type, 15/-.

HIGH VOLTAGE CONDENSERS.
T.C.C. .001 mfd. 6 Kv. 4/6, .003 mfd. 12.5 Kv. 7/6, .01 mfd. 6 Kv. 4/6, .1 mfd. 9 Kv. 13/6. All new stock.

MISCELLANEOUS.
Full range of Morganite Type "I" Miniature resistors, max. rating ½ watt 6d. each, 5-piece polished aluminium Int. Octal Valve cans 1/6. Miniature Val. Controls, with w. 5/-, less 3/6. Aladdin Formers and Cores ½" 10d., ¾" 7d. New High Resistance Lightweight Headphones 12/6 pair. Rotary toggles SP/ST 2/6, DP/ST 4/3. B Lee Co-Ax. Plugs 1/6. Sockets 1/6.

Stockists of :—
HAYNES, WEARITE, WEYMOUTH, VIEWMASTER, B.V.A. Valves, ELSTONE Products.
Our 32-page Catalogue No. 10 6d.

RADIO SERVICING Co.

444 Wandsworth Road, London, S.W.8

Phone: MACaulay 4155.
77, 77A Bus. 28 Tram. Wandsworth Rd. S.R. Station. Open till 6.30 p.m.

COIL WINDING MACHINERY



We invite your enquiries for the Type A1·1 automatic machine, as illustrated above. For which prompt deliveries can now be made. Also for the Type H·1 hand coiled winder and Type A.W.1 Armature Winding Head.

KOLECTRIC LTD

71 UXBRIDGE RD., EALING, LONDON W.5
Telephone: EALing 9096

★ —If yours is a (RARE) valve problem BULLS are the people most likely to solve it.

"DEMOBBED VALVES"

Manual Post free 2/9

Giving Equivalents of British and American Service and Cross References of Commercial Types with an Appendix of B.V.A. Equivalents, and comprehensive Price List. We have still some Valves left at PRE-BUDGET rates which are actually sold at the old prices.

E X P O R T

to all parts of the Commonwealth and beyond—safely packed fully insured (no C.O.D.) and free of tax.

LOUDSPEAKERS.
5in. P.M., less transformer 14/6
6½in. P.M., less transformer 12/6
8in. P.M., less transformer 11/6
8in. P.M., less transformer 13/6
9in. M.E. Rola, 700 ohm field, L/T 12/6
8in. P.M., less transformer 14/6
10in. M.E., less transformer 20/-
12in. P.M. Truvox, less transformer £0/-
Plus 1/- post.

CONDENSER TESTERS AND RECTIFIER UNITS. Plugs straight into A.C. mains, 200/240 v., and is indispensable for examination of condensers. Very slight and intermittent leakages which cannot be discovered by conventional instruments can be traced by this unit. Complete 29/6. Post 1/-. Supplies are becoming limited.

PIFCO ALL-IN-ONE RADIOMETER. A.C. and D.C. test everything in radio. Complete with test prods, 27/6. Post 1/6.

TAYLOR Orange multimeters. A.C./D.C., 0-6-30-120-600 v., 0-30 m.a.—300 m.a.-3 amperes precision M.I. movement, 50/-.

NEW: COLOURED FILTERS FOR TELEVISION SCREENS. For viewing in three delightful colours graduating from blue at the top, red in centre to green at the bottom. Gives a three-colour pastel shade picture on any black and white screen. 9in. and 10in., 10/9; 12in., 12/6; 15in., 19/6. Post 1/-.

AMERICAN TYPE ELECTRIC SPRAYERS. British made. Just plug in and spray. No vacuum cleaner or compressor needed. Easier than a brush and twice as fast. A.C. model, £3/15/-. Post 1/6.

"WIRELESS WORLD" Radio Data Charts, 7/9

8 T.H. Germanium Crystal Diodes 3/- only

1,000 MFD. 12 V. BLOCK CONDENSERS, brand new surplus, 7/6.

ROD ANTENNAS, 4-foot sections, interlocking and extending, copper plated steel, 2/6 dozen.

5CP1 19/6. **SU2150A.** 9/9.

A.C. D.C. NEON TESTER, TYPE 400. This new mode is specially designed for one-pole tests on mains, incorporating a highly sensitive neon tube—striking voltage 100/500v. A.C./D.C. Also suitable for indicating polarity on D.C. current, when the glow of the lower electrode will indicate the negative pole. 11/3

TAYLOR ON EASY TERMS. EASY TERMS up to 10 months—and very near Cash Price on all TAYLOR METERS.

EX-W.D. CHASSIS with brand new valves, IR5, 1S4, 1S5, 1T4, and circuit diagram showing conversion to excellent Personal Portable 52/6, post 1/6.

RESISTOR COLOUR CODE INDICATORS accurate, dial type, 1/3.

ADCOLA 3/16in. DIA. BIT SOLDERING INSTRUMENT. Miniature type to meet every requirement for Radio, Television, etc., 22/6, post 1/-.

HYDROMETERS. Unbreakable, all plastic, correct for 60 F., 7/6.

EX-GOVT. 4 mfd. 400 v. Dry Electrotype Condensers, 4/-.

RECHARGE DRY BATTERIES. New device which will have us in test within a very short while for with it, the life of its batteries, either H.T. or L.T. can be extended six or more times. Price £3/5/-.

SPEAKER MATCHING TRANSFORMERS. Ex.-Govt. Surplus, guaranteed 2/-, post 6d.

MORSE BUZZER OUTFITS. Consisting of a buzzer, a morse key and a battery compartment, all mounted on a polished baseboard. All parts high grade ex-Air Ministry. An excellent gift for a boy. 6/-, post free.

(Kindly mark envelope W.W.)

EASY TERMS. 28-page Illustrated Catalogue 6d. Stamps.

RADIO BULLS VALVES
246 HIGH ST. HARLESDEN N.W.10

COMPONENTS—SURPLUS AND SECONDHAND

RADIO CLEARANCE, Ltd., 27, Tottenham Court Rd., London, W.1. SPECIAL offer of electrolytic condensers, capacity, voltage, size, type of mounting, price, post paid, in that order.—4/30, 6v., 1in.×¾in., lug, 2/6; 250+250, 6v., 1in.×2in., lug, 2/6; 500+500, 6v., 1in.×3in., lug, 2/6; 700+700, 1in.×3in., lug, 2/9; 1,500, 1in.×3in., clip, 5/-; 50+50, 150v., 1¼in.×2in., clip, 3/3; 40+40 150v., 1¼in.×2in., clip, 3/3; 40, 150v., 1in.×2in., clip, 2/6; 20+20, 275v., 1in.×2in., lug, 4/-; 16+32, 275v., 1in.×2in., lug, 4/-; 16+16, 275v., 1in.×2in., clip, 4/-; 32+32, 275v.+50mf, 25v., 1in.×3in., lug, 4/6; 60+100, 275v., 1¾in.×3in., lug, 5/6; 100+200, 275v., 1¾in.×4¼in., clip, 5/6; 100, 275v., 1¾in.×2in., clip, 3/9; 50, 550v., 1¼in.×2in., clip, 5/6; 32×32, 550v., 1¾in.×2in., clip, 4/9; 16+16+16, 350v., 1¾in.×2in., clip, 5/3; 40+40+20, 350v., 1¾in.×3in., lug, 5/3; 40+40, 550v., 1¾in.×3in., clip, 4/9; 16, 550v., ¾in.×2in., lug, 2/3; 40+40, 300v., 1in.×3in., lug, 4/6; 64+120, 300v., 1¾in.×4¼in., clip, 5/9; 10, 450v., ¾in.×2in., lug, 2/6; 16, 450v., ¾in.×2in., 3/3; 20, 450v., 1in.×2in., lug, 3/3; 32, 450v., 1¼in.×2in., clip, 4/-; 16+8, 450v., 1¾in.×2in., clip, 5/3; 16+16, 450v., 1in.×3in., lug, 5/3; 24+12, 450v., 1¾in.×2in., clip, 5/3; 40, 450v., 1in.×3in., lug, 3/6; 16+16, 450v., 1¾in.×2½+2in., clip, 5/3; 32+32, 450v., 1¾in.×3in., clip, 6/-; 80+30, 450v.+20mf, 25v., 1¾in.×3in., lug, 6/-; 15+15, 450v.+20mf, 25v., 1¼in.×3in., lug, 5/3; 60+100, 475v., 1¾in.×4¼in., clip, 7/6, all are all cans, screw with cardboard sleeves, all voltages are WKG, all new stock, some limited quantities.

TELEVISION: Set of 3 components, comprising line output trans., with E.H.T. winding to give 7kV, using EY51 (heater winding for EY51 also included), and fitted with width control scanning coils, low impedance line and frame, focus coil (res. 10,000 ohms, current approx. 20 mA), the set of 3 for 42/-, plus 1/6 post, diagram of line trans. supplied.

PERSONAL receivers, 3 valve T.R.F. using 1T4s, contained in handsome table cabinet with lift-up lid, size 7×6¼×5in. with lid closed, plastic carrying handle, fram AE in lid, these receivers cover the medium waveband and operate from self-contained dry batteries, standard types W1435 and U2, output to a pair of lightweight 'phones (H.R.) controls, SM tuning and reaction, opening lid switches on, supplied brand new, with valves, batteries, 'phones, an ideal set for invalids, hospitals, patients etc., these receivers are not Govt. surplus and are offered ready to play, carr. paid, £4/10.

CHASSIS steel, 5¼×5¼×1in. drilled 5 button base holes, 1/9, 5×9×1½ drilled 5 button base holes, 2/3; all, 14¼×10×2½, drilled 10-B8A, int. octal, ex. T.V., 4/3, primary 0-110-210-240v 50c/s, secs 300-0-300v 80ma, 4v 2a, 6.3v, 2.5v, 15/6; smoothing chokes, 8H 250ma 50Ω size 4×5×5, bottec 10/6 post paid; supernet coils 10×15, formers M. wave H.F., AE, Osc., L. wave H.F., AE, Osc., 1/9 per coil; I.F. trans. 465kc/s, 1¼×1¼×4in iron cored 8/- pair; meters 2in square bakelite case, 0-5ma 6/6, 0-50ma 7/6, 0-500v d.c. with series res., 7/6. Rotary power units, type 104, d.m. rotary, mounted on chassis with input 12v d.c. output, 250v 60ma, 6.5v, 2.5a, d.c., 7/-, type 87 24v input, outputs as 104, 6/6 post paid; plugs and sockets, bakelite with keyway, 5-7, 1/6 pair; extension speaker controls, 1Ω wire wound, ¼in spindle, 9d.; "Eye Strips," the well-known 45mc/s vision strips brand new, less EF50s with EA50, perfect condition, 5/6, focus coils, low res., 200Ω, stated on TV, 6/6, can be had as alternative with kit if required; 6½in loudspeakers, n.m., less trans., boxed, 12/6 post paid; v.c. with sp switch, long spindle 25k, 50k, 100k, 2m., 4/-.

VALVEHOLDERS, Amphenol, int. octal 7d., 10IN loudspeakers with trans. (4,500Ω), 54/-, small size, 4P 3w switches, 1in spindle, 2/9.

RADIO CLEARANCE, Ltd., 27, Tottenham Court Rd., London, W.1. Tel. Museum 9188. [0015

SUPREME RADIO, 746b Romford Rd., Manor Park, London, E.12. Tel. Ilf. 1260. Est. 17 years.—Look! Twin balanced feeder for television, 4d. per yd.; alum. num. can-type condensers, electrolytic, 8mf 500v, 5/-; 8+8, 16+16mfd 500v 5/9 each; small can-type, 16+32mfd 350v, 4/9 each.

WONDERFUL bargain!! 8mfd 500v tubular cardboard tag-end cond., 2/- each; 4mfd 500Ω tubular cardboard wire-end cond., 1/6 each.

BIAS cond., tubular cardboard, 50mfd 50v. wire end, also 50mfd 25v., 1/- each.

WESTINGHOUSE-type metal rectifiers, 250v R.M.S. 65ma, 5/6 each; 2-bank 50pf trimmers, 6d each; 3-bank, 1/- each; 4BA brass n/plated terminals, 2/3 doz.; 2Bway tag strip, break it as required, 1/- each; int. octal, amphenol-type v/holders, 7d each; B7G moulded-type v/holders, 10d. each; B9G (EF50) slate-type v/holders, 6d each; panels with 6 resistors, 1pf and W.6 Westector, 1/- each.

VOL. controls, Standard size, with long spindle and s/pole switch, 2meg, 100K ohms, 25K ohms and 5K ohms, 2/6 each, also the following values less switch, 2meg, 250K ohms and 100K ohms, 1/6 each; heavy-duty carbon, w/controls, 50K ohms or 20K ohms, w/wound, 2/9 each.

FLAT type mains dropper, tapped, 200-250v, 650 ohm at 0.2amp, 1/6 each.

MANY other bargain lines in stock; terms c.w.o.; no c.o.d.; send 6d extra for postage orders under £5; 2½d s.a.e. all enquiries and list. [0021

AMATEUR selling up; universal Avominor, as new, brand new, leather case and resistance range extension unit; £8; s.a.e. for list of bargains to J. Rundell, 124, Goddington Lane, Orpington. [8274

ELECTROLYTICS (not Govt. surplus), tub., wire end, 500vw., 8mf 2/3, 16mf 3/3, 32mf 4/-; 25v, 25mf, 20/- doz.; moulded case mica conds., 0.1mf 1,500v d.c.w., 20/- doz.; dis. silvered ceramics, 20, 25 & 30pf, 1/6 doz., add postage.—Ward, 9, West Cliff, Dawlish, Devon. [0214

High Fidelity at Its Best
can be Heard at our address

LEAK. T12 Amplifier with T.C. Unit £37 18 0
V.S. Radio Tuner Unit £37 2 4

SOUND SALES. A-Z Amplifier and Tone Colour Unit £32 10 0
Tonemaster Amplifier and T.C. Unit £25 0 0
D.X. Plus One Radio Tuner Unit £22 14 7

ACOUSTICAL. Q.U.A.D. Amplifier and T.C. Unit £35 0 0
Pre-set Radio Tuner £26 0 0

ROGERS DEVELOPMENTS. Williamson Amplifier £29 0 0
Baby de Luxe Amplifier with T.C. Unit £25 10 0
R.D. Junior De Luxe with T.C. Unit £17 10 0

GOODSELL. S.A.8. Amplifier £15 15 0
Tone Control Unit £6 10 0
V.S. Radio Tuner £19 10 0

ARMSTRONG. 7-valve Radiogram Chassis £25 12 4
10-valve All-wave Radiogram Chassis £34 12 10

WHARFEDALE. W12C.S. Speaker Units £9 0 0

TANNOY. 12in. Dual Concentric Speaker Unit £27 10 0
15in. Dual Concentric Speaker Unit £33 10 0

BARKER. 150. 12in. Loudspeaker Unit £18 18 0

VOIGT. Domestic Corner Horn (in white) £47 10 0
P.M. Unit with 23 k. line gap flux £40 0 0

LEAK. Moving Coil Pick-up.. £14 10 0

DECCA. X.M.S. Pick-up with 78 and L.P. Heads £7 0 0

CONNOISSEUR. Super Lightweight pick-up £6 9 0

ACOS. G.P.20 Super lightweight Crystal P.U. £3 11 5

CONNOISSEUR. 2-speed A.C. Motors £22 18 8

COLLARO. 3-speed Autochangers, from £11 16 9

RADIOGRAM CABINETS, from £12 12 0

CORNER SPEAKER CABINETS, from £7 10 0

DECCA. G.U.4 Transcription type Player Units £13 19 6

GOLDRING. Three-way Lightweight Pickup.

GOODMANS. Axiom 150 Mk. II 12in. Speaker Units
Audiom 60, 12in. Units.... £2 12 6

Daily demonstrations of above equipment, hours 9.30 a.m.—6 p.m.; 9.30—1 p.m. Thursday at :—

HOLLEY'S RADIO STORES,
285 CAMBERWELL ROAD, S.E.5.

Open all day Saturday. Callers only.

Phone: RODney 4988

EX GOVERNMENT BARGAINS

Dynamotors for R.C.S.S.4 Receivers 28 v. input 500 v. at 60 m.A. output. 25/-, postage 1/6.

Motor Flasher Unit, contains small 24 v. Motor coupled to a worm reduction gear running at about 30 r.p.m. and fitted with 4 sets of make and break contacts, connected to 6 coax sockets, this unit is ideal for flashing signs etc., 10/6, postage 1/6.

Uniselectors P.O. Type. Three banks of 25 contacts. Rolled 7/6 and 12/6. 10/10 as new, six banks of contacts 21/6, postage 1/6.

Ex-G.P.O. Wall Telephones. These are brand new, all complete and ready to use, hand generator ringing, all contained in polished teak box. A real bargain. 90/- per pair, carriage 7/6.

Telephone Hand Sets. P.O. Type, 10/6, postage 1/6.

Pumps Submersible Type, 24 v., 130 g.p.h. 200ft. lift 45/-, postage 2/-. Ideal for wells, boats, garden fountains, etc.

L.F. Transformers, 465 k.c. in perfect condition as stripped from chassis 5/- per pair, postage 1/-.

Ohmite Wire Wound Pots. Vitreous 100 ohm. 25 watt, 4/6; 350 ohm 25 watt, 3/6, postage 9d.

Hydraulic Pumps. American "Tyler Iron" brand new Type 9905 M.K.1, 40/-, postage 2/-.

Rotary Converters, input 11 volts, output 200 volts at 70 m.A. with smoothing condenser, 21/-, postage 3/-.

Time Base Units. Containing two slow-motion gear driven 9000 condensers, 2 Yaxley switches, 6-way one pole, each connected to six silver Mica Condensers, all in metal case, part of the 62 Indicator Unit, 10/6, postage 1/6.

Oil Furnace Units consisting of One-third H.P. Universal 220 Motor direct coupled to 8in. fan and belt driven oil pump. Inlet and outlet types, etc., 67/10/-, carriage 15/6.

Uniselectors double acting. These units have two separate drive mechanisms and therefore will rotate in both directions, 4 banks of 25 contacts complete with dial plate and pointer. Resistance of coil 12 ohms, 35/-, postage 1/6. These units are ideal for pin tables or other devices where adding or subtracting is required.

Our new List No. 8 containing 200 Ex-Government items is now available price 6d. inland, 1/6 overseas air mail.

A. T. SALLIS
93, North Road, Brighton, Sussex
Phone: Brighton 25806

"Go to it"—
If you want to get right down to a speedy and sure way of becoming a highly efficient Morse operator, get it

—the CANDLER way

The Candler system of Morse Code Training was devised for those who intend to enter or have entered the commercial side of telegraphy, the Services, or who take a real interest in Amateur Radio work.

The Special Course covers all the Code training necessary to pass the G.P.O. test for an Amateur Transmitting Licence.

The Junior Course. This is a complete Course for the **Beginner** who desires to have a thorough training in Code to fit him for securing the G.P.O. Certificate in which he is interested.

The Advanced Course is recommended for those who have already attained a consistent sending and receiving speed of not less than 15 w.p.m. With this Course the average student reaches speeds of 25-35 w.p.m.

Courses supplied on Cash or Monthly Payment Terms.

Please send for the
CANDLER "BOOK OF FACTS"
—it gives details of all the above Courses.

THE CANDLER SYSTEM CO.,
(55W) 52b, ABINGDON RD., LONDON, W.8
Candler System Company, Denver, Colorado, U.S.A.

COMPONENTS—SURPLUS AND SECONDHAND

MIDGET I.F.s. 2¼×1¼×1, 465kc, iron cored, 7/6 pr.; 5 pr. for £1. 0005 var. 2-gang conds., slightly soiled, 4/6 ea. 6d. P. and P. under £1.—226, Merton Rd., London, S.W.19. [8255

G. A. RYALL, "Utopia," Mayfield Rd., Herne Bay, Kent, offers post-free bargains:—switches, Yaxley-type, 3B, 8P, 9-way, 1/4; 2B, 8P, 6-way, no stop switch drilled for this, 1/4; smaller type switch, 3B, 2P, 6-way, total of five poles only, 2/3; miniature instrument switch, 8B, 2P, 6-way, 1/4, all unused; two only soldered tags 2B, 3P, 5-w., with coloured leads, 1/9, and 2B, 4-way, with total of five poles, 1/3; toggles, bakelite, 250v a.c., close either of 2 poles, 1/3, and 2P DT change-over, 1/9, and heavy-duty, break several amps, on/off, 5/-; panel mtg. coil switches are all single hole fixing; 4-way bakelite fuse boxes, with 5amp cartridge fuses, and spare, 5/-, well made; 4 resistor panels, with 30 0-½-1-2w carbon colour-coded resistors, 3/6; panel high-grade screw sockets, with 0.1mf and 4,700 1w resistor, and 2½w res., six 4/6, insulation O.K.; pairs of 25mf 50v condensers, 1/9; mica 0.004mf, 1,250v pkg., six 1/6; 0.01mf mica, six 1/6; 1mf 500v wkg., upright or inverted, two 1/6; Manobridge heavy-duty 5×3mf 250v N.L., 4/6 each, and heavy-duty 11×7mf, 8/6 each; radio mains filter, 4 division, 4½×4, metal box, fixing lugs, full screened, 5/9 each, and ex-W.D. a.c. switches, with voltage regulators combined, type 5U/1504T, etc., 5/9 each; Paxolin panels, 4in. 12×8, 3/9; triple leads, one cover plastic, over 3yds., 1/4; twin screened, 5yds., in two lengths, 1/4; variable 4 gangs, straight type, new, 3/10; 3-gang soldered tags, 3/10; both types 0.0005mf measured; voltmeters, 2in. 0-300v., 5ma FSD, separate series resistance, boxed, new, 6/9; 0-5ma 2in. best make, 6/9; both square front and fixing; and 0-30ma 2¼in. boxed, new, 6/9, or best make 8/9; both circular, flush, front flange fixing. [0205

WORK WANTED

ASSEMBLY, wiring, chassis making, prototypes, trade or private.—Box 7295. [8210

CAPACITY available for Ministry of Supply sub-contract work in transformer, coil and wave winding.

AMPLE capacity available also for Ministry of Supply sub-contracting in radio assembly, light metal pressing and paxolin pressing work. FULLY A.I.D. approved.

WRITE: Pennine Amplifiers, Southgate, Elland, Yorks. Tel. Elland 2107. [8206

HOT press and transfer printing, long or short runs.—Wiltshear's, 9, Liverpool Gardens, Worthing, Sussex. [8092

SMALL manufacturer has capacity available for manufacturing small precision press tools and short runs.—Box 7297. [8246

HIGH quality draughting, design and development work undertaken of small electrical or mechanical equipment.—Box 7298. [8247

ASSEMBLY, wiring, conversions carried out. Any one of quantity, trade or private.—Radiovizier, 377 High Rd., London, N.2. [8107

SMALL electronics workshop capable of development or of manufacturing to your specifications small quantities of electronics equipment, requires work in the above.—Write Box 7276. [8184

DRAUGHTING, tracing and photoprinting services; estimates free; contractors to the Ministry of Supply and the Admiralty for drawing and tracing work to their requirements and specifications; sub-contracting work of this nature undertaken.—DRAWING & TRACING, Ltd., 456a, Ewell Rd., Tolworth. Surbiton 4466. Tel. Elmbridge 7406, 7975.

WANTED, EXCHANGE, ETC.

WANTED, R1155N receivers.—Box 7293. [8279

WANTED dynamometer, a.c. test set, also oscilloscope type 339A, also L050A oscillator.—LESLIE DIXON & Co., 214, Queenstown Rd., Battersea, S.W.8. Macaulay 2159. [0176

WANTED.—Copies of W.W. first six months 1941; offers.—Pratt, 10, W. Winstanley, 115, Middleton, Cowling, Keighley, Yorks. [8241

WANTED, laboratory test equipment, including standard signal generator, watt meter, oscilloscope, bridges, recorders; send price and details to HATFIELD INSTRUMENTS, 175, Uxbridge Rd., Hanwell, W.7. Tel. Ealing 0779. [0057

WANTED, HRO coils, Rxs, etc., A.R.88s, LC.5548s, S27s, etc.—Details to R.T. & A.I. Service, 254, Grove Green Rd., London, E.11. Ley 4986. [0165

H11B or similar marine transceivers wanted; any radio goods bought.—Electronix, 220b, Canterbury St., Gillingham, Kent. Tel. 50205 [8222

WANTED, set manufacturers' or ex-Government radio equipment, large or small quantities of valves, electrolytics, speakers, meters, also components.—LOWE BROS., 199, Mile End Rd., London, E.1. Ste. 2579. [6554

WE pay highest price in the trade, modern test equipment, tape recorders, modern radio and television receivers, car radios, amplifiers, record-changers, etc., etc.; call, write or send.—MILLER'S RADIO, 58a, Newport Court, Charing Cross Rd., near Leicester Sq. Tube. Ger. 4638. [7903

WANTED, AN-APR-4 receiver, any units, any other good quality U.S. surplus radio and radar tubes, test sets, laboratory equipments, etc.; give condition and price in first letter.—Littell, Farhills, Box 26, Dayton 2, Ohio, U.S.A. [6546

SOLONS FOR ESSENTIAL JOBS!

Use SOLONS for the jobs that matter—this modern precision tool makes soldering speedier, simpler and more reliable. 5 models: 65 watt with oval tapered and round pencil bit; 125 watt with oval tapered and round pencil bit; 240 watt with oval tapered bit; each with 6 feet 3-core Henley flexible. Voltage ranges from 100 to 250.

W. T. HENLEY'S TELEGRAPH WORKS CO. LTD.
51-53 Hatton Garden, London, E.C.1

Write for Folder Y.10.

HENLEY SOLON ELECTRIC SOLDERING IRONS
FOR INDUSTRIAL USE

How much do you know about RADIO and TELEVISION?

This world-famous book contains all latest radio and television developments. Earlier copies sold 300,000; this **entirely new volume** has 400 pages, 1440 entries, hundreds of illustrations, covers every aspect of radio; new sections include radar, television, remote control, oscillators, Kirchhoff's laws, photo-electric cells, new series of modern circuits for receivers and amplifiers, automatic station sel., car radio, electron-multipliers, fault finding, *building television receiver*, new colour codes, etc.—contains all the accumulated knowledge of radio science!

FIVE DAYS' APPROVAL TERMS

You are invited to examine this grand book on our Five Days' Approval terms; if you decide not to keep the book return it and we will refund your money in full.

POST COUPON TODAY

To: **A. THOMAS & CO. (W)**
111 Buchanan Street, Blackpool

I enclose 22/- for one copy of above **OR** I enclose no money—send C.O.D.

Name .....

Address .....

JOHN FARMER

AUTO TRANSFORMER, single phase 50 cycles, 100 watts, tappings 0-10-120-200-230-250 v., other voltages available are 110-190-220-240 v. All terminations marked, superior job, brand new, 21/- each, post 1/3. **MICRO SWITCHES**, U.S.A. patt., type 'Z' Double throw make or break, extended press, very light pressure, for std. or ¼in. hole panel mounting, 3/- each, post 3d.; 30/- per doz., post 8d. **VHF SWITCH UNITS**, patt. W6777. Fitted 4 pos. switch, 1 input and 2 output Pye plug connectors for std. Pye sockets. Ideal for use when one aerial feeds 2 receivers. Switch provides for both sets on or off, or for one set on and the other off. In metal case, base mounting, new, 7/6 each, post 1/d. **CIRCUIT TESTING OHMMETERS** by Evershed and Vignoles. Twin scale with selector sw., 0 to 1,000 ohms, and 100 to 200,000 ohms and inf. In bakelite case with leather carrier, fitted new battery and tested, perfect condition. Our price £5, postage and reg. 1/4. **MOVING COIL METERS**, centre zero, 30-0-30 m/A, 2in. scale, 2½ in. dia., brand new, boxed, 12/6, post 6d. **CARRIER LEVEL METERS**, m/c, graduated 0 to 10, pointer zero at 10. 2 m/A full scale deflection, 2¼in. sq. panel mounting, provision for scale illumination. A first grade meter, brand new, boxed, 15/- each, post 6d. **BERCO POTS**, wire wound. 1¼in. dia., panel mounting, fitted 1in. long ¼in. shafts, 50 ohms, makes an ideal low imp. speaker vol. control, a useful job for other purposes as they will carry up to ½ amp. Brand new, 2/6 each, post 4d. **VARIABLE RHEOSTATS**, 60 ohms approx. 1 amp., wire wound, laminated slider operated by thumb wheel on threaded rod, traverse bar is graduated. Bakelite end plates for base mounting, size overall 6in. long, 4in. wide, 2¼in. high. New, boxed, 10/- each, post 1/d. **VARIABLE RHEOSTATS**, wire wound on vit. steel, (a) 2 ohms 20 amps., laminated slider, base fitting, 14¼in. long, 7/6 each, post 1/6. (b) 5.3 ohms 8 amps., helical traverse control, carbon brush slider, 15in. long, base fitting, 12/6 each, post 1/6. **TRANSFORMERS**, U.S.A. pattern, all 110-115-120 v. 60 cycle primary, superior type, new unused. (a) Sec. 6.3 v. 1.2 amp., 6.3 v. 1.25 amp., 12/6, post 1/d. (b) Sec. tapped 1207/453 v. at 0.015 amp. D.C., 15/-, post 1/3. (c) Two secs., 9,000 v (no load 9240 v.) at 0.008 amp. D.C., 30/-, carr. and packing 5/-. (d) Sec. 8.1 v. at 1.5 amp., 12/6, post 1/-. (e) Sec. 735 v. 272 amp. (no load voltage), 12/6, post 1/d. **TRANSFORMERS**, U.S.A. pattern, new as above. (i) Magnetron pulse input, Pri. 2830 v Sec. 13000 v. (both windings) hermetically sealed, 25/-, post and packing 1/6. (ii) Pulse output, 8000v capped at 2830 v., 12/6, post 1/-. **ADMIRALTY PATTERN W727 GENERATOR SPARES**, consists of approx. 100 high class precision parts for the Patt. 4732A Generator. Includes—set of engine bearings, ¼in. and ¾in. bore ball bearings, Hoffman 110 and 120 bearings, var. carbon brushes, JAP carburettor with spares, cut-out Ref. APW-960, bakelite case with cover, Magneto ref. APW-961, Mag. spares in leatherette and velvet lined case, also 3 sparking plugs 14 mm. screened, piston rings, valve with springs, washers jointing, etc., etc. All packed in hardwood case 15¾in. x 11¼in. x 4¾in. Brand new, complete, £5 carriage 3/6. **PVC COVERED CABLE**, flat twin, fig. '8' 14/36, transparent, superior quality, brand new, 100 yd. coil, 30/-, post 1/-. **CABLE**. 10/44, twin flat, fig. '8' pvc covered, a useful lighting cable, brand new, 100 yard coil 30/-, post 1/8. **MULTIPLE LT TRANSFORMERS**, pri. 200-220-240v., sec. 30v at 2 amps. tapped at 3-4-5-6-8-9-10-12-15-18-20-24v. Brand new, boxed, 22/6 each, post 1/3.

A copy of our 40-page 1952 catalogue sent free with all orders. Price 6d. on request.

JOHN FARMER (DEPT. A.1.),
194 HARBORNE PARK RD.,
HARBORNE, B'HAM, 17

Tel.: HARborne 1309

WANTED, EXCHANGE, ETC.

TRANSMITTERS, types ET4336, BC610, etc.; valves, type 805, 807, 815, 832, 829B, 55T, etc., urgently required; highest prices paid. PIPE-HAYES RADIO, 606, Kingsbury Rd., Birmingham, 24. Tel. Erdington 4942. [8192

COPPER wire and transformer laminations C. urgently wanted; top prices paid, or similar goods in exchange.—Porchester Electrical, 15-16 Gerrard St., London, W.1. [0211

VALVES, type 805, 807, 815, 832, 100th and 250th, urgently required; good prices paid. Details Pype-Hayes Radio, 606, Kingsbury Rd., Birmingham, 24. Tel. Erdington 4942. [8025

WANTED, R.C.A. speech amplifiers, type MI-11220, J. or K. and Ariel tuning units B.C.939A.—Offers, stating quantity and price to P.C.A. Radio, The Arches, Cambridge Grove, W.6. [0049

WE purchase all types of domestic or ex-Government radio receivers and equipment; send full details or call and collect cash; large or small quantities.—Watson's Wireless Stores, 48, Stafford St., Wolverhampton. [0146

WANTED, B.C.-610 Hallicrafter, R.C.A. ET-4336 transmitter, SX-28, AR-88, S-27, H.R.O. receiver and spare parts for above; best price.—Write, Box 864, c/o Spiers Service, 82, Centurion Rd., Brighton, Sussex. [0061

WANTED, "Wireless World" volumes for 1946 to 1949, "Wireless Engineer" volumes for 1945 to 1948, "Electronic Engineering" volumes for 1945 to 1953, also January to July, 1951; please write stating whether complete with indexes, condition and price to—Librarian, Ferranti, Ltd., Hollinwood, Lancs. [8290

URGENTLY wanted.—VHF test equipment, TS47AP, TS13AP, TS658AP, TS830, TS1287, BC221s and any other types; valves, klystrons, magnetrons 723 AB; receivers, RCA AR88s, S27s, SX28s, 827CA and any late types; microwave equipment or spares; highest prices given; please write, call or telephone Gerrard 9410; prompt attention assured.—Universal Electronics, 27, Lisle St., Leicester Square, London, W.C.2. [0219

NOTICES

BRITISH SOUND RECORDING ASSOCIATION.—MEMBERSHIP of the Association is essential to all actively engaged or keenly interested in high quality sound recording and reproduction; the annual fee is £1 payable and within the reach of all; the 1951-2 lecture season is as usual very successful, and arrangements are also in progress to further increase our activities in the provinces; the publications of the association are extensive and include the journal, "Sound Recording and Reproduction"; full information is given on list P.104, this also includes particulars and prices of our topical and exclusive test records; membership of the association is world-wide and growing rapidly; particulars are given in the new brochure and this, with a membership application form and P.104, may be obtained from the membership secretary—Harrie J. King, 46, Mount View Rd., North Chingford, London, E.4, England. [0119

REPAIRS AND SERVICE

A SCOTTISH winding service.

ALL types of transformers, chokes, field coils, etc., rewound and manufactured to highest standards; write for details:—WILPLO PRODUCTS, 9, Brand St., Glasgow, S.W.1. Tel. No. Ibrox 0140. [7947

MAINS transformers rewound. New transformers to any specification.

MOTOR rewinds and complete overhauls; first-class workmanship, fully guaranteed.

F.M. ELECTRIC Co., Ltd., Potters Bldgs., Warser Gate, Nottingham. Est. 1917. Tel. 54655.

LOUDSPEAKERS repaired promptly.—Modern Loudspeaker Service, 54a, Bullingdon Rd., Oxford. [6919

MAINS transformers rewound or constructed to any specification; prompt delivery.—Bede Transformer Co., Ltd., Bedesway, Bede Trading Estate, Jarrow. [8198

REPAIRS.—E.H.T., mains and O.P. transformers, field coils and chokes; also armatures and motors; new transformers designed to any specification, all work fully guaranteed.—WILLESDEN TRANSFORMER Co., Ltd., 20a, Church Lane, Church Rd., N.W.10. Tel. Willesden 7095. [0076

ELECTRICAL measuring instruments of every make, multi or single range, repaired and standardised; prompt attention.—The Electrical Instrument Repair Service, 529, Kilburn Lane, London, W.9. Tel. Ladbroke 4168. [5715

BERNARD J. BROWN can supply individual designs and constructional data for radio/television/amplifiers kits assembled or built to order; callers only by appointment.—55, Goldhawk Rd., Shepherds Bush, London, W.12. Tel. Riverside 3519. [0217

24-HOUR service, 6 months' guarantee, any transformer rewound, mains outputs and l.t.s., etc.; all types of new transf. etc., supplied to specification; business heading or service card for trade prices.—Majestic Winding Co., 180, Windham Rd., Bournemouth. [6520

A SERVICE with a smile, by F.R.I., great repair and winding service all speakers, osc., r.f., h.f., coils, etc., mains, special, trans and tele. rewinds all armature, fields, electric motor rewinds up to 1hp, engineering, electrical work, send it to F.R.I., they will help; outside television service, London and near; electrical contracting, experimental work.—79, Church Hill Rd., East Barnet. [0112



A WINDOW WORTH LOOKING INTO

Television Coil Formers. With iron dust cores. Polystrene, 1in. x ¼in. with single hole fixing, 6 BA, 6d. each, 5/6 per dozen.

Ex-W.D. A.C. Mains Transformers, 230 volt 50 cycle. Output 4 volt C.T. at 3 amps., 3 times, very useful job, 22/6 each.

Television. EF50 (VR91) Boxed, brand new, 7/6 each.

Television. Diode Holders. 3d. each; Cradle type, 6d. each; Ditto, Polystrene, 8d. each.

Television. Wire-Wound Pots 10k, 20k, 25k, 50k. All at 2/- each.

Television Dural Aerial Masts. Telescopic from 15in.—7ft. 6in. long, ideal for making your own Television Aerial, 4/6 each.

Wavemeters. Ex-W.D. Type W1185, crystal controlled 4 switched bands 20/30 Megs, 30/45 Megs, 45/69 Megs, 68/100 Megs., A.C. mains operated, 200/250 volt 50 cycle, complete with valves and crystal, £14 each.

Micro-Amp Meters, Brand New and Boxed. 0-100, 2½in. Scale 39/6 each.

Special Offer. Condensers 16 x 16 x 16 Mfd. 450 working, brand new, 3/6 each.

Micro Switches. Several types available. Large stocks, please let us have your enquiries.

1000 P.F. Midget Moulded Mica Condensers, wire ends, 6d. each.

Ex-W.D. 2-Valve Battery Amplifiers. Complete with 2-volt driver and Q.P.P. output valve. Brand new. Ideal for mic. or gramophone, 12/6 each, valves alone are worth this.

Bendix Command. 12/14-volt input plug-in type Rotary Transformers, output 250 volts 60 M/a. Very limited number only, 39/6 each.

Moving Coil Headphone Microphone Sets. Ex-W.D., 10/6 per set. Limited number only available.

Rotary Convertors. 24 volt D.C. input, 230 volts A.C. 50 cycle output at 100 watts, 92/6 each.

Welding Transformers. Input 230 volts A.C., output 14 volts 80 amps, 82/6 each.

Midget Wire-Wound Volume Controls. 20 ohm centre tapped, ¼in. diameter, ¼in. spindle, large number available 2/- each.

Chokes. Ex-W.D. 30 Henry 100 M/a., will pass up to 150 M/a., wonderful bargain, 12/6 each.

Chokes. Ex-W.D. 5 Henry 200 M/a., resistance 100 ohms, 5/6 each.

B7G Button Base Holders. With bottom screen, large stocks available, 1/2 each.

Bendix Command Receivers, 6-9 Meg., brand new in sealed boxes, with valves, absolute 100 per cent condition, 89/6 each.

Geared Drives. Ex 1132 receivers, very fine precision job, limited number only 7/6 each.

Don't forget your postage

Open all day Saturday.

G. W. SMITH & CO.
(RADIO) LTD.

3 LISLE STREET, LONDON, W.C.2.

Telephone: GERrard 8204/9155.

"AUTOMAT" HOME CHARGERS, SELENIUM RECTIFIERS, CHARGER KITS

All New Goods with Full Guarantee

"AUTOMAT" HEAVY DUTY HOME CHARGER, for car or radio cells. Virtually non-workable. Selenium rectification. Impregnated transformer of large size. Fine workmanship and appearance. 12 months' guarantee. For A.C. mains only. Standard model 6 v. 1/2 v. 2 amp. output, 8lb. wt., **59 6**. Post 2/-.

ELIMINATOR KIT. Transformer, selenium h.t. rect., 1 h. rect., 2 x 15 mfds. condensers for 100 v. 20-30 mA. eliminator with 1 amp trickle charge, 35/-, or with handsome steel case, **43/-**, post 1/2.

FOOLPROOF CHARGER KITS, standard model, 45 watts trans., triple tapped, large 12 v. 2 amp. selenium rectifier, ballast indicator bulb for 2 v., 6 v., 12 v. charger, simple and foolproof, **38 6**, post 1/-, or with handsome steel case, screws grommets, **52 6**. Dittо kit, but 60 watt trans. and 12 v. 3 amp. rectifier, **46/-**, or with case **58/-**, weight 8 lb., post 1/6 extra. Junior kit, 6 v. 1.5 a. rect., 40 w. trans., ballast bulb case, screws, for 6 v. 1.5 a. charge, **42/-**, wt. 7lb. Senior model, 12 v. 4 amp. H.T.C. rectifier 4in. diam. 70 watt transformer, ballast bulb for 6 v., 12 v. charger, **55/-**, post 1/9, ammeter **12 6** extra (not essential). Heavy duty kit for 5 to 6 amp., 6 v./12 v. 100 watt trans. large finned 6 a. rect., slider resistance, ammeter flush type, **64 10/-**, post 2/-. 24 v. trickle rectifier, 2 amp., with high-grade layer wound transformer, **12 6**.

SELENIUM RECTIFIERS. New stock not surplus. 12/15 v. 2 amp. **15 6**, 6 v. 2 amp. **9/-**, post 9d. 12 v. 1 amp. half wave, **9/-**; 12 v. 3 amp., **16 6**, post 9d., 6 v. 4 amp., **18 6**; 12/15 v. 3 amp., **27/-**, post 9d. Giant finned type, 12 v. 6 amp., **35/-**, post 1/3; 24 v. 4 amp., **54 6**; 24 v. 6 amp., **67/-**; 24 v. 2 amp., **29 6**. Small space H.T. rectifiers, selenium, 200 v. 60 m.a., **7 6**, 110 v./150 v. 60 m.a., **6 6**; 250 v. 100 m.a. bridge, **14 6**. All 6d. extra postage. 250 v. 200 m/a. bridge or half-wave (4 units), **22 6**.

"RENEWBAT" battery desulphator and conditioner **1 9**, post 3d. Car size, 3/-, post 4d.

CHAMPION PRODUCTS

43 Uplands Way, London, N 21. Phone LAB 4687

WILCO ELECTRONICS

CATHODE RAY TUBE, No. 3 BPI. New 3" tubes with shield and holder; useful for building oscilloscope, etc., **35/-**, post 1/6.

TWIN P.A. LOUDSPEAKERS. Reflex re-entrant type, very sensitive and directional, 8in. diam., 16in. overall. Brand new with matching transformers 4 5 to 1 and 6 to 1 Ratios. Voice coil 7 ohms. Only **75/-**. Case & Pkg. 5/-.

POWER MICROPHONE INSERTS. Tannoy self-energising, carbon, which can be used directly with a microphone transformer requiring no external voltage. Diam. 2¼in. x 1in. **5/-** each. Post 6d.

THROAT MICROPHONES. American twin button type with strap lead and plug. **5/-** each. Post 6d.

HEAD SET ADAPTOR, MC38S. High to low impedance. **2 6** each. Post 6d.

RESISTANCE MATS.—Make ideal heating mats for Aquariums, Photographic solutions, Print dryers, etc. Mains voltage. Black Heat, size 10in. x 6in. Price **2 6**, post free.

B.T.H. 16 mm. TALKIE PROJECTORS. Complete. Model S.R.B. also spares.

SLOW-MOTION DIALS, 6in. Scaled 0-100, reduction 200 to 1 or direct, ideal for wavemeters, signal generators, etc. Our price, while they last, **5 6** each, post 1/-.

"ELF" CIRCUIT BREAKER, 220 volts 2 amps., size 3 inches round, **10 6**, post 1/-.

CUTTER HEADS. "Recording" high impedance. Amazing bargain, **55/-** ea. Post 1/-.

CUTTERS STYLII, **6/-** per doz., large quantity available at special rates.

ACFIL PUMPS. These pumps enable you to fill all accumulators on the bench with the carboy at floor level. Brand new, only **30/-**, post 1/6.

VOLTMETERS. 0-300 M.I. 3½in. flush or surface type, **22 6**. Post 1/6.

AERIAL RODS. 12in. long, ¼in. diameter. Any number of sections can be fitted together **2 6** dozen; **6/-** for 3 dozen; **11/-** half gross; **20/-** gross; **£6** per 1,000.

204 LOWER ADDISCOMBE ROAD, CROYDON.

MISCELLANEOUS

WORLDS." '49 to '51 complete, in good condition; offers.—Box 7428. [0297]

METALWORK; all types cabinets, chassis, racks, etc., to your own specifications.—PHILPOTTS METAL WORKS, Ltd., (G4BI), Chapman St., Loughborough. [0208]

WALNUT radiogram cabinets, stamp leaflets.—Cabinetware, 1a, Heyes St., Blackburn.

FOR sale, 46, 44, 38 swg enamelled copper wire.—Champion, 45, Uplands Way, N.21. Lab. 4457. [0102]

WALNUT radiogram cabinets, stamp details.—E. Wisker, 501, Hale End Rd., Highams Park, E.4. [0302]

40 lb. 26 s.w.g. enamel silk wire for sale.—Bel Sound Products, Marlborough Yard, London, N.19. Arc. 5078. [0190]

WALNUT radiogram and television cabinets, soundly constructed, stamp details.—R. Shaw, 69, Fairlop Rd., Leytonstone, E.11.

TV cabinets, baffles, consoles, etc., to your own design requirements and finish; no enquiry too small or too large.—Write or 'phone, Ashdown, 98, Hertford Rd., N.9. Tot. 2621.

ENGRAVING.—On all metals and plastics, name plates, panels, dials, instruction panels, advertising novelties, etc., etc.; trade enquiries invited.—E. S. Reddish, 17, Standard St., New Kent Rd., S.E.1. Hop. 0505. [7990]

ENGRAVING, amateurs and trade could take the opportunity of engraving problems in the future by getting in touch with A.G. Engraving, 15a, Windmill Rd., London, S.W.18. Brass, bronze, ermoid, Perspex dials, one knob or reputation equally entertained. [0034]

ALLSCREWS, Ltd., for B.A. screws, nuts, washers, studding, grub-screws, bolts, soldering tags, woodscrews, etc., plain or nickel or cadmium plated, one-gross packets or large quantities.—Enfield 2706. King St., Hammersmith, W.6. Riv. 7762. [5426]

COPPER wires enamelled, tinned, Litz, cotton, silk covered, all gauges; B.A. screws, nuts, washers, sockets, eyelets, ebonite and laminated bakelite panels, tubes, coil formers, Tufnol rod; headphones, flexes, etc.; latest radio publications, full range available; list, s.a.e.; trade supplied.—Post Radio Supplies, 33, Burnt Oak Gardens, London, E.4. [0158]

TV-1118, a complaint suffered by many who have no black screen; our conversion kit will change your ordinary television set into a black screen set from 9/6, post free; will fit any size of set from 12in tube downwards; no suckers, no screws, no glue, and can be removed and replaced at any time; trade enquiries invited. Unit Light Manufacturing Co., 19, Queen Street, Hackpool. [0221]

FLUORESCENT 80w ballast units, Gow starter, tested ready for use, less 5ft tube, 42/6; battery chargers, 6 or 12v at 5amp, state type, 47/6; dry cell boosters charger, all types, cell or battery, up to 5v, 14/6; large size 12v 5amp metal rectifiers, full-wave; trade supplied; three 2kva constantly variable transformers, give any voltage from 0 to 250v at 4amp, £25; bench grinders, 1ahp 2,800 rpm, 4in stone, 59/6; all about for 250v a.c.—Maiden Transformer Supplies, 200, Cambridge Rd., Kingston-on-Thames. [0058]

SITUATIONS VACANT

The engagement of persons answering these advertisements must be made through the local office of the Ministry of Labour and National Service, etc., if the applicant is a man aged 18-64 or a woman aged 18-59 inclusive, unless he or she or the employer is excepted from the provisions of The Notification of Vacancies Order 1952.

ADMIRALTY.

APPLICATIONS are invited from engineering, electrical and ship draughtsmen for temporary service in Admiralty Departments at Bath. CANDIDATES must be British subjects of 21 years of age and upwards, who have had practical workshop and drawing office experience. SALARY will be assessed according to age, qualifications and experience within the range £320-£545 per annum.

APPLICATIONS, giving age and details of technical qualifications, apprenticeship (or equivalents), workshop and drawing office experience, should be sent to Admiralty (C.E. 11, Room 88), Empire Hotel, Bath. Candidates required for interview will be advised within two weeks of receipt of application. [6952

SUDAN Government.

THE Meteorological Service requires an electronics technician; the duties are to maintain and assist in the operation of the radar and other radio equipment of a radio-sonde/radar-wind station in Khartoum; if necessary a familiarisation course on the particular type of equipment used (Kew pattern radio-sonde and G.L.III radar) will be arranged.

APPOINTMENT will be on probation for (a) secondment from the British Government for five years, or (b) short term contract (with bonus) up to six years; salary applicable to (a) £E600 to £E1,120, and for (b) £E700 to £E1,400, starting rate would be determined according to age qualifications and experience, a varying cost of living allowance is at present payable subject to quarterly review; outfit allowance of £E50 is payable when the contract is signed; there is at present no income tax in the Sudan; free passage on appointment. FURTHER information and application form will be sent on receipt of a postcard only addressed to The Sudan Agent in London, Wellington House, Buckingham Gate, London, S.W.1, quoting "Electronics Technician 4/1710" and name and address in block letters. [6291

NEW S.T.C. SELENIUM RECTIFIERS. Largest L.T. range in Great Britain. Current products. NOT SURPLUS. E.H.T. N2 100 17-; for "W.W." Televisor, for VR97 N2 50, 12-; post 6d. PRIORITY ORDERS ONLY.

PLUS 15% ON ALL THESE PRICES

HALF WAVE HEAVY DUTY 7½in. SQUARE COOLING FINS, 16 v. 5 a., **26-**; 10 a., **29-**; 16 a. **53-**; 30 v. 5 a., **41 6**; 8 a., **47-**; 48 v. 2.5 a., **31-**; 5 a. **56-**; 8 a. **65-**; all post 1/-.

BRIDGE CONNECTED FULL WAVE. 17 v. 1.25 a., **14 2**; 1.7 a., **22 9**; 2.5 a., **25-**; 3 a., **26-**; 4 a., **30-**; 5 a., **32 6**; all post free. 33 v. 0.7 a., **21-**; 1 a., **24 3**; 1.5 a., **39-**; 2 a., **44-**; 3 a., **45-**; 4 a., **54-**; 5 a., **58-**; all post 11d. 54 v. 1 a., **33 6**; 1.5 a., **54/-**; 2 a., **60-**; 3 a., **61-**; 5 a., **81-**; 72 v. 1.5 a., **68-**; 2 a., **79-**; 3 a., **80-**; 5 a., **106-**; 100 v. 1.5 a., **97-**; 2 a., **112-**; 5 a., **152-**; all post 1/1.

BRIDGE CONNECTED HEAVY DUTY 7½in. SQUARE COOLING FINS. 17 v. 6 a., **43-**; 10 a., **49-**; post 1/6.

BRIDGE CONNECTED HEAVY DUTY Funnel Cooled, also **7½in. SQUARE COOLING FINS.** Revised price, same both types. 17 v. 12 a., **88-**; 20 a., **102-**; 30 a., **142-**; 50 a., **£11**; 33 v. 6 a., **79-**; 10 a., **91-**; 12 a., **146-**; 20 a., **164-**; 54 v. 6 a., **104-**; 10 a., **124-**; 72 v. 6a., **134-**; 10 a. **154-**; 100 v. 6 a., **192-**; 10 a. **£11**; all post 1/8.

SOME G.E.C. & "WESTINGHOUSE" RECTS. NOW STOCKED.

VERY SLOW DELIVERY OF MANY RECTS. WILL DO OUR BEST! HOSPITALS, RESEARCH LABS. AND GOVERNMENT CONTRACTS GIVEN PRIORITY.

Wholesale & Retail

T. W. PEARCE (Est. 20 Yrs.)

98 GREAT PERCY STREET, LONDON, W.C.1

Off Pentonville Rd. Between King's Cross and Angel



THE 'FLUXITE" QUINS AT WORK

"Our T.V. light is almost done.
So I borrowed your headlamp old son.
With the aid of FLUXITE
It's a much better light.
I'd a tee if the Arsenal's won."

See that **FLUXITE** is always by you—in the house—garage—workshop—wherever speedy soldering is needed. Used for over 40 years in Government works and by leading engineers and manufacturers. Of all Ironmongers—in tins from 1/-.

TO CYCLISTS! For stronger wheels that will remain round and true, here's a time tested tip. Tie the spokes where they cross with fine wire AND SOLDER. It's simple—with FLUXITE—but IMPORTANT.

The **FLUXITE GUN** puts **FLUXITE** where you want it by simple pressure. Price 2 6, or filled 3/6.

FLUXITE

SIMPLIFIES *ALL* SOLDERING

Write for Book on the Art of "SOFT" soldering and for leaflet on CASE-HARDENING STEEL, and TEMPERING TOOLS with FLUXITE. Price 1½d. ea.

FLUXITE LTD. (Dept. WW), BERMONDSEY STREET, LONDON, S.E.1.

Come to Classic for

"The Classic Service"

We will ship to any part of the British Isles or Abroad.

All goods advertised are available from Stock at time of going to Press.

AMPLIFIERS AND HI-FI EQUIPMENT

Leak T.12 with Control Unit	£37	16	0
Williamson (Goodsell)	£40	15	0
Quad with Control Unit	£35	0	0
Sound Sales A.Z.	£32	10	0
Quad Radio Feeder Unit	£26	10	0
Leak Radio Feeder Unit	£37	2	4
Chapman Radio Feeder Unit	£17	12	6

PICKUPS AND PICKUP HEADS

Acos GP.20 Standard Head	£3	11	5
Acos Heads, Standard or L.P.	£2	3	4
Brierley pickup and diamond stylus	£8	12	0
Collaro pickup arm	£1	7	6
Collaro crystal dual purpose head	£3	3	3
Collaro Magnetic head	£2	6	0
Decca pickup arm	£1	7	6
Decca Magnetic head	£2	19	2
Garrard pickup with magnetic head	£3	0	1
Leak pickup with ruby stylus	£11	17	6
Leak pickup with diamond stylus	£18	19	6
Connoisseur Super Lightweight P/up	£7	9	0

MOTORS AND AUTO CHANGERS

Connoisseur 2-speed motor	£22	18	8
Connoisseur 2-sp. motor with pickup	£29	7	8
Plessey Auto changer 8-rcd. 3-spd.	£23	13	0
Collaro 3-speed 8 record	£13	10	0
Collaro Single speed S.P.	£6	16	6
Decca 2-speed Motor and pickup	£9	19	6
Decca Deccalian	£37	10	0
Trix Autogram (Garrard RC80)	£44	0	0
Chancery Long Playing attachment	£3	12	6

SPEAKERS AND UNITS

Goodmans Audiom 60, 12in. unit	£8	12	6
Goodmans Axiom 150, 12in. unit	£10	5	6
Decca Corner 3 or 15 ohm	£21	10	0
W.B. 10in. or 12in. units, from	£7	7	6
Wharfedale Units from	£4	14	7
Acoustical Corner Ribbon	£83	0	0
Decca Hi-fi Cabinet Speakers	£105	0	0

TAPE RECORDING EQUIPMENT

Simon Simphonic Model 2B	£69	10	0
Sound Mirror, table	£69	10	0
Sound Mirror, Portable	£79	10	0
R.G.D. Portable	£99	0	0
Bradmaster Tape Desks	£42	10	0
Microphones, Acos, from	£6	16	6
Tapes, Scotch Boy, GEC, EMI, from	£1	5	0
Bradmatic Heads 6RP	£3	15	0
Bradmatic Heads 5RP	£3	5	0

COMPONENTS AND PARTS

Viewmaster television receiver	£29	10	0
Mullard C.R. Tubes, 9in., 12in., 17in. from stock.			
Mullard Valves, full range available.			

Viewmaster enthusiasts in Northern and Scottish districts send for details of our special H.P. facilities. Wenvoe supplies soon available.

All Prices quoted are Retail Prices including Tax.

Goods despatched by Post or Passenger train. Please include carriage.

EXPORT ENQUIRIES WELCOMED. Goods for shipment free of Purchase Tax. Packing and Insurance extra. Send Stamps for List.

The Classic Electrical Co. Ltd.

"THE HI-FI TELEVISION SPECIALISTS"

352/364 Lower Addiscombe Road, Croydon, Surrey. *Telephone: Addiscombe 6061/2.*

SITUATIONS VACANT

NORTHERN POLYTECHNIC, LONDON, N.7.
THE governing body invite immediate applications for appointment as full-time lecturer in telecommunications engineering for the three-year full-time course in preparation for the full technological certificate of the City & Guilds of London Institute in Telecommunications engineering; a knowledge of radar and television engineering is desirable; salary scale £900 × £25–£1,000, plus London allowance; form of application, together with full particulars, will be forwarded on receipt of a stamped, addressed foolscap envelope.
R. H. CURRELL,
Clerk.
18272

SUPPLEMENTARY RESERVE.
VOLUNTEERS who are specialist or technicians are invited to join this Reserve, which provides the skilled men the Army needs on mobilisation. WIRELESS and Line operators, draughtsmen, despatch riders and radio and line mechanics are among the tradesmen needed. Ex-N.C.O.s of the Royal Signals especially required. No liability for evening drills or week-end training. Maximum training liability is annual 15-day camp with Regular Army rates of pay. Annual bounty in addition. By joining the S.R. a man will play a vital part in the defence of this country and will ensure that his skill is used in the event of war.—Details from any Recruiting Office or the War Office (A.G.10/SRC2), London, S.W.1.
18221

CROWN Agents for the Colonies.
WIRELESS station superintendent required by the Government of Nigeria for the Posts and Telegraphs Department for one tour of 18 to 24 months in the first instance with prospect of permanency; salary (including allowance) between £711 and £1,042 a year according to qualifications and experience; outfit allowance £60; free passages for officer and wife and assistance towards cost of children's passage or their maintenance in this country; liberal leave on full salary; candidates (under 40 years) must have had wide practical experience of modern radio techniques and equipment, in particular V.H.F. equipment and preferably also V.H.F. multi-channel equipment; apply at once by letter, stating age, full names in block letters and full particulars of qualifications and experience and mentioning this paper to—The Crown Agents for the Colonies, 4, Millbank, London, S.W.1, quoting on letter M.28927/B. The Crown Agents cannot undertake to acknowledge all applications and will communicate only with applicants selected for further consideration.
18288

THE ROYAL NEW ZEALAND NAVY.
TELEGRAPHISTS and Signalmen. The R.N.Z.N. wants ex-R.N., P.O. and Leading Telegraphists, Yeomen of Signals, Leading Signalmen, Signalmen and Radio Electricians/Mates 1st Class for minimum 6-year engagements. Age limit 40. Those accepted retain original R.N. rating and seniority. Excellent chances of promotion. High pay (married P.O. gets 40/3—45/3 a day tax-free). Generous superannuation or gratuity. Full pay from day of leaving U.K. Passage paid. Families follow passage free when accommodation found. Social service benefits, free education and 10/- a week family allowance for every child on arrival in N.Z.—Write now for particulars to: Dept. 80, Royal New Zealand Navy Headquarters, The Adelphi, John Adam St., London, W.C.2.

ELECTRONIC laboratory assistants required. APPLY Employment Manager, Vickers-Armstrongs Ltd. (Aircraft Section), Weybridge, Surrey.
18201

KINGSTON UPON HULL Education Authority.
MUNICIPAL Technical College.
REQUIRED as soon as possible for appointment to the Kingston upon Hull Municipal Technical College, teacher, assistant, grade A, for radio engineering (theoretical and practical) for P.M.G. Certificate and C.G.L.I. Telecommunication courses; applicants should possess a P.M.G. Certificate in Radio Telegraphy (First Class) or similar qualifications; preference will be given to applicants with knowledge and experience of marine radar.
SALARY: Burnham Technical Scale 1951—£375 × £18—£630 per annum; the scale provides for the payment of increments in respect of suitable teaching and/or industrial experience, plus additions for training and/or graduate qualifications.
FURTHER particulars and application forms, to be returned within fourteen days of the date of this issue, will be sent by the Director of Education, Guildhall, Kingston upon Hull, on receipt of stamped addressed foolscap envelope.
18248

SOBELL INDUSTRIES, Ltd., Hirwaun, South Wales, require:—
1.—Mechanical designer draughtsmen.
2.—Radio television development engineers.
WRITE stating qualifications, experience and salary required to Personnel Dept.
18194

RADIO engineer required, some television experience, aircraft radio systems.
APPLY Employment Manager, Vickers-Armstrong, Ltd., (Aircraft Section), Weybridge, Surrey.
18200

THE DE HAVILLAND AIRCRAFT Co., Ltd., require a junior radio engineer with current M.C.A. Air Licence required for aircraft installation testing and flying duties.
WRITE, stating experience and salary required, to the Personnel Manager, The de Havilland Aircraft Co., Ltd., Airspeed Division, Christchurch, Hants.
18219

THE LATEST

A New Line Transformer capable of fully scanning any Tube from 9in. up to 16in. (Double D) Scan at 16 Kv.



Frame Transformer, Focus Coil, Deflector Coil, Linearity and Width controls are available for wide angle tubes.

Full details on request. Please send S.A.E.

"Electronic Engineering"—
Focus Coil
Deflector Coils
Line Output Transformer

"Viewmaster"—
Deflector Coils
E.H.T. Transformer

I.F. TRANSFORMERS
Iron Core
Tuned 472Kc. Per pair 15/-

ALLEN COMPONENTS LTD

CROWN WORKS, 197, LOWER RICHMOND ROAD, RICHMOND, SURREY

'Phone: Prospect 4463

SOUTHERN RADIO'S WIRELESS BARGAINS

WALKIE-TALKIE (TRANSMITTER-RECEIVER). Type 38 Mark II. Complete with 5 valves, Throat Microphone, Headphones and Aerial. 7mc/s Amateur Band suitable for field use. Powerful Superhet Receiver. Modulated Transmitter. Guaranteed ready for the Air, less batteries. £4/12/6.

R.3515 TELEVISION UNITS. Complete with 21 valves. 6 Stage 14 mc/s I.F. Strip. Ideal for T.V. Conversion. Brand new in original wooden cases. £3/10/-. Carriage 7/6.

G.E.C. "MINISCOPE" M861B. MINIATURE CATHODE RAY OSCILLOSCOPES 1½" Tube. Time Base, etc., etc. Brand New in Makers Sealed Cartons with Leatherette Carrying Case—£15 10 0 plus 5/- carriage.

LUFBRA HOLE CUTTERS. Adjustable from ⅜in. to 3½in. for use on Wood, Metal, Plastic, etc., 5/9. LUFBRA FLY CUTTERS, 14/6.

LIONEL "BUG" KEYS. Genuine U.S.A. Automatic Morse Key, Type J36. Few only, £3/7/6.

THROAT MICROPHONES. Magnetic type complete with long lead and plug, 4/6.

2-POLE A.C. MOTORS. 110 volts to 240 volts 50 cycles, 2,740 r.p.m. Suitable for Magnetic Tape Recording. Size 4in. x 2¾in. x 3in.—30/-.

PLASTIC TRANSPARENT MAP CASES, 14 inches by 10½ inches. Ideal for Maps, Charts, Display, Photographs, etc., 5/6.

STAR IDENTIFIERS. With Hydrographic Office Modifications A-N Type I. Complete in case, 5/6.

WESTECTORS. Type WX6 and W112, 1/- ea., 11/- doz.

MARCONI AERIAL FILTER UNITS. Type "916" in conformity with P.O. Specification. Full instructions for fixing, 4/-.

CONTACTOR TIME SWITCHES. 10-hour movement, 2 impulses per second. Thermostatic Control in soundproof Cases, 11/6.

VISUAL INDICATOR UNIT Type 3 (10Q/4). Contains two Moving Coil movements, two Neons, etc. Easily convertible to very efficient M.C. Meters, 11/-. Conversion fully described in "W.W." Sept. 1951.

Full list of Radio Publications, 2½d.

SOUTHERN RADIO SUPPLY LTD.,
11, LITTLE NEWPORT STREET, LONDON W.C.2. *GERrard 6653.*

They're worth waiting for...

A lot more people than ever before have been ordering a lot more Savage Transformers than ever before. This, and the shortages of raw materials are extending deliveries more than somewhat. As one of our Welsh customers said, however, "Savage Transformers are worth waiting for."

SAVAGE TRANSFORMERS LIMITED DEVIZES

SAVAGE TRANSFORMERS LTD.
Nursteed Road, Devizes, Wilts.
Telephone: Devizes 536

SITUATIONS VACANT

WANTED, radio engineer with M.C.A. licence. Apply Skyways, Ltd., Liverpool Airport. [8235]

RADIO engineer required, some television experience necessary; country town near Newmarket.—Box 7502. [8251]

FERRANTI, Ltd., Moston Works, Manchester, have staff vacancies for circuit development work associated with a long-term telecontrol project.

VACANCIES exist in the senior engineer, engineer and technical assistant grades, salaries according to age and experience, for engineers and senior engineers, within the range £500 to £1,200 p.a., and for technical assistants between £400 and £600 p.a.; applicants should have a degree in physics or engineering, higher national certificate, or its equivalent.

THE company has a staff pension scheme.

APPLICATION forms may be obtained from Mr. R. J. Hebbert, Staff Manager, Ferranti, Ltd., Hollinwood, Lancs. Please quote reference N.H.S. [8249]

A SKILLED television and radio service engineer required to take charge of dept.—Apply H. Payne (Cov), Ltd., 11, Ford St., Coventry. [8180]

AMPLIFIERS, quality. — Sales assistant (counter) required with practical knowledge.—Berry's (Short Wave), Ltd., 25, High Holborn, W.C.1. [8238]

MAGNETIC Tape Recording.—Counter sales assistant required with practical knowledge.—Berry's (Short Wave), Ltd., 25, High Holborn, W.C.1. [8239]

TELEVISION/RADIO engineers (drivers), please state age, experience and salary required.—W. J. Elliott, Ltd., Howardsgate, Welwyn Garden City, Herts. [8237]

QUALIFIED aerial erector for guyed poles up to 100ft; must hold current driving licence.—Write, giving full details of past experience and salary required, to Box 7275. [8181]

GUIDED weapon projects at the Research and Development Armament Division of the Fairey Aviation Company, Ltd., offer work of exceptional interest and opportunity to the following:—

ELECTRONIC engineers experienced in microwave, pulse or communication techniques; there are both senior and junior vacancies and although a degree or equivalent is normally required, applicants who lack such a qualification but who have considerable experience will also be considered.

A SENIOR electro-mechanical engineer for servo-mechanism analysis and automatic control design, electro mechanical, hydraulic or pneumatic.

ACCOMMODATION assistance will be given in selected cases, pension scheme, good salaries. British born applicants wishing to be interviewed should send full details to:—The Manager, Dept. W., The Fairey Aviation Company, Ltd., Research & Armament Development Division, Heston Aerodrome, Hounslow, Middlesex. [8296]

MURPHY RADIO, Ltd., offer the following vacancies in an expanding programme covering the field of domestic equipment and many branches of electronic development.—

(1) SENIOR development engineers having degrees in engineering or physics with post-graduate experience of equipment design who would be capable of leading a development team.

(2) DEVELOPMENT engineers with similar academic qualifications having less or no industrial experience.

(3) A SPECIALIST engineer with good academic qualifications having a sound knowledge of components and raw materials used in the radio industry; this vacancy is only suitable for an applicant who is experienced in electrical measurements and life testing of components.

THESE posts are permanent and pensionable and offer good opportunities for advancement.—Applications giving full details of experience and qualifications should be forwarded to the Personnel Manager, Murphy Radio, Ltd., Welwyn Garden City. [8050

E. K. COLE, Ltd. (Malmesbury Division), invite applications from electronic engineers for permanent posts in development laboratories, engaged on long-term projects involving the following techniques:—

1. Pulse Generations & Transmission.
2. Servo Mechanisms.
3. Centimetric & V.H.F. Systems.
4. Video & Feedback Amplifiers.
5. V.H.F. Transmission & Reception.
6. Electronics as applied to Atomic Physics.

THERE are vacancies in the senior engineer, engineer and junior grades. Candidates should have had at least three years' industrial experience in the above types of work, together with educational qualifications equivalent to A.M.I.E.E. examination standard. Commencing salary and status will be commensurate with qualifications and experience. Excellent opportunities for advancement are offered with entry into Pension Scheme after a period of service. Forms of application may be obtained from Personnel Manager, Ekco Works, Malmesbury, Wilts. [7922

TELEVISION engineers required by E. London firm with all leading agencies; applicants should have extensive experience and initiative; and will work with 1st class team of engineers; salary according to ability.—Apply to "LB," Leytonia Radio, 628, High Rd., Leyton, E.10. [8022

RADIO/television engineer, experienced, preferably able to drive, permanent and progressive position to suitable applicant; write full details and salary expected to—Ewell Court Electrical, Ltd., 197, Kingston Rd., Ewell, Surrey. [8252]

GENERAL LAMINATION PRODUCTS LTD.

1942 — 1952

TEN YEARS MANUFACTURING TRANSFORMERS, SOUND AMPLIFIERS, RECORDERS

The sign of "G.L." regularly appearing in this journal until 1949.

In 1948 we introduced the Sound Magnet Tape Recorder, resulting in the curtailment of many other lines.

NOW—1952, with a larger factory, increased facilities will enable us to revive many of our former popular productions.

1. **The G.L. "Sound Magnet"** Tape Recorder ..... **48 gns.**
2. **GL/PP/12,** 4 v. Push-Pull Gramo., port ..... **9 gns.**
3. **GL/GP/15,** 5 v. General Purpose, P.A. ..... **11 gns.**
4. **GL/HQ** "Hi-Fi" Gramo. Amplifier, designed on the "Williamson" ..... **14 gns.**
5. **GL/SE/TR,** Magnetic Recorder Amp. ..... **10 gns.**
6. **GL/DT/TR,** de Luxe Recorder Amp. ..... **19 gns.**
7. **GL/HZ,** Fidelity Sound Heads **37/6**
8. **GL/E,** Erase Heads **37/6**
9. **GL/O,** Recording Oscillator Unit **60/-**
10. **Complete range transformers.**

Here are ten items selected from our 1952 range of G.L. Products. Send 2½d. stamp for new lists. Write us your requirements.

G. L. PRODUCTS LTD.
"Sound Magnet" Works,
62 PLUMSTEAD HIGH ST., LONDON, S.E.18.

CABINETS & CHASSIS

A.C. 5 valve 3 W/B Superhet Radiogram chassis. Absolutely complete kit of parts including detailed wiring diagram **£10 15 0**
Or fully wired and tested **£12 10 0**

CABINETS OF DISTINCTION

Send 6d. for our new illustrated cabinet catalogue.

AMPLIFIERS:

4 to 15 watts ..... from **£3 19 6**

Full details from:—

LEWIS RADIO CO.
(Dept. 452)
32 HIGH RD., WOOD GREEN, LONDON, N.22.

Callers to:—
120 GREEN LANES, PALMERS GREEN LONDON, N.13
(near Bowes Road)
Phone: Bowes Park 6064

ALPHA OFFERS

FOCUS UNITS. Latest types. R20 and R25, 19/6 each.

YAXLEY SWITCHES. 2-pole change over, 1/- each. 1 pole 6-way 3-bank, 1/6 each. 3-pole 3-bank 3-way, 1/6 each.

CHOKES. Small type, 6h. 50 mA., 5/- each. Midget, 15 h. 5 mA., resistance 3,700Ω, with tap at 1,800Ω, 2/6 each.
Midget pitch dipped, 1 h. 500 mA., 15Ω, 2/- each.

WIRE WOUND VOLUME CONTROLS 5kΩ, 200Ω, 1kΩ, 5kΩ, 10kΩ, 15kΩ, 20kΩ, 25kΩ, 35kΩ, 2/9 each.

CARBON TYPE VOLUME CONTROLS 500Ω, 1kΩ, 2kΩ, 5kΩ, 10kΩ, 20kΩ, 25kΩ, 100kΩ, 1/- each.

SPECIAL PURPOSE VALVES. Side contact RF Pentode, VR123, 7/- each. 954, 2/9; 955, 5/-; 956, 2/9. VR136 (EF54), 6/-; VU111, 4/6; CV54, 3/-; EI148, 2/-; CV6, 2/-; VR116, 4/-.

SWITCHES. Standard Slotted Dolly, S.P.S.T., 1/- each. Hoover Vacuum Cleaner, replacement type, 1/6 each. 5 amp. panel mounting, 2-hole fixing, S.P., 2/- each.

TRIMMERS. Midget ceramic 200/200 2-bank, 10d. each; 3/10 PF Philips type, 10d. each; 3/30 PF, Philips type, 10d. each.

KNOBS. 1¼in. dia. for ¼in. spindle, black or brown, fluted grip, 6/- doz. As above, 1¼in., 6/6 doz. Black pointer knob, 7/6 doz.

CONDENSERS. 1 mfd. 500 v., block type, 3d. each; 8 mfd. 500 v., electrolytic, 1/11 each; 16 mfd. 175 v. electrolytic, 1/- each.

TELEPHONE WIRE. Plastic covered stranded 6 steel 1 copper, colour green, 1,000 yds. 20/-.

BRIDGE RECTIFIERS. 12 volts ½ amp., 1/- each; 36 volts 45 mA., 1/- each.

INSULATED SLEEVING. Bright colours, 1 mm., 2 mm., 3 mm., 4 mm., 1/- doz. yds.; 5 mm., 6 mm., 8 mm., 10 mm., 1/6 doz. yds.

VALVE HOLDERS. Ex equipment but perfect. Ceramic British 7-pin, 9d. each; 89G (EF50) ceramic with screw retainer, 10d. each.

BULLDOG CLIPS. Instrument type, 1¼in. long, 4/6 doz.; battery charger type, 3in. long, ¾in. jaws, 7/6 doz.

VALVE HOLDERS. AMPHENOL TYPES. International octal, 7/- doz.; Mazda octal, 4/- doz.; B7G with base screen, 10/- doz.; UX 5-pin, 2/6 doz.; British 5-pin 5/- doz.

PAXOLIN TYPES. International octal, British 5- and 7-pin, all 5/- doz.; British 4-pin, 2/6 doz.

TRANSFORMERS. Pentode output, 3/11; class "B" driver, 3/11; class "B" output, 3/11; Q.P.P. output, 3/11. Small battery intervalve, 2/9. Filament 210/240, 6.3 v. 1.5 amps., 8/6 each.

WAX TUBULAR CONDENSERS. Wire ends, .1 mfd. 500 v., .02 mfd. 1,000 v., .002 mfd. 400 v., .5 mfd. 450 v., .25 mfd. 1,000 v., .001 mfd. 350 v., .005 mfd. 350 v., all 4/- doz.

PANELS. All ex brand new equipment at unbeatable value. Panel No. 1 contains 6 .01 mfd. 600 v. condensers and sundry other resistors and condensers, 3/- each. Panel No. 2, 15 resistors, some wire wound, 1/11 each. Panel No. 3, 36 mixed resistors and condensers, 2/6. Also dozens of small types from 4d. each. Send for a 10/- selection or order separately if you wish.

RESISTORS. 1 watt carbon, 350Ω, 30kΩ, 33kΩ, 47kΩ, 1kΩ, 10kΩ, 100kΩ, 6d. each. ½ watt carbon: 1 megΩ, ¼ megΩ, 20kΩ, 25kΩ, 200kΩ, 4½d. each. 2 watt carbon: 150kΩ, 8d. each. 5 watt carbon: ¼ megΩ, 9d. each

TERMS. Cash with order or C.O.D. List 3d. stamps.

MAIL ORDER ONLY. Please include postage: 6d. under 10/-, 1/- under 20/-, 1/6 under 40/-.

ALPHA RADIO SUPPLY CO.

5/6 Vinces Chas., Victoria Square, LEEDS 1

SITUATIONS VACANT

TELEVISION engineer, experience and competence on leading makes essential, permanent position, high salary, no overtime able to drive, East London area.—Box 7286. [8202

RADIO service engineer with knowledge of public address equipment urgently required for Middle East.—Write full particulars, Magneta Time Co., Ltd., 6, Gt. Queen St., London, W.C.2. [8195

WEST END dealer, associated with leading firm of car distributors, require experienced television and radio engineer to handle all types of servicing and to drive company's van; no Saturdays.—Box 7288. [8207

DRAUGHTSMEN—senior and junior electro-mechanical and circuit draughtsmen required for work on electronic computing apparatus, pension scheme, canteen.—Apply Head of Communications Laboratory, FERRANTI, LTD., Bromhall Rd., Wandsworth, S.W.18. [8206

MULLARD Research Laboratory in Surrey has a number of vacancies suitable for honours graduates in Physics, Electrical Engineering, Mathematics, or for persons with other but similar qualifications for work on:—
1. LINE Communications.
2. RADIO Communications.
3. RADAR.
4. COMPUTORS.
5. ELECTRONIC Measurement and Control Devices.
6. METAL Physics.
7. ELECTRON Accelerators.
8. TELEVISION.
9. ULTRASONICS.
PREVIOUS experience in one or more of these fields is an advantage, but is not essential, and equal significence is attached to the candidate's potential ability to apply himself to such work. IN addition to these posts there are a number for which several years' experience in addition to academic qualifications is essential:—
1. DEVELOPMENT of carrier systems and filter design.
2. COMMUNICATION receiver and transmitter design.
3. RESEARCH and development associated with television reception.
RATES of pay are proportional to qualifications, experience and age. Publication of original work wherever possible is desirable and is encouraged. Successful candidates are eligible for the superannuation scheme.
APPLICATIONS should be made in the first case to the Personnel Officer, Mullard Research Laboratory, Redhill, Surrey. [8148

AIRLINE requires ground radio operators for U.K. bases. pmg or equiv. licence, plus experience air-ground and point-to-point R.T. W.T necessary, good technical and radio maint. ability, age limit 40, single men only.—Write Box 7348. [8278

TELEVISION engineer required, experience in fault diagnosis, capable of using modern test equipment, circuit alignment by visual methods, etc., salary £400-500 p.a.; situation Reading.—Apply Box 779, Granthams Advertising, Reading. [8265

DRAUGHTSMEN senior and junior required, experience in electronics and light electrical engineering an advantage.—Apply by letter, stating age, nationality and experience to E.M.I. Engineering Development, Ltd., Penleigh Works, Wells, Somerset. [8125

SENIOR design draughtsman required by manufacturers of electrical and electronic equipment; a thorough knowledge of materials and production methods is essential; the salary will be commensurate with qualifications and experience.—Box 6632. [8109

EXPERIENCED radio service engineer with some television experience required, first-class rates and excellent working conditions.—Write, stating age, qualifications, experience and salary required, to British Relay Wireless, Ltd., Services Department, 397, Albany Rd., S.E.5. [7951

ATTRACTIVE working partnership immediately available in long established radio correspondence school; possibility of sole control in due course; investment about £1,000, some of which can be paid from salary; please state full qualifications in strict confidence.—Box 7350. [8259

SENIOR and junior electronic development engineers required, H.N.C. and degree standard experience in D.R.F. or centimetric work an advantage.—Apply by letter, stating experience, nationality and salary required, to E.M.I. Engineering Development, Ltd., Penleigh Works, Wells, Somerset. [8126

WEBB'S RADIO require senior engineer for specialized service department, must be conversant with the overhaul and alignment of communication receivers, including the provision of test figures to laboratory precision.—Write to the Manager, Webb's Radio, 14, Soho St., London, W.1. [8240

MERSEYSIDE firm of electrical engineers and radio retailers require a general sales manager to control entire retail turnover of four branches; excellent prospects for man of ability and initiative; state age and full details of experience; basic salary of £600 plus commission.—Box 7301. [8250

QUALIFIED accountant required by Merseyside electrical engineers (175 employees), must have commercial experience, energy and initiative essential, but sound prospects accordingly; salary £550, according to ability and experience; please reply in own handwriting giving full details of training and experience.—Box 7299 [8248

GALPINS

ELECTRICAL STORES

408 HIGH ST., LEWISHAM, LONDON, S.E.13

Tel.: Lee Green 0309 Near Lewisham Hospital

TERMS: CASH WITH ORDER NO C.O.D.
All goods sent on 7 days' approval against cash.

EARLY CLOSING DAY THURSDAY

EX-U.S.A. W.D. ROTARY TRANSFORMERS, 12 volts D.C. input, 500 volts, 50 m/amps. 275 volts 100 m/amps D.C. output. Complete with smoothing switches, fuses, etc., as new, 17/6 each, carriage 2/6, can be run on 6 volts giving half the stated output.

EX-W.D. ROTARY CONVERTERS, 24 volts D.C. input; 100 volts, 500 cycles, 1 phase at 300 watts output, £4/10/- each, carriage 10/-.

ROTARY CONVERTERS. 24-28 volts D.C. input, 1,200 volts 70 m/amps D.C. output, 10/- each, P.P.

TYPE 101 R.F. UNITS (NEW) containing 6 valves including grounded grid triode F.H.P. 24 volt Universal motor, numerous resistances and condensers, etc., 35/- each, Carriage 3/6.

EX-NAVAL ROTARY CONVERTERS, 110 volts D.C. input, output 230 volts A.C. 50 cycles, 1 phase, 250 watts capable of 50% overload, weight 100 lbs, price £10/10/- each, carriage forward.

PREPAYMENT 1/- SLOT METERS, all calibrated at 3d. per unit 200/250 volts, 50 cycles, A.C. mains, 5 amp. load, 45/- each, carriage 2/6; 10 amp. load, 57/6 each, carriage 2/6; 20 amp. load, 75/- each, carriage 2/6.

SWITCHBOARD. 4in. scale Amp. meters, moving coil meters, 100 to 250 amps., complete with shunt, 30/- each, post 1/6.

ELECTRIC LIGHT QUARTERLY TYPE CHECK METERS, all for 200/250 volts A.C. 50 cycles 1 phase, 5 amp load, 17/6 each, post 1/6, 10 amp. 21/- each, post 1/6, 20 amp load, 25/- each, post 1/6.

EX-R.A.F. ROTARY CONVERTERS, 24 volts D.C. input 50 volts, 50 cycles, 1 phase at 450 watts output, complete with step-up transformer 50 to 230 volts, £9/10/- each, carriage 10/-.

AUTO WOUND VOLTAGE CHANGER TRANSFORMERS, tapped 0/110/200/230 volts 350 watts, 48/6 each, post 1/6, as above but 500 watts 62/6 each, carriage 3/6, as above 2000 watts, 35/- each, post 1/6.

MAINS TRANSFORMERS (NEW), input 200/250 volts in steps of 10 volts output 350/0/350 volts 300 m/amps. 6.3 volts 8 amps. twice, 4 volts 4 amps., 5 volts 4 amps. 65/- each, carriage 3/6; Ditto, 450/0/450 volts 250 m/amps. 6.3 volts 8 amps. twice 4 volts 4 amps., 5 volts 4 amps 65/- each, carriage 3/6. Another, input as above, output, 500/0/500 volts 250 m/amps. 6.3 volts 8 amps. twice 6.3 volts 4 amps., 4 volts 4 amps., 5 volts 4 amps., 70/-, carriage 3/6. Another, wound to (electronic) specifications, 350/0/350 volts 250 m/amps 4 volts 8 amps, 4 volts 4 amps 6.3 volts 8 amps., 0/2/6.3 volts 2 amps 48/6 each, carriage paid, another, input as above output 500/350/0/350 500 volts 250 m/amps 6.3 volts 6 amps, 0/2/6.3 volts 2 amps, 0/4/5 volts 4 amps. twice, 67/6 each, carriage 3/6.

MAINS TRANSFORMERS (NEW). Input 200/250 volts in steps of 10 volts, outputs, 350/0/350 volts 180 m/amps 4 volts 4 amps. 5 volts 3 amps., 6.3 volts 4 amps., 39/6 each, post 1/6. Another, 350/0/350 volts 180 m/amps 6.3 volts 8 amps., 0/4/5 volts 4 amps., 39/6 each, post 1/6, another 500/0/500 volts 150 m/a. 4 volts 4 amps., C.T., 6.3 volts 4 amps., C.T., 5 volts 3 amps., 42/6 each, post 1/6, another 425/0/425 volts 160 m/amps., 6.3 volts 4 amps., C.T. twice 5 volts 3 amps., 42/6 each, post 1/6.

MAINS TRANSFORMER, 200/250 volts in steps of 10 volts output 400/0/400 volts, 280 m/amps. 6.3 v. 8 a., 2 v. 3 a., 5 v. 3 a., 4 v 2 a. twice at H.P., 75/- each, carriage 3/6.

MAINS TRANSFORMERS, 230 volts input, tapped output 0/6/12/18 volts at 4 amps., 32/6 each, post 1/6. Another auto wound, 230 volts input, output 0/14/17 volts at 30 amps., 45/- each, carriage 3/6. Another 230 volts input 4 volts, 20 amps., twice (auto wound), 25/- each, carriage 2/6.

MAINS TRANSFORMERS (NEW) suitable for spot welding, input 200/250 volts, in step of 10 volts, output suitably tapped for a combination of either 2/4/6/8/10 or 12 volts 50/70 amps, 87/6 each, carriage 7/6.

MAINS TRANSFORMERS (NEW), 200/250 volts input, in steps of 10 volts, outputs, 0, 6, 12, 24 volts 6 amps, 37/6 each, post 1/6. Another as above but 10-12 amps., 48/6 each, post 1/6, another as above but 25/30 amps., 70/- each, carriage 3/6, another, input as above, output 0/18/30/36 volts, 6 amps., 42/6 each, post 1/6.

The House for Quick Delivery

The following Goods Ex-Stock.

Cash with Order or C.O.D.

PLESSEY Multi-Speed Auto Record Changer. 10in.-12in. at 78 r.p.m. 10in.-12in. at 33⅓ r.p.m. 7in. at 33⅓ r.p.m. 7in. at 45 r.p.m. Virtually no needle changing. Simple design and construction, extremely easy to operate. Price including Tax, **£23 13 -.**

B.S.R. G.U.4. Three-Speed Gramophone Unit complete with lightweight Pick Up, and High Fidelity crystal Head. Price including Tax, **£9 19 11.**

Limited number of G.E.C. Multi-Beam Loudspeakers. List Price **£35.** My Price **£10 10 -.** New, in original packing. Carriage extra.

ACOS G.P. 20, complete with either Standard or L.P. Heads, **£3 11 5.**

ACOS Heads, Standard or L.P., **£2 3 4.**

GARRARD Standard Playing Unit with Pick-Up, **£6 3 2.**

COLLARO Standard Playing Unit with Pick-Up, **£6 10 6.**

LEAK TL/12 Watt "Point One" Feedback Amplifier, **£28 7 -.**

LEAK RC/PA/U. Remote Control Pre-Amplifier, **£9 9 -.**

LEAK V.S. Superhet Tuner Unit complete with Valves, **£37 2 4.**

Send me your order for all your Wharfedale Speakers.

A. ERNEST BUCHAN

(M.O. Dept.), 28 Belmont Street, Aberdeen. Phone 23579

A REMARKABLE ACHIEVEMENT IN FILTER DESIGN

Pat. Applied For

E.M.G. STEEP-CUTTING INFINITELY VARIABLE FILTER

- Cuts at any selected frequency between 4,000 and 8,000 c.p.s.
- Average steepness of cut 30 db. per octave.
- Connects between secondary of output transformer and speaker 15 ohms, rated impedance.
- Specially valuable for use with new microgroove records.
- Greatly reduces needle-hiss on ordinary records with minimum high note loss, and suppresses high pitched interferences on radio.
- No distortion, and no appreciable loss of volume.
- Leaflet available from the manufacturers.
- Some circuit patents pending.

£4 - 10 - 0

Trade Enquiries invited

E.M.G. HANDMADE GRAMOPHONES LTD

Newman St., Oxford St., W.1

Telephone: Museum 9971-2-3

SITUATIONS VACANT

ELECTRONIC computing section to be started will require Leader (Honours degree) and Assistants (Degree or H.N.C.).—Apply Employment Manager, Vickers-Armstrongs, Ltd. (Aircraft Section), Weybridge, Surrey. [8235

INSTRUMENT makers and laboratory technicians required by firm of instrument makers in the Guildford area, for work on prototype instruments and electrical equipment; varied and interesting work; canteen, 5-day week.—Write, stating age and experience, to Box 6618. [8076

WANTED, radio engineer for technical writing and correspondence in radio valve and cathode ray tube sales division of large manufacturing firm; lecturing ability an advantage.—Write, stating qualifications, experience, age and salary required, to Box 7405. [8292

MERSEYSIDE radio and electrical retailers require an experienced branch manager for a shop carrying a good class trade of £60,000 per annum; please state age and give full details of previous employment, commencing salary from £500 plus commission according to experience.—Box 1768. [8249

ELECTRONIC engineer with good academic qualifications and practical experience required for development work on vibration pickups and associated equipment in South Bedfordshire area.—Apply, stating age, experience, qualifications and salary required, to Box 7277, quoting reference S.4. [8185

ELECTRONIC assistant required for laboratory at Cambridge, duties will include the wiring and testing of circuits, and the use of hand and machine tools in the making of the mechanical parts of research apparatus designed in the laboratory; salary according to qualifications and experience; £250-£300 p.a.—Box 7404. [8286

TECHNICIANS, junior and senior, wanted, with experience on production development, or design of metal rectifiers and rectifier equipment for power frequencies; H.N.C. or Degree (Electrical Engineering or Physics) required for senior appointments; applications, stating education, experience and salary required.—Box 7295. [8226

ILFORD, Ltd., require mechanical draughtsmen with experience mainly concerned with process machinery, particularly of the automatic type; 5-day working week, canteen facilities and staff pension scheme.—Reply in writing, giving age and full particulars of experience and qualifications, to Ilford, Ltd., P.O. Box No. 10, Romford. [8049

A JUNIOR engineer is required for work on magnetic amplifiers and airborne electronic equipment, an engineering degree or Higher National Certificate would be preferred, but a young man studying for either of these examinations would be considered; Guildford area.—Write, giving qualifications and experience to Box 7290. [8149

DEVELOPMENT Engineers required for development laboratory of light engineering factory in Stockport, experienced in circuit design for radio test gear and electronic instruments; H.N.C., City and Guilds (tele-communications) Degree essential.—Write, stating age and full details of experience and qualifications, Box 7291. [8224

RADIO valve stock-keeper required to take full charge of valve section in large electrical warehouse, must be fully conversant with all types of radio and television valves, and experienced in testing, ordering and distribution.—Apply J. & F. Stone Lighting & Radio, Ltd., Edgware Rd., The Hyde, N.W.9 (Corner of Colindale Avenue). [8212

MACHINE Shop Foreman wanted; long experience on all types of machining (milling, turning, autos, drilling and press tool work) under piece-work conditions, for light engineering factory in Stockport district; must have at least 5 years' supervisory experience in similar position; good rate of pay, 44-hour week; canteen facilities.—Box 7292. [8225

MURPHY RADIO require engineers with knowledge of magnetic amplifiers and servo-mechanisms; applicants should have the mathematical and engineering knowledge necessary to design systems and undertake original development work in this field.—Apply, giving full details, to Personnel Manager, Murphy Radio Ltd., Welwyn Garden City. [8146

MCMICHAEL RADIO, Ltd., require qualified draughtsman with experience in the mechanical design of radio and electronic instruments for the Government services; salary will be commensurate with ability.—Write, stating age, training, experience and salary required, to the Chief Engineer, Equipment Division, McMichael Radio, Ltd., Slough, Bucks. [8069

ELECTRONIC Engineer, with good theoretical background to Higher National Certificate standard and with practical experience in use of valves in audio and radio frequency circuits, is required in the valve life testing laboratory at the G.E.C. Research Laboratories, Wembley, Middlesex.—Apply to the Staff Manager (Ref. GBLC/0.567), stating age and record. [8230

SENIOR Engineer required to undertake development work on low frequency iron cored components. Previous experience in this subject is essential, and a degree or equivalent would be an advantage. The salary will be in accordance with qualifications and experience. Apply in writing to Advance Components, Ltd., Back Rd., Shernhall St., Walthamstow E.17. [8097

ENGINEER required to initiate and maintain small scale production of specialised miniature valves, applicants must have had considered experience in a technical capacity on valve development and production; attractive salary will be paid to the successful applicant; initial applications treated in strictest confidence. Write, giving age, experience, etc., to Box 7285. [8194

ALL the Virtues!

THE GRAMOPHONE Amplifier gives high fidelity performance from 30-20,000 cycles, 8 watts output, with only 0.15 per cent. harmonic. The pre-amplifier is suited to almost any modern pick-up, with tone control for standard and L.P. recordings. *Yet you can make both units for about* **£19** *or buy them complete for* **22 Gns.** Such excellent performance at low cost can only be achieved by careful design and choice of parts. Output and mains transformers are generously proportioned. New Mullard all-glass valves.

"A constructor writes:—'reproduction is the best I have ever heard. I am more than satisfied with this amplifier.'"

Constructional details with diagrams, 1/6, post free. Full specification on request.

Goldring 3-way Pick-up, Type 150, for standard and L.P. records, two interchangeable sapphire styli. Fine performance and only **64/3.**

Decca XMS Magnetic, 2 heads, **£7.**

Connoisseur Super, £6/9/0; extra heads **£3/11/8.**

Chancery GPX microcell crystal, **53/-**; extra head, **31/6.**

Decca B.S.R. Motors, 3-speed, only **£6/8/6**; 2-speed, **£3/17/8.**

Goodmans Audiom 60 12in. 15W., **£8/12/6**; and soon the NEW Axiom 150. **W.B.** Stentorian 10in., 3 and 15Ω, **44/6.** **Truvox** 12in. 3Ω, **84/-.**

SEND STAMP FOR NEW LIST

QUALITY MART

MAIL ORDERS ONLY

8 Dartmouth Park Avenue, London, N.W.5.

PHILIPS FOR SOUND INSTALLATIONS

PHILIPS

TRADE MARK,

PHILIPS ELECTRICAL LTD.

All enquiries to:

PHILIPS ELECTRICAL LTD.

DEPT. ELA AMPLIFIERS

Century House · Shaftesbury Ave.

London · W.C.2.

OR

C. W. CAMERON LTD.

(Sole Distributors for Scotland)

57, Oswald Street · Glasgow · C.1.

(AR70)

14 TESTED CIRCUITS in our NEW CONSTRUCTOR'S HANDBOOK

Get your copy today, it costs 2'6 only and Contents include:—

(a) Circuits of these sets
(1) 2-wave plus Gram. Superhet.
(2) Fixed Station T.R.F. Transportable.
(3) 2-wave plus Gram. T.R.F. Set.
(4) 3-wave Superhet Feeder Unit.
(5) 3-wave Superhet Feeder Unit with H.F. Stage and incorporating Gram. and Quality switching.
(6) 5 v. A.C. all-wave Superhet.
(7) 5 v. A.C. D.C. all-wave Superhet.
(8) Feeder Unit Amplifier and Power Pack.
(9) 6 v. A.C. all-wave Superhet.
(10) 6 v. A.C. D.C. all-wave Superhet.
(11) Signal Tracer.
(12) 4 v. Battery Superhet.
(13) 5-watt Amplifier.
(14) 10-watt Quality Amplifier.

(b) Full constructional details of our very popular 2-wave plus gram. Superhet Coil Pack (extremely simple point-to-point wiring given in detail).

(c) Illustrations of many Receivers you can build with no previous experience.

(d) Complete Technical and Descriptive details of all our products.

(e) Pages of Constructional and Servicing hints.

(f) Many simple formulae in constant use.

(g) Complete Resistance Colour Code.

(h) Catalogue of our extensive Radio Stock forwarded with each Handbook.

A HANDBOOK YOU CANNOT AFFORD TO BE WITHOUT.

It will save you pounds.

Send 2/6 **now** for your copy to :—

SUPACOILS MAIL ORDER OFFICE

98, Greenway Ave., London, E.17

B. & H. RADIO
EAST STREET, DARLINGTON

BASS & TREBLE SEPARATOR
Cross-over 1,000 c.p.s. and including treble matching transformer.
Kit of Parts, Mod. A, 6Db per octave £1 19 0
Kit of Parts, Mod. B, 12Db per octave £2 16 0

SCRATCH FILTER
Easily fitted to pick-up and gives very marked reduction of scratch with little effect on treble £1 5 0

9 K.CS WHISTLE FILTER
Easily fitted giving a cut guaranteed better than 40Db with negligible effect on adjacent frequencies..... £2 12 6

TONE COMPENSATOR
Adjustable for microgroove recordings and easily fitted..... £2 5 0

SITUATIONS VACANT

MURPHY RADIO, Ltd., have a vacancy in the Electronics Division for a technical writer for publications dealing with radio, radar and similar equipment, duties will consist of the preparation of Technical Handbooks and the editing of descriptive matter, etc.—Write giving full details of experience and qualifications to Personnel Manager, Murphy Radio, Ltd., Welwyn Garden City. [8209

DRAUGHTSMAN, age 19-24, required, with some experience of light mechanical and radio or telephone equipment; excellent opportunity in new organization for young man capable of working largely on his own initiative.—Write stating age, experience and salary required to Central Engineering Department, British Relay Wireless, Ltd., 397, Albany Rd., Camberwell, S.E.5. [8244

ENGINEER required for work on vibration and noise problems, duties would include the development and active use of electronic measuring apparatus for this work; applicant should have honours degree in engineering or equivalent; apply in writing giving details of qualification and past experience to—The Manager, Electronics Engineering Dept., The British Thomson-Houston Co., Ltd., Rugby. [8269

LABORATORY assistant required by loudspeaker manufacturers, experience in a similar capacity, together with some knowledge of drawing office practice an advantage; the work is interesting and varied and the situation offers scope for initiative.—Write giving full details of age, experience and salary required to Electro Acoustic Industries, Ltd., Broad Lane, London, N.15. [8277

E.M.I. ENGINEERING DEVELOPMENT, Ltd., have a number of vacancies for engineers and senior engineers on interesting development work in various electronic engineering projects. The posts are for permanent pensionable staff and offer good prospects. Qualifications: a degree in Physics or Engineering or equivalent, together with several years' design or specialised experience in the following fields:—
(a) L.F. Equipment.
(b) Television Equipment.
(c) Microwave Techniques.
(d) Pulse Techniques.
(e) Servo Mechanisms.
(f) Test Gear Design.
(g) Inspection.
APPLICANTS should write, giving full details of experience and type of work required, and quote ED 33, to: Personnel Department, E.M.I. Engineering Development, Ltd., Blyth Rd., Hayes, Middx. [8229

DEVELOPMENT engineers.—International Aeradio, Ltd., specialists in equipment design for aviation service due to expansion of development section at Bovingdon Airport, near Watford, require junior and senior development engineers; salary according to experience; single quarters provided, pension scheme, 5-day week, canteen facilities.—Write, quoting D/EB, Personnel Officer, 40, Park St., London, W.1. [8260

DAVID MORGAN, Ltd., Cardiff, require for their new television, radio and electrical appliance workshop, (a) head working engineer to work directly under the buyer of the department and to be responsible in the first instance for the organisation of the workshop and engineers to work under the head engineer.—App'y in writing, stating age, experience and qualifications in detail, and salary required, to the Staff Office. [8256

WAYNE KERR require several senior and junior draughtsmen for design and development work on high priority electronic test equipment; the work is interesting and offers considerable scope for men with initiative and design ability; attractive salaries in excess of the revised A.E.S.D. rates will be offered to suitable applicants.—Write giving details of past experience to Wayne Kerr Laboratories, Ltd., Sycamore Grove, New Malden, Surrey. [8199

AN electronic technician is reqd. by St. Bartholomew's Hospital, London, E.C.1; duties involve servicing, planning, construction and testing of electronic equipment used in radioactive and radiation assaying and in other applications to medicine; salary according to experience in the Medical Laboratory Technicians scale of £410×£15 (3)× £20 (1) to £475, plus London Weighting; applications, together with references to—The Clerk to the Governors. [8294

EXPERIENCED Electronic Engineers required for interesting development work on a number of projects. Applicants should have a sound theoretical background with several years' experience in the design and engineering of prototype electronic equipment. The posts are for permanent staff and offer good salaries and prospects.—Please write, giving full details and quoting ED/63, to Personnel Department, E.M.I. Engineering Development, Ltd., Hayes, Middx. [8228

PHYSICISTS and electrical engineers. Interesting and varied work is available in a West London Research Department for versatile qualified physicists and electrical engineers on applied measurements—electrical, acoustic and mechanical; persons should have several years' industrial experience of this type of work; write to us for a preliminary interview and also state full details of education, qualifications, experience and salary required; suitable persons will be required under the Notification of Vacancies Order, 1952, to make their application through the Ministry of Labour or a Scheduled Employment Agency.—Write to Box A.E.751, Central News, Ltd., 17 Moorgate, London, E.C.2. [8127

L·R·S
Est. 1925

FOR PROMPT & EFFICIENT SERVICE
CASH or EASY TERMS

We have a limited stock of the following quality equipment available for cash or on our Revised Easy Terms.

ARMSTRONG ALL WAVE CHASSIS
(See Makers Advertisement page 101)

MODEL EXP. 73. Cash £25.12.4 or £8/11/- with order and 10 monthly instalments of 40/-.

MODEL RF. 104. Cash £34.12.10 or £12 with order and 12 monthly instalments of 40/-.

Passenger carriage 10/- extra payable with deposit.

LOUDSPEAKERS

GOODMANS AUDIUM 60. Cash £8.12.6 or £3/-/- with order and 6 monthly instalments of 20/-.

GOODMANS AXIOM 150. Cash £10.5.6 or £3.15/- with order and 7 monthly instalments of 20/-.

10in. W.B. CONCENTRIC-DUPLEX. Cash £7.15/- or £2/12/- with order and 6 monthly instalments of 20/-.

CONNOISSEUR
(See Makers Advertisement page 44)

SUPER L.W PICK-UPS. Complete, with one Green Spot and one Red Spot interchangeable Heads for Standard and Microgroove recordings. **Cash £10.0.8** or £3.15/- with order and 7 monthly instalments of 20/-.

DUAL SPEED GRAMOPHONE MOTORS. 33⅓ and 78 r.p.m. Full 12in. turntable. Synchronous type motor, dynamically balanced—virtually vibrationless. Cash price **£20.19.3** or £7/-/- with order and 8 monthly instalments of 40/-. Delivery from stock.

The L.R. SUPPLY CO. Ltd.
(LONDON RADIO SUPPLY CO)
BALCOMBE - - SUSSEX
Telephone : Balcombe 254

TRANSFORMERS

FOR ALL PURPOSES
SINGLY OR IN QUANTITIES
FROM OUR STANDARD RANGE
OR TO YOUR SPECIFICATIONS

GOOD DELIVERIES
REASONABLE PRICES

We have also a department for rewinds giving you a 24-hour service and a better job. Please label all burnt-outs with your name and address when despatching

P. HOWORTH
51 POLLARD LANE BRADFORD
Tel.: 37030

Convert that old Gramophone
OR CABINET RADIOGRAM
into a
MODERN All-WAVE
RADIO GRAM
A POWERFUL RECORD PLAYER

Our "Skyway" DESIGNS" Book gives full details on how to build FOUR first-class Amplifiers and Radiogram chassis. No radio experience is required to understand the clear circuit diagrams and stage by stage wiring plans.

2/6 POST FREE

All parts and materials are easily obtainable, mostly without purchase tax. Performance equal to radiograms costing over £100

only from

Phone 58971
Erith RADIOCRAFT Ltd
69-71 CHURCH GATE LEICESTER

AUTOMATIC SWITCHES
RECONDITIONED

ELECTRIC	CLOCKWORK
1 to 100 AMPS.	7 to 35 DAYS

From 35/- EACH

All guaranteed for a year.
Write for illustrated lists.

DONOHOE'S (Timers), 6, GEORGE ST., NORTH SHIELDS, NORTHUMBERLAND.

HIGH QUALITY CABINETS

Radiogram Cabinets from	£12.10.0
T.V. Console (Suit Viewmaster, etc.)	£11.10.0
10" Reflex (Suit Wharfedale, etc.)	£7.10.0
12" " " "	£8.5.0
12" Corner Reflex, from	£12.10.0

Special designs quoted for.

THE CHAFFEY CABINET CO.
50A, CHELTENHAM ROAD, LONDON, S.E. 15
Telephone: Orpington 3559

THE HAYES RG/135
RADIOGRAM CHASSIS



Combining advanced design with a high standard of construction, the RG/135 7-valve circuit includes a 6 watt output stage with negative feedback, and a new tone control system. Price £19.10.- complete. Write for full details of this chassis and also of our popular RG/120 5-valve model, price £14 complete. Demonstrations on Saturdays from 10 a.m. to 6 p.m., or on other days by appointment.

THE HAYES COMPANY
1 Alcester Road, Birmingham 13
Telephone South 0202

SITUATIONS VACANT

RADIO Service Technician required for the car radio department of a firm of car distributors in Guildford. Thorough knowledge (technical) of radio and radio servicing is essential; applicants should also have had experience and will be required to do electrical work on cars; apply by letter, giving particulars to—The Hassemere Motor Co., Ltd., Morris House, Woodbridge Rd., Guildford. [8295

ENGINEERS required for interesting work on the development of radio transformers and similar components. The work involves investigation of the application of new magnetic materials to transformer design.—Applicants should write, giving full details of experience, etc., and salary required, to the Personnel Department (ED.20), E.M.I. Engineering Development, Ltd., Hayes, Middx. [8227

DESIGNERS and draughtsmen with experience in electronic or light mechanical engineering are required by the G.E.C. Research Laboratories, Wembley Middlesex, for work at Stanmore; vacancies exist for seniors with good academic qualifications and also for juniors; excellent and interesting openings with good prospects. Apply to the Staff Manager (Ref. GBLC 5543), stating age and record. [8217

NATIONAL COAL BOARD.—Applications are invited for the appointment of a senior electronic engineer at the Central Research Establishment, Stoke Orchard, near Cheltenham, to undertake the design and provision of electronic devices as required for research; considerable responsible experience of this type of work and a wide knowledge of electronics circuit design (other than radio) are essential. THE post is superannuable and appointment will be as senior scientific technologist on the scale £670×£25 to £820 per annum, initial salary depending on qualifications and experience.
APPLY in writing, giving full particulars (in chronological order) of age, education, qualifications and experience (with dates) to National Coal Board, Establishments (Personnel), Hobart House, Grosvenor Place, London, S.W.1, marking envelope TT/459. Original testimonials should NOT be forwarded. Closing date 12th April, 1952. [8261

A PROJECT engineer is required by a well-known firm of instrument makers to direct the work of a section responsible for the layout and installation of specialised electronic equipment in aircraft; applicants should be qualified electrical engineers having had experience in, and enthusiasm for, this kind of work; they are asked to send full particulars of experience and training, stating salary required, to reference PE, Box 7281. [8190

BELLING & LEE, Ltd., Cambridge Arterial Rd., Enfield, Middlesex, require research assistants in connection with work on electronic components, fuses, interference suppressors and television aerials; applicants must be graduates of the I.E.E. or possess equivalent qualifications together with similar laboratory experience; salary will be commensurate with previous experience; applications must be detailed and concise, and will be treated as confidential.

ENGLISH ELECTRIC VALVE Co., Ltd., Chelmsford, have vacancies for young engineers to work on radio valve design and development; applicants should be of degree standard; whilst experience of this type of work is desirable, it is not essential and otherwise suitable candidates will be considered.—Write, giving full details, quoting ref. 497, to Central Personnel Services, English Electric Co., Ltd., 24-30, Gillingham St., London, S.W.1. [8165

MCMICHAEL RADIO, Ltd., require senior project engineers in their equipment division development laboratory at Slough. Training and experience in the field of applied electronics (including communications) and experience of working with Government departments, are the chief qualifications required; salary will be commensurate with ability.—Write, stating age and full details of training, qualifications and experience, to the Chief Engineer, Equipment Division, McMichael Radio, Ltd., Slough, Bucks. [8070

ENGINEERS and physicists with experience or in the following fields are required by the G.E.C. at the Stanmore Laboratories: (a) servo-mechanisms; (b) microwave aerials, transmitters or receivers; (c) small mechanisms; (d) electronic circuitry; (e) D.C. amplifiers; (f) test gear for field trials; preference will be given to men with good academic qualifications.—Applications should be sent to the Staff Manager (Ref. GBLC/5551) G.E.C. Research Laboratories, Wembley, Middlesex. [8216

MIDLAND engineering company manufacturing tele-communication equipment has vacancies for engineers in its laboratories and testing departments; applicants should preferably have had experience on carrier, coaxial, V.F. telegraph, repeating, local line networks, or trunk cables; academic qualifications are desirable but not essential if practical experience has been acquired.—Write, giving full particulars, including age, qualifications, experience, etc., to Box 7228. [8186

LEADING London Company producing electronic and radar equipment requires a chief draughtsman for the drawing office of their research laboratories. Engaged on interesting advanced work in this field, a man of first-class experience with high design ability who has held a similar post successfully is required; a good salary and prospects are offered to suitable applicant having the necessary qualifications combined with initiative and enthusiasm; housing assistance will be given if necessary; pension scheme.—Write in first instance full particulars and state salary to Ref. ST, Box 7479. [8167

100 kcs. QUARTZ CRYSTAL UNIT Type Q5/100

for Secondary Frequency Standards

★ Accuracy better than 0.01%. ★ Temperature coefficient 2 parts in a million per degree Centigrade temperature change. ★ Gold electrodes applied by cathodic sputtering direct to the faces of the crystal, giving permanence of calibration. ★ Simple single valve circuit gives strong harmonic at 100 kcs. intervals up to 20 Mcs. ★ Octal based mount of compact dimensions. PRICE 45/- Post Free

Full details of the Q5/100 including circuit are contained in our leaflet Q1. Send stamp to-day for your copy.

THE QUARTZ CRYSTAL Co. Ltd.
63-71 Kingston Road,
NEW MALDEN, SURREY
Telephone: MALden 0334

All types of Multimeters, Single-Range & special meters skilfully serviced and recalibrated.

THE ELECTRICAL INSTRUMENT REPAIR SERVICE, 329 Kilburn Lane, LONDON, W.9. Tel. LAD 4168.

BRASS, COPPER, DURAL, ALUMINIUM, BRONZE
ROD, BAR, SHEET, TUBE, STRIP, WIRE.
3,000 STANDARD STOCK SIZES
No Quantity too Small. *List on application.*
London: H. ROLLET & Co. Ltd. Liverp'l: 6, Chesham Place, S.W.1. Kirby Estate.
SLOane 3463 *SIMONSWOOD 3271/3*

WEST END RADIO LTD.
Estd. 20 YEARS
FOR RADIO BARGAINS

0-250 v. A.C. Meters. 2½in. New boxed. **25/-.**
0-500 Micro-amp. Meters. 2in., scaled, 0-10 volts D.C. Brand new, **7/6.**
2 C.34 (RK34). New, **2/11** each.
V.U. 120 Rectifiers, 2/11 each.
Selenium Rectifiers for Charging. 6 v. 1 a., **7/6** each.

SPECIAL OFFER!
Handsome Walnut Console T.V. Cabinets 34 x 16½ x 20in., to take up to 12in. tube. Our price, **8 gns.** each. P. and p. 10/-.
C.R.100 Ex-Navy Communication Receivers. 11 valves, A.C. 200-250 v. operation. B.F.O. crystal gate, etc. Send 6d. for illustrations. As new, **£29 10 0.**
Thousands of bargains for callers. Please enclose postage with order.

WEST END RADIO LTD.,
14, LISLE ST., LEICESTER SQUARE, LONDON, W.C.2. Phone GER 7341
OPEN ALL DAY SATURDAY.
NO LISTS AT PRESENT.

ADCOLA
(Regd Trade Mark)

SOLDERING INSTRUMENTS
means
SOUND JOINTS
for
SOUND EQUIPMENT
★
Reduce your
H.R. JOINTING FAULTS

Any volt range supplied
6.7 to 230 250

Designed for
Telecommunications
Radar - Wireless
Assembly - Maintenance, etc.

MADE IN ENGLAND

- 1/8" dia. bit Standard Model
- 1/4" dia. bit Standard Model
- 1/4" Detachable Bit Type (Factory Bench Line)
- Heating time : 90 seconds
- Consumption : 25 watts
- Weight : 4 ozs.
- Total length of instruments : 9 inches
- High temperature
- Good temperature control
- Handle unaffected by element temperature

Registered Design
(British, U.S.A. & Foreign Patents)

Sole Manufacturers and Distributors :
ADCOLA PRODUCTS LTD.
Gen. Offices & Works : Cranmer Court, Clapham High Street, London, S.W.4. MACaulay 4272

'Radiospares' Quality Parts

THE SERVICE ENGINEER'S FIRST CHOICE

SITUATIONS VACANT

FERRANTI, Ltd., have immediate vacancies for men with electrical engineering qualifications to undertake the advanced testing of naval anti-aircraft fire control equipment involving electronic and servo mechanisms, either in firm's workshops or on board H.M. ships in Home ports; salary in accordance with age and experience between £556 and £650 per annum; normal expenses plus a generous allowance are paid when working out. PREVIOUS experience of this type of work though desirable, is not essential.—Forms of application from Mr. R. J. Herbert, Staff Manager, Ferranti, Ltd., Hollinwood, Lancs. Please quote reference H.O.N. [8262

ELECTRONIC development engineer required for work on industrial electronic control systems, applicant should have a degree or equivalent in physics or electrical engineering and practical knowledge of machine control techniques, some experience on radiation and capacitive methods of mass measurement an advantage, minimum salary £600 per annum and upwards according to qualifications.—Bendix Manchester district.—Reply giving full details of education, qualifications, experience, age, etc., Box 7287. [8203

DEVELOPMENT Engineers required in the radio component laboratory of the Plessey Company, Ltd. Applicants for these positions should preferably have a Degree in Engineering or Physics, or Higher National Certificate, and should have experience in the development of light electro mechanical mechanisms. The positions give the right of entry into the company's pension fund and life assurance scheme after a probationary period and offer excellent opportunities of promotion. Applications should be made in writing, stating full details, to the Personnel Manager, The Plessey Co., Ltd., Ilford, Essex. [8218

THE GENERAL ELECTRIC Co., Ltd., Browns Lane, Coventry, have vacancies for development engineers, senior development engineers, mechanical and electrical, for their Development Laboratories on work of national importance; fields include microwave and pulse applications, salary range £400–£1,250 per annum; vacancies also exist for specialist engineers in component design, valve applications, electro-mechanical devices and small mechanisms; the Company's laboratories provide excellent working conditions with social and welfare facilities, superannuation scheme, assistance with housing in special cases.—Apply by letter, stating age and experience, to the Personnel Manager (Ref. CHC). [8185

TELEPHONE MANUFACTURING Co., Ltd., West Dulwich, S.E.21, require men for vacancies in the engineering laboratory; the company is engaged in the development, design and manufacture of switchboards, telephones, relays and other communication equipment apparatus; minimum qualifications, Higher National Certificate; salaries according to qualifications and experience plus, after a qualifying period, the benefits of a participating bonus scheme and a pension scheme; engineers interested to visit the works in connection with these vacancies should telephone or write to the Personnel Manager for an appointment.—Gipsy Hill 2211. [8256

AIRBORNE radio communication development engineer. Marconi's Wireless Telegraph Co., Ltd., have a number of vacancies for senior engineers possessing sound experience and design experience in aeronautical equipment, degree not essential if the candidate has long experience and other qualifications; salary £700–£1,000 per annum depending upon qualifications; the positions are permanent and good prospects are offered; pensions scheme; applicants should state whether they have specialised in development of aircraft aerial systems, transmitters or receivers.—Write giving full details quoting ref. 875 to Central Personnel Services, English Electric Co., Ltd., 24-30, Gillingham St., London, S.W.1. [8186

SITUATIONS WANTED

SALES manager executive seeks position, Surrey area preferred.—Box 6607. [8054

RADIO communications technical assistant, experienced in m.f., h.f., v.h.f. techniques, desires appointment U.K., returned from abroad, free immediately, age 35, married.—Box 7409. [8295

ELECTRONICS engineer, 35, married, returning shortly from overseas contract, seeks interesting and remunerative position with progressive organisation, preferably in commercial or administrative capacity; experienced in U.H.F. and pulse techniques, etc., used to responsibility.—Box 7284. [8197

PERSONAL

YOUNG Cypriot seeks radio tuition.—Box 7346. [8275

PAINTS, CELLULOSE, ETC.

PAINT spraying handbook 5/6, post free; cellulose and synthetic paints and all spraying requisites supplied.—Catalogue free.—Leonard Brooks, 55, Harold Wood, Romford. [0207

TECHNICAL TRAINING

INDUSTRY needs trained men, send for free brochure giving details of our Home Study Courses in radio, television and all branches of electronics; we prepare students for the A.M.Brit.I.R.E., City and Guilds Telecommunications, R.T.E.B., and other professional examinations. Train with the college backed by Britain's largest electronic industry.—Write to E.M.I. Institutes, Postal Division, Dept. WW55, 43 Grove Park Rd., London, W.4. Chiswick 4417 (Associated with H.M.V.). [0175

NUSOUND PRODUCTS
136 WARDOUR STREET, LONDON, W.1
(Oxford Street End)
Tel : GERrard 8845

NUSOUND FIDELITY-TEN. The latest super quality Amplifier. All Triode line up P-Pull PX4 output. Frequency response 20-25 kcs. ± .6 d.b. and continuing up to 50 kcs. ± 9 d.b. Sensitivity 120 mv for max 10 w output. Total harmonic distortion 1 per cent. at 1,000 c.p.s. at 6 watts. 20 d.b. neg. feedback. Independent Treble and Bass controls. Chassis size : 14 x 9 x 7½in. high. A.C. model only, **£36.**

A NEW FEEDER UNIT. This is our latest addition to our range, and employs a s/het c.c.t. with two I.F. stages and variable selectivity controls giving bandwidths of 7-10 and 14 kcs. The unit covers the medium-long and short wavebands and has a large illuminated dial. Price **17 gns.** inc.

RETAIL TRADE ENQ. ON ABOVE ITEMS. PLEASE SEND STAMP FOR LEAFLETS.

NUSOUND QUALITY AMPLIFIERS. 8½-WATT OUTPUT.—PP 6V6s—independent bass and treble boost and cut—switch for L.P. records—neg. feedback—provision for radio feeder unit—freq. response 25 to 20,000 c.p.s. ± ½ d.b.—hum 80 d.b. down at 6.5 watts—feedback 14 d.b.—sensitivity .05 volt. Price only **£15.17.6.** Also available with remote control unit. Price **£17.10.-.**

NUSOUND REFLEX CABINETS.—For Wharfedale speakers—10in., **£9.9.-**; 12in., **£10.10.-.** Veneered polish finish mahogany, oak or walnut.

Please send stamp for list of all our products. Our other products inc. 4½ watt Amp.—A.C. Model **£11.10.-**; A.C./D.C. **£12**; T.R.F. Preset Feeder, 3 station, **£7.12.6**; 3 station Preset S.Het, **£8.10.-**; two-band variably tuned S.Het, **£11.5.-.**

Remote control pre-amp. Unit, inc. tone controls, **£5.7.6.**

GRAMOPHONE EQUIPMENT

Decca 33 or 78 r.p.m. motor, **£3.14.4**, inc. Connoisseur Plups. Send. L.weight, **£4.11.8.** Trans. **13/-.** Super L.weight, one head, **£6.9.-.** LP Head **71/8.** Trans **15/-.** Fibre Plup **£4.3.2.** Trans. **25/-.** Two-speed Stroboscope **3.11.** Garrard Heads : Standard **25/3.** Miniature **50.11.** HiFi **56/-.** Type A Adaptor **7.7.** Decca Mag. Heads **59.2.** Decca XMS Plup **£7** complete. Chancery Attachment **72.6.** Decca 3-speed motor **£7/3/4.** Connoisseur 2-speed motor **£22.18.8.** Chancery Xtal Plup (LP20 insert) **53/-.** Spare insert, LP **31/6.** Garrard AC6 motor, speed controlled, 12in. table **£6.15.10.** Collaro A.C. 514MB motor and Plup **£6.10.5.** Collaro A.C./D.C. motor, 12in. table **£12.2.7.**

(We stock a full range of Wharfedale & Goodmans speakers and accessories.) TV and Gram. list **4d.** (Please Add Postage.)

COVENTRY RADIO
Component specialists since 1925

10,000

Radio Valves in stock, all types. Immediate delivery at current list prices. Full range of 1st Grade makes of components—Note we do NOT stock surplus, only new goods.

New list available shortly.

COVENTRY RADIO
189, Dunstable Road, Luton.

—TUNERS—

Our Type 84 is the ideal Quality Tuner for your high-quality amplifier. This four-stage Super-Het Unit has a lively performance with very low distortion. Fitted variable selectivity 7K.C. and 10K.C. Waveband coverage 16-50m., 190-500m., 900-2,000m. Using latest Mullard valves ECH42, EF41, EBF80, £17 6 8 tax paid.



Type 85 with R.F. stage also available.

Manufacturers of Ventex Products

C. T. CHAPMAN (Reproducers) LTD.
RILEY WKS., RILEY ST., CHELSEA, S.W.10
FLAxman 4577/8
Demonstration at **Webb's Radio**, London.
Distributors for S. Wales:—
Snell & Haines, Ltd., 132, Western St., Swansea.

GRAMOPHONE AMPLIFIERS

BRAND NEW. Will fit all portable gramophones and record players. Measures 10" × 5½" × 2". 4 watts quality output. Suits all pickups. Complete with valves, 6J7GT, 6V6GT, 6X5GT. **£4.17.6.** Carriage 2/6.

ELECTRO-ACOUSTICAL LABS.
EDDERTON - - ROSS-SHIRE

"CALLBOY"

CARRIES YOUR VOICE

COMPLETE INTER-COM SYSTEM FOR OFFICE FACTORY, STORES, ETC.

EASCO ELECTRICAL LTD.
4/8 BRIGHTON TERRACE
LONDON, S.W.9
Telephone - - - - Brixton 4961-2-3

When it's **Tenawire** *it's* **TROUBLE FREE**

Science brings a new high standard wiring in Tenawire. A high quality wire with outside covering which will not harden, split or crack. Really flexible yet tough, Tenawire is absolutely resistant to corrosion. Let our technical representative call and show you this important and unrivalled development.

TENAPLAS (SALES) LIMITED
Southern Sales & Export:
24/25, Manchester Sq., London, W.1.
Tel.: Welbeck 7341.
Midland & Northern Sales Office:
181, Wollaton St., Nottingham.
Tel.: 43584.

TECHNICAL TRAINING

CITY & Guilds (Electrical, etc.) on "no pass—no fee" terms; over 95% successes; for full details of modern courses in all branches of electrical technology send for our 144-page handbook—free and post free.—B.I.E.T. (Dept. 388A), 17, Stratford Place, London, W.1. [0117

TUITION

THE College of Aeronautics.

THE Board of Entry of the College invites applications from suitable candidates for the two-year course commencing in the autumn of this year; candidates should be of graduate standard, although the possession of a degree is not essential; a good Higher National Certificate is an acceptable qualification.

The College, a post-graduate institution, is devoted to the study of aeronautical science and engineering. The curriculum covers the five main subjects of Aerodynamics, Aircraft Design, Aircraft Electrical Engineering, Aircraft Propulsion, and Aircraft Economics and Production. Instruction in the first year is designed to provide students with a broad background of knowledge in all subjects, with opportunity for limited specialisation in two or three subjects. In the second year students specialise more particularly, usually in one subject.

EXPERIMENTS in the air are an important part of the work, both in the first year, when all students take part in them, and in the second year, when they are linked to the specialist work of the departments.

STUDENTS who satisfactorily complete the course will receive the Diploma of the College.

FURTHER particulars and details of the procedure for enrolment may be obtained on application to:—

THE Registrar, The College of Aeronautics, Cranfield, Bletchley, Bucks. [8271

RADIO training.—P.M.G. exams and I.E.E. Diploma; prospectus free.—Technical College, Hull. [0111

WIRELESS operating, attendance and postal courses.—Stamp for reply to Manager, The Wireless School, Manor Gdns., London, N.7.

NOTHING succeeds like success! What we have done a thousand times we can do again, for you.—See the B.N.R.S. advt., page 117.

SEE the world. 600 Radio Officers required; send 2d stamp for prospectus to Britain's leading college; we train most in shortest period at lowest cost.—Wireless College, Colwyn Bay.

A.M.I.Mech.E., A.M.Brit.I.R.E., City and Guilds, etc., on "no pass—no fee" terms; over 95% successes; for details of exams. and courses in all branches of engineering, building, etc., write for 144-page handbook—free.—B.I.E.T. (Dept. 387B), 17, Stratford Place, London, W.1. [0118

WIRELESS Telegraphy.—Merchant Navy offers to youth, 15½ upwards when qualified, lucrative positions as radio officers.—Apply British School of Telegraphy, Ltd., 179, Clapham Rd., London, S.W.9. Also postal courses in theory of wireless for P.M.G. Certificates and Amateur Transmitting Licence. [0124

THE Institute of Practical Radio Engineers have available home study courses in every phase of radio and television engineering, specialising in the practical training of apprentices in the retail trade; enrolments limited; fees moderate.—The Syllabus of Instructional Text may be obtained post free from the Secretary, I.P.R.E., Fairfield House, 20, Fairfield Rd., Crouch End, London, N.8. [0088

FREE! Brochure giving details of home study training in radio, television and all branches of electronics; courses for the hobby enthusiast or for those aiming at the A.M.Brit.I.R.E., City and Guilds Telecommunications, R.T.E.B., and other professional examinations; train with the college operated by Britain's largest electronic organization; moderate fees.—Write to E.M.I. Institutes, Postal Division, Dept. W.W.28, 43, Grove Park Rd., London, W.4. Chiswick 4417. (Associated with H.M.V.). [0001

BOOKS, INSTRUCTIONS, ETC.

WIRELESS WORLD, 1947-50, £1 each year; Radio T.V. News, 1948 30/-, 1950 35/-, offers.—68, Middle Pk. Rd., Birmingham, 29. [8215

"RADIO Servicing," by Abraham Marcus. A practical guide to the methods of finding faults together with a complete technical background of theory and practice; 36/- (post free).—Write to Allen & Unwin, 40, Museum St., W.C.1, for descriptive leaflet. [7779

I.P.R.E. technical publications, 5,500 Alignment Peaks for Superheterodynes, 5/9 post free; data for constructing TV aerial strength meter, 7/6; sample copy "The Practical Radio Engineer," quarterly publication of the Institute, 2/-; membership and examination data, 1/-.—Secretary, I.P.R.E., 20, Fairfield Rd., London, N.8. [0089

RADIO G200 OFFERS

Govt. Surplus Components, Transmitting, Obsolete Receiving, Special Purpose and Industrial Type Valves. NGT1, 1B24, HK304H, 35T, HK24G, FG27A, 878a, 725a, 2V36, WL2J32 magnetron, CV2, etc., available from stock.

EXPORT—IMPORT Enquiries invited.

ARTHUR HOILE 55 UNION STREET, MAIDSTONE, KENT. Telephone 2812

SAMSONS SURPLUS STORES

BRAND NEW R103A 6 VALVE RECEIVERS with built-in power pack for A.C. 100-250 v. or 6 v. D.C. Freq. range 1.7 mc/s. to 7.5 mc/s. Output is matched for L.R. phones. Complete with manual. **£12.** Carr. 5/-.

36FT. AERIAL MAST. R.A.F. Type 50. Complete kit consists of 9 Tubular Steel sections, length 4ft., diameter 2in. Set of pickets, top plate guys and all fittings. Supplied brand new in canvas carrying bags. Ideal for T.V. aerial masts. **£8 10/-**, carr. 7/6.

MASTER VOLTMETERS. 0-20 v. A.C. Moving Iron, 6in. mirrored scale, by Metro-Vickers, **25/-**. Carr. 1/6.

HEAVY DUTY TRANSFORMERS. Prim. 180-230 v. A.C. 50 cy. 4.2 + 4.2 v. 10 amps. **25/-**, carr 2/6. Prim. 200-240 v. 50 cy., Sec. 6.3 v. 15 amps. **18/6**, carr. 1/6.

V.C.R.97 BASES, 2/6, post 6d.

1 MFD. CONDENSERS, 600 v. D.C. with insulated terminals, **3/6**, post 6d.

Callers only: **PRITCHETT AND GOLD 6 v. 125 A.H. BATTERIES,** in Teak cases. **£6 10/-**.

DELCO 6 v. 90 A.H. CAR BATTERIES, size 9 × 9 × 7. Brand new. **£4 17 6.**

169/171 Edgware Road
London, W.2. Tel. Pad. 7851
125 Tottenham Court Road, W.1
Tel. EUS. 4982

All orders and enquiries to our Edgware Road branch, please. Open all day Saturday at the Edgware Road Branch.

REQUIRED

Design Engineer, B.Sc., or Higher National Certificate, with experience in miniature equipment, for hearing aid and electronic instrument factory, High Wycombe, Bucks. House provided if required, 5 day week, canteen, pension scheme. Full details of age, experience, and salary required, in confidence, to Box M.3382, Haddons, Salisbury Square, London, E.C.4.

REQUIRED

Laboratory Engineers (Junior), National Certificate standard, for hearing aid and electronic instrument factory, High Wycombe. 5 day week, canteen, pension scheme. Accommodation found if required. Give full details of experience, age, and salary required, in confidence, to Box M.3383, Haddons, Salisbury Square, London, E.C.4.

ODDIE FASTENERS

PAT. 507249



THE FASTENER WITH ENDLESS APPLICATIONS—SIMPLE—POSITIVE SELF-LOCKING. MADE IN A VARIETY OF TYPES AND SIZES.

SPECIAL FASTENERS TO SUIT CUSTOMERS REQUIREMENTS.

WIDELY USED IN THE RADIO INDUSTRY.

Illustrated brochures and other information will be gladly sent on request.

DEPT. "W.W."

Oddie, Bradbury & Cull Ltd., Southampton
Tel.: 55883 Cables: Fasteners, Southampton

FIDELIA *Plus*



The whole range of Fidelia receivers has variable selectivity: wide-range tone control circuit with separate Bass and Treble controls; audio response of 20-20,000 cycles; triode-operated output stages. The range includes: Fidelia Standard 7 valve model, £21 15.-; Fidelia Plus (illustrated above) has been particularly successful in difficult reception areas, and has a very lively short wave performance. Price £24 5.-; Fidelia De Luxe 9 valve model, with 7-watt push-pull output stage, £25 5.-; Fidelia Major 10 valve model, £31 10.-. Data sheets free on request.

Our new "home" faces the main Brighton-Newhaven road. We shall be very pleased to demonstrate any of our equipment by appointment. This includes Easter should you be visiting the coast, provided you let us know in advance. Phone: Peacehaven 3156

ELECTRO-ACOUSTIC DEVELOPMENTS

8 Amherst Road, Telscombe Cliffs, Sussex.

MANUFACTURERS' SURPLUS BARGAINS

Standard 80-ohm Co-ax. Cable, ¼in. dia., 10d. per yd. Pitney 10in. P.M. Speakers, less trans., 25/6; Truvox 12in. ditto, 59/6; both 3 ohm. P. p. 1/-. Resistors, ½ w., 4d.; 1 w., 6d.; 1 w. 8d. 60/40 resin-cored Solder, 6d. 16g., 4d. yd. Army Wireless Ratios, soiled. Wooden cabinet, 4-valve superhet chassis, 485 k.c., I.F.s, med. and short wave, 5in. Goodmans spkr., less valves (require 6 v. 1.5 amp. and 200 v. 60 m.a. m-ch). To clear, 30/- each, carr. 5/-. Volume Controls. Midget, all values, long spindles, S.P., 4/-; D.P., 4/9, less switch 3/-. E.H.T. Transformer, 4 k.v., 2 v. heater, 75/-. P. p. 1/-. Hundreds bargains, valves, etc. Full list 2½d. THO 166.

T.R.S. RADIO 367 WHITEHORSE ROAD, W. CROYDON.

SPECIALISED REPAIR SERVICE

WEBB'S Radio

specialise in the repair and alignment of complex communication receivers

All makes of British and American communication receivers completely overhauled to satisfy makers' original test specification. Calibration over entire coverage of tuning range. We issue a test report giving sensitivity—selectivity—signal/noise ratio on I.F's, and sensitivity—image ratio—signal/noise—A.V.C. characteristics overall.

Recognised Service Agents for
EDDYSTONE R.C.A., HALLICRAFTER, etc.

WEBB'S RADIO
14 Soho Street, London, W.1. Gerrard 2089.

WE SPECIALISE IN

VALVES!

(AT B.O.T. PRICES)

RETURN OF POST SERVICE

CITY & RURAL RADIO,
101, HIGH STREET,
SWANSEA

Telephone: Swansea 4677

BARKER SOUND UNITS TELL THE TRUTH

We have often said that our units are notable for having no personality of their own. They simply produce in sound what they receive in electrical form from the amplifier, without adding to it. A new friend puts it neatly by writing:—

"I have purchased one of your 150 Units and am completely satisfied. I can best describe it not by saying 'It has something which the others haven't got,' but by saying 'It hasn't got a lot of things the others have.'"

Without its context this looks a bit backhanded! But what it really means is that our sound is free from coloration, whiskers, boom and other additives: it is just NATURAL.

Our leaflet tells you why.

Write for details to

BARKER NATURAL SOUND REPRODUCERS
3 Newman Yard, London, W.1.

SURPLUS BARGAINS

MANUFACTURERS' & BANKRUPT STOCKS
LIMITED SUPPLIES ONLY

We can offer for immediate delivery

JUST PURCHASED

LARGE CONSIGNMENT OF RESISTORS

ALL VALUES: ⅛, ¼, ½, 1, 2, and 3 WATT

Low and High Resistance Headphones

EX. W.D. AERIAL—BRAND NEW—CAN ALSO BE USED AS FISHING RODS.

12 ft. Light Blue Aerials in 3—ft. sections, screw-in or plug-in type



Electrolytic Condensers—All Types

Yaxley Type Switches, Mansbridge Condensers (Oil filled and Jelly), Burgoyne Solder Guns, Tannoy Handmikes, Dinghy Transmitter Sets, Adhesive Tape, Coaxial Cable, Magnifying Lenses, Rubber Masks, speakers, Coaxial Plugs and Sockets etc., etc.

Your enquiries are invited.

WHOLESALE AND EXPORT ONLY

Our Catalogue will be sent on receipt of NEW trade card.

RADIO MERCHANDISE
COMPANY LIMITED
65, Farringdon Road, London, E.C.1
Telephone: HOLborn 6377 Cables: Radmer, London

IMPORTANT ANNOUNCEMENT

BISHOP SOUND & ELECTRICAL COMPANY LIMITED, 48, Monmouth Street, W.C.2, the originators of the renowned "**CUEBAR**" and the owners of the Trade Mark No. 610839 and Reg. Design Nos. 624083, 847049, 849583 and 840536 and Patent Nos. 524787 and 589996 concerning such devices respectfully call the attention of the Trade and users of recording, reproduction and sound effects equipment to the fact that no permission has been granted by them to the use of the name "**CUEBAR**" by any party other than the authorised users of their own specialised product.

Recently steps were taken to protect their proprietary interest in the name "**CUEBAR**" in respect of an unauthorised use thereof by the **DECCA RECORD CO. LTD.**, 1-3 Brixton Road, S.W.9, who have undertaken on behalf of themselves and their associated concerns not to repeat such use or to use any similar name likely to confuse and to withdraw from use any devices so identified or marked by them.

The "**CUEBAR**" is the most reliable Record Cueing Device in use where precision, durability and ease of working are necessary, a feature of the products and service of:

BISHOP SOUND & ELECTRICAL COMPANY LIMITED.

L-O-N-G RANGE BIG PICTURE

4ft. × 3ft.



A UNIQUE PROJECTION T.V.

A chassis for the individualist or for dealers who want big pictures of first-class quality for hotels, clubs, hospitals, institutes, schools, etc. Also made for smaller pictures 18" x 14".

23 valve S/H circuit. Sensitivity better than 50 microvolts. Full bandwidth. Wal. screen projection 4 x 3'. 5 channel facility. A.C supply. Insulated chassis. Complete with valves, tube, optical unit, speaker.

TELEMECHANICS LTD.
3 NEWMAN YARD, NEWMAN ST.
LONDON, W.1 Tel.: LANGHAM 7965

ANOTHER OF BROOKES FAMOUS CRYSTALS

TYPE "SM"

Range 3 to 17 mc/s.

Hermetically sealed metal can 1.125" high under pins, 0.825" wide, 0.457" thick, with 3.32" diameter pins at 0.490" centres.

BROOKES CRYSTALS LTD.
19, Stockwell St., Greenwich, London, S.E.10.
Phone: GREenwich 1828. Cables: Xtals London.
Grams: Xtals Green London.

MAGNETIC TAPE RECORDERS and COMPONENTS
from
WILL DAY, LIMITED
19 Leslie Street, London, W.C.2.
GERrard 7105 and 4476
SEND 1½d. STAMP FOR LIST — SENT BY RETURN

ENGINEERS!
Whatever your age or experience, you must read "ENGINEERING OPPORTUNITIES." Full details of the easiest way to pass A.M.I.Mech.E., A.M.I.C.E., C. & G. (Electrical, etc.) General Cert., etc., on "NO PASS—NO FEE" terms and details of Courses in all branches of Engineering—Mechanical, Electrical, Civil, Auto., Aero., Radio, etc., Building, etc. If you're earning less than £14 a week, tell us what interests you and write for your copy of "ENGINEERING OPPORTUNITIES" today—FREE

144 PAGES Free!

B.I.E.T.
387 Shakespeare Hse.
17-19 Stratford Place,
London, W.1.
BRITISH INSTITUTE OF ENGINEERING TECHNOLOGY

TAMSA
TAPE & WIRE RECORDING
We supply ALL RECORDING COMPONENTS.
Write for Latest Price List of :—
TAPE MECHANISMS, TAPES, WIRES and SPOOLS, HEADS, AMPLIFIERS, OSCILLATOR COILS and UNITS.
NOW AVAILABLE—HIGH COERCIVITY TYPE H60 EMITAPE.
TOPHET M, High Quality Recording Wire.
Constructors' Envelopes. Books on Tape Rec'd'g.
Manufactured by
AUDIGRAPH LTD.
Dept. MR1, 74 Great Hampton Street, HOCKLEY, BIRMINGHAM, 18.

NEO-MAINTEST

THE PERFECT FAULT FINDER
NEO ELECTRICAL INDUSTRIES LTD. MANCHESTER 4

TRANSFORMERS & COILS TO SPECIFICATION.
MANUFACTURED OR REWOUND
Filter Coils ± 1% a Speciality.
JOHN FACTOR LTD.
9-11 EAST STREET, TORQUAY, DEVON
'Phone: Torquay 2162

NUTS, BOLTS, SCREWS AND WASHERS
ALL CADMIUM PLATED

SET 305 (Size 2BA). Assorted screws and bolts from ⅛in. to 1¼in. long, with plain hex. nuts, Pinnacle nuts, double anchor nuts, lock washers and plain washers. All rust proof. **Average Contents, 450 Pieces, 7/6** plus 6d. post.

SET 306 (Size 4BA). Assorted screws and bolts from ⅛in. to 1¼in. long, with plain hex. nuts, Simmonds nuts, and plain washers. All rust proof. **Average Contents, 600 Pieces, 7/6** plus 6d. post.

SET 307 (Size 6BA). Assorted screws from ⅛in. to 1¼in. long, with plain hex. nuts, Simmonds nuts, shake proof washers, and plain washers. All rust proof. **Average Contents, 750 Pieces, 7/6** plus 6d. post.

By post, air-freight or ship, anywhere in the world.

BERNARD F. WADE LTD.
2, WELLINGTON RD., ILKLEY, YORKS.
Tel.: Ilkley 1767.

TOROIDAL WINDING CAPACITY AVAILABLE
BEL SOUND PRODUCTS CO.
Marlborough Yard, London, N.19
Tel: ARChway 5078

The VOIGT Loudspeaker is still ahead of all others. P.M. Unit with 20,000 line gap flux £40 ex works.
Corner Horns (in the white) £19.10.0 or £47.10.0 ex works.
Demonstrations in Toronto, Canada, by arrangement with Mr. Voigt.
VOIGT PATENTS LTD.
Sydenham, S.E.26 SYD 6666
Sole makers of VOIGT Products

QUALITY TELEVISION COMPONENTS
Scanning and Focus Coils
P.M. Focus Units
5/10 Kv. R.F. E.H.T. Units
E.H.T. and Output Transformers
Line fly-back E.H.T. Units
"TELEVISION CIRCUITS"
3rd Edition. 2/6
HAYNES RADIO Ltd.
Queensway : Enfield : Middlesex

AMPLIFIERS. Type A. 1134, less valves (210-LF QP21) 3 Transformers, 3-way key switch, on-off switch, resistors, condensers, etc. Make an ideal pick-up amplifier, or suitable 2-way intercom. amplifier, new, in wood transit cases. **12/6**, post 1/6.
MICRO-AMMETERS 0-500, 2 inch scale, **12/6**, post 6d.
Many other meters and relays. *S.A.E. for list.*
L. C. NORTHALL
16 Holly Road, Quinton, Birmingham, 32
Retail: 416 High Street, Smethwick. Phone: WOO 3166

TESTOSCOPE Mains Tester



For high & low voltage testing :—
130 & 100/850 volts A.C. or D.C. Write for interesting leaflet 30F.
Visit Stand C.730 B.I.F.
RUNBAKEN · MANCHESTER 1

LOCKWOOD
makers of
Fine Cabinets
and woodwork of every description for the Radio and allied trades
LOCKWOOD & COMPANY
Lowlands Rd., Harrow, Middlesex. Byron 3704

ELECTRONICS
DUPLEY LTD.
CRANMER AV. EALING.W 13.
Transformer and Coil Manufacturers to the Trade
Telephone EALing 5688

U.S. WAR SURPLUS WANTED
APR-4, APR-5, APR-1, ARC-3, etc ; TS-12, 13, 34, 35, 36, 45, 120, 146, 155, 173, 174, 175, 323 and other "TS-" units, etc., particularly for the MICROWAVE REGION ; also U.S. commercial laboratory equipment (General Radio, Ferris, etc.) ; special tubes, such as 721A/B, 3C22, etc. ; spare parts, technical manuals ; single units or large quantities.
Sell direct to us, receive the full top price. Describe and price to :
ENGINEERING ASSOCIATES
434 Patterson Road
Dayton 9, Ohio, U.S.A.

RADIO COMPONENT SERVICE
FREE Our new T.R.F. Feeder unit circuit with our catalogue of guaranteed radio components.
Coils, Superhet Coils, T.R.F. Dust cored and Air spaced, etc.
Send stamp to-day to
RADIO COMPONENT SERVICE
68 Chesterfield Road, Leyton, E.10

YOUR METER DAMAGED?

Leading Electrical Instrument Repairers to the Industry

Contractors to The Ministry of Supply.
Repairs by skilled craftsmen of all makes and types of Voltmeters, Ammeters, Microammeters, Multirange Testmeters, Electrical Thermometers, Recording Instruments, Synchronous Clocks, etc. Quick deliveries—for speedy estimate send defective instrument by registered post to :—
L. GLASER
Electrical Instrument Repairers
341 CITY ROAD, E.C.1
Tel. Terminus 2489

TANNOY
SOUND EQUIPMENT
clearly the best for all occasions

WEST NORWOOD S.E. 27 Tel: Gipsy Hill 1131 (7 lines)

RECTIFIERS

NEW SELENIUM RECTIFIERS

IMMEDIATE DELIVERY

Half Wave : 18 v. A.C. working : ½ amp. 8/- ; 1 amp. 11/- ; 2 amp. 16/- ; 2½ amp. 19/- ; all 6d. postage.

Full Wave : 18 v. A.C., 14 v. D.C. output : ½ amp. 8/- ; ½ amp. 11/- ; 1 amp. 13/6 ; all postage 6d. 2 amp. 29/- ; 4 amp. 33/- ; 5 amp. 39/- ; 8 amp. 63/- ; 10 amp. 70/- ; 20 amp. 129/- ; all postage 1/-. 36 v. A.C., 28 v. D.C. output : ½ amp. 11/- ; ½ amp. 18/- ; 1 amp. 24/- ; 2 amp. 36/- ; 4 amp. 59/- ; 5 amp. 69/-.

Special Rectifiers to Order

Automat Company
104 Hazelhurst Rd., Worsley, Manchester

"SENSITIVE TRF RECEIVER"
(Amos & Johnstone, November Issue)

SMITH'S
OF
EDGWARE ROAD

The Component Specialists

can supply ALL the parts, as used by the designers, for this amazing receiver.

Total cost about £7.

Send for complete, priced, list of parts.

H. L. SMITH & CO. LTD.
287-9, EDGWARE ROAD, LONDON, W.2.
Tel. Paddington 5891. Hours 9 to 6 (Thursdays 1 o'clock)
Near Edgware Road Stations, Metropolitan and Bakerloo

THE BRITISH NATIONAL RADIO SCHOOL
ESTD. 1940

NOW IN OUR THIRTEENTH YEAR AND STILL

NO B.N.R.S. STUDENT HAS EVER FAILED

to pass his examination(s) after completing our appropriate study course.

Become an
"ENGINEER ADVENTURER"
and join the battle for production in this New and again
Glorious ELIZABETHAN era !

A.M.Brit.I.R.E. and CITY and GUILDS Radio and Telecommunications Exams., etc., etc.

Please mention this advert. and send for free booklet to :—

STUDIES DIRECTOR
BRITISH NATIONAL RADIO SCHOOL
66, ADDISCOMBE ROAD, CROYDON
Phone : Addiscombe 3341

TELECRAFT

AERIALS ENSURE THE
BEST TELEVISION
TRY ONE AND SEE FOR YOURSELF

Welded Steel Cabinets



Ideal for housing communication receivers, amplifiers, test gear, etc.

15/-
Plus 3/- carr. and pkg.

Cabinets have detachable brass escutcheons. Cellulose sprayed. Overall size : 18½in. wide, 10½in. high, 9in. deep. Escutcheons 6½in. wide by 6½in. high ; and 5½in. square.

MOTORS. A.C 50 c/s. 230 volt ¼ h.p. 1425 r.p.m. £5 10/- ; ½ h.p. 230 volt 1425 r.p.m. £8 10/- ; ½ h.p. 400 volt 3-ph. 1425 r.p.m. **£9**, carriage extra at cost.

D.C. Motors 230 volt ¼ h.p. shunt wound 1425 r.p.m. £4 10/- ; 24 volt starter Motors, new **25/-** ; 12 volt ¼ h.p. high speed **55/-**, carr. 5/- ; ¼ h.p. 110 volts A.E.G. 1400 r.p.m. **25/-**, carr. 2/-.

RESISTANCES. Variable slider, 6 ohms 6 amps. **2 5/-** ; 14 ohms 5 amps. **32/6** ; 5 ohms 10 amps. **27/6** ; 152 ohms 2 amps. **30/-** ; 300 ohms ½ amp. **18/-**.

MOTOR GENERATOR, 24-28 volts D.C. input 120 volts 7 amps. 800 cycles 8,000 r.p.m. output, enclosed, fan cooled **65/-**, carr. 5/-.

ALTERNATORS. Inductor type totally enclosed 230 volts 2 amps. 460 watts 50 c/s. 3-ph. 3,000 r.p.m., **£8 10/-**, need exciter 6 volts 6 amps. Can also be wired for 230 volts 230 watts single phase 50 cycles.

RECORDING METERS by Evershed & Vignoles, in iron case, wall type Murday system, 3-0-3 or 10-0-10 m.a. full scale, chart 12in. per min. as new. Send for List of Instruments and Apparatus. Motors, Dynamos, Transformers, Morse Keys, Buzzers, Relays, Switches, etc., etc. Stocks always available.

ELECTRADIX RADIOS
Dept. A, 214 Queenstown Road, London, S.W.8
Telephone : MACaulay 2159

The business of
COULPHONE RADIO
has closed down

Any communications to :
SEA VIEW HOUSE, ST. BEES, CUMBERLAND.

G.E.C. GERMANIUM CRYSTAL DIODES

Midget Size, 5/16in. x 3/16in.
Wire Ends for Easy Fixing.
4/6 each, postage 2½d.
Technical Details and Selected Types available.

B.T.H. GERMANIUM CRYSTAL DIODES

Moulded in thermo-setting plastic.
4/6 each, postage 2½d.

SILICON DIODES, 3/6. Postage 2½d.
Fixing Brackets, 3d. pair.

COPPER INSTRUMENT WIRE
ENAMELLED, TINNED, LITZ.
COTTON and SILK COVERED
Most gauges available.
B.A. SCREWS, NUTS, WASHERS.
soldering tags, eyelets and rivets.
EBONITE AND BAKELITE PANELS.
TUFNOL ROD, PAXOLIN TYPE COIL FORMERS AND TUBES, ALL DIAMETERS.
ERIE AND DUBILIER RESISTORS.
Latest Radio Publications.
SEND STAMP FOR LIST. TRADE SUPPLIED

POST RADIO SUPPLIES
33 Bourne Gardens, London, E.4

THE MODERN BOOK CO.

Radio Amateur's Handbook. By A.R.R.L. 1952 edition. Price **32s.** Postage 1s.

Feedback. By N. H. Crowhurst. Price **3s. 6d.** Postage 3d.

Television Receiver Practice. By R. Holland. Price **5s.** Postage 3d.

Magnetic Recording. By S. J. Begun. Price **25s.** Postage 9d.

The De Luxe Home-built Televisor and Radiogram. By W. I. Flack. Price **6s. 6d.** Postage 4d.

Television Receiving Equipment. By W. T. Cocking. Price **18s.** Postage 9d.

Microphones—B.B.C. Engineering Training Manual. Price **13s.** Postage 6d.

Radio Engineers' Handbook. By F. E. Terman. Price **50s.** Postage 9d.

Radio Engineering. By F. E. Terman. Price **50s.** Postage 9d.

Sound Reproduction. By G. A. Briggs. Price **10s. 6d.** Postage 6d.

Encyclopedia on Cathode-Ray Oscilloscopes. By Rider and Uslan. Price **75s.** Postage 1s.

Wireless Servicing Manual. By W. T. Cocking. Price **12s. 6d.** Postage 6d.

Reference Data for Radio Engineers. By W. L. McPherson. Price **7s.** Postage 6d.

Application of the Electronic Valve. Volume II. Book V. By Dr. B. G. Dammers etc. (Phillips' Technical Library). Price **45s.** Postage 9d.

Radio Installations. By W. E. Pannett. Price **45s.** Postage 9d.

Radio Valve Data. Compiled by "Wireless World." Price **3s. 6d.** Postage 3d.

We have the finest selection of British and American books in the country. Complete list on application.

19-23 PRAED STREET
(Dept. W.3.)
LONDON, W.2
PADdington 4185

INDEX TO ADVERTISERS

	PAGE
Acoustical Mfg. Co., Ltd.	55
Acru Electric Tool Mfg. Co., Ltd. The	118
Adcola Products, Ltd.	114
Advance Components, Ltd.	17
Allan Richard Radio, Ltd.	96
Allen Components, Ltd.	107
All-Power Transformers, Ltd.	28
Alpha Radio Supply Co., The	116
Altham Radio Co.	46
Ampere Appliances (Kent), Ltd.	96
Amplivox, Ltd.	64
Anders Radio, Ltd.	10
Antiference, Ltd.	12
Armstrong Wireless & Television Co., Ltd.	101
Ashworth, F.	12
Associated Cine Equipments, Ltd.	52
Astor, Bousseller & Lawrence, Ltd.	96
Audiorama, Ltd.	116
Audio-Acoustic Diffusers, Ltd.	16
Automat Co.	117
Automatic Coil Winder & Electrical Equipment Co., Ltd., The	1
Automatic Telephone & Electric Co., Ltd.	53
A.W.F. Radio Products	96
Bakers "Selhurst" Radio	80
B. & H. Radio	111
Baker Natural Reproducers	115
Bel Sound Products, Ltd.	116
Belling & Lee, Ltd.	69
Bennett College, Ltd., The	42
Berry's (Short Wave), Ltd.	52
Bird, S. S. & Sons, Ltd.	78
Birmingham Sound Reproducers, Ltd.	64
Bishop Sound & Electrical Co.	115
Black & Decker, Ltd.	58
Bradmatic, Ltd.	56
Brierley, J. H. (Gramophone & Recording), Ltd.	24
Britain, Chas. (Radio), Ltd.	57
British Communications Corpn., Ltd.	96
British Industries Corporation	2
British Institute of Engineering Technology	102, 16
British Insulated Callender's Cables, Ltd.	Cover ii
British National Radio School	117
British Physical Laboratories	50, 54
British Sacma, Ltd.	3
Brookes Crystals, Ltd.	116
Brown, S. G., Ltd.	19
Buchan, A. E.	110
Bugin, A. F. & Co., Ltd.	Edit. 167, 96
Bull, J. & Sons	105
Bullers, Ltd.	10
Candler System Co.	94
Chaffey Cabinet Co., The	112
Champion Products	106
Chapman, C. T. (Reproducers), Ltd.	114
Cinema-Television, Ltd.	15
City & Rural Radio	115
C.J.R. Electrical & Electronic Development, Ltd.	62
Classic Electrical Co., Ltd.	107
Clydesdale Supply Co.	88
Cohen, D.	82, 85
Cosmocord, Ltd.	66
Cossor, A. C., Ltd.	75
Coulphone Radio	112
Coventry Radio	115
Davis, A. C. Supplies, Ltd.	50, 100
Davis Sack (Relays), Ltd.	93
Day, W. H., Ltd.	116
De Faviland Enterprise, The	96
Donohoe's (Times),	112
Du Bois Co., Ltd., The	58
Duke & Co.	102
Duperix Electronics, Ltd.	116
Easco Electrical, Ltd.	114
Edison Swan Electric Co., Ltd.	25
Electradix Radios	112
Electrical Instrument Repair Service, The	112
Electro-Acoustic Developments	115
Electro-Acoustical Laboratories	114
Electronic Precision Equipment	78, 79, 80, 81
Elm Electric Co.	24
E.M.G. Handmade Gramophones, Ltd.	110
E.M.I. Institutes	40, 76
Engineering Associates	118
Erkhoven, H. J., & Sons, Ltd.	61
Factor, J., Ltd.	116
Farmer, John	105
Ferranti, Ltd.	14
Fidelon (Electronics), Ltd.	26
Fluxite, Ltd.	106
Foyle, W. & G., Ltd.	94
Frith Radiocraft, Ltd.	54, 112
Gaipins	109
Garland Bros.	64, 65
Gee Bros. Radio, Ltd.	101
General Electric Co., Ltd.	45
General Lamination Products, Ltd.	108
Graser, L.	116
Gramdata Industries, Ltd.	4, 5
Goodwill, Ltd.	57
Grampian Reproducers, Ltd.	56
Gray, Arthur, Ltd.	48
Hall Electric, Ltd.	42
Haslam, Leigh & Cheston, Ltd.	54
Hanney, L. F.	14
Hartley, H. A., Co., Ltd.	100
Hayes Co., Ltd.	114
Haynes Radio, Ltd.	116
Heaters, W. T., Telegraph Works Co., Ltd.	104
Henry's	95
Hoile, Arthur	114
Hosley's Radio Stores	105
Homeab Instruments, Ltd.	42
Howorth, P.	111
H.P. Radio Services, Ltd.	97
Hunt, A. H., Ltd.	51
Hyde, J. B., & Co., Ltd.	56
Iliffe & Sons Ltd.	28
Imhof, Alfred, Ltd.	14
International Correspondence Schools	22
Jay Developments	26
Kolectric, Ltd.	102
Lasky's Radio	88, 90, 91
Leak, H. J., & Co., Ltd.	77
Lewis Radio Co.	108
Lockwood & Co.	116
Lonjes, Ltd.	62
London Central Radio Stores	47
Lowther Mfg. Co.	46
L.R. Supply Co., Ltd.	111
Lyons Radio	94
Mail Order Supply Co.	19, 20, 21
Marconi Instruments, Ltd.	41
Marconi's Wireless Telegraph Co., Ltd.	75
Marks, C., & Co.	64
Massgrado, Ltd.	22
Mayco Electric	92
Mcgilroy-Adams Mfg. Group, Ltd.	58
McMurdo Instruments Co., Ltd.	16
Measuring Instruments (Pullin), Ltd.	60
Miers, N., & Co., Ltd.	82
Modern Book Co.	117
Modern Electrics, Ltd.	58
M.R. Supplies, Ltd.	52
M.S.S. Recording Co., Ltd.	37
Mullard, Ltd.	3, 58, 66
Multicore Solders, Ltd.	Cover iv
Murex, Ltd.	61
Neo Electrical Industries, Ltd.	116
Newman, J., & S., Ltd.	28
Northall, E. C.	116
Northern Radio Services	42
N.S.F., Ltd.	27
Nuscund Products	113
Oddie, Bradbury & Cull, Ltd.	114
Olympic Radio Components	96
Osmor Radio Products, Ltd.	10
Painton & Co., Ltd.	13
Park Radio, Ltd.	55
Partridge Transformers, Ltd.	99
P.C.A. Radio	94
Pearce, T. W.	106
Philips Electrical, Ltd.	62, 110
Post Radio Supplies	14, 117
Pratts Radio	50
Premier Radio Co.	7, 8, 9
Quality Mart	110
Quartz Crystal Co., Ltd.	114
Radio Component Service	116
Radio & Electrical Mart, The	96
Radio Exchange Co.	56
Radiomemders, Ltd.	92
Radio Mercnandise Co., Ltd.	115
Radio Servicing Co.	102
Radiospares, Ltd.	113
Radio Supply Co.	56
Radio Traders, Ltd.	22
Rainbow Radio & Mfg. Co., Ltd.	62
Record Electrical Co., Ltd., The	38
Roding Laboratories	56
Rogers Developments Co.	50
Rola Celestion, Ltd.	48
Rollet, H., & Co., Ltd.	112
Rose, A.	30
Royal Air Force, The	29
Runbaken Electrical Products	116
Salford Electrical Instruments, Ltd.	46
Sali, Ltd.	72
Sallis, A. T.	104
Salmons Surplus Stores	114
Sangamo Weston, Ltd.	74
Savage Transformers, Ltd.	108
Savage, W. Bryon, Ltd.	54
Scharf, Erwin	54
Scophony-Baird, Ltd.	51
Scram Electrical Instruments Co., Ltd.	55
Simmonds Aerocessories, Ltd.	6
Simon Sound Service	34
Smith, G. W. (Radio), Ltd.	105
Smith, H. L., & Co., Ltd.	117
Sound Sales, Ltd.	74
Southern Radio Supply, Ltd.	108
Spencer-West	96
Stability Radio Components, Ltd.	50
Standard Telephones & Cables, Ltd.	67, 70
Steatite & Porcelain Products, Ltd.	59
Stern Radio, Ltd.	86, 87
Sutton & Co., Ltd.	53
Sugden, A. R. & Co. (Engineers), Ltd.	44
Supacoils	111
Szymanski, S.	52
Tannoy Rentals, Ltd.	116
Taylor Electrical Instruments, Ltd.	25
Telecraft, Ltd.	57, 117
Telegraph Condenser Co., Ltd.	Cover iii
Telegraph Construction & Maintenance Co., Ltd., The	49
Telemechanics, Ltd.	115
Tele-Radio (1943), Ltd.	44
Tensilas (Sales), Ltd.	114
Thermionic Products, Ltd.	63
Thomas, A., & Co.	104
Trix Electrical Co., Ltd.	Edit. 165
T.R.S. Radio	115
Uncles, Bliss & Co., Ltd.	50
University Electrical Instruments Corpn.	92
Universal Electronics	96
University Radio, Ltd.	95
Valradio, Ltd.	82
Verdik Sales, Ltd.	59
V.E.S. Wholesale Services, Ltd.	44, 98
Vitavox, Ltd.	24
Voigt Patents, Ltd.	116
Vortexion, Ltd.	71
Wade, B. F., Ltd.	116
Walton's Wireless Stores	94
Wayne Kerr Laboratories, Ltd., The	63
Webb's Radio	115
West End Radio, Ltd.	112
Westinghouse Brake & Signal Co., Ltd.	38
Wharfedale Wireless Works	51
Whiteley Electrical Radio Co., Ltd.	11
Wilco Electronics	106
Wilkinson, L.	98
Wolf Electric Tools, Ltd.	59
Wright & Weaire, Ltd.	76
Young, C. H.	92


THERE ARE 12 DIFFERENT MODELS OF
ACRU NEON INDICATORS
Ask for Leaflet.
Made by
The ACRU ELECTRIC TOOL MFG. CO. LTD.
Chapel Street, Stockport Road, Levenshulme, Manchester 19.
Tel.: RUSholme 6134

Printed in Great Britain for the Publishers, ILIFFE & SONS LTD., Dorset House, Stamford St., London, S.E.1, by CORNWALL PRESS LTD., Paris Garden, London, S.E.1. *Wireless World* can be obtained abroad from the following: AUSTRALIA AND NEW ZEALAND: Gordon & Gotch, Ltd. INDIA: A. H. Wheeler & Co. CANADA: The Wm. Dawson Subscription Service Ltd.; Gordon & Gotch, Ltd. SOUTH AFRICA: Central News Agency, Ltd.; William Dawson & Sons (S.A.), Ltd. UNITED STATES: The International News Co.

ELECTROLYTICS for 85°C without voltage de-rating

T.C.C. introduce a new range of electrolytics with outstanding features. Independent tests at full working volts at 85°C. for 1,000 hours substantiate our claims on these condensers.

ABILITY TO WORK AT HIGH TEMPERATURES

These condensers work satisfactorily up to 85°C. full working voltage, i.e., no de-rating is necessary.

LEAKAGE CURRENT

Exceptionally low at room temperature, with minor increase as temperature is raised.

SHELF LIFE CHARACTERISTIC

Whereas the leakage current of the normal commercial electrolytic increases when idling over a long period, that of the 85°C. construction remains relatively constant.

RIPPLE RATINGS

Because of characteristic low leakage current and ability to work at high temperatures, these condensers are capable of handling much higher ripple currents for the same size of case

ETCHED FOIL CONSTRUCTION

Cap. µF	V. Pk. Wkg.	Dimensions In Inches		Max. Permissible Ripple m.A		Type No.
		L.	D.	60°C.	85°C.	
8	450	1¾	¾	100	60	SCE160PE
16	450	1¾	¾	175	100	SCE120PE
32	450	2¼	1	280	160	SCE122PE
60	450	2⅞	1¼	520	300	SCE125PE
100	450	4¼	1¼	800	450	SCE126PE



TCC

Further details of this range available on request

For those who are unable to meet us at our stand at the R.E.C.M.F. Exhibition we show our advertisement pages in the Exhibition Catalogue.

Why does it pay to use ERSIN MULTICORE? Because it cuts down production costs. *Why is this?* Because it contains 3 cores of non-corrosive, extra active ERSIN FLUX, ensuring fast, efficient soldering. *Who uses it?* Leading manufacturers of electronic equipment throughout the world, including the U.S.A., where television and radio engineers insist upon ERSIN MULTICORE, despite freight and import duties. *How can I, as a manufacturer, get more information?* Let us have your name and address and we will be pleased to send you, without charge, new technical literature, samples and bulk prices. Radio enthusiasts can obtain our Size 1 Carton from their usual supplier.

SIZE 1 CARTON—5/- RETAIL

Catalogue Ref. No.	Alloy Tin/Lead	S.W.G.	Approx. Length per carton
C16014	60/40	14	13 feet
C16018	60/40	18	37 feet
C14013	40/60	13	13 feet
C14016	40/60	16	26 feet